

Documentation for Confluence 5.0

Contents

Confluence User's Guide	8
Getting Started with Confluence	8
About Confluence	9
Dashboard	9
Page in View Mode	11
Confluence Glossary	14
Keyboard Shortcuts	18
Creating Content	23
Using the Editor	25
Quick Reference Guide for the Confluence Editor	30
Working with Text Effects	42
Working with Links	44
Linking to Pages	45
Linking to Images	48
Linking from an Image	50
Linking to Attachments	51
Linking to Blog Posts	52
Linking to Personal Spaces and User Profiles	53
Working with Anchors	53
Using a Link to Create a New Email Message	56
Linking to Confluence Pages from Outside Confluence	56
Inserting JIRA Issues	56
Trackback	58
Displaying Images	59
Deleting an Image	63
Working with Tables	63
Using Symbols, Emoticons and Special Characters	65
Using Autocomplete	67
Working with Page Layouts and Columns and Sections	72
Working with Macros	75
Activity Stream Macro	80
Anchor Macro	81
Attachments Macro	81
Blog Posts Macro	81
Change-History Macro	85
Chart Macro	86
Cheese Macro	98
Children Display Macro	99
Code Block Macro	101
Column Macro	103
Content by Label Macro	103
Content by User Macro	108
Content Report Table Macro	109
Contributors Macro	111
Contributors Summary Macro	115
Create Space Button Macro	119

Excerpt Include Macro	120
Excerpt Macro	122
Expand Macro	123
Favourite Pages Macro	124
Gadget Macro	125
Gallery Macro	127
Global Reports Macro	131
HTML Include Macro	132
HTML Macro	133
IM Presence Macro	133
Include Page Macro	134
Info Macro	136
JIRA Issues Macro	137
JIRA Macro	144
JUnit Report Macro	144
Labels List Macro	146
Livesearch Macro	146
Loremipsum Macro	147
Multimedia Macro	148
Navigation Map Macro	148
Network Macro	150
Noformat Macro	151
Note Macro	152
Page Index Macro	152
Page Properties Macro	153
Page Properties Report Macro	160
Page Tree Macro	163
Page Tree Search Macro	167
Panel Macro	168
Popular Labels Macro	169
Profile Picture Macro	170
Recently Updated Dashboard Macro	171
Recently Updated Macro	172
Recently Used Labels Macro	177
Related Labels Macro	178
RSS Feed Macro	179
Search Results Macro	181
Section Macro	183
Space Attachments Macro	183
Space Details Macro	183
Space Jump Macro	184
Spaces List Macro	186
Status Macro	187
Table of Contents Macro	188
Table of Content Zone Macro	192
Tasklist Macro	197
Tip Macro	200
User List Macro	201
User Profile Macro	202
User Status List Macro	203
View File Macro	204
Warning Macro	206

Widget Connector Macro	207
Working with Drafts	218
Configuring the Time Interval at which Drafts are Saved	219
Concurrent Editing and Merging Changes	219
Resuming the Editing of a Draft	220
Recording Change Comments	221
Creating Attractive and Dynamic Pages	222
Working with Templates	226
Adding a Template	227
Creating a Page using a Template	233
Editing a template	234
Removing a Template	235
Working with the Office Connector	236
Office Connector Prerequisites	237
Displaying Office Files in Confluence	239
Importing a Word Document into Confluence	241
Editing an Office Document from Confluence	245
Editing an Office Spreadsheet from Confluence	248
Editing an Office Presentation from Confluence	251
Installing the Firefox Add-On for the Office Connector	254
Importing Content Into Confluence	263
Importing Content from Another Wiki	264
Importing Pages from Disk	264
Sharing Content	265
Network Overview	266
Likes and Popular Content	268
User Status Updates	269
Using Mentions	272
Emailing a Page	274
Exporting Confluence Pages and Spaces to Other Formats	275
Exporting Confluence Pages and Spaces to HTML	275
Exporting Confluence Pages and Spaces to PDF	277
Customising Exports to PDF	280
Creating PDF in Another Language	291
Exporting to a Word document	291
Exporting Confluence Pages and Spaces to XML	292
Commenting on pages and blog posts	293
Linking to Comments	295
Sample Page	296
Printing Confluence Pages	296
Managing Changes and Notifications and Tasks	297
Watching a Page or Blog Post	298
Watching a Space	299
Managing Watchers	302
Subscribing to Email Notifications of Updates to Confluence Content	302
Subscribing to RSS Feeds within Confluence	307
Using pre-specified RSS feeds	308
Using the RSS Feed Builder	309
Subscribing to a Network RSS Feed	311
Managing Notifications in Confluence	312
Managing Tasks in Confluence	316
Finding Content	320

Searching Confluence	323
Text Tokenisation and Filtering	331
Confluence Search Syntax	331
Confluence Search Fields	335
Ranking of Search Results	340
Searching the People Directory	343
Organising Content	344
Working with Pages	345
Moving a Page	345
Copying a Page	348
Renaming a Page	349
Deleting a Page	349
Purging Deleted Pages	350
Restoring a Deleted Page	351
Viewing All Pages in a Space	351
Changing the Sequential Order of Pages	353
Managing Orphaned Pages	355
Managing Undefined Pages	356
Using the Documentation Theme	356
Viewing Page Information	360
Viewing Recently Visited Content	361
Page History and Page Comparison Views	362
Using a WebDAV Client to Work with Pages	365
Working with Blog Posts	365
Working with Spaces	367
Viewing All Confluence Spaces	369
Creating a Space	372
Setting Up your Personal Space	373
Administering a Space	374
Editing Space Details	376
Deleting a Space	377
Backing Up and Restoring a Space	378
Archiving a Space	378
Viewing Space Activity	380
Viewing Recently Updated Content	381
Working with Mail Archives	382
Adding a Mail Account	383
Deleting Mail	384
Fetching Mail	385
Importing Mail	385
Managing Mail Accounts	386
Working with Confluence Labels	387
Adding Labels	388
Using Labels to Categorise Spaces	390
Removing Labels	392
Using Label Macros to Categorise Wiki Content	393
Viewing Labels and Labelled Content	394
Viewing Personal Labels	397
Working with Favourites	398
Working with Attachments	400
Using Drag-and-Drop in Confluence	401
Attaching Files to a Page	403

Attachment Versions	404
Deleting an Attachment	405
Displaying a List of Attachments	406
Downloading Attachments	409
Editing Attachment Properties	410
Embedding Multimedia Content	410
Embedding PowerPoint Presentations in a Page	413
Moving an Attachment	415
Viewing Attachment Details	415
Customising Confluence	417
Personal Customisations	417
User Profile Overview	418
Changing Password	419
Editing User Settings	419
Editing Your User Profile	422
Email Address Privacy	423
Updating Email Address	423
Choosing a Profile Picture	424
Viewing User Profile	426
Viewing and Revoking OAuth Access Tokens	427
Choosing your Home Page	429
Customising your Personal Dashboard	429
Customising the Look and Feel of a Confluence Space	431
Applying a Theme to a Space	431
Configuring the Documentation Theme	433
Configuring a Sidebar	442
Changing a Space's Logo	443
Changing the Confluence Browser Icon, aka favicon	444
Customising Space Layouts	445
Editing a Space's Colour Scheme	446
Styling Confluence with CSS	448
Basic Styling Tutorial	451
Styling Fonts in Confluence	453
Requesting Add-ons	454
Giving People Access to Content	456
Page Restrictions	457
Inaccessible Page	461
Setting a Page's Restrictions	461
Viewing a Page's Restrictions	462
Viewing Restricted Pages	463
Site Administrators and their Permissions	464
Contacting Confluence Administrators	464
Space Administrators and their Permissions	465
Space Permissions Overview	466
Assigning Space Permissions	467
Users and Groups	471
Searching for Users	471
Using Confluence on a Mobile Device	474
Notes about Confluence Mobile	478
Advanced and Special Uses of Confluence	479
Working with Confluence Markup	480
Confluence Storage Format	480

Confluence Storage Format for Macros	504
Confluence Storage Format Examples for Chart Macro	576
Confluence Wiki Markup	594
Confluence Wiki Markup for Macros	603
Wiki Markup Examples for Chart Macro	667
Working with Confluence Gadgets	673
Adding a Confluence Gadget to a JIRA Dashboard	674
Configuring Confluence Gadgets for Use in Other Applications	679
Confluence Gadgets	682
Activity Stream Gadget	683
Confluence News Gadget	685
Confluence Page Gadget	686
Confluence Quicknav Gadget	689
Adding JIRA Gadgets to a Confluence Page	690
Developing Technical Documentation on Confluence Wiki	690
Creating your Technical Documentation Space	691
Using Templates in Technical Documentation	698
Re-using Content in Technical Documentation	700
Managing the Life Cycle of your Technical Documentation	705
Providing PDF Versions of your Technical Documentation	711
Exporting and Printing Technical Documentation	718
Essential Confluence Features for Technical Documentation	722
Confluence Add-ons for Technical Documentation	731
Further Reading about Developing Technical Documentation on Confluence	738
Developing a Knowledge Base on Confluence Wiki	738
Creating Your Knowledge Base Space	739
Using Templates and Formatting Macros in a Knowledge Base	754
Proactive Communications in a Knowledge Base	756
Additional Add-ons for a Knowledge Base	756
Developing an Intranet on Confluence Wiki	757

Confluence User's Guide

About this document

The Confluence user's guide begins with an overview of the key features of [Confluence](#), and goes on to describe the use of Confluence as a knowledge management tool and a collaborative environment. If you still have a question that has not been answered, [please ask us](#).

This guide assumes that your Confluence site uses the default theme. If your site's theme has been customised, then your site may look different and the menu items may appear in different locations from those in this guide.

Would you like a full list of the pages in this guide? Here it is: [Table of Contents for Confluence User's Guide](#).

Downloads



You can [download the Confluence documentation](#) in PDF, HTML and XML formats.

More resources

Visit the [Confluence Administrator's Guide](#) for information on how to administer and configure your Confluence site, or go to the [Confluence Documentation Home](#) for a list of further resources.

In this guide

[Getting Started with Confluence](#)

[Creating Content](#)

[Sharing Content](#)

[Managing Changes and Notifications and Tasks](#)

[Finding Content](#)

[Organising Content](#)

[Customising Confluence](#)

[Giving People Access to Content](#)

[Using Confluence on a Mobile Device](#)

[Advanced and Special Uses of Confluence](#)

Getting Started with Confluence

Getting to know Confluence

[The dashboard](#)
[Page layout](#)
[Spaces in Confluence](#)
[Other users](#)

Personalising Confluence
Changing your password Updating your user profile Creating your personal space Choosing the home page you see when you log in Customising the dashboard for yourself Getting notifications about changes

Things to do
Creating Content Adding a space

More helpful things
Keyboard shortcuts Confluence glossary About Confluence

Take me back to the [Confluence User's Guide](#).

About Confluence

Confluence is a wiki. You can use it to collaborate on writing and sharing content with your team. Your team can be as small or as big as you like. It could encompass the whole world. Your content can be as simple or as rich as you like. It can be just words, or you can add images, diagrams, activity streams, web service integration and more

In a nutshell, a wiki is a piece of software that runs on a server. It publishes web pages that you can read via a web browser such as Mozilla Firefox, Google Chrome or Microsoft Internet Explorer. The thing that makes wiki pages different from other web pages is the **edit button**. Provided that you have the right permissions, you can edit the page, save your changes, and the updates will be visible to other people immediately.

Confluence provides extra functionality that transforms it into a social collaboration platform:

- Add a [space](#) for your team, then add a [page](#) or [comment](#) on someone else's page.
- Share content by writing a [blog post](#), [sharing a link](#) or calling someone's attention to a page via [@mentions](#). Form a [social network](#) and tell people what you are doing via a [status update](#).
- Add [images](#), [picture galleries](#), [videos](#) and [more](#).

Related pages:

- [Getting Started with Confluence](#)
- [Confluence User's Guide](#)

Dashboard

The dashboard is the front page of a Confluence site. It provides an overview of the site, gives access to the spaces that you have permission to view, and displays a few different lists of the most recently updated content.

You can go to the dashboard from anywhere in your site by choosing the **site logo** at the top left of the page. This might be the Confluence logo, or may be a customised logo set by your Confluence Administrator.

Overview of the dashboard

The dashboard is divided into these sections:

- **Welcome message:** The information that appears in the top left section of the dashboard. Confluence Administrators can [customise this message](#).
- **Get started:** A quick-start guide for administrators. This section of the dashboard is visible to Confluence administrators and system administrators only. It is not configurable via the web interface, but you can update or remove it by [editing the site layout](#).
- **Spaces, Pages, Network:** Tabs displaying your [favourite](#) content and people, displayed in the lower left section of the dashboard.
 - **Spaces** displays the [spaces](#) you have marked as favourites, followed by all the spaces that you have permission to view.
 - **Pages** displays the [pages](#) you have marked as favourites.
 - **Network** displays the [users](#) that you are following (or who are following you).
- **Recent activity:** Tabs on the right-hand side of the dashboard, displaying recently-updated content:
 - **Popular** displays content that has been recently created, liked or commented on. See [below](#) for more details.
 - **All Updates** displays updates from all spaces that you have permission to view.
 - **Favourite Spaces** displays updates from your [favourite](#) spaces.
 - **Network** displays updates made by the [users](#) that you are following (or who are following you).
 - **Space Categories** displays updates from spaces in the [category](#) you have selected from the list.

On this page:

- [Overview of the dashboard](#)
- [More about popular content](#)
- [Notes](#)

Related pages:

- [Confluence Glossary](#)
- [Working with Spaces](#)
- [Confluence User's Guide](#)

Screenshot: The dashboard

The screenshot shows the Confluence 5.0 Dashboard. At the top, there's a 'Dashboard' header with a 'Create Space' button. Below the header, there's a 'Welcome to Confluence' message. The main content area is divided into two columns. The left column contains 'Get started' links: 'Create a new space', 'Invite your colleagues', and 'Upload your picture'. Below these are 'Favourite Spaces' (Confluence Development, Documentation Sandbox, Sarah Maddox) and 'Site Spaces' (35sdfgikj34t, Angry Nerds). The right column shows a list of updates under the 'Popular' tab, including 'Rollin' in Confluence 5.0', 'Meeting Notes 2013-02-11', 'Re: Git branches for 5.0.1 Bugfixing', 'Git branches for 5.0.1 Bugfixing', 'Team Black - Confluence 5.1', and another 'Re: Git branches for 5.0.1 Bugfixing' entry. Each update includes a user profile picture, the title, the user's name, and the time ago.

More about popular content

The 'Popular' tab on the dashboard displays recent activity of the following types:

- Pages, blog posts and comments that people have recently **liked**.
- Pages and blog posts that people have recently **commented** on, and threaded comments that people have recently replied to.
- Pages and blog posts that have recently been **created**.

'Recent' means any activity in the last seven days.

A **bold** link means that you have not yet visited the page.

The activities are listed in order of popularity, with the most popular at the top. Likes, comments and content creations are scored equally. Activity that involves people in your network ranks higher than activity not involving your network. The most recent activity ranks higher than earlier activity.

Notes


- If you have the right permission, you can [add a new space](#) from the dashboard. Choose **Create Space** at the top right of the dashboard, or on the 'Spaces' tab.
- By default, the dashboard is the home page for the Confluence site. However, you can set any other page in Confluence as your home page via your [user profile](#) settings.
- Administrators can [customise the global dashboard](#) that all users see.
- Users can [customise the dashboard](#) for themselves.
- Are you looking for a way to build an [RSS feed](#)? Choose **Help > Feed Builder**.
- Are you looking for a list of the [people](#) in your site? Choose **People** on the header.

Page in View Mode

The images below show the menus and other controls on a typical Confluence page using the default theme. The sidebar is on the left of each page. On the right is the body of the page.

Related pages:

- [Creating Content](#)
- [Using the Editor](#)
- [Overview of Spaces](#)
- [Sharing Content](#)
- [Confluence User's Guide](#)



Section or option	Explanation
Sidebar	The sidebar helps you to see where you are in the space, and helps you to find pages and other content in the space. The sidebar contains shortcut links to important pages in your space. Space administrators can access options to configure the sidebar and other parts of the space. At the bottom of the sidebar is a contextual navigation section, which adapts depending on the page or blog post that you are viewing. See Finding Content .
Application Navigator	The application navigator gives you quick and easy access to applications that are linked to your site, for example JIRA. Confluence Administrators can add links to the application navigator, for example external websites.
Dashboard	Choose the site logo to access to the Confluence dashboard. By default, the dashboard is the home page of your Confluence site.
Spaces	Choose this option to see the space directory, containing a list of all the spaces that you have permission to view.
People	Choose this option to see the people directory, showing all the users of your Confluence site.

Create	Create pages, blog posts, and other content types in Confluence.
Search	Type text into this box to see a list of matching pages. Select a page to go directly to it, or press Enter to use the full Confluence search. See Searching Confluence .
Help	Go to the documentation for help and support, view a list of keyboard shortcuts, or access other help options from this menu.
Administration	The cog icon gives access to the site administration menu. If you are a Confluence administrator or a system administrator, you can access user and add-on management, and other site administration options here. (Note that the space administration options are in the sidebar, not in the administration menu.)
Workbox	View and respond to notifications collected from Confluence page watches, shares and mentions. Manage your personal tasks. See Managing Notifications in Confluence and Managing Tasks in Confluence .
User	After you have logged in, your profile picture will appear at top right of the page. When you choose your profile picture, the user menu drops down with options to log out, access your user profile, or view your editing history, personal labels and page watches. You can also retrieve drafts of pages you are editing.
Tools	Perform miscellaneous actions relating to the page.
Like	Let people know that you like this page.
Edit	Edit the current page. (Shortcut: press e on your keyboard.)
Share	Email a link to the current page to another Confluence user or email address.
Labels	View and edit labels (tags) attached to the current page. (Shortcut: press l on your keyboard.)
Add a comment	Click in the text box to begin writing a comment. (Shortcut: press m on your keyboard.)
Title and breadcrumbs	The title is the page name. The breadcrumbs show the position of the page in relation to its parent pages in the space.
Byline	Shows the original author and the most recent editor of the page, and the date of the most recent edit.

Byline icons

A small padlock indicates page restrictions. A paperclip indicates that the page has attachments. Both icons are clickable, leading to the 'Page Information' and 'Attachments' pages, respectively.

Confluence Glossary

Administration Console

The Administration Console is the interface for the global administration of Confluence.

Only [administrators](#) can access the Administration Console.

Administrators

The Confluence permission scheme allows the following main levels of administrator permissions:

- System Administrator – full administrative access to Confluence.
- Confluence Administrator – access to most of the Confluence administrative functions, but excluding those which could compromise the security of the Confluence system.

Please refer to the [overview of global permissions](#) for details of the functions which each level of administrator can perform.

CamelCase

CamelCase is a form of markup commonly used in wikis where words compounded together LikeThis without spaces are used to create links.

In Confluence, Camelcasing can be turned on from the Administration Console.

Change Comment

A change comment is a short description entered during the edit of a page to record the changes being made in the edit.

Child Pages

Creating child pages is a means of hierarchically organising content in Confluence. A child page can only have one parent page.

Comments

A comment may be a remark, question, or any other additional information you wish to add to a page pertaining to the topic the page covers. You can comment on any page or news item in Confluence.

Confluence Administrators

The Confluence permission scheme allows the following main levels of administrator permissions:

- System Administrator – full administrative access to Confluence.
- Confluence Administrator – access to most of the Confluence administrative functions, but excluding those which could compromise the security of the Confluence system.

Please refer to the [overview of global permissions](#) for details of the functions which each level of administrator can perform.

Custom Decorators

Decorator files are used to define layouts in Confluence. They are vmd files and require knowledge of the language, [Velocity](#), to edit.

Dashboard

The dashboard is the front page of a Confluence site. It provides an overview of the site, access to all spaces, and displays a list of the most recently updated content within them.

Form Field Markup

Form field markup is a specialised markup used when creating page templates in Confluence 4.2 and earlier. It is no longer needed, because the template editor offers form fields as an option in the editor toolbar.

Global Administrators

A global administrator is the same as a [system administrator](#).

Global Spaces

Known as Site Spaces, these spaces contain content on any theme or topic of your choice.

For more information about *site spaces* and *personal spaces*, see [Working with Spaces](#).

Hover Profile

The hover profile is the pop-up you see when the mouse pointer pauses over a Confluence user's name. Use the hover profile to follow the user, visit their profile, and more.

JIRA

JIRA is Atlassian's award winning Issue tracking and project management application.

Visit Atlassian's website to learn [more about JIRA](#).

Labels

Labels are user-defined tag words assigned to pages to categorise content in Confluence.

Macros

A macro is a command wrapped inside curly braces {...} used to perform programmatic functions and generate more complex content structures in Confluence.

Blog Posts

A blog post may be a journal entry, status report or any other timely information pertaining to a space.

Notifications

A notification is an email message sent to you updating you of changes to pages and spaces you choose to 'watch'.

Orphaned Pages

An orphaned page is a page without any incoming links.

Pages

Pages are the primary means of storing information in Confluence and are the building blocks of spaces.

Parent Page

A parent page is a page that has one or more child pages. It may itself be a child of another page.

People Directory

The [People Directory](#) contains a list of all users in your Confluence site. Each user's name links to their [personal space](#).

Permalink

A permalink is the url used to link to specific content items like comments.

Personal Spaces

Personal spaces belong to particular users, and rather than being listed on the [Dashboard](#), are available from the [People Directory](#).

For more information about *global spaces* and *personal spaces*, see [Working with Spaces](#).

RSS Feeds

An RSS feed is a format for delivering summaries of regularly changing web content. RSS is read by RSS newsreader programs.

You will need an RSS reader to subscribe to feeds within Confluence.

Confluence acts as an RSS reader for feeds from sites outside of Confluence.

RSS Reader

An RSS reader is a specialised RSS program (also called aggregator) that displays the contents of RSS feeds for you. To subscribe to RSS feeds within Confluence, you will need an RSS reader.

Site Administrators

The Confluence permission scheme allows two levels of administrator permissions:

- System Administrator – full administrative access to Confluence.
- Confluence Administrator – access to most of the Confluence administrative functions, but excluding those which could compromise the security of the Confluence system.

Please refer to the [overview of global permissions](#) for details of the functions which each level of administrator can perform.

Site Spaces

Site spaces contain content on any theme or topic of your choice. Previously known as global spaces.

For more information about site spaces and personal spaces, see [Working with Spaces](#).

System Administrators

The Confluence permission scheme allows two levels of administrator permissions:

- System Administrator – full administrative access to Confluence.
- Confluence Administrator – access to most of the Confluence administrative functions, but excluding

those which could compromise the security of the Confluence system.

Please refer to the [overview of global permissions](#) for details of the functions which each level of administrator can perform.

Space Administrators

A space administrator is a user with the 'Space Admin' permission for the space. A user with this permission can perform a host of functions relating to the management of a space and has complete access to the space regardless of any other control settings or permissions.

Permissions for a space are only assigned and modified by space administrators.

Spaces

A space is an area within Confluence, containing your pages, blog posts and other content. You can think of each space as a sub-site, or mini-site, each with its own home page.

There are two types of spaces: site spaces and personal spaces - see [Working with Spaces](#).

Templates

A template is a pre-defined page that can be used as a prototype when creating pages. Templates are useful for giving pages a common style or format.

Themes

Themes are pre-defined 'look and feel' styles which are configured from the administration menu and can be applied across Confluence or to a single space.

Thumbnails

As of Confluence 4.0, all images on the page that aren't links are displayed as thumbnails: when you click on an image the full-size image is displayed in a pop-up.

Tiny links

A tiny link is the shortened url of a page which is useful when sending links to the page, for example, via email.

Trackback

Trackback is a mechanism by which two sites can stay informed each time one site refers to the other by means of trackback 'pings'.

In Confluence, Trackback is enabled from the Administration Console.

Trackback Autodiscovery

Trackback autodiscovery is a block of code that can be placed in a web-page to describe where trackback pings should be sent for that page. You can read the [technical specification for autodiscovery here](#).

When Trackback is enabled, Confluence uses Trackback Autodiscovery to ping pages that are linked to, and to advertise its own pages as being able to receive pings.

Undefined Links

An undefined link is a link to a page that has not yet been created. Clicking on the page link allows you create the page.

User Profile

Every user account in Confluence is linked to a profile that contains user related information and options to configuring user preferences.

Watching a Page or Blog Post

When you watch a page, you are sent an email notification whenever that page has been modified.

Watching a Space

When you watch a space, you are sent an email notification whenever content has been added or modified in that space.

Wiki

Pioneered by Ward Cunningham, and named after the Hawaiian word for 'quick', a wiki is a website that makes it easy for anyone to contribute pages, and link them together.

Wiki Markup

This is the markup used to write and edit page templates in Confluence.

Related Topics

Take me back to [Confluence User's Guide](#)

Keyboard Shortcuts

Confluence provides a number of keyboard shortcuts that you can use to speed up your editing and viewing. This page describes the keyboard shortcuts for the English language. The shortcut keys (letters of the alphabet) may be different in other languages.

Confluence can display a list of available keyboard shortcuts. There are a few ways to see this keyboard shortcuts dialog:

- Choose the help icon  at top right of the screen, then choose **Keyboard Shortcuts**.
- When viewing a page, press Shift+?
- In the editor, choose the question mark icon on the editor toolbar.

The keyboard shortcuts dialog shows the following information:

- **General** – global, page and blog post shortcuts.
- **Editor** – text editing and formatting shortcuts.
- **Editor Autoformatting** – wiki markup and autoformatting shortcuts.

On this page:

- [Keyboard shortcuts](#)
 - [All screens](#)
 - [Editor](#)
 - [Tables in the editor](#)
 - [Autocomplete in the editor](#)
 - [View screen](#)
 - [Workbox](#)
- [Disabling and re-enabling keyboard shortcuts](#)
- [Notes](#)

Related pages:

- [Using Autocomplete](#)
- [Confluence User's Guide](#)

Keyboard shortcuts

The first section below describes the keyboard shortcuts that are available on all Confluence screens. Subsequent sections describe the shortcuts specific to each type of screen.

Note: If you are using Safari on OS X, please substitute 'Control' for 'Cmd' in the shortcuts below.

All screens

Windows	Action	Mac OS X
/	Enable the quick search	/
Ctrl+s	• Submit (where a form is active). • Editor -- save the Confluence page. • Outside the editor -- save the browser page.	Cmd+s
g then d	Go to the dashboard	g then d
g then s	Browse the current space	g then s
?	Open the Keyboard Shortcut help	?
[	Toggle the sidebar (left-hand navigation panel) when the space is using the default Confluence theme or the Documentation theme .	[

Editor

Windows	Action	Mac OS X
Ctrl+0	Apply the paragraph style.	Cmd+0

Ctrl+(1–6)	Apply a heading level (of the number chosen) to the current line.	Cmd+(1–6)
Ctrl+7	Apply the preformatted style.	Cmd+7
Ctrl+8	Apply the block quote style.	Cmd+8
Ctrl+Shift+a	Open the Macro Browser.	Cmd+Shift+a
Ctrl+B	Make the selected text bold .	Cmd+b
Ctrl+Shift+b	Format text as a bulleted list.	Cmd+Shift+b
Ctrl+Shift+d	Insert wiki markup. (Opens the Wiki Markup dialog.)	Cmd+Shift+d
Ctrl+Shift+e	Preview the page you are editing.	Cmd+Shift+e
Ctrl+i	Make the selected text <i>italic</i> .	Cmd+i
Ctrl+Shift+j	Insert a JIRA issue. (Opens the Insert JIRA Issue dialog.)	Cmd+Shift+j
Ctrl+k	Insert a link. (Opens the Insert Link dialog.)	Cmd+k
Ctrl+Shift+k	See a list of suggested pages or other locations to link to from your page. More about autocomplete...	Cmd+Shift+k
Ctrl+m	Insert an image. (Opens the Insert Image dialog.)	Cmd+m
Ctrl+Shift+m	See a list of suggested images, documents and other files to embed in your page. More about autocomplete...	Cmd+Shift+m
Ctrl+Shift+n	Format text as a numbered list.	Cmd+Shift+n
Ctrl+s	Save the page you are editing.	Cmd+s
Ctrl+Shift+s	Format text with a strike through.	Cmd+Shift+s
Ctrl+u	Make the selected text <u>underlined</u> .	Cmd+u
Ctrl+y	Revert an action that was undone.	Cmd+y
Ctrl+z	Undo the most recent action.	Cmd+z
Tab	Indent current line (only in bulleted lists and numbered lists).	Tab
Shift+Tab	'Outdent' current line (only in bulleted lists and numbered lists).	Shift+Tab
Shift+Enter	Force a line break without a paragraph break. This is a line break with no extra space.	Shift+Enter

[then]	Start a list of tasks. More about tasks...	[then]

Tables in the editor

Windows	Action	Mac OS X
Ctrl+Shift+c	Copy the current table row, or the selected rows.	Cmd+Shift+c
Ctrl+Shift+i	Insert a table. (Opens the Insert Table dialog.)	Cmd+Shift+i
Ctrl+Shift+v	Paste the table rows from your clipboard, placing them above the current row.	Cmd+Shift+v
Ctrl+Shift+x	Cut the current table row, or the selected rows.	Cmd+Shift+x
Alt+Up Arrow	Add a row above the current row.	Alt+Up Arrow
Alt+Down Arrow	Add a row below the current row.	Alt+Down Arrow

Autocomplete in the editor

Key	Action
[	See a list of suggested pages or other locations to link to from your page.
!	See a list of suggested images, multimedia files and documents to embed in your page.
{	See a list of suggestions as you begin typing a macro name.
@	See a list of suggested users to mention.

See more about using [autocomplete](#).

View screen

Windows	Action	Mac OS X
b	Create a blog post.	b
c	Create a child page of your current page.	c
e	Edit a page or blog post, or return to Edit mode when previewing.	e
k	Open the Link To dialog.	l
l	Add or edit labels.	l

m	Add a comment to a page or blog post.	m
s	Share the current page	s
t	View attachments.	t
v	Return to page view (only if you are viewing page attachments).	v
w	Add or edit watchers.	w

Workbox

Key	Action
g then n	Open the Confluence workbox.
j	Move down to the next entry in the notification list.
k	Move up to the previous entry in the notification list.
n	Move down to the next notification for a particular page or blog post.
p	Move up to the previous notification for a particular page or blog post.
Enter	Open the selected notification.
u	Return to the notification list after opening a particular notification.

Note: The above keyboard shortcuts are available for notifications only, not for tasks, inside the Confluence workbox.

See more about [managing notifications](#) and [tasks](#).

Disabling and re-enabling keyboard shortcuts

Keyboard shortcuts are enabled by default. You can disable general keyboard shortcuts for your personal editing sessions. This setting will not affect other Confluence users. You cannot disable the editor keyboard shortcuts.

To disable or re-enable general keyboard shortcuts:

1. Log in to Confluence.
2. Open the keyboard shortcuts dialog, by doing one of the following:
 - Choose the help icon  at top right of the screen, then choose **Keyboard Shortcuts**.
 - When viewing a page, press Shift+?
 - In the editor, choose the question mark icon on the editor toolbar.
3. Choose the **General** tab.
4. Select or clear the **Enable General Shortcuts** check box as required.

Notes

- **Note about supported web browsers:** Please ensure that you are using one of the web browsers supported by Confluence. If you are using an unsupported browser or browser version, some features

may not work correctly. You can find the list of supported web browsers and browser versions on this page: [Supported Platforms](#).

- The keyboard shortcuts dialog also displays the trigger characters for the Confluence autocomplete feature. See [Using Autocomplete](#).
- Confluence keyboard shortcuts are consistent with [JIRA keyboard shortcuts](#).

Creating Content

Do you want to add a page or a blog post? Just choose the **Create** option in the Confluence header. It looks like this:



Below is a description of this and other options for creating content, and some answers to questions you may have.

Do you want to update an existing page or blog post? Jump straight to the topic on [Using the Editor](#), or see [Working with Pages](#) for help with moving, renaming and organising content.

A note about permissions: To create a page, you need the 'Add Pages' permission for the space where you will add the page. To create a blog post, you need the 'Add Blog' permission for that space. A space administrator can give you these permissions. See [Giving People Access to Content](#).

Adding a page or a blog post

You can add pages and blog posts via the 'Create' dialog.

To create content via 'Create' in the header:

1. Choose **Create** in the Confluence header. The 'Create' dialog will open.
2. Select the **space** where you want to put your page or blog post. Confluence will offer a list of your recently-visited spaces.
Note: If the space you want is not in the list, please go to the space and try again. (In very large Confluence sites, Confluence cannot show all spaces in the selection list. By going to the space, you will ensure that it appears in the list.)
3. Choose the **type of content** you want to create.
You can create an empty page, a blog post, or a page based on a template.
4. Choose **Next**.
5. The Confluence editor will open. Add your content in the editor pane, or update the default content supplied by the template.
6. Choose **Save**.

Other ways to open the 'Create' dialog:


- Go to the parent page and choose **Create child page** in the sidebar. (This option is not available in the Documentation theme.)
- Shortcut key: Press **C** on your keyboard.

On this page:

- Adding a page or a blog post
- Location of the new page
- Using an undefined link to create a page later
- Other ways to create a page

Related pages:

- Using the Editor
- Creating Attractive and Dynamic Pages
- Adding a Template
- Finding Content
- Organising Content
- Confluence User's Guide

Screenshot: Creating content**Location of the new page**

When you create a new page, that page will be a child of another page, in the space that you selected in the 'Create' dialog. The parent page depends on where you are when you create the page.

Your location when creating the page	Location of new page
You are viewing a page in the same space where you will put the new page – that is, the space that you select in the 'Create' dialog.	A child of the page you are currently viewing.

You are viewing any other Confluence screen. For example:

- You are on the dashboard.
- You are on the 'Pages' view of a space.
- You are viewing a blog post.
- You are viewing a page in a space, and choose to add your new page in a different space.

A child of the home page in the space you select in the 'Create' dialog.

The space sidebar in the default theme has useful links to your pages, blog posts, and other parts of the space. For more about the sidebar and the location of pages, see [Finding Content](#).

Using an undefined link to create a page later

You may want to insert a link pointing to a Confluence page that does not yet exist, but which you intend to create later. This type of link is called an [undefined link](#).

To add an undefined link for later creation of a page:

1. Edit the page in which the link should appear.
2. Type '[' to trigger autocomplete, and type the name of the undefined page. Alternatively, type the text first, then select the text and type '['.
3. Choose **Insert Link to Create Page**.

When you save the page, Confluence colours the undefined link red. When someone clicks the link, the new page opens in edit mode. That person can then enter the page name, add content and save the page, as usual.

Other ways to create a page

You can import content from other Confluence sites, other wikis, Microsoft Word, and HTML pages. See [Importing Content Into Confluence](#).

The Confluence APIs allow programmatic and scripted creation of pages. See our [developer documentation](#).

Using the Editor

The Confluence editor is the tool that you will use to create and edit Confluence pages, blog posts and comments. You can enter content as you would in a Word document, apply formatting, and embed other content and files into the page.

Looking for a quick start? See the [Quick Reference Guide for the Confluence Editor](#).

To begin an [editing session](#), choose **Edit** at the top of a page (or press E on the keyboard).

A note about permissions: To edit a page, you need the 'Add Pages' permission for the space. See [space permissions](#). Someone may also apply [page restrictions](#) that may prevent you from editing the page.

An editing session

You start an editing session whenever you:

- create a new [page or blog post](#), or add a [comment](#)
- edit an existing page, blog post or comment (by pressing 'E' on the keyboard, or choosing **Edit**).

While in an editing session, you can also:

- Name, or rename, a page or blog post. Note that [renaming](#) has effects that you should consider.
- Add a [comment](#) describing the changes you made.

- Choose whether or not people [watching](#) the page get notified of the change you made
- Add [labels](#) to the page.

Confluence automatically saves [drafts](#) of your page as you work. If another user begins editing the same page as you, Confluence will display a message, and will try to [merge the changes](#) when you save your page.

Click **Cancel** (at the bottom of the page) if you want to end the session without saving any changes.

The session ends when you click **Save**.

When you create a new page you can choose the location where the page should be saved. You can also [move a page](#) after it has been saved, to make it a [child page](#) of a different page, or to move it to another space.

To see changes between different versions of the page, look at the [history](#) of the page.

On this page:


- [An editing session](#)
- [The editor](#)
- [Toolbars](#)
- [Embedding content in the page](#)
- [Things to help you work faster](#)
 - [Autoformatting](#)
 - [Autocomplete](#)
 - [Autoconvert for pasted links](#)
 - [Drag-and-drop for external images and files](#)
 - [Drag-and-drop within the editor](#)
 - [Keyboard shortcuts](#)
- [Finding and replacing text](#)
- [Enabling and disabling autocomplete and autoformatting](#)

Related pages:

- [Quick Reference Guide for the Confluence Editor](#)
- [Page in View Mode](#)
- [Working with Tables](#)
- [Working with Page Layouts and Columns and Sections](#)
- [Displaying Images](#)
- [Linking to Images](#)
- [Linking to Attachments](#)
- [Using Symbols, Emoticons and Special Characters](#)
- [Confluence User's Guide](#)

The editor

Screenshot: The Confluence editor




Item	Explanation
Page title	Type the name of the page. This name is used in links to the page.
Page content	Add the words, images and other content that forms the content of the page.
Editor toolbar	Use these tools to format and colour content, create lists and tables, indent and align text, and insert other content into the page, such as symbols, links, images, multimedia files and macros. The toolbar also provides the find and replace option, and the help option.
Restrictions	Control who can view or edit the page. See Page Restrictions .
Attachments	View, and manage, the attached files on the page.
Labels	Add labels to a page, to categorise the page content.
Change comment	Type a comment that describes the changes you have made.
Notify watchers	Select this option to prompt Confluence to send an e mail notification of your changes to people who are watching the page.
Preview	See how your changes will appear, without saving the page.
Save	Save the changes you have made to the page. (Keyboard shortcut: Ctrl+S).
Cancel	End the editing session, without saving any changes.

Toolbars

From the toolbar you can:

- Apply paragraph styles and character formatting (such as bold, italics, superscript).
- Choose colour for text.
- Create numbered and bulleted lists.
- Set the indenting and alignment for text and images.
- Create [links](#) to other pages, attachments, anchors and external resources.
- Add [tables](#), and add, remove, cut and paste rows and columns, highlight cells, rows and columns, and merge and split cells.
- [Insert other content](#) into the page, such as images, multimedia, attachments, symbols and wiki markup.
- Use [macros](#) to add other types of content, such as a list of JIRA issues or a table of contents.
- Add [layouts and columns and sections](#) to your page.
- [Find and replace](#) content within the page that you are editing.

Screenshot: The editor toolbar



Embedding content in the page

Choose **Insert** on the editor toolbar to include any of the following types of content into your page:

- An [image](#).
- A link to another Confluence page or external URL, or a [link to an attachment or image](#).
- An [emoticon or symbol](#), or a horizontal line.
- A [macro](#). Choose either a specific macro, or **Other Macros**, from the **Insert** menu.

Things to help you work faster

Autoformatting

You can type [Confluence wiki markup](#) directly into the editor to have Confluence auto-format your text as you type. To learn more, choose **?** on the editor toolbar and choose the **Editor Autoformatting** tab. See also [See the Quick Reference Guide for the Confluence Editor](#).

Autocomplete

When editing a page or blog post, you can enter a trigger character to show a list of suggested links, media files or macros to add to your page. This feature is called 'autocomplete' and provides you with a fast editing solution if you prefer to use key strokes rather than pointing and clicking with the mouse.

Quick summary of autocomplete:

Type:	To see suggested:
[	pages and blog posts
!	multimedia files
{	macros
@	mentions

For details, see [Using Autocomplete](#).

Autoconvert for pasted links

When you paste URLs into Confluence, the editor will analyse what you are pasting and automatically convert it into something that will display well in Confluence. Examples include:

- YouTube videos
- JIRA issue queries
- Google Maps
- Confluence pages, blog posts, comments, user statuses, user profiles.
- Shared screenshot links from Skitch
- And more.

Drag-and-drop for external images and files

You can drag a file from a location outside Confluence, and drop it directly into the editor. For example, try it with images, video files, audio files, Office documents, and PDF files. The contents of the file will be embedded into the page or blog post. Please refer to the following pages for more information:

- [Using Drag-and-Drop in Confluence](#) – Using Confluence's drag-and-drop feature, including details about its requirements and configuration.
- [Displaying Images](#) – Embedding images onto a Confluence page or blog post.
- [Embedding Multimedia Content](#) – Embedding videos, audio files and other multimedia files onto a Confluence page or blog post.
- [Displaying Office Files in Confluence](#) – Embedding Office and PDF files onto a Confluence page or blog post.

Drag-and-drop within the editor

Working within the editor panel, you can drag an image or a macro from one location on the page and drop it into a different location on the page. Hover your cursor over the image or the macro placeholder. The cursor changes to a drag-and-drop icon  and you can click the image or macro and drag it to a new location.

If you want to abandon the drag-and-drop action, press Escape. The image/macro will return to its original position.

Note: For the drag-and-drop of images and macros in the editor, Confluence supports the following browsers: Chrome, Firefox, and Internet Explorer 9. (Drag and drop in the editor does not work in Internet Explorer 8.)

Keyboard shortcuts

To see the [keyboard shortcuts](#) available, choose **?** on the editor toolbar.

Finding and replacing text

Click the find / replace icon on the toolbar, or use the keyboard shortcut **Ctrl+F** (Windows) or **Cmd+F** (Mac OS).

Search matches are highlighted in yellow. You can step through the results one by one, replace the matching text strings one by one, or replace all matching strings at once. This find and replace feature works only within the current page.

Enabling and disabling autocomplete and autoformatting

You can enable or disable the editor's autocomplete and autoformatting functions, by editing the settings in your user profile.

In summary:

1. Choose **your profile picture** at top right of the screen, then choose **Settings**.
2. Choose **Editor** under 'Your Settings' in the left-hand panel.

For more details, see [Editing User Settings](#).

Quick Reference Guide for the Confluence Editor

This page is a quick-reference guide to using the Confluence editor. The aim is to give you enough information about the editor's features for you to experiment yourself, rather than describing every possible shortcut key, autocomplete feature or toolbar option.

This guide is for people who want to use the autocomplete, autoformatting and keyboard shortcuts provided by the editor. If you prefer to use the toolbar options, the editor itself should be mostly self-explanatory.

Introductory tips

1. **Jump in and start using the Confluence editor.** The editor toolbar contains the most important buttons you'll need for creating and editing content.

2. **Use the keyboard shortcuts.** For example, type these characters in the editor panel:

- Type `[` (angle bracket) to insert a link.
- Type `!` (exclamation mark) to insert an image or other media.
- Type `{` (curly bracket) to insert a macro.

These characters will trigger the autocomplete functionality, prompting you with a list of suggestions to

finish off the entry. For more shortcuts, click the help icon  on the editor toolbar.

3. **See how to undo the autocomplete and autoformatting actions.** To undo something that autocomplete or autoformatting has done, press **Ctrl+Z** (Windows) or **Cmd+Z** (Mac).

On this page:

- [Introductory tips](#)
- [Seeing it in action](#)
- [Using the most common formats and features](#)
 - [Formatting text](#)
 - [Using symbols](#)
 - [Linking text](#)
 - [Using lists](#)
 - [Using tables](#)
 - [Using macros](#)
 - [Displaying images and multimedia](#)
- [Enabling and disabling autocomplete and autoformatting](#)

Related pages:

- [Using Autocomplete](#)
- [Using the Editor](#)
- [Confluence User's Guide](#)

Seeing it in action

This short video shows the autoformatting and autocomplete features of the editor.

[See the video on YouTube](#)

This video shows how to add macros, links and images by wiki markup alone. Type the macro, including its parameters and the closing curly bracket. Add a link, such as an anchor link, and end it with a square bracket. Insert an image or other embedded object, enclosed between exclamation marks. As soon as you close the macro, link, or embedded image, Confluence will convert it to rich text format and add it to the page.


[See the video on YouTube.](#)

Using the most common formats and features

Below is a list of the most commonly used editor features, and the related keyboard shortcuts.

Formatting text

Formatting text	What to do	Windows keyboard shortcuts (For Mac OS X, replace 'Ctrl' with 'Cmd')
Heading levels	Type the heading level and a full stop. Autoformat will convert the line to the appropriate heading immediately. You can continue typing your heading text immediately. Example: h2 .	Ctrl + 1 to 6
Bold text	Type an asterisk '*', your text, then another asterisk. Confluence autoformat will convert the text to bold immediately. Example: *Surf's Up*	Ctrl + b
<i>Italic text</i>	Type an underscore '_', your text, then another underscore. Confluence autoformatting will convert the text to italics immediately. Example: _Surf's Up_	Ctrl + i
<u>Underlined text</u>	Type a plus sign '+', your text, then another plus sign '+'. Confluence autoformatting will convert the text to underlined immediately. Example: +Surf's Up+	Ctrl + u
Monospace text	Type two curly braces {}, your text, then another two curly braces {}. Confluence autoformat will convert the text to monospace immediately. Example: {{Surf's Up}}	{{

Left, centre and right alignment	Click the left, centre and right alignment buttons on the editor toolbar:  i This can also be used to align images independently of text.	None
Indentation	Click the left and right indentation buttons on the editor toolbar: 	Tab (<i>right</i>), Shift + Tab (<i>left</i>)
Line break	Press Shift + Enter to force a line break without a paragraph break. This is a line break with no extra space.	Shift + Enter
Quotation	Use the <i>Quote</i> style – select 'Quote' from the style dropdown menu or use the keyboard shortcut. Example: 	Ctrl + 8
Colour	Click the colour options on the editor toolbar. Example: 	None

Using symbols


Adding symbols and emoticons	What to type	Keyboard shortcut (Windows)
Tick or check mark	Type a forward slash in round brackets. Autocomplete will convert it as you type. Example: (/)	(+ / +)
Smiley	Type the globally-recognised markup for a smiley face (colon and round bracket), a wink (semicolon and round bracket), and so on. Autocomplete will convert it as you type. Example: :)	: +)

Linking text

Linking text	What to type	Keyboard shortcut (Windows)

Linking to a Confluence page

Type a square bracket '[' and start typing the page name to see the suggested pages to link to. Press the arrow keys to select the page you want. Example:




Alternatively, use **wiki markup entirely**. Type the link, including the alias and the page name or URL. As soon as you type the closing square bracket, Confluence will convert the link to rich text format and add it to the page. This means that you can skip the link browser.

- This works if you have 'Autoformatting' enabled in the editor settings in your user profile.
- This does not work if you paste the wiki markup onto the page. You need to enter the closing bracket manually.
- Example: [Modern Girl|Modern Girl song lyrics]

Linking text to a web page

Type a square bracket '[' and select **Insert Web Link**, then paste the URL into the link dialog. Example:




Alternatively, use **wiki markup** **entirely**. Type the link, including the alias and the URL. As soon as you type the closing square bracket, Confluence will convert the link to rich text format and add it to the page. This means that you can skip the link browser.

- This works if you have 'Autoformatting' enabled in the editor settings in your user profile.
- This does not work if you paste the wiki markup onto the page. You need to enter the closing bracket manually.
- Example: [Modern Girl|http://www.example.com/song]

Linking to a page that does not yet exist

Type a square bracket '[' and the name of the non-existent page, then select '**Insert Link to Create Page**'. Example:




Alternatively, use **wiki markup entirely**. Type the link, including the alias and the page name or URL. As soon as you type the closing square bracket, Confluence will convert the link to rich text format and add it to the page. This means that you can skip the link browser.

- This works if you have 'Autoformatting' enabled in the editor settings in your user profile.
- This does not work if you paste the wiki markup onto the page. You need to enter the closing bracket manually.
- Example: [Future of the Modern Girl]

Linking to an attachment

Type a square bracket '[' and start typing the attachment name to see the suggested attachments to link to. Press the arrow keys to select the item you want. Example:

[chocs



Alternatively, use **wiki markup entirely**. Type the link, including the alias (if required), the caret character ^ and the attachment name. As soon as you type the closing square bracket, Confluence will convert the link to rich text format and add it to the page. This means that you can skip the link browser.

- This works if you have 'Autoformatting' enabled in the editor settings in your user profile.
- This does not work if you paste the wiki markup onto the page. You need to enter the closing bracket manually.
- Example: [^attachment name]

Linking to an anchor	To create the anchor: Add an anchor macro using wiki markup. Confluence will convert the macro to rich text format and add it to the page. For example, to create an anchor named 'index', type the following: {anchor : index} To create the link: Use wiki markup too. Type the link, including the alias (if required), the hash character # and the anchor name. As soon as you type the closing square bracket, Confluence will convert the link to rich text format and add it to the page. This means that you can skip the link browser. • This works if you have 'Autoformatting' enabled in the editor settings in your user profile. • This does not work if you paste the wiki markup onto the page. You need to enter the closing bracket manually. • Example: [Index #index]	[

Using lists

Using lists	What to type	Keyboard shortcut (Windows)
Adding a bullet list	Type an asterisk '*' followed by a space. Autoformat will convert the line to a bulleted list. You can continue typing your text immediately. Example: My list: • bullet item i To add another line of text to an entry without creating a new list item, press Shift + Enter at the end of the line.	Ctrl + Shift + b


Adding a numbered list	Type a hash or pound '#' followed by a space. Autoformat will convert the line to a numbered list. You can continue typing your text immediately. Example: My list: 1. bullet item  To add another line of text to an entry without creating a new list item, press Shift + Enter at the end of the line.	Ctrl + Shift + n

Using tables

Using tables	What to type	Keyboard shortcut (Windows)
Adding a table	Type a series of pipe characters ' ' then press Enter. Autoformat will convert the pipes to a table. Example – to create a table with three columns:	None


Using macros



Adding macros	What to type	Keyboard shortcut (Windows)

Adding a macro to your page.	Type '{' and start typing the macro name to see a list of macros that match your text. Press the arrow keys to select the macro you want. Example:  Alternatively, use wiki markup entirely. Type the macro, including its parameters and the closing curly bracket. As soon as you close the macro, Confluence will convert it to rich text format and add it to the page. This means that you can skip the macro browser. • This works if you have 'Autoformatting' enabled in the editor settings in your user profile. • This does not work if you paste the wiki markup onto the page. You need to enter the closing bracket manually. • Example: {blogposts:content=titles author=jsmith} • For details of wiki markup syntax, see Confluence Wiki Markup for Macros.	}

Displaying images and multimedia

Displaying images	What to type	Keyboard shortcut (Windows)

Display an image attached to the page	Type an exclamation mark '!' and start typing the image name to see the suggested images to insert onto the page. Press the arrow keys to select the item you want. Example:  Alternatively, use wiki markup entirely. Type the wiki markup for the image insertion, including the exclamation marks, the space and/or page name (if different from the current page) and the image name, as well as any other allowed parameters. As soon as you type the closing exclamation mark, Confluence will convert the image to rich text format and add it to the page. This means that you can skip the image browser. • This works if you have 'Autoformatting' enabled in the editor settings in your user profile. • This does not work if you paste the wiki markup onto the page. You need to enter the closing exclamation mark manually. • Example: <code>!NoMatterWhat.png align=right!</code>	!
Displaying an image attached to another page	<i>Exactly the same as when the image is attached to the same page.</i>	!
Embedding multimedia files	What to type	Keyboard shortcut (Windows)

Embedding a video, movie or audio file into a page	Type an exclamation mark '!' and select 'Insert Other Media'. Example:  Or type '{' and start typing the macro name 'Multimedia'. Example: 	!

Enabling and disabling autocomplete and autoformatting

You can enable or disable the editor's autocomplete and autoformatting functions, by editing the settings in your user profile.

In summary:

1. Choose **your profile picture** at top right of the screen, then choose **Settings**.
2. Choose **Editor** under 'Your Settings' in the left-hand panel.

For more details, see [Editing User Settings](#).


Working with Text Effects

The Confluence editor supports most text effects available in standard text editing applications.

Applying paragraph styles

Choose a paragraph style from the editor toolbar, or click in the paragraph and use one of the [keyboard shortcuts](#) Ctrl+(0–8) .

Screenshot: Choosing paragraph styles from the editor toolbar



On this page:

- [Applying paragraph styles](#)
- [Applying character formats](#)
- [Applying colours to text](#)
- [Aligning text](#)
- [Indenting text](#)

Related pages:

- [Using the Editor](#)
- [Keyboard Shortcuts](#)
- [Confluence User's Guide](#)

Applying character formats

To apply a character format, select the text and click one of the editor toolbar buttons, or use a [keyboard shortcut](#). Some formats are available from the 'More' menu.

Screenshot: Text formatting buttons on the editor toolbar



Format	Shortcut Key
Bold	Ctrl+B
<i>Italics</i>	Ctrl+I
<u>Underline</u>	Ctrl+U
~~Strikethrough~~	Ctrl+Shift+S
Sub ^{script}	none
Super ^{script}	none
Monospace	none

i Choose **Clear Formatting** from the 'More' menu to remove all formatting.

Applying colours to text

To apply a colour to text, select the text and click the 'Colour' button. Choose the colour using the 'More colours' button.


Screenshot: Picking colours from the editor toolbar



Aligning text

You can align text to the left, right or centre of a content block. Select the text and click the appropriate alignment option on the editor toolbar.


Screenshot: Left, centre and right alignment options on the editor toolbar



Indenting text

You can move text to the left or right by a predefined sequence of indentations. Confluence determines the size of the indentation. Select the text and click the left or right indentation option on the editor toolbar.

Screenshot: Left and right indentation options on the editor toolbar



Working with Links

By adding a link on a Confluence page, you can link to content anywhere within the Confluence site or on another web site.

You can add links to the following types of content:

- [Pages](#) in the same space, in another space, or outside Confluence (webpages).
- [Blog posts](#).
- [Pages that have not yet been created](#), but for which you require a placeholder on the current page.
- [Attachments](#), such as images and multimedia files.
- [User profiles or personal spaces](#).
- A section of a page, using an [anchor](#).


You can also [link from an image](#), or use a link to begin composing a [new email message](#).

You create all these kinds of links using the 'Insert Link' dialog that is available in the editor (click **Link** in the menu bar while editing the page). You can also create links using [autocomplete](#) as a shorthand way of creating the most common types of links.

Related pages:

- [Working with Anchors](#)
- [Trackback](#)
- [Linking to Confluence Pages from Outside Confluence](#)
- [Working with Attachments](#)
- [Confluence User's Guide](#)

You can edit and remove links while editing the page, using the link properties panel that appears when you click on a link in the editor:

**Notes**

- Links in Confluence will not break even when you rename pages or move them between spaces on your site. Confluence will rename the links, provided you have inserted them as relative links, not as full URLs.
- Looking for a link type not shown above? You might find a [plugin](#) can help you.

Linking to Pages

This page describes how to create a link in your Confluence page to another page.

You can create links on your page to:

- Other pages in the Confluence site.
- Web pages outside of Confluence.
- Anchors or headings, on the same page or other pages.

You can also create a link to a non-existent Confluence page.

You can use the following methods to create links:

- Autocomplete - to link to Confluence pages or a non-existent page.
- The 'Insert Link' dialog - to link to Confluence pages and web pages.
- Cutting and pasting a link from your browser - to link to Confluence pages and web pages.

Linking to Confluence pages**Adding a link using autocomplete**

You can use autocomplete to create a link to any page in the Confluence site, if you know the name of the page you want to link to.

You can type [to see a list of suggested links. For details, see [Using Autocomplete](#).

Adding a link using the Insert Link dialog**To create a new link using the 'Insert Link' dialog:**

1. While editing the page, place your cursor at the point where you want to create the link, or highlight the text that you want linked.
2. Click **Link** in the toolbar, or press **Ctrl+K**. See [keyboard shortcuts](#) for more information.
3. Choose one of the tabs on the left to help you find the page or other location that you want to link to:
 - **Search**— Use this option to link to a page or file in Confluence.

- Start typing the page name into the text box. Confluence will suggest options as you type.
 - If necessary, limit the search to the current space.
 - Select your link destination from the autocomplete results, or click **Search** and select the link destination from the search results.
 - **Recently Viewed**– Use this option to link to a page in Confluence.
 - Select your link destination from recently-visited pages.
4. Enter link text that will be displayed on the page, if required. If you have not highlighted text in the page, and leave the 'Link Text' text box empty, the link will display the destination page name or URL.
 5. Click **Insert**.

On this page:

- [Linking to Confluence pages](#)
 - [Adding a link using autocomplete](#)
 - [Adding a link using the Insert Link dialog](#)
 - [Copying and pasting a link from your web browser](#)
- [Linking to web pages](#)
- [Linking to an anchor](#)
- [Linking to a heading](#)
- [Linking to an undefined Confluence page](#)
- [Using a shortcut link](#)

Related pages:

- [Working with Links](#)
- [Working with Anchors](#)
- [Trackback](#)
- [Linking to Confluence Pages from Outside Confluence](#)
- [Confluence User's Guide](#)

Copying and pasting a link from your web browser**To paste a link from your web browser:**

1. In your web browser, select and copy the title of a Confluence page.
2. Edit your Confluence page and paste the title where you want the link to appear.

Linking to web pages

Use the 'Insert Link' dialog to link to an external web page.

To create a link to a web page:

1. While editing the page, place your cursor at the point where you want to create the link, or highlight the text that you want linked.
2. Click **Link** in the toolbar, or press **Ctrl+K**. See [keyboard shortcuts](#) for more information.
3. Click **Web Link** and enter or paste the web address into the **URL** text box.
4. Enter link text that will be displayed on the page if required. If you have not highlighted text in the page, and leave the 'Link Text' text box empty, the link will display the destination page name or URL.
5. Click **Insert**.

You can also simply copy and paste a link to a web page into your Confluence page, as described above.

Linking to an anchor

You can link to a specific location within a page, by marking that location with an [Anchor macro](#) and then linking to the anchor name.

You can link to an anchor from:

- A link on the same page as the anchor
- Another page in the same space
- A page in another space of the same Confluence site.
- Another web page or another Confluence site, using a specifically formatted URL.

To link to an anchor from within the same Confluence site:

1. Edit the page where you want to place the link.
2. Choose **Link** in the editor toolbar, or press **Ctrl+K**.
3. Choose **Advanced** and enter the anchor name into the **Link** box, noting the following:
 - The anchor name is case sensitive. You must use the same pattern of upper and lower case letters as you used when creating the Anchor macro.
 - Use the following syntax:

Anchor location	Link syntax for anchor	Examples
Same page	#anchorname	#bottom #important information
Different page	pagename#anchorname	My page#bottom My page#important information
Page in another space	spacekey:pagename#anchorname	DOCS:My page#bottom DOCS:My page#important information

4. Enter the **Link Text** (alias) that will be displayed on the page, if required. If you leave the 'Link Text' box empty, the link will display the destination page name or URL.
5. Choose **Insert**.

To link to an anchor from another web page or another Confluence site:

Use a full URL in the following format:

Link syntax	Examples
http://myconfluence.com/display/spacekey/pagename#pagename-anchorname	http://myconfluence.com/display/DOCS/My+page#My page-bottom http://myconfluence.com/display/DOCS/My+page#My page-importantinformation

Notes about the full URL:

- The page name is repeated in the URL, after the # sign. The second occurrence of the page name is concatenated into a single word, with all spaces removed.
- There is a single dash (hyphen) between the concatenated page name and the anchor name.
- The anchor name in the full URL is concatenated into a single word, with all spaces removed.
- The anchor name is case sensitive. You must use the same pattern of upper and lower case letters as you used when creating the Anchor macro.

Linking to a heading

You can link to a heading that is on the same page, on another page in the same space, or on a page in another

space of the same Confluence site.

To link to a heading:

1. Edit the page where you want to put the link.
2. Choose **Link** in the toolbar, or press **Ctrl+K**.
3. Choose **Advanced** and enter the heading into the **Link** box, noting the following:

- The headingname is case-sensitive and must be entered without spaces.
- Use the following syntax:

Heading location	Link syntax for heading
Same page	#headingname
Different page	pagename#headingname
Page in another space	spacekey:pagename#headingname

4. Enter link text that will be displayed on the page, if required. If you leave the **Link Text** box empty, the link will display the destination page name or URL.
5. Choose **Insert**.

Linking to an undefined Confluence page

You may want to insert a link pointing to a Confluence page that does not yet exist, but which you intend to create later. This type of link is called an [undefined link](#).

To add an undefined link for later creation of a page:

1. Edit the page in which the link should appear.
2. Type '[' to trigger autocomplete, and type the name of the undefined page. Alternatively, type the text first, then select the text and type '['.
3. Choose **Insert Link to Create Page**.

When you save the page, Confluence colours the undefined link red. When someone clicks the link, the new page opens in edit mode. That person can then enter the page name, add content and save the page, as usual.

Using a shortcut link

If you have [configured shortcut links](#) on your Confluence site, then you can link to an external site using a shortcut link that looks like this: CONF-17025@jira. Our Confluence site (where this documentation is housed) is configured to allow shortcut links to our JIRA site, using the shortcut @jira. So the shortcut link CONF-17025@jira produces [this link](#).

To add a shortcut link using the 'Insert Link' dialog:

1. Click **Link** in the toolbar, or press **Ctrl+K**. See [keyboard shortcuts](#) for more information.
2. Click **Advanced** and enter or paste the shortcut link into the **Link** box. Shortcut links are case-insensitive.
3. Enter link text that will be displayed on the page, if required. If you leave the **Link Text** box empty, the link will display the destination page name or URL.
4. Click **Insert**.

You can also type '[' and choose **Insert Web Link > Advanced** to enter a shortcut link.

See [Configuring Shortcut Links](#) for more details.

Linking to Images

This page describes how to insert a link on your Confluence page that points to an image. Linking to an image is a way to have text on a page that, when clicked, takes the user to that image.



Quick guide to linking to an image

1. Click **Link** on the editor toolbar.
2. Select one of these options:
 - **Search** – Search for and link to any image or file attached to any page in your Confluence site.
 - **Attachments** – Link to an image or file attached to the current Confluence page.

The rest of this page gives more details of the above procedure and additional options.

On this page:

- [Adding a Link with the Link Browser](#)
- [Adding a Link using Autocomplete](#)

Related pages:

- [Linking to Attachments](#)
- [Displaying Images](#)

Adding a Link with the Link Browser


To link to an image that is attached to the current page:

1. Edit the page where you want to insert the link.
2. Click **Link** on the toolbar.
3. Choose the **Attachments** tab in the left-hand panel. You will see a list of all files attached to the page.
Now you can:
 - Select an image that is already attached to the page.
 - Attach a new image to the page by clicking **Browse** and uploading your file.
4. Enter the **Link Text**. These are the words that will appear as the hyperlink on the page.
5. Click **Insert**.

To link to an image that is attached to any Confluence page:

1. Edit the page where you want to insert the link.
2. Click **Link** on the toolbar.
3. Select the **Search** option in the left-hand panel.
4. Start typing the name of the image. Confluence will suggest image files. If the image does not appear in the list, click **Search**.
5. Click the image name in the autocomplete results or the search results.
6. Click **Insert**.

Screenshot: The link browser, showing autocomplete in the 'Search' option



Adding a Link using Autocomplete

You can use the autocomplete functionality to link to an image attached to any Confluence page.

You can type [to see a list of suggested links. For details, see [Using Autocomplete](#).

Linking from an Image


This page describes how to create a link from an image on one page to another page or URL. When the user clicks the image, they will be redirected to the linked page or other resource.

To create a link from an image:

1. Display the image on the page. The image can either be attached to the page or available on another page. See [Displaying Images](#).
2. Create the link by clicking on the image and then clicking **Link** in the properties panel. Specify the link target using the 'Insert Link' dialog. See [Linking to Pages](#).

You can edit the link by clicking on the image, when editing the page, and clicking **Edit Link** in the properties panel.

Screenshot: The properties panel for an image



Related pages:

- [Working with Links](#)
- [Working with Attachments](#)
- [Displaying Images](#)
- [Confluence User's Guide](#)

Linking to Attachments

This page describes how to add a text link pointing to a file attached to your Confluence page. When a reader clicks the link, the file is displayed in the browser.

**Quick guide to linking to an attachment**

1. Click **Link** on the editor toolbar.
2. Select one of these options:
 - **Search** – to search for and link to any image or file attached to any page in your Confluence site.
 - **Recently Viewed** – to link to a recently visited page.
 - **Attachments** – to link to an image or file attached to the current Confluence page.
 - **Web Link** – to link to any webpage.

On this page:

- [Adding a Link using Autocomplete](#)
- [Adding a Link using the Link Browser](#)

Related pages:

- [Linking to Images](#)

Adding a Link using Autocomplete

You can use autocomplete to add a text link to a file or image attached to any Confluence page.

You can type **[** to see a list of suggested links. For details, see [Using Autocomplete](#).

Adding a Link using the Link Browser

The 'link browser' is the 'Insert Link' or 'Edit Link' dialog that appears when you click **Link** in the editor toolbar.

To link to a file or image that is attached to the current page:


1. Edit the page where you want to insert the link.
2. Click **Link** in the editor toolbar, and then the **Attachments** tab. You will see a list of all files attached to the page. Now you can do one of the following:
 - Click on the file that you want to link to, if it is already attached to the page.
 - Attach a new file to the page by clicking **Browse** and uploading your file.
3. Enter the **Link Text**. These are the words that will appear as the hyperlink on the page.
4. Click **Insert** to add the link.

To link to a file or image that is attached to any Confluence page:

1. Edit the page where you want to insert the link.
2. Click **Link** in the editor toolbar, and then the **Search** tab.
3. Start typing the name of the file or image. Confluence will offer a list of matching file names. If the file does not appear, click **Search** to find pages that contain the search text.
4. Click the required file in the list or the search results.
5. Enter the **Link Text**. These are the words that will appear as the hyperlink on the page.

- Click **Insert** to add the link.

Screenshot: The link browser, showing autocomplete in the 'Search' option



Linking to Blog Posts

You can link to blog posts in similar ways to how you [link to pages](#). Only two methods are described on this page.

You can also use the Blog Posts macro to display a [dynamic list of blog posts](#) on your page.

i You must create the blog post first

Linking to a blog post that has not been created yet will not result in a link. Blog posts are very tightly bound to the time at which they were created, so it makes no sense to link to them before they exist.

Linking to a Blog Post using Autocomplete

i You need to know the title of the blog post.

You can use autocomplete to create a link to any blog post in the Confluence site, if you know the name of the post you want to link to.

You can type `[` to see a list of suggested links. For details, see [Using Autocomplete](#).

Linking to a Blog Post using its URL

i You need to know the absolute path to the blog post.

To create a link to a blog post using the the 'Insert Link' dialog:

- While editing the page, place your cursor at the point where you want to create the link, or highlight the text that you want linked.
- Click **Link** in the toolbar, or press **Ctrl+K**. See [keyboard shortcuts](#) for more information.

3. Click **Web Link** and enter or paste the absolute path to the blog post into the **URL** text box.
4. Enter link text that will be displayed on the page if required. If you have not highlighted text in the page, and leave the 'Link Text' text box empty, the link will display the destination page name or URL.
5. Click **Insert**.

Related Topics

[Working with Blog Posts](#)

[Working with Links](#)

[Blog Posts Macro](#)

Take me back to [Confluence User's Guide](#)

Linking to Personal Spaces and User Profiles

This page describes how to add a link to a user's personal space or user profile from within another Confluence page.

You can link to a user's personal space (or user profile) easily if you know their username.

If the user does not have a personal space, then the link will go to their user profile.

Linking to a User's Personal Space using Autocompletion

You can use autocomplete to create a link to a user's personal space in the Confluence site. Trigger autocomplete and start typing their name.

You can type [to see a list of suggested links. For details, see [Using Autocomplete](#).

Linking to a User's Personal Space using the Insert Link Dialog

1. While editing the page, place your cursor at the point where you want to create the link, or highlight the text that you want linked.
2. Click **Link** in the toolbar, or press **Ctrl+K**. See [keyboard shortcuts](#) for more information.
3. Click the **Search** tab on the left.
4. Start typing the user's name into the search field. Confluence will suggest options as you type.
5. Select the user from the autocomplete results.
6. Enter link text that will be displayed on the page, if required. If you have not highlighted text in the page, and leave the 'Link Text' text box empty, the link will display the destination page name or URL.
7. Click **Insert**.

Related Topics

[User Profile Overview](#)

[Setting Up your Personal Space](#)

[Working with Links](#)

Take me back to [Confluence User's Guide](#)

Working with Anchors

You can link to a specific location within a page, by marking that location with an Anchor macro and then linking to the anchor name. Anchor links can be especially useful when navigating between sections of a long document, or when you want to link to a segment of a page instead of the top of the page.

Anchors are invisible to the reader when the page is displayed.

There are two steps to using an anchor:

1. Create the anchor on the page.
2. Create the link to the anchor.

Creating an anchor

Use the Anchor macro to mark the location you want to link to.

1. **Add the Anchor macro to a page.**
 - a. In the Confluence editor, choose **Insert > Other Macros**.
 - b. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

2. **Specify the name of your anchor.** For example, 'bottom' or 'important information'. See the 'Anchor Name' parameter described below.

On this page:

- [Creating an anchor](#)
- [Creating a link to an anchor](#)
- [Code examples](#)
- [Notes](#)

Related pages:

- [Working with Links](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Macro options (parameters)

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Anchor Name	None	This is the anchor name that you will use when creating the link. • The anchor name can include spaces. Confluence will remove the spaces automatically when building a URL that points to this anchor. • The anchor name is case sensitive. You must use the same pattern of upper and lower case letters when creating the link as you use when creating the Anchor macro.

Creating a link to an anchor

You can link to an anchor from:

- A link on the same page as the anchor

- Another page in the same space
- A page in another space of the same Confluence site.
- Another web page or another Confluence site, using a specifically formatted URL.

To link to an anchor from within the same Confluence site:

1. Edit the page where you want to place the link.
2. Choose **Link** in the editor toolbar, or press **Ctrl+K**.
3. Choose **Advanced** and enter the anchor name into the **Link** box, noting the following:
 - The anchor name is case sensitive. You must use the same pattern of upper and lower case letters as you used when creating the Anchor macro.
 - Use the following syntax:

Anchor location	Link syntax for anchor	Examples
Same page	#anchorname	#bottom #important information
Different page	pagename#anchorname	My page#bottom My page#important information
Page in another space	spacekey: pagename#anchorname	DOCS:My page#bottom DOCS:My page#important information

4. Enter the **Link Text** (alias) that will be displayed on the page, if required. If you leave the 'Link Text' box empty, the link will display the destination page name or URL.
5. Choose **Insert**.

To link to an anchor from another web page or another Confluence site:

Use a full URL in the following format:

Link syntax	Examples
<code>http://myconfluence.com/display/spacekey/pagename#pagename-anchorname</code>	<code>http://myconfluence.com/display/DOCS/My+page#My page-bottom</code> <code>http://myconfluence.com/display/DOCS/My+page#My page-importantinformation</code>

Notes about the full URL:

- The page name is repeated in the URL, after the # sign. The second occurrence of the page name is concatenated into a single word, with all spaces removed.
- There is a single dash (hyphen) between the concatenated page name and the anchor name.
- The anchor name in the full URL is concatenated into a single word, with all spaces removed.
- The anchor name is case sensitive. You must use the same pattern of upper and lower case letters as you used when creating the Anchor macro.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)

- [Confluence Storage Format for Macros](#)

Notes

- **Table of contents on page:** Consider using the [Table of Contents Macro](#) to generate a list of links pointing to the headings on the page. The list of links will appear on the page, and will be automatically updated each time someone changes the wording of a heading.
- **Linking to headings:** You can link directly to the headings of a page. See [Linking to Pages](#). However, if someone changes the wording of a heading, those direct links will be broken. Use the Anchor macro to ensure a lasting link within the body of a page.
- **Site welcome message:** If you are adding an anchor to a page that you are using in the site welcome message, you can only link to that anchor from another page. Internal links within that page will not work.
- **Templates:** When you are previewing a template, a link to an anchor is displayed as a 'broken' link. However, when you create a page using the template the resulting page will have the correct link.

Using a Link to Create a New Email Message

This page describes how to insert a link that, when clicked, launches the default email client.

 You can provide your own text to use as the link text instead of the 'mailto' tag.

To insert a link that creates a new email message:

1. Edit the page on which you want to insert the link.
2. Choose **Insert** > **Link** and select the **Web Link** tab.
3. Enter an email address, such as 'jsmith@non.existent.corp.com'.
4. Enter your own link text, if required.
5. Click **Save**.

Related Topics

[Working with Links](#)

Take me back to [Confluence User's Guide](#)

Linking to Confluence Pages from Outside Confluence

Sometimes you may want to link to a Confluence page from outside Confluence, such as from another website or from within an email. In this case, you should consider using a link to a 'permanent' URL (also called a 'permalink'), in case the name of the Confluence page changes.

 If you are linking to a page from another page in the same Confluence site, it is better to use an internal wiki link rather than a permalink. Confluence can keep track of internal links and will let you know if the link is broken, such as when someone removes the linked page. See [Linking to Pages](#). Internal wiki links are automatically updated if the page is renamed. This only works for page links that use the relative link syntax, for example [\[Renaming a Page\]](#).

To link to a page's permanent URL:

1. View the page that you want to link to.
2. Choose **Tools** > **Link to this Page**.
3. Copy the **Tiny Link** and paste it into your email or external web page. This will create a link to the latest version of your Confluence page.

Related Topics

[Linking to Pages](#)

[Working with Links](#)

Take me back to [Confluence User's Guide](#)

Inserting JIRA Issues

If your Confluence site is connected to a JIRA site using an application link, you can easily insert individual

issues from this JIRA site directly into text on your Confluence page using the 'Insert JIRA Issue' dialog. Each issue inserted onto the page is linked to the issue in JIRA itself.

Using the 'Insert JIRA Issue' dialog, you can also:

- Create a new issue on the JIRA site *and* insert the issue onto your page.
- Insert a table of JIRA issues onto your page based on the results of a search (using [JIRA Query Language \(JQL\) syntax](#)).

i If your Confluence site is not connected to any JIRA site via an application link, this feature will not be available. However, you can still list JIRA issues on a page or blog post using the [JIRA issues macro](#).

On this page:

- [Inserting a JIRA Issue from a List of Recently Viewed Issues](#)
- [Creating a New JIRA Issue and Inserting it](#)
- [Searching for JIRA Issues and Inserting them](#)
- [Notes](#)

Related pages:

- [JIRA Issues Macro](#)
- [Configuring Application Links](#) *Not applicable to Confluence OnDemand.*
- [Confluence User's Guide](#)

Quick guide to inserting JIRA issues

- Choose **Insert > JIRA Issue** from the editor toolbar.
 - To insert a single issue, use either:
 - **Recently Viewed** — Insert an issue onto your page from a list of issues you have recently viewed on the JIRA server.
 - **Create New Issue** — Create a new issue on the JIRA server and insert it into your page.
 - **Search** — Use JQL syntax to narrow down a list of issues, from which you can select one to insert onto a page.
 - To insert a table of issues:
 - Click **Search** on the 'Insert JIRA Issues' dialog, use JQL syntax to narrow down a list of issues and choose to insert the list onto a page.

i If Confluence is connected to more than one JIRA server, ensure that you choose the appropriate JIRA server before using this dialog to select, create or search for issues.

Inserting a JIRA Issue from a List of Recently Viewed Issues

To insert a JIRA issue onto a page from a list of recently viewed issues on a JIRA site:

1. Choose **Insert > JIRA Issue** from the editor toolbar.
2. Go to the **Recently Viewed** tab of the 'Insert JIRA Issue' dialog.
3. If necessary, select a JIRA server from the **Server** list. See the [notes below](#) regarding OAuth outgoing authentication.
4. Select an issue from your list of recently viewed JIRA issues on the JIRA site. The number of items in the list is defined in JIRA.

Creating a New JIRA Issue and Inserting it

i This feature works best with JIRA issue types whose mandatory field requirements have not been altered. With the exception of a JIRA issue's 'Component/s' or 'Fix Version/s' fields, you cannot use this dialog to add an issue whose issue type has customised mandatory field requirements upon issue creation.

To create a new JIRA issue on a JIRA site and insert this issue onto a page:

1. Go to the **Create New Issue** tab of the 'Insert JIRA Issue' dialog.
2. Complete the dialog:

Setting	Description
Server	The available JIRA servers. See the notes below regarding OAuth outgoing authentication.
Project	The project on the selected JIRA server to which the new issue will be added.
Issue Type	The type of issue to log in this project.
Summary	A one-line summary for the issue.
Component/s	Choose one or more components which apply to this issue.
Version/s	Choose one or more versions in which the issue will be addressed.
Description	A more detailed description about the issue.

 Some of these fields may not be visible if they have been customised in your JIRA project.

3. Click **Insert** to create the JIRA issue and insert it onto the page.

Searching for JIRA Issues and Inserting them

To search a JIRA site for a subset of issues matching a JQL query and insert one or more of these issues:

1. Choose **Insert > JIRA Issue** from the editor toolbar.
2. Go to the **Search** tab of the 'Insert JIRA Issue' dialog.
3. Enter a [JQL query](#).
4. If necessary, select the JIRA server whose issues you want to insert.
5. Click **Search** to find the issues on the JIRA server which match your JQL query. The first 20 issues retrieved by your JQL query are displayed.
 - To insert a single issue, select the issue from your list and click **Insert**.
 - To insert the full list of issues, select the **Insert all query results as a table** check box before clicking **Insert**.

Notes

The issues from a JIRA site which you can access in the 'Insert JIRA Issues' dialog depends on the application link's *outgoing authentication* used by Confluence to communicate with that JIRA site. While you can always access publicly visible issues:

- If 'Trusted Applications' outgoing authentication is used — you can also view issues restricted to an account on JIRA whose user name matches your user name in Confluence.
- If 'OAuth' outgoing authentication is used, you may need to click **Login & Approve** at this point to gain access to the JIRA server and restricted issues. You can also view issues restricted to the user account that you 'Login & Approve' (to the JIRA site) on the 'Insert JIRA Issues' dialog.
- If 'Basic Access' outgoing authentication is used — you can also view issues restricted to the user account configured for the JIRA site's 'outgoing authentication'.

Trackback

Trackback is a mechanism by which two sites can stay informed each time one site refers to the other by means of trackback 'pings'.

In Confluence, Trackback is enabled by a [site administrator](#) from the [Administration Console](#). When Trackback is enabled, any time you link to an external webpage that supports [Trackback Autodiscovery](#), Confluence will send a Trackback ping to that page to inform it that it has been linked to.

Confluence pages also support Trackback Autodiscovery, and when Trackback is enabled can receive trackback pings sent by other sites.

To see who has sent a Trackback ping to a Confluence page:

1. Go to the page.
2. Choose **Tools** > **Info** to go to the 'Information' view for the page.

Any Trackback pings the page has received will be listed under the page's **Incoming Links**



Confluence incoming trackback pings only work with referenced pages that are public (anonymously viewable)

See more information about the [Information View](#).

Related Topics

[Enabling Trackback](#)

[Managing External Referrers](#)

[Linking to Pages](#)

[Working with Links](#)

Take me back to [Confluence User's Guide](#)

Displaying Images

You can display an image on a Confluence page in the following cases:

- The image is attached to the page.
- The image is attached to another page of the same Confluence site, even if in another space.
- The image is on a remote web page.

Once the image is displayed on the page, you can:

- Move the image to a new position on the page simply by cutting and pasting.
- Change how the image appears on the page.
- [Link from an image](#) to another page.

Displaying an image attached to the page

There are several methods for [attaching image files to a page](#).

Once you have attached an image to a page, there are different methods for choosing where on the page the image should appear:

Using the 'Insert Image' dialog

Once an image is attached to the page, you can edit the page to choose where the image should appear.

On this page:

- [Displaying an image attached to the page](#)
- [Displaying an image attached to a different page](#)
- [Displaying an image from a remote web page](#)
- [Controlling the image appearance](#)
- [Setting other image attributes](#)
- [Displaying a gallery of images](#)
- [Image file formats](#)

Related pages:

- [Deleting an Image](#)
- [Linking from an Image](#)
- [Linking to Images](#)
- [Working with Attachments](#)
- [Choosing a Profile Picture](#)
- [Confluence User's Guide](#)

To position an attached image on the page:

1. While editing the page, position the cursor where you want to place the image.
2. Choose **Insert** > **Image** and choose the **Attached Images** tab.
3. Select the required image and choose **Insert** (or just double-click the image).

Using autocomplete

Once an image is attached to the page, you can use autocomplete while editing the page to choose where the image should appear.

To position an attached image on the page:

1. While editing the page, position the cursor where you want to place the image.
2. Trigger the autocomplete function by typing '!'.
3. Choose the image from the list that appears.

Using drag-and-drop

Depending on the browser you are using, you can attach and position an image in one step. While you are editing a page, simply [drag-and-drop](#) an image file on to the page. The image is attached to the page and is placed at the current cursor position.

Displaying an image attached to a different page

You can display an image that is attached to a different page of the same Confluence site, as long as you know the name of the image. This approach can make it easier to manage your images by allowing you to keep them all in the same place.

To display an image attached to a different page:

1. While editing the page, position the cursor where you want to place the image.
2. Choose **Insert** > **Image** and choose the **Search** tab.
3. Type in the name of the image.
4. Choose whether to search the current space or **All Spaces** and choose **Search**.
5. Select the required image from the search results and choose **Insert**.

Alternatively, you can simply cut and paste the image from another page.

Displaying an image from a remote web page

You can display an image from a remote web page on your Confluence page, without needing to attach it to your page. You need to know the URL for the image, not for the web page it appears on. Note that you should have permission to use that image on your page.

To display an image located on a web page:

1. While editing the page, position the cursor where you want to place the image.
2. Choose **Insert** > **Image** and choose **From the Web**.
3. Type in the URL for the image. An example is: http://www.atlassian.com/software/confluence/images/icon_customerslove_big.png
4. Choose **Preview** to check that the URL and image are correct.
5. Choose **Insert**.

Alternatively, you can simply cut and paste the image from a web page.

Controlling the image appearance

When editing the page, click the image to show the image properties panel. The panel allows you to set the display size for the image and choose whether the image has a border. See also [Linking from an Image](#).

To set the size of the image, do one of the following:

- Choose one of the size 'preset' buttons (the image width in pixels is displayed to the left).
- Choose the image size text and enter a new image width in pixels (you can specify a size between 16px and 900px).

Note that images are displayed as [thumbnails](#).

To add a border to the image:

- Choose **Border** in the image properties panel.

To add a hyperlink to the image:

- Choose **Link** in the image properties panel. For more detail, see [Linking from an Image](#).

To align an image:

- Select the image and choose the paragraph alignment buttons on the editor [toolbar](#).
- If you choose the left or right alignment, the text will wrap around the image. The text does not wrap for centre alignment.

To add border effects to an image:


- Choose **Effects** in the image properties panel and make a choice.
- **Note:** The **Instant Camera** effect only works with Latin character languages, due to a lack of handwriting style fonts in multi-byte languages.

To add a caption to an image:


- Choose **Effects** in the image properties panel and choose the **Instant Camera** image effect.
- Save the page.
- Choose **Tools** > **Attachments** to go to the 'Attachments' view of the page.
- Choose **Properties** next to the image file.
- Add a **comment** to the attachment. The text in your comment will appear as the image caption.

Note: You will need to re-do the comment each time you upload a new version of the image.

Screenshot: The image properties panel beneath an image



Screenshot: Examples of image border effects



Setting other image attributes

Certain attributes such as alt-text, title and other HTML parameters can still be set by using the **Insert > Wiki Markup** function from the editor toolbar, then using the syntax described in [Confluence Wiki Markup](#).

Displaying a gallery of images

See the [Gallery Macro](#).

Image file formats

You can attach image files of any format to a page. Confluence supports the following image formats in the Gallery macro and when displaying an image on a page:

- gif
- jpeg
- png
- bmp (depending on browser support)

Deleting an Image

This page describes how to remove an image from a page. You may want to remove the image from the content of the page, but leave the image available in Confluence. Or you may want to remove the image from Confluence entirely.

Removing an image from the content of a page

A Confluence page can display one or more images, as described in [Displaying Images](#).

To remove an image from the content of a page:

1. Edit the page.
2. Select the image. The image properties panel will appear, letting you know that the image is selected.
3. Press the Delete key on your keyboard.
4. Save the page.

The image will no longer appear as part of the page content. If the image file was originally uploaded as an attachment on the current page or another page, the image is still available in Confluence. If you want to remove the attachment, follow the steps below.

Removing an image attachment from Confluence

To remove an image file from Confluence, you must remove the attachment. See [Deleting an Attachment](#).

Note: A page can display an image that is attached to another page. If you remove an image that is used on a page, readers will see an error message on that page.

Example error message that appears when image attachment is removed:

? Unknown Attachment

Related pages:

- [Displaying Images](#)
- [Working with Attachments](#)
- [Confluence User's Guide](#)

Working with Tables


Confluence pages can include multi-row and multi-column tables. You can highlight cells, rows and columns in different colours. When viewing the page, people can sort the table by clicking the column headers.

Inserting a table

To create a table:

1. While editing the page, place your cursor at the point where you want to insert the table.
2. Choose **Table** on the toolbar.
3. A dropdown menu will appear, showing a table with a variable number of rows and columns. Click in a cell to set the number of columns and rows for your table.
4. Add content and more rows and columns as needed. See below for guidelines on what you can do with your table in the editor.

Screenshot: Inserting a table with 3 rows and 3 columns



On this page:


- [Inserting a table](#)
- [What you can do with your table in the editor](#)
- [Shortcut keys](#)
- [Sorting the table in view mode](#)

Related pages:

- [Working with Page Layouts and Columns and Sections](#)
- [Using the Editor](#)
- [Confluence User's Guide](#)

What you can do with your table in the editor

While editing a page, place your cursor inside a table to see the table toolbar.



Using the table toolbar you can:

- Insert an empty row above the current one.
- Insert an empty row below the current one.
- Remove the current row.
- Cut the current row and copy it to the clipboard.
- Copy the current row to the clipboard.
- Paste the row from the clipboard to the current row.
- Insert an empty column to the left of the current one.
- Insert an empty column to the right of the current one.
- Remove the current column.
- Merge the selected cells.
- Split the selected merged cells.
- Mark a row as a table header. The cells in the row will be highlighted in grey and the text will be bold.
- Mark a column as a table header. The cells in the column will be highlighted in grey and the text will be bold.

- Highlight cells with a background colour.
- Remove the table.

Shortcut keys


Windows	Action	Mac OS X
Ctrl+Shift+c	Copy the current table row, or the selected rows.	Cmd+Shift+c
Ctrl+Shift+i	Insert a table. (Opens the Insert Table dialog.)	Cmd+Shift+i
Ctrl+Shift+v	Paste the table rows from your clipboard, placing them above the current row.	Cmd+Shift+v
Ctrl+Shift+x	Cut the current table row, or the selected rows.	Cmd+Shift+x
Alt+Up Arrow	Add a row above the current row.	Alt+Up Arrow
Alt+Down Arrow	Add a row below the current row.	Alt+Down Arrow

For more editor keyboard shortcuts, see [Keyboard Shortcuts](#).

Sorting the table in view mode

When readers view a table on a page, they can sort the table by clicking the sort icons in the header row.

Screenshot: A colourful, sortable table



Document	Author	Reviewer
Getting Started	Sandy	Joan
Installation Guide	Sandy	Pete
Upgrade Guide	Juan	Lise

Using Symbols, Emoticons and Special Characters

You can add various symbols and special characters to Confluence pages. You can also use them in other places that display content, such as blog posts, comments, the dashboard welcome message and the configuration panels offered by the Documentation theme.

Inserting symbols and special characters

To add a symbol to your page:

1. Edit the page.
2. Choose **Insert** > **Symbol**. This will display the 'Insert Custom Character' window.
3. Choose a symbol to insert it.

I m a g e																					
	N o t a t i o n	:)	:(	:P	:D	;	(y)	(n)	(i)	(/)	(x)	(!)	(+)	(-)	(?)	(o n)	(o ff)	(*)	(*r)	(* g)	(* b)

Preventing emoticons from appearing

To undo the conversion of a character combination into an emoticon, press **Ctrl+Z** (Windows) or **Cmd+Z** (Mac).

To prevent Confluence from converting text to emoticons automatically, disable 'Autoformatting' in your user profile. See [Editing User Settings](#).

The Confluence knowledge base has an article on [disabling emoticons](#) for the Confluence site as a whole.

Using Autocomplete

When using the Confluence editor, you can type a trigger character or press a [keyboard shortcut](#) to see a list of suggested links, files or macros to add to your page, or to mention another user (and automatically notify them of this).

Summary of autocomplete

What you want to do	Trigger character	Keyboard shortcut	Description
Add a link on your page	[	Ctrl+Shift+K	See a list of suggested pages or other locations to link to from your page. More...
Display an image, video, audio file or document on your page	!	Ctrl+Shift+M	See a list of suggested images, multimedia files and documents to embed in your page. More...
Add a macro on your page	{	None	See a list of suggestions as you begin typing a macro name. More...
Notify another user by email that you have mentioned them on your page	@	None	See a list of suggested users to mention. More...

On this page:

- [Summary of autocomplete](#)
- [Using autocomplete for links](#)
- [Using autocomplete for images, videos, audio files and documents](#)
- [Using autocomplete for macros](#)
- [Using autocomplete for mentions](#)
- [Cancelling autocomplete](#)
- [Enabling and disabling autocomplete](#)
- [Ignoring autocomplete](#)

Related pages:

- [Working with Links](#)
- [Using Images](#)
- [Working with Macros](#)
- [Keyboard Shortcuts](#)
- [User Profile Overview](#)
- [Confluence User's Guide](#)

Using autocomplete for links

Type '[', or press Ctrl+Shift+K, to see a list of suggested pages or other locations to link to from your page. You can link to pages, user profiles, images, documents and other file attachments.


To autocomplete a link:

1. Edit the page.
2. Click where you want to insert a link and do one of the following:
 - Type '[' and then the first few characters of the page title, user's name, image name or file name.
 - Type the first few characters of the page title, user's name, image name or file name (or select relevant text) and then press Ctrl+Shift+K.
3. Click the relevant link from the list of suggestions.

If the item you need is not in the list, either:

- Choose **Search for 'xxx'** to continue looking for the page within Confluence, or
- Choose **Insert Web Link** to insert a link to an external web page using the link browser.

Screenshot: Autocomplete for a link



Using autocomplete for images, videos, audio files and documents

You can use the autocomplete as a fast way of embedding images, videos, audio files and documents into your page. Type an exclamation mark or press Ctrl+Shift+M to see a list of suggested images, multimedia files and documents to display on your page. You can use autocomplete to embed the following file types:

- Images – any format that Confluence supports. See [Displaying Images](#).
- Videos, audio files and all multimedia formats that Confluence supports. See [Embedding Multimedia Content](#).
- Office documents supported by the [Confluence Office Connector](#): Word, Excel and PowerPoint.
- PDF files.

i Autocomplete works most efficiently for files that are already attached to the Confluence page. See [Attaching Files to a Page](#).


To embed an image, video, audio file or document:

1. Edit the page.
2. Click where you want to insert the image, video, audio file or document and do one of the following:
 - Type '!' and then the first few characters of the image, file or document name.
 - Type the first few characters of the name of the image, file or document (or select relevant text) and then press Ctrl+Shift+M.
3. Choose the relevant file from the list of suggestions.

If the item you need is not in the list, either:

- Choose **Open Image Browser** to find images and documents using the image browser, or
- Choose **Insert Other Media** to embed videos, audio and other multimedia files using the macro browser. Insert the 'Multimedia' macro to display your multimedia file.

Screenshot: Autocomplete for an image or document



Using autocomplete for macros

Type '{' to see a list of suggested macros to add to your page.

Autocomplete provides access to all available macros in your Confluence site, including any user macros that your administrator has added and made visible to all.


i You need to know the name of macro. Autocomplete for macros will only match the name of the macro, not the description.

To autocomplete a macro using '{':

1. Edit the page.
2. Click where you want to insert the macro.
3. Type '{' and then the first few characters of the macro name.
4. Choose the relevant macro from the list of suggestions.
5. Configure the macro by completing the form fields as prompted.

If the macro you need is not in the list, choose **Open Macro Browser** in the list of suggestions to continue looking for the macro in the macro browser. See [Working with Macros](#).

Screenshot: Autocomplete for a macro

**Using autocomplete for mentions**


You can use autocomplete to automatically notify another Confluence user that you have mentioned them in a page, blog post, or comment. Type '@' and part of the person's name, to see a list of suggested users.

Note: Use the person's full name. Autocomplete will recognise users' full names only, not their usernames.

To mention someone using '@':

1. Edit the page.
2. Click where you want to insert a mention and type '@' and then the first few characters of the user's full name.
3. Choose the user's name from the list of suggestions.

Screenshot: Autocomplete for mentions

**Cancelling autocomplete**

The autocomplete starts automatically when you press the trigger characters. You may want to close the autocomplete menu or escape from autocomplete once it has started.

There are a few different ways to stop the autocomplete once it has started:

- Press the escape key, 'Esc', on your keyboard.
- Click somewhere else in the editor panel.
- Press an arrow key to move out of the autocomplete area.
- For the *link* autocomplete only: enter a right-hand square bracket, like this: **]**

Enabling and disabling autocomplete

You can turn off the triggering of autocomplete by the '[' and '!' characters. This will prevent the autocomplete from starting automatically when you press one of the trigger characters. You can also turn it back on again.


Notes:

- This setting does not affect the keyboard shortcuts for autocomplete (Ctrl+Shift+K and Ctrl+Shift+M). Even if the trigger characters are disabled, you can still use the keyboard shortcuts for autocomplete.
- This setting affects only you. Other people using Confluence can enable or disable the setting on their user profiles independently.
- Note that autocomplete is enabled by default.

To enable or disable the autocomplete trigger characters:

1. Choose **your profile picture** at top right of the screen, then choose **Settings**.
2. Choose **Editor** under 'Your Settings' in the left-hand panel.
3. Choose **Edit**.
4. Either:
 - Disable autocomplete by selecting **Disable Autocomplete**.
 - Enable autocomplete by clearing **Disable Autocomplete**.
5. Choose **Submit**.

Screenshot: User settings for the editor



Ignoring autocomplete

You can add macros, links and images by [wiki markup](#) alone. Type the macro, including its parameters and the closing curly bracket. Add a link, such as an anchor link, and end it with a square bracket. Insert an image or other embedded object, enclosed between exclamation marks. As soon as you close the macro, link, or embedded image, Confluence will convert it to rich text format and add it to the page.

More information about mouse-free macros, links and images:

- [Quick Reference Guide for the Confluence Editor](#)

- [Video](#)

Working with Page Layouts and Columns and Sections

When you want to add structure to the information on your page, it is often useful to split the information into columns. By 'column', we mean a vertical block of content. You may want more than one column across the width of the page.

You may also want to use a common structure on a number of pages, so that readers know where to find the information within each page. In addition to columns, sections are useful here. By 'section', we mean an area of the page. A section may contain one or more columns.

Confluence provides the following ways of creating columns and sections on a page:

- Page layouts offer a set of predefined columns and sections.
- The Section and Column macros allow more flexibility. You can set the width of the columns, and put the sections and columns in any part of the page.

On this page:

- [Using page layouts](#)
- [Using the Section and Column macros](#)
- [Code examples](#)

Related pages:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Using the Editor](#)
- [Working with Macros](#)
- [Working with Tables](#)


Using page layouts

The Confluence editor offers a set of predefined page layouts. Each layout provides one or more columns. Some layouts also provide a horizontal block at the top and bottom of the page. The layout that you select determines the position of the sections and columns on the page, as well as the relative width of the columns. The page's content is confined within the borders of the layout. You cannot add content above or below the sections and columns provided by the layout.

To choose a page layout:


1. While editing the page, click the page layout icon. A dropdown list appears, showing icons that illustrate the available layouts.
2. Select a layout.

Screenshot: Choosing a page layout



If your page already has content on it, Confluence will put the existing content into the left-hand column of the new layout. If the page was using a different layout, Confluence will put the content into the appropriate sections and columns of the new layout.

Screenshot: A page with a three-column layout, in edit mode



Notes about page layouts

- **Very wide tables.** The width of each column is set to a percentage of the page width. The icons in the drop down menu indicate the relative widths for each layout. In most cases, Confluence will adapt the width of the columns to fit the width of the page. If a column includes a large table, the content may not fit into the width of the page. You will see a horizontal scroll bar when viewing the page.
- **Mixing and matching.** You can put Section and Column macros inside page layouts. You can also put tables inside page layouts.

Using the Section and Column macros


You can use the Section and Column macros to add a set of columns to the page. The Section macro defines an area that will contain the columns. You can have as many sections as you like. Within each section, you can have as many columns as you like.

To add a section and some columns to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find the **Section** macro, select it and insert it onto the page.
3. Choose **Insert > Other Macros** again.
4. Find and insert the **Column** macro.

5. Add your content to the column.
6. Insert as many columns as you like within the section.

Screenshot: A section and two columns in the editor



When you see the page in view mode, the above layout is displayed like this:

Content for column 1 goes here
Content for column 2 goes here

Macro parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameters of the Section macro

Parameter	Default	Description
Show Border	false	Select this option to draw a border around the section and columns. Note: Without a Column macro, the border will not be displayed correctly.

Parameters of the Column macro

Parameter	Default	Description
Column Width	100% of the page width, divided equally by the number of columns in the section.	Specify the width of the column, in pixels (for example, 400px) or as a percentage of the available width (for example, 50%).

Notes about sections and columns

- All content within your section must be enclosed within a Column macro, otherwise the section layout will not work as expected.
- You can put tables inside columns.
- PDF exports do not handle page layouts. See this issue report:

 [CONF-25240 - Authenticate](#) to see issue details

Code examples

See:

- [Confluence Wiki Markup for Macros -- Section macro](#)
- [Confluence Storage Format for Macros -- Section macro](#)

Working with Macros

Using a macro, you can add extra functionality or include dynamic content on a page. For example, the [Attachments macro](#) will list a page's attachments in the page itself, so that readers do not have to visit the Attachments tab.

Adding a Macro to your Page

Including Macros with the Macro Browser

To add a macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type **{** and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Macro Parameters

Many macros allow you to include optional parameters to control the macro's output.

With the Attachments Macro, for instance, you have two optional parameters allowing you to:

- Specify the file formats of the attachments displayed.
- Choose whether or not you want old versions of the attachments displayed.

Macro Placeholders

Macro placeholders are displayed in the editor where you have added a macro to the page.

When editing a page, you can:

- Double-click a macro placeholder (or click the placeholder and choose **Edit**) to open the macro dialog window, where you can edit the macro's parameters.
- Select a macro placeholder to cut, copy and paste the macro.

On this page:

- [Adding a Macro to your Page](#)
- [Macros Shipped with your Confluence Installation](#)
- [Information about Other Macros](#)
- [Writing your own Macros](#)
- [Code examples](#)

Related pages:

- [Atlassian Plugin Exchange](#)
- [Confluence User's Guide](#)

Macros Shipped with your Confluence Installation

When you download your Confluence installation file, many macros are shipped with the download. Below is a list of the macros currently shipped with Confluence. Click a macro name for details of the usage, including optional parameters and examples.

Activity Stream Macro***Anchor Macro***

Allows you to link to a specific part of a page.

Attachments Macro

Displays a list of attachments on a given page.

Blog Posts Macro

Lists the most recent news items in the space.

Change-History Macro

Displays a history of updates made to a page.

Chart Macro

Displays a chart based on tabular data.

Cheese Macro

Displays the words "I like cheese!"

Children Display Macro

Displays the children and descendants of the current page.

Code Block Macro

Displays code in your document with the appropriate syntax highlighting.

Column Macro

Used with the Section macro to define columns on a page. See [Working with page layouts and columns and sections](#).

Content by Label Macro

Displays a list of content associated with specific labels.

Content by User Macro

Displays a list of the content items that have been created by a specified Confluence user.

Content Report Table Macro

Displays a set of pages and blog posts in tabular format, based on the labels specified in the macro parameters.

Contributors Macro

Displays a list of Confluence users who have made a contribution of some type to a page.

Contributors Summary Macro

Displays a table of contribution-based statistics for a set of pages.

Create Space Button Macro

Displays a create space button linked to the create space page.

Excerpt Include Macro

Allows you to display an excerpt from another page within the current page.

Excerpt Macro

Define a part of a page as the page's 'excerpt' which can then be displayed in another page.

Expand Macro

Displays an expandable/collapsible section of text.

Favourite Pages Macro

Displays a list of your favourite pages.

Gadget Macro

Allows you to add Confluence gadgets to pages or blog posts.

Gallery Macro

Forms a thumbnail gallery of all images attached to a page.

Global Reports Macro

Displays a list of links to global reports within a table.

HTML Include Macro

Includes the content of an external HTML file into a Confluence page.

HTML Macro

Renders your specified HTML code within the current page.

IM Presence Macro

Displays graphically when a contact is online.

Include Page Macro

Inserts the contents of the specified page into the current one.

Info Macro

Displays a block of text in a blue highlight box.

JIRA Issues Macro

Displays a list of JIRA issues in a page.

JIRA Macro

Displays one or more JIRA issues on your Confluence page.

JUnit Report Macro

Display a summary of JUnit test results.

Labels List Macro

Displays a hyperlinked alphabetical index of all labels within the current space.

Livesearch Macro

Add a dynamic search box to a wiki page.

Loremipsum Macro

Display a few paragraphs of pseudo-Latin text.

Multimedia Macro

Displays videos, animations and more, sourced from a file attached to a Confluence page and displayed on your page.

Navigation Map Macro

Renders the list of pages associated with a specified label as a navigable map.

Network Macro

Displays a list of Network activity for users in your Confluence site

Noformat Macro

Displays a block of text in monospace font.

Note Macro

Displays a block of text in a yellow highlight box.

Page Index Macro

Creates a hyperlinked alphabetical index of all page titles within the current space.

Page Properties Macro

Allows you to embed metadata into a page and then display that data in tabular form using the Page Properties Report macro .Previously known as the Metadata Details macro.

Page Properties Report Macro

Presents a tabulated summary of selected metadata, which has been embedded on pages using the Page Properties macro. Previously known as the Details Summary macro.

Page Tree Macro

Displays a dynamic, hierarchical list of pages starting from a specified parent (root) page.

Page Tree Search Macro

Adds a search box to your Confluence page and searches a hierarchy of pages starting from a specified parent (root) page.

Panel Macro

Displays a block of text within a fully customisable panel.

Popular Labels Macro

Displays the most popular labels used throughout your Confluence site or within a space.

Profile Picture Macro

Displays a user's profile picture on a page.

Recently Updated Dashboard Macro

Displays a list of the most recently changed content within Confluence and is intended for use on the Confluence dashboard.

Recently Updated Macro

Displays a list of recently changed content (pages, news items, comments, etc).

Recently Used Labels Macro

Lists labels most recently used in a specified scope (global, space, or personal)

Related Labels Macro

Lists labels frequently appearing on the same pages as the current page's labels.

RSS Feed Macro

Displays the contents of an RSS feed.

Search Results Macro

Searches Confluence, and includes the results in the page.

Section Macro

Used with the Column macro to define columns on a page. See [Working with page layouts and columns and sections](#).

Space Attachments Macro

Displays a list of attachments belonging to the current space.

Space Details Macro

Includes the summary of a Confluence space in the page.

Space Jump Macro

Allows you to link from a page in one space to a page with the same name in another space, without knowing the name of the page when you create the link.

Spaces List Macro

Displays a list of all spaces visible to the user.

Status Macro

Displays a coloured lozenge, useful for reporting project status.

Table of Contents Macro

Displays a table of contents from your page headings.

Table of Content Zone Macro

Displays a table of contents from a defined page 'zone'.

Tasklist Macro

Displays a dynamic task list which can be modified in 'view' mode.

Tip Macro

Displays a block of text in a green highlight box.

User List Macro

Displays a list of Confluence users, from an optional group.

User Profile Macro

Displays a short summary of any Confluence user's profile on your Confluence page or blog.

User Status List Macro

Displays a history of any Confluence user's status updates on your Confluence page or blog.

View File Macro

Embeds an Office document or PDF file into your Confluence page.

Warning Macro

Displays a block of text in a red highlight box.

Widget Connector Macro

Displays videos, slide shows, twitter chats, documents and more, sourced from other web sites and displayed on your Confluence page.

Information about Other Macros

Other macros are available as [plugins](#) or as [user macros](#), and can be installed by your Confluence administrator. For example, macros that may be of interest are available from [Adaptavist](#), [CustomWare](#) and the [Confluence SharePoint Connector](#). *Not applicable to Confluence OnDemand.*

Writing your own Macros

To learn how to write your own macro, take a look at the following documentation:

- User macros are simple template-like macros that allow you to create simple formatting macros using the Confluence web interface. Read more about [Writing User Macros](#). *Not applicable to Confluence OnDemand.*
- The [Confluence Plugin Guide](#) tells you how to develop a plugin for Confluence.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Activity Stream Macro

The Activity Stream macro is a specific instance of the Gadget macro. It inserts an Activity Stream gadget onto your page. For instructions, see [Activity Stream Gadget](#).

Related pages:

- [Activity Stream Gadget](#)
- [Gadget Macro](#)
- [Confluence User's Guide](#)

Anchor Macro

 The Anchor Macro is documented in [Working with Anchors](#).

Attachments Macro

See [Displaying a List of Attachments](#).

Blog Posts Macro

The Blog Posts macro allows you to display blog posts on a Confluence page. Clicking on a title takes you to the blog post.

Using the Blog Posts Macro**To add the Blog Posts macro to a page:**

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the Blog Posts Macro](#)
- [Parameters](#)
- [Code examples](#)

Related pages:

- [Working with Macros](#)
- [Working with Blog Posts](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description

Content Type to Display	titles	Available values: • titles — Display only the title of each blog post. • excerpts — Display a short excerpt from each blog post. If the post contains an Excerpt macro, the Blog Posts macro will display the content defined in the Excerpt macro. If the post does not contain an Excerpt macro, the Blog Posts macro will display the first few sentences of the post.
Time Frame	no limit	Specify how far back in time Confluence should look for the blog posts to be displayed. Available values: • m — Minutes • h — Hours, so '12h' displays blog posts created in the last twelve hours. • d — Days, so '7d' displays blog posts created in the last seven days. • w — Weeks

Restrict to these Labels	None	Filter the results by label. The macro will display only the blog posts which are tagged with the label(s) you specify here. You can specify one or more label values, separated by a comma or a space. • To exclude content which matches a given label, put a minus sign (-) immediately in front of that label value. For example: If you specify a label value of -badpage you will get only content which is not labelled with 'badpage'. • To indicate that the results must match a given label value, put a plus sign (+) immediately in front of that label value. For example: If you specify a label value of +superpage, +goodpage you will get only content which has at least two labels, being 'superpage' and 'goodpage'.
Restrict to these Authors	None	Filter the results by author. The macro will display only the blog posts which are written by the author(s) you specify here. You can specify one or more authors, separated by a comma. For example: jsmith, jbrown
Restrict to these Spaces	@self, i.e. the space which contains the page on which the macro is coded	This parameter allows you to filter content by space. The macro will display only the pages which belong to the space(s) you specify here. You can specify one or more space keys, separated by a comma or a space.

		- To exclude content in a specific space, put a minus sign (-) immediately in front of that space key. For example: If you specify a space key of -BADSPACE you will get only content which is not in the BADSPACE. - To indicate that the results must come from a specific space, put a plus sign (+) immediately in front of that space key. For example: If you specify a space key of +GOODSPACE you will get only content in GOODSPACE. (Note that this is not particularly useful, because each content item belongs to one space only. If you put a plus sign next to one space key and list other space keys too, the other space keys will be ignored.) Special values: @self — The current space. @personal — All personal spaces. @global — All site spaces. @favorite — The spaces you have marked as favourite. @favourite — The same as @favorite above. @all — All spaces in your Confluence site. * — The same as @all above When specifying a personal space, remember to use the tilde (~) sign in front of the username, such as ~jbloggs or ~jbloggs@example.com.
Maximum Number of Blog Posts	15	Specify the maximum number of results to be displayed. Note that the results are sorted first, and then the maximum parameter is applied.

Sort By	creation	Specify how the results should be sorted. If this parameter is not specified, the sort order defaults to descending order (newest first) based on the creation date. Values: • title — Sort alphabetically by title. • creation — Sort by the date on which the content was added. • modified — Sort by the date on which the content was last updated.
Reverse Sort	false	Select to change the sort from descending to ascending order (oldest first). Use this parameter in conjunction with the Sort By parameter. This parameter is ignored if the Sort By parameter is not specified.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Change-History Macro

The Change-History macro shows the history of updates made to a page: version number, author, date and comment. It displays the information inline.

Screenshot: The Change-History macro in Confluence

This is the change history macro		
Version	Date	Comment
Current Version (v. 4)	Feb 19, 2013 16:27	Rach Admin: Formatting change
v. 3	Feb 19, 2013 16:27	Rach Admin: Added the change history macro
v. 2	Feb 19, 2013 16:26	Rach Admin: Added a macro
v. 1	Feb 19, 2013 16:25	Rach Admin

Related pages:

- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

To add the Change-History macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Note: There are no parameters for this macro.

Code examples

See:


- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Chart Macro

The Chart macro allows you to display a chart based on tabular data. When you add the macro to a page, you:

- supply the data to be charted by the macro as a table in the placeholder of the macro.
- edit the macro parameters in the Macro Browser to configure the format of the chart.


Screenshot 1: A table of data in the Chart macro placeholder



The screenshot shows the Chart macro interface. At the top, there is a header bar with the text: "Chart | type = timeSeries | columns = Weeks, Issues Burndown | dataOrientation = vertical | tim...". Below this header is a table with two columns: "Weeks" and "Issues Burndown". The table contains 11 rows of data, showing a decreasing trend from 81 issues in early July to 0 issues by early September.

Weeks	Issues Burndown
04/07/2011	81
11/07/2011	68
18/07/2011	67
25/07/2011	66
01/08/2011	65
08/08/2011	65
15/08/2011	64
22/08/2011	44
29/08/2011	24
05/09/2011	0

Screenshot 2: The resulting chart



On this page:

- [Using the Chart Macro](#)
- [Parameters](#)
- [Examples](#)
 - [Pie Chart](#)
 - [Bar Chart](#)
 - [3D Bar Chart](#)
 - [Time Series Chart](#)
 - [XY Line Chart](#)
 - [XY Area Chart](#)
 - [Area Charts](#)
- [Code examples](#)

Related pages:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Using the Chart Macro

To add the Chart macro to a page:

1. Edit the page and use autocomplete to add the Chart macro. (Type '{chart}'.)
2. Enter your chart data as one or more tables in the body of the macro placeholder. (See the [screenshot](#) above.)
3. Click the macro placeholder and choose **Edit**.
4. Select a chart type using the **Type** parameter (see below).
5. Choose other parameter settings in the macro browser, as described below.
6. Click **Refresh** in the 'Preview' area, to check that the chart appears as you expect.
7. Click **Save** to add the chart to your page.
8. Click **Save** again when you are ready to save the page.

Parameters

[Chart Type Parameters](#) | [Display Control Parameters](#) | [Title and Label Parameters](#) | [Data Specification](#)

[Parameters](#) | [Colour Parameters](#) | [Axis Parameters](#) | [Pie Chart Parameters](#) | [Attachment Parameters](#)
Chart Type Parameters

These parameters determine the type of chart to display and the way the chart looks.

Parameter	Default	Description
Type	pie	The type of chart to display. XY charts have numerical x- and y-axes. The x values may optionally be time-based (see the Time Series parameter). <i>Standard</i> — pie, bar, line, area <i>XY Plots</i> — xyArea, xyBar, xyLine, xyStep, xyStepArea, scatter, timeSeries <i>Other</i> — gantt (beta)
Display Orientation	vertical	Applies to area, bar and line charts. • vertical — y-axis is vertical • horizontal — x-axis is vertical
Show in 3D	false	Applies to area, bar and line charts.
Stacked Values	false	Applies to area and bar charts.
Show shapes	true	Applies to line charts. Shapes are shown at each data point.
Opacity	• 75 percent for 3D charts • 50 percent for non-stacked area charts • 100 percent for all other charts	A percentage value between 0 (transparent) and 100 (opaque) that determines how opaque the foreground areas and bars are.

Display Control Parameters

Parameter	Default	Description
Width	300	The width of the chart in pixels.
Height	300	The height of the chart in pixels.

Display rendered data	false	Sets whether to display the rendered body of the macro (usually the data tables). By default, the chart data table isn't rendered. • before — the data are displayed before the chart. • after — the data are displayed after the chart.
Image format	png	The image format to be used for the chart. • png • jpg

Title and Label Parameters

Parameter	Default	Description
Chart Title	none	The title of the chart.
Chart Subtitle	none	A subtitle for the chart, using a smaller font than for Title .
Horizontal-axis Label	none	The label for the x-axis (domain).
Vertical-axis Label	none	The label for the y-axis (range).
Show Legend	true	Show a legend or key.

Data Specification Parameters

The data for the chart is taken from tables found when the macro body is rendered. These options control how this data is interpreted. By default, numeric and date values are interpreted according to the Confluence global default language (locale) formats. If conversion fails, other languages defined in Confluence will be tried. Additional conversion options can be specified using the parameters below.

Parameter	Default	Description
Tables	all first level tables	Comma separated list of table ids and/or table numbers (starting at 1) contained within the body of the macro that will be used as the data for the chart. If data tables are embedded in other tables, then table selection will be required. This occurs when more complex formatting is done (for example using section and column macros).

Columns	all columns	Comma separated list of column labels and/or column titles and/or column numbers for tables used for chart data. This applies to all tables processed. Columns are enumerated starting at 1. Column label is the text for the column in the header row. Column title is the (html) title attribute for the column in the header row.
Content Orientation	horizontal	• vertical — data table columns will be interpreted as series. • horizontal — data tables rows will be interpreted as series.
Time Series	false	• true — the x values in an XY plot will be treated as time series data and so will be converted according to date formats.
Date format	Confluence language defined date formats	For time series data, the date format allows for additional customization of the conversion of data to date values. If a Date format is specified, it will be the first format used to interpret date values. Specify a format that matches the time series data. See simple date format .
Time Period	Day	The time period for time series data. Defines the granularity of how the data is interpreted. Valid values are: Millisecond, Second, Minute, Hour, Day, Week, Month, Quarter, Year .
Language	none	Use in combination with the Country parameter to form a locale. These additional number and date formats will be used for data conversion before the default languages. Valid values are 2 character ISO 639-1 alpha-2 codes .
Country	none	Use in combination with the Language parameter to form a locale. Valid values are 2 character ISO 3166 codes .

Forgive	true	• true — the macro tries to convert numeric and date values that do not totally match any of the default or user-specified formats. • false — enforce strict data format. Data format errors will cause the chart to not be produced.

Colour Parameters

Colours are specified using hexadecimal notation or HTML colour names.

Parameter	Default	Description
Background Colour	White	Background of the chart.
Border Colour	no border	Border around the chart.
Colours		Comma-separated list of colours used to customise category, sections, and series colours.

Axis Parameters

Depending on the chart type, the range and domain axis may be customised. These values are automatically generated based on the data but can be overridden by specifying one or more more of these parameters.

Parameter	Default	Description
Range Minimum Value	none	Range axis lower bound.
Range Maximum Value	none	Range axis upper bound.
Range Axis Tick Unit	none	Range axis units between axis tick marks.
Range Axis Label Angle	none	Angle for the range axis label in degrees.
Domain Axis Lower Bound	none	Only applies to XY plots. Domain axis lower bound. For a date axis, this value must be expressed in the date format specified by the Date format parameter.
Domain Axis Upper Bound	none	Only applies to XY plots. Domain axis upper bound. For a date axis, this value must be expressed in the date format specified by the Date format parameter.

Domain Axis Tick Unit	none	Only applies to XY plots. Domain axis units between axis tick marks. For a date axis, this value represents a count of the units specified in the Time Period parameter. The Time Period unit can be overridden by specifying a trailing character: y (years), M (months), d (days), h (hours), m (minutes), s (seconds), u (milliseconds).
Domain Axis Label Angle	none	Only applies to XY plots. The angle for the domain axis label, in degrees.
Category Label Position	none	Placement of the axis label text for categories. • up45 — 45 degrees going upward • up90 — 90 degrees going upward • down45 — 45 degrees going downward • down90 — 90 degrees going downward
Date Tick Mark Position	start	Placement of the date tick mark. • start — tick mark is at the start of the date period. • middle — tick mark is in the middle of the date period. • end — tick mark is at the end of the date period.

Pie Chart Parameters

Parameter	Default	Description

Pie Section Label	Show only the pie section key value	Format for how pie section labels are displayed. The format uses a string with special replacement variables: • %0% is replaced by the pie section key. • %1% is replaced by the pie section numeric value. • %2% is replaced by the pie section percent value. Example 1: "%0% = %1%" would display something like "Independent = 20" Example 2: "%0% (%2%)" would display something like "Independent (20%)"
Pie Section Explode	No exploded sections	Comma separated list of pie keys that are to be shown exploded. Note: requires jFreeChart version 1.0.3 or higher.

Attachment Parameters

These are advanced options that can be used for chart versioning, to enable automation and to improve performance. Use these options carefully! Normally, the chart image is regenerated each time the page is displayed. These options allow for the generated image to be saved as an attachment and have subsequent access re-use the attachment. This can be useful especially when combined with the Cache Plugin to improve performance. Depending on the options chosen, chart images can be versioned for historical purposes.


Parameter	Default	Description
Attachment	none	The name and location with which the chart image will be saved as an attachment. The user must be authorised to add attachments to the page specified. • ^attachmentName.png — the chart is saved as an attachment to the current page. • page^attachmentName.png — the chart is saved as an attachment to the page name provided. • space:page^attachmentName.png — the chart is saved as an attachment to the page name provided in the space indicated.



Attachment Version	new	Defines the the versioning mechanism for saved charts. • new — creates new version of the attachment. • replace — replaces all previous versions of the chart. To replace an existing attachment, the user must be authorized to remove attachments for the page specified. • keep — only saves a new attachment if an existing export of the same name does not exist. An existing attachment will not be changed or updated.
Attachment Comment	none	Comment used for a saved chart attachment.
Thumbnail	false	• true — the chart image attachment will be shown as a thumbnail.

[Chart Type Parameters](#) |
 [Display Control Parameters](#) |
 [Title and Label Parameters](#) |
 [Data Specification Parameters](#) |
 [Colour Parameters](#) |
 [Axis Parameters](#) |
 [Pie Chart Parameters](#) |
 [Attachment Parameters](#)


Examples

Pie Chart


Parameters in Macro Browser		Data Table in Macro Placeholder		Rendered Chart							
Type	pie	<table><tr><th>Fish Type</th><th>2011</th></tr><tr><td>Herring</td><td>9,500</td></tr><tr><td>Salmon</td><td>2,900</td></tr><tr><td>Tuna</td><td>1,500</td></tr></table>	Fish Type	2011	Herring	9,500	Salmon	2,900	Tuna	1,500	 Fish Sold Herring ■ Herring (9,500 - 68%) ■ Salmon (2,900 - 21%) ■ Tuna (1,500 - 11%)
Fish Type	2011										
Herring	9,500										
Salmon	2,900										
Tuna	1,500										
Chart Title	Fish Sold 2011										
Show Legend	true										
Content Orientation	vertical										

Bar Chart**3D Bar Chart****Time Series Chart**


Parameters in Macro Browser		Data Tables in Macro Placeholder				Rendered Chart
Type	Time Series	Month	Revenue	Month	Expenses	
Date Format	MM/yyyy					



XY Line Chart




XY Area Chart



Area Charts

Example 1



		sati sfie d				

Example 2

Parameters in Macro Browser		Data Table in Macro Placeholder				Rendered Chart																			
Type	area	<table><tr><th>Sat isf action</th><th>2009</th><th>2010</th><th>2011</th></tr><tr><td>Ver y sati sfie d</td><td>12</td><td>23</td><td>31</td></tr><tr><td>Sat isfi ed</td><td>1</td><td>34</td><td>36</td></tr><tr><td>Dis sati sfie d</td><td>4</td><td>6</td><td>22</td></tr><tr><td>Ver y dis sati sfie d</td><td>2</td><td>7</td><td>12</td></tr></table>	Sat isf action	2009	2010	2011	Ver y sati sfie d	12	23	31	Sat isfi ed	1	34	36	Dis sati sfie d	4	6	22	Ver y dis sati sfie d	2	7	12	Very satisfied Satisfic Very dissatisfied		
Sat isf action	2009		2010	2011																					
Ver y sati sfie d	12		23	31																					
Sat isfi ed	1		34	36																					
Dis sati sfie d	4		6	22																					
Ver y dis sati sfie d	2		7	12																					
Show Legend	true																								
Width	300																								
Height	300																								
Stacked Values	true																								

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Cheese Macro

The Cheese macro simply displays the words "I like cheese!" You can use this macro to test the Confluence macro functionality. 😊

To add the Cheese macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of

suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Note: There are no parameters for this macro.

Related pages:

- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [How to Make Gorgonzola Cheese](#)
- [Confluence User's Guide](#)

Children Display Macro

Use the Children Display macro to list the child pages of a page and the further descendants (children's children). By default, the macro displays links to the child pages as shown in the screenshot below. People viewing the page will see only the links for pages that they have permission to view.

Screenshot: The Children Display macro in Confluence

This is the Children Display macro

- [Step 1 - download the game](#)
- [Step 2 - Play](#)
- [Step 3 - share your favourite nerd](#)
- [Sample page](#)
- [Games as a communication medium](#)

On this page:

- [Using the Children Display macro](#)
- [Example](#)
- [Parameters](#)
- [Code examples](#)

Related pages:

- [Working with Pages](#)
- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Using the Children Display macro

To add the Children Display macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Example

This list of child pages is generated by a Children Display macro on this page:

- [Child Page 1](#)
- [Child Page 2](#)

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Show Descendants	false	Choose whether to display all the parent page's descendants. • If true shows the complete tree of pages underneath the parent page, regardless of Depth of Descendants
Parent Page	current	Specify the page to display children for, from either the current space or a different space. Enter: • ' / ' — to list the top-level pages of the current space, i.e. those without parents. • ' pagename ' — to list the children of the specified page. • ' spacekey : ' — to list the top-level pages of the specified space. • ' spacekey : pagename ' — to list the children of the specified page in the specified space.
Number of Children	none	Restrict the number of child pages that are displayed at the top level.
Depth of Descendants	none	Enter a number to specify the depth of descendants to display. This setting has no effect if Show Descendants is enabled.
Heading Style	none	Choose the style used to display descendants.
Include Excerpts	false	Display excerpts for the child pages, if they exist.

Sort Children By	Manual if manually ordered, otherwise alphabetical	Optional. Choose: • creation — to sort by content creation date • title — to sort alphabetically on title • modified — to sort of last modification date.
Reverse Sort	false	Use with the Sort Children By parameter. When set, the sort order changes from ascending to descending.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Child Page 1

Grandchild

Child Page 2

This page is used to test the {children} macro.

Related Topics

[Children Display Macro](#)

Code Block Macro

The Code Block macro allows you to display source code in your document with the appropriate syntax highlighting. The code block displays on the page as shown below:

```
public static void main(String[] args)
{
    System.out.println("Hello World!");
}
```

On this page:

- [Using the Code Block Macro](#)
- [Parameters](#)
- [Code examples](#)

Related pages:

- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Using the Code Block Macro

To add the Code Block macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.

2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

You can now type the code block directly into the macro placeholder in the editor. Note that any white space contained in the placeholder is not manipulated in any way by the Code Block macro. This is to provide the writer with flexibility over code indentation.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Syntax highlighting	java	Specifies the language (or environment) for syntax highlighting. The default language is Java but you can choose from one of the following languages/environments: • actionscript3 • bash • csharp (C#) • coldfusion • cpp (C++) • css • delphi • diff • erlang • groovy • html/xml • java • javafx • javascript • none (no syntax highlighting) • perl • php • powershell • python • ruby • scala • sql • vb
Title	none	Adds a title to the code block. If specified, the title will be displayed in a header row at the top of the code block.

Collapsible	false	If selected, the code macro's content will be collapsed upon visiting or refreshing the Confluence page. Clicking the expand and source link allows you to view this content. If false, the code macro's content is always displayed in full.
Show line numbers	false	If selected, line numbers will be shown to the left of the lines of code.
First line number	1	When Show line numbers is selected, this value defines the number of the first line of code.
Theme	Default	Specifies the colour scheme used for displaying your code block. Many of these themes are based on the default colour schemes of popular integrated development environments (IDEs). The default theme is Confluence (also known as Default), which is typically black and coloured text on a blank background. However, you can also choose from one of the following other popular themes: • Django • Emacs • FadeToGrey • Midnight • RDark • Eclipse • Confluence

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Using the Code Block Macro](#)
- [Parameters](#)
- [Code examples](#)

Column Macro

Used with the Section macro to define columns on a page. See [Working with page layouts and columns and sections](#).

Content by Label Macro

The Content by Label macro displays links to pages, blog posts and attachments that have been tagged with

specific labels.

A working example

Below is a working example of the Content by Label macro, displaying content with the label 'LDAP'.

 [Connecting to SSL services \(JIRA 5.2\)](#)
[ssl](#) [ldap](#) [smtp](#) [imap](#)

 [User Management Limitations and Recommendations \(JIRA 5.2\)](#)
[group](#) [user](#) [login](#) [authentication](#) [user-management](#) [directory](#) [repository](#) [ad](#)
[active-directory](#) [ldap](#) [user-directory](#) [sso](#) [single-sign-on](#) [hostedna](#)

 [Managing Nested Groups \(JIRA 5.2\)](#)
[group](#) [user](#) [login](#) [authentication](#) [user-management](#) [directory](#) [repository](#) [ad](#)
[active-directory](#) [ldap](#) [user-directory](#) [nested-groups](#) [hostedna](#)

 [Connecting to an LDAP Directory \(JIRA 5.2\)](#)
[group](#) [user](#) [login](#) [authentication](#) [user-management](#) [directory](#) [repository](#) [ad](#)
[active-directory](#) [ldap](#) [user-directory](#) [nested-groups](#) [hostedna](#)

 [Configuring an SSL Connection to Active Directory \(JIRA 5.2\)](#)
[ldap](#) [active-directory](#) [ad](#) [ssl](#) [https](#) [certificate](#) [hostedna](#)

Showing first 5 of 809 results

On this page:

- [A working example](#)
- [Using the Content by Label Macro](#)
- [Parameters](#)
- [Code examples](#)

Related pages:

- [Related Labels Macro](#)
- [Navigation Map Macro](#)
- [Recently Used Labels Macro](#)
- [Working with Confluence Labels](#)
- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Using the Content by Label Macro

To add the Content by Label macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Label(s)	None	Filter by label(s). The macro will display only the content tagged with the label(s) specified here. See also the Operator parameter below. This parameter is required. Specify one or more labels, separated by a comma or a single space. • To exclude content which matches a given label, put a minus sign (-) immediately in front of that label value. For example: If you specify a label value of -badpage you will get only content which is not labelled with 'badpage'. • To indicate that the results must match a given label value, put a plus sign (+) immediately in front of that label value. For example: If you specify a label value of +superpage, +goodpage you will get only content which has at least two labels, being 'superpage' and 'goodpage'.
Author(s)	None	Filter by author. The macro will display only the content created or updated by the author(s) specified here. Specify one or more authors, separated by a comma. For example: jsmith, jbrown

Include this Content Type Only	all	Filter by content type. The macro will display only the content of the type specified here. Specify one or more content types, separated by a comma or a space. To exclude content of a given content type, put a minus sign (-) immediately in front of that content type. For example: If you specify a content type of -blogpost you will get pages and all other content except for blog posts. Available values: • page – Pages. • blogpost or news – Blog posts, also known as news items. • attachment – Attachments
Show Labels for Each Page	true	Show or hide labels in the results.
Show Space Name for Each Page	true	Show or hide spaces in the results.
List Title	None	Add a title or heading to the list.
Maximum Number of Pages	15	Limit the maximum number of results to be displayed. Note that the results are sorted first, and then the maximum parameter is applied.
Display Excerpts	false	Include excerpts from each page listed. Note that you must have defined excerpts on each of those pages, by adding the excerpt macro to the page. Only the first few lines of the excerpt for each page are displayed.

Restrict to these Spaces	@all	Filter by space. The macro will display only the content which belongs to the space(s) specified here. Specify one or more space keys, separated by a comma or a space. • To exclude content in a specific space, put a minus sign (-) immediately in front of that space key. For example: If you specify a space key of -BADSPACE you will get only content which is not in the BADSPACE. • To indicate that the results must come from a specific space, put a plus sign (+) immediately in front of that space key. For example: If you specify a space key of +GOODSPACE you will get only content in GOODSPACE. (Note that this is not particularly useful, because each content item belongs to one space only. If you put a plus sign next to one space key and list other space keys too, the other space keys will be ignored.) Special values: • @self — The current space. • @personal — All personal spaces. • @global — All site spaces. • @favorite — The spaces you have marked as favourite. • @favourite — The same as @favorite above. • @all — All spaces in your Confluence site. • * — The same as @all above When specifying a personal space, remember to use the tilde (~) sign in front of the username, such as ~jbloggs or ~jbloggs@example.com.

Operator	OR	The operator to apply when matching content against the labels specified in the Label(s) parameter: • OR – Display content with <i>any</i> of the non-prefixed labels. • AND – Display content with <i>all</i> of the specified non-prefixed labels.  Note that this parameter only modifies the behaviour of the Label(s) parameter and only affects label values without a plus (+) or minus (-) sign prefix.
Sort By	modified	Specify how the results should be sorted. Values: • title — Sort alphabetically by title. • creation — Sort by the date on which the content was added. • modified — Sort by the date on which the content was last updated. Note: If this parameter is not specified, the sort order defaults to descending, based on the last modification date (latest first). To change the sort order from ascending to descending, use the Reverse Sort parameter.
Reverse Sort	false	Select Reverse Sort to change the sort from descending to ascending. Use this parameter in conjunction with the Sort By parameter. Reverse Sort is ignored if Sort By is not specified.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Content by User Macro

The Content by User macro generates a tabulated list of the content items, throughout the Confluence installation, that have been created by a specified Confluence user. The list includes all current pages, comments and spaces created by the user. Each item in the table is linked to its corresponding page, page comment or space dashboard.

Note that items for page comments contain a link to the page, followed by a second link to the comment itself, with these separated by a greater-than sign (>).

Using the Content by User macro

To add the Content by User macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the Content by User macro](#)
- [Parameters](#)
- [Code examples](#)

Related pages:

- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Username	none	The Confluence username for a person who has created content.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Content Report Table Macro

The Content Report Table macro displays a set of pages and blog posts in tabular format, based on the labels specified in the macro parameters.

A working example

Below is a working example of the Content Report Table macro, displaying content with the label 'LDAP'.

Title	Creator	Modified

Connecting to LDAP or JIRA or Other Services via SSL	Nick Faiz	Apr 29, 2013
Connecting to an LDAP Directory	Sarah Maddox [Atlassian]	Jul 30, 2012
Connecting to an Internal Directory with LDAP Authentication	Sarah Maddox [Atlassian]	Jul 03, 2012
Configuring User Directories	Sarah Maddox [Atlassian]	Jul 03, 2012
Managing Nested Groups	Sarah Maddox [Atlassian]	Apr 26, 2012
Requesting Support for External User Management	Matt Ryall [Atlassian]	Oct 27, 2011
User Management Limitations and Recommendations	Sarah Maddox [Atlassian]	Sep 30, 2011
Diagrams of Possible Configurations for User Management	Sarah Maddox [Atlassian]	Sep 30, 2011
Synchronising Data from External Directories	Sarah Maddox [Atlassian]	Sep 30, 2011
Managing Multiple Directories	Sarah Maddox [Atlassian]	Sep 30, 2011
Configuring an SSL Connection to Active Directory	Sarah Maddox [Atlassian]	Sep 30, 2011
Configuring the LDAP Connection Pool	Sarah Maddox [Atlassian]	Sep 30, 2011

On this page:

- [A working example](#)
- [Using the Content Report Table Macro](#)
- [Parameters](#)
- [Code examples](#)

Related pages:

- [Related Labels Macro](#)
- [Content by Label Macro](#)
- [Working with Confluence Labels](#)
- [Working with Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Using the Content Report Table Macro**To add the Content Report Table macro to a page:**

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of

suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Label(s)	None	This parameter is required. Specify one or more labels, separated by a comma. The macro will display only the content tagged with the label(s) specified here.
Space(s)	(All spaces)	Specify one or more space keys, separated by a comma or a space. The macro will display only the content which belongs to the space(s) specified here. When specifying a personal space, remember to use the tilde (~) sign in front of the username, such as ~jbloggs or ~jbloggs@example.com.

Code examples

See [Confluence Storage Format for Macros](#).

Wiki markup is not available for this macro. You cannot add this macro via wiki markup.

Contributors Macro

The Contributors macro displays a list of Confluence users who have made a contribution of some type to a page. It can also be used to list watchers of the page.

The scope of this macro can be extended to include the immediate children or descendants of the specified page. The list of contributors can be based on people who have:

- authored or edited the page(s)
- contributed comments or added labels to the page(s), or
- are simply watching the page(s).

Screenshot: Example list of Contributors



In this example, the **Display Format** parameter has been set to **list**.

On this page:

- [Using the Contributors Macro](#)
- [Parameters](#)
- [Code examples](#)

Related pages:

- [Contributors Summary Macro](#)
- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Using the Contributors Macro

To add the Contributors macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type **{** and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Contribution Type	authors	Filters by either the type of contribution made to a page (and optionally its descendant pages), or the watches on the page. Contribution types are: • authors - includes people who created or have edited the page(s) • comments - includes people who have added comments to the page(s) • labels - includes people who have added labels to the page(s) • watches - includes people who are watching the page(s). You can specify one or more contribution types, separated by commas.

Sort By	count	Specifies the criteria used to sort contributors. Sort criteria are: • count - sorts people based on the total number of contributions to the page(s) • name - sorts people into alphabetical order • update - sorts people based on the date of their last contribution to the page(s).
Reverse Sort	false	Reverses the sort order of contributors in the list. Must be used in conjunction with the Sort By parameter.
Maximum Number of Contributors	no limit	Limits the number of contributors in the list. If a number is not specified, all contributors are included.
Display Format	inline	Sets how the list of contributor's names is formatted: • inline — a comma-separated list • list — a bullet list.
Show Anonymous Contributions?	false	Sets whether to include those who contributed anonymously to a page.
Show Count?	false	Sets whether to show the number of times each person made a contribution of the specified Contribution Type.
Show Last Contribution Time?	false	Sets whether to show the last time each person made a contribution of the specified Contribution Type.
Page Name	current	Specifies the page to use when generating the list of contributors. If Page Name and Space(s) are left blank, the current page is assumed.
Label(s)	none	Filters the list of contributors to those who created the specified labels from a page. You can specify one or more labels, separated by commas.

Space(s)	current	Specifies the space key of the Confluence space that contains the page set in Page Name or alternatively, specifies the spaces to search. Space keys are case-sensitive. This parameter also takes special values, including: • @global — All site spaces. • @personal — All personal spaces. • @all — All spaces in your Confluence site. You can specify one or more space keys or special values, separated by commas. If no Page Name and Label(s) are specified, all pages from the specified set of spaces are included.
Content Type	both pages and blog posts	Restricts the content type to use when generating the list of contributors: • pages — pages • blogposts — blog posts.
Blog Post Date	none	Specifies the publish date for a blog post. The date format required is: YYYY/MM/DD.
Include Page Hierarchy	specified page only	Specifies additional pages to include when generating the list of contributors: • children — just the child pages of the specified page • descendants — all descendants of the specified page.
Show Selected Pages	false	Sets whether to show a list of the pages used to generate the list of contributors.
Custom "None Found" Message	default message	Specifies the message to be used to override the default message that is displayed when no contributors are found.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Contributors Summary Macro

The Contributors Summary macro displays a table of contribution-based statistics for a set of pages. These statistics can be grouped according to individual pages or individual contributors.

The default scope for this macro is an individual page, but this can be extended to include the immediate children or descendants of a specified page. The statistics cover the following types of contributions:

- edits to the page(s)
- comments added to the page(s)
- labels added to the page(s)
- people watching the page(s)

On this page:

- [Using the Contributors Summary Macro](#)
- [Parameters](#)
- [Code examples](#)

Related pages:

- [Contributors Macro](#)
- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

A simple example of the Contributors Summary macro is shown in the screenshot below. It lists statistics for the number of times each contributor has edited, added comments and added labels to this page.

Screenshot: Example Contributors Summary table of statistics

User	Edits	Comments	Labels
Sarah Maddox	2	2	0
Edwin Dawson	2	0	0
Giles Gaskell	2	0	0
Rosie Jameson	2	0	0
Andrew Lui	2	0	1
Charles Miller	1	0	0
Andrew Prentice	0	0	1

In this example, all default parameter settings are used. For more information about this macro's parameters, refer to the [Parameters](#) section below.

Using the Contributors Summary Macro**To add the Contributors Summary macro to a page:**

1. In the Confluence editor, choose **Insert > Other Macros**.

2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type **{** and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Group By	contributors	Specifies the basis for grouping contribution-based statistics: • contributors — group by the people who have contributed • pages — group by the pages used to find contributors.
Columns to Display	edits,comments,labels	Sets the columns that should appear in the table. The statistics or type of information presented depends on the basis for grouping set with the Group By parameter. Statistics may be calculated for:

- `edits` — the number of times each contributor has edited the page(s) or the number of edits made to each page.
- `edited` — a list of the pages edited by each contributor or a list of contributors who have edited each page.
- `comments` — the number of times each contributor has added comments to the page(s) or the number of comments on each page.
- `commented` — a list of pages to which each contributor has added comments or a list of contributors who have commented on each page.
- `labels` — the number of times each contributor has added labels to the page(s) or the number of labels on each page.
- `labeled` — a list of pages to which each contributor has added labels or a list of contributors who have added a label to each page.
- `labelList` — a list of labels either added by each contributor or on each page.
- `watches` — the number of pages being watched by each contributor/person or the number of contributors/people watching each page.
- `watching` — a list of pages being watched by each contributor/person or a list of contributors/people watching each page.
- `lastupdate` — the last time each contributor made an update or when each page was last updated. Valid updates can include edit, comment or label modifications to a page.

One or more columns can be used.

Sort By	edits	Sets the criterion used for sorting items in the table. The items sorted depend on the basis for grouping set with the Group By parameter. Sort criteria are: • edits — sorts items in the table based on the total number of edits made, either by a contributor or to a page. • name — sorts items in the table in alphabetical order, either by contributor or page name. • editTime — sorts items in the table based on when the contributor last edited a page (or a specified set of pages) or when the page was last edited. • update — sorts items in the table based on when the contributor last made any contribution to a page (or a specified set of pages) or when the page last had any contribution made to it.
Reverse Sort	false	Reverses the sort order of items in the table, as specified using the Sort By parameter. (Used only in conjunction with the Sort By parameter.)
Maximum Number of Items	no limit	Limits the number of contributors or pages in the table to the value specified. If no number is specified, all items are included.
Show Anonymous Contributions?	false	Includes individuals who have made anonymous contributions to a page.
Show Zero Counts?	false	Sets whether contributors or pages are included for which a calculated statistic is zero.
Page Name	current	Sets the page for which to calculate the contribution-based statistics. If no values for Page Name and Space(s) are specified, the current page is assumed.

Label(s)	none	Restricts the contribution-based statistics to the specified labels only. You can specify one or more labels, separated by commas.
Space(s)	current	Specifies the space key of the Confluence space which contains the specified page name or alternatively, specifies a scope of spaces to search. Space keys are case-sensitive. This parameter also takes special values, including: • @global — All site spaces. • @personal — All personal spaces. • @all — All spaces in your Confluence site. You can specify one or more space keys or special values, separated by commas. If no Page Name and Label(s) are specified, all pages from the specified set of spaces are included.
Content Type	both pages and blog posts	Restricts page types to either pages (pages) or blog posts (blog posts). If no value is specified in the Macro Browser, both pages and blog posts are included.
Blog Post Date	none	Specifies the publish date for a blog post. The date format required is: YYYY/MM/DD.
Include Page Hierarchy	specified page only	Includes either the immediate children or all descendants of the specified page. If no value is indicated in the Macro Browser, only the specified page is included.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Create Space Button Macro

The Create Space Button macro displays a create space icon that links to the 'Create Space' page. To see this icon, viewers need the 'Create Space' permission which is assigned by a [site administrator](#).

Screenshot: The 'create space' button in Confluence



Using the Create Space Button macro

To add the Create Space Button macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the Create Space Button macro](#)
- [Parameters](#)
- [Code examples](#)

Related pages:

- [Creating a Space](#)
- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Icon Size	large	Specify whether to use large or small icon. Available values: • large • small

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Excerpt Include Macro

The Excerpt Include macro is used to display 'excerpted' (that is, a segment of) content from one page in another.

Before you can use this macro, the excerpt must have been defined using the [Excerpt macro](#). Note that you can have more than one Excerpt Include macro on a page (although you can have only one Excerpt macro on a

page).

Example

The paragraph below shows an example of an Excerpt Include macro, containing content from an excerpt which we have defined on the [Excerpt Macro](#) page. On the Excerpt Include macro below, we have set the options to show both the title of the page and the panel surrounding the content.

Excerpt Macro
Define a part of a page as the page's 'excerpt' which can then be displayed in another page.

On this page:

- [Example](#)
- [Using the Excerpt Include Macro](#)
- [Parameters](#)
- [Code examples](#)

Related pages:

- [Excerpt Macro](#)
- [Page Properties Macro](#)
- [Working with Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence User's Guide](#)

Using the Excerpt Include Macro

To add the Excerpt Include macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type **{** and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description

Page Containing the Excerpt	none	Type the name of the page that contains the excerpt to be displayed. You can use an excerpt from a page in the same space or another space in the same wiki. When you type the name of the page into the Excerpt Include macro dialog, Confluence will offer a list of matching pages, including those from other spaces. Alternatively, you can type the space key followed by a colon (:) and the page name, like this: SPACEKEY : Page name
Remove Surrounding Panel	false	Determines whether Confluence will display a panel around the excerpted content. The panel includes the title of the page containing the excerpt, and the border of the panel. By default, the panel and title are shown.

Code examples

See:

- [Confluence Storage Format for Macros](#)
- [Confluence Wiki Markup for Macros](#)

Excerpt Macro

The Excerpt macro is used to mark a part of a page's content for re-use. Defining an excerpt enables other macros, such as the [Excerpt Include](#) and [Blog Posts](#) macros, to display the marked content elsewhere.

You can only define one excerpt per page. In other words, you can only add the Excerpt macro once to a page.

On this page:

- [Using the Excerpt Macro](#)
- [Parameters](#)
- [Code examples](#)

Related pages:

- [Excerpt Include Macro](#)
- [Working with Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence User's Guide](#)

Using the Excerpt Macro

To add the Excerpt macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.


Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

To add reusable content to the macro:

1. Add your content inside the Excerpt macro placeholder.
2. Choose the macro placeholder to see the options panel, and select the option to **Display on new line** or to **Display inline**. The default is to display the content of the macro on a new line. If you choose the inline option, the content of the macro will form part of the same paragraph as the text preceding and following it. Note that this option affects only the page that contains the Excerpt macro. It does not affect any pages where the content is reused.

Screenshot: The Excerpt macro placeholder and options panel

**Parameters**

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Hide Excerpted Content	false	Controls whether the page content contained in the Excerpt macro placeholder is displayed on the page.

Code examples

See:

- [Confluence Storage Format for Macros](#)
- [Confluence Wiki Markup for Macros](#)

Expand Macro

The Expand macro displays an expandable/collapsible section of text on your page.

Here is an example:

▼ [Click here to expand...](#)

This text is hidden until you expand the section.

Using the Expand Macro

To insert the Expand macro into a page using the macro browser:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the Expand Macro](#)
- [Parameters](#)
- [Code examples](#)
- [Notes](#)

Related pages:

- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Title	Click here to expand...	Defines the text that appears next to the expand/collapse icon.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Notes

- **Text is expanded in PDF and HTML exports.** When you export the page to PDF or HTML, the text between the macro tags is expanded so that readers can see it in the PDF and HTML versions of the page.
- **Nesting your Expand macros.** You can put one Expand macro inside another, and Confluence will correctly show and hide the contents of all Expand macros, including the nested ones.

Favourite Pages Macro

Use the Favourite Pages macro to display a list of your favourite pages.

The output of the Favourite Pages macro appears as in the following screenshot.

Screenshot: The Favourite Pages Macro in Confluence

This is the Favourite Pages macro

Favourite Pages

Displaying pages recently added to your favourites list.

 Why I loved Angry Nerds (Angry Nerds)



 Which nerd are you? (Angry Nerds)



 Our new logo (Angry Nerds)



On this page:

- [Using the Favourite Pages Macro](#)
- [Code examples](#)

Related pages:

- [Working with Favourites](#)
- [Working with Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence User's Guide](#)

Using the Favourite Pages Macro

To insert the favourite pages macro into a page using the Macro Browser:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

There are no parameters for this macro.

Code examples

See:

- [Confluence Storage Format for Macros](#)
- [Confluence Wiki Markup for Macros](#)

Gadget Macro

Gadgets are small applications that can offer dynamic content. They are typically served from a web application server and can be re-used in many other web applications. In Confluence, use the Gadget macro to add gadgets to pages or blog posts.

Confluence comes bundled with a few of its own gadgets that you can add to your pages or blog posts. The Confluence gadgets are listed in [Confluence Gadgets](#). However, you can access additional gadgets in this list if your Confluence Administrator has:

- Installed additional gadgets in Confluence (typically as a Confluence plugin) or
- Registered gadgets served from an external web application or website (such as those from a JIRA installation or iGoogle).

Unlike other macros, the name of each gadget macro is unique and follows the convention "**<gadget-name> macro**", where **<gadget-name>** is the name supplied by the gadget itself.

On this page:

- [Inserting gadgets into a Confluence page or blog post](#)
- [Editing gadgets on a Confluence page or blog post](#)
- [Standard gadget parameters](#)
- [Contents of a Gadget macro](#)
- [Code examples](#)

Related pages:

- [The big list of Atlassian gadgets](#)
- [Confluence Storage Format for Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence User's Guide](#)

Inserting gadgets into a Confluence page or blog post**To add a gadget to a page:**

1. Edit your page or blog post.
2. Choose **Insert** > **Other Macros**.
3. Click **External Content** to see a list of gadgets configured for use in your Confluence installation.
(Some Confluence macros like the [JIRA Issues](#), [RSS Feed](#), [Tasklist](#) and [Widget Connector](#) macros also appear in this category because they can also access external content.)
4. Click the desired gadget to access its parameters and properties.
Almost all gadgets allow you to set basic parameters ([listed below](#)), which appear on the right of the macro dialog. Each gadget may also have its own set of parameters, which appear on the left of the macro dialog.
5. Set the parameters to your requirements.
6. Click **Refresh** to preview your changes.
7. Click **Insert** to add the gadget to the page.

Editing gadgets on a Confluence page or blog post**To edit an existing gadget on a page or blog post:**

1. Edit your page or blog post.
2. Click the Gadget macro placeholder and choose **Edit** (or double-click the placeholder).
3. Set the gadget's parameters to your requirements.
4. Click **Refresh** to preview your changes.
5. **Save** the gadget.

Standard gadget parameters

Almost all gadgets allow you to set basic parameters (listed below), which appear on the right of the macro dialog. Each gadget may also have its own set of parameters, which appear on the left of the macro dialog.

Parameter	Default	Description

Width	450 pixels	Set the width of the gadget, using one of the following conventions: • Width in pixels, using px or plain numbers. For example, 500px or 500 • A percentage of the page width, using %. For example, 50% • Automatic resizing of the gadget to fit 100% of the page width: auto
Border	true	Places a thin grey border around the gadget.

Contents of a Gadget macro

In the addition to the standard parameters, the gadget macro contains 'parameter-like' content, which represents specific property settings that are particular to each gadget. Hence they are not documented here. Typically, this content would only be changed by customising the gadget's default properties using the macro browser.

Code examples

See:

- [Confluence Storage Format for Macros](#)
- [Confluence Wiki Markup for Macros](#)

Gallery Macro

The Gallery macro displays a collection of thumbnail images in a table, based on the images attached to a Confluence page. When viewing the page, a user can click a thumbnail image to zoom into a screen-sized image and then view the images as a slide show.

Overview:

- The images shown in the gallery are taken from the files attached to the Confluence page. You can also specify a different page where the attachments are located. For information about attaching images to a page, see [Attaching Files to a Page](#).
- The captions below the images are drawn from the comments on the attachments. For information about adding comments to attachments, see [Attaching Files to a Page](#).
- By default, the gallery will include all the images attached to the page. You can also exclude or include images using parameters.
- You can sort your images into a particular order.
- You can specify a title for the gallery and also configure how many columns you want for the table in which your images are displayed.

On this page:

- [Using the Gallery macro](#)
- [Parameters](#)
- [Image file formats](#)
- [Code examples](#)

Related pages:

- [Displaying Images](#)
- [Attaching Files to a Page](#)
- [Editing Attachment Properties](#)
- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Illustration: Live example of the Gallery macro

Some office photos, and a waterfall





Here's an office photo



Here is the waterfall photo

Using the Gallery macro

To insert the Gallery macro onto a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

The full list of parameters is shown in the following table. If the name of an attached file or page contains a comma, you can refer to it in the relevant parameters below by enclosing it in single or double quotes, for example "this,that.jpg", theother.png

Parameter	Default	Description
Gallery Title	Nothing	Specify a title for your gallery.
Number of Columns	4	Specify the number of columns for your table.
Images to Exclude	No exclusions. Include all the pictures on the page.	The gallery will ignore any pictures specified. You can specify more than one picture, separated by commas. Note: The filename and filetype for this parameter are case-sensitive. For example, 'my picture.PNG' will not be recognised as 'my picture.png'.

Include these Images Only	Include all the pictures on the page.	If you specifically include one or more pictures, the gallery will show only those pictures. You can specify more than one picture, separated by commas. Note: The filename and filetype for this parameter are case-sensitive. For example, 'my picture.PNG' will not be recognised as 'my picture.png'.
Exclude Images with these Labels	No exclusions. Include all the pictures on the page.	The gallery will ignore any pictures that have the specified label. You can specify more than one label, separated by commas. For information on labelling the attachments, see Adding Labels .
Include Images with these Labels Only	None. The images are not filtered by label.	Filters the images to display, based on a list of labels. If you wish to enter more than one label, separate the labels with commas. Confluence will show only images that have all the labels specified. (The match is an AND, not an OR.) For information on labelling the attachments, see Adding Labels .
Use Images in these Pages	If no page is specified, the gallery macro displays the images attached to the page on which the macro is used.	Specify the title of the page which contains the images you want displayed. You can specify more than one page name, separated by commas. To specify a page in a different space, use the following syntax: SPACEKEY:Page Title
Sort Images By	None. The sort order is unspecified and therefore unpredictable.	Specify an attribute to sort the images by. Sort order is ascending, unless you select the Reverse Sort parameter (see below). Options are: • name – file name. • comment – comment linked to the attached file. • date – date/time last modified. • size – size of the attached file.
Reverse Sort	Off. Sort order is ascending	Used in combination with the Sort Images By parameter above. Use Reverse Sort to reverse the sort order, from ascending to descending.

Image file formats

You can attach image files of any format to a page. Confluence supports the following image formats in the Gallery macro and when displaying an image on a page:

- gif
- jpeg
- png
- bmp (depending on browser support)

Code examples

See:


- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Global Reports Macro

The Global Reports macro displays a list of links to some reports about content on your site.

These reports include a list of new or updated pages, [orphan pages](#), [undefined pages](#), and [RSS feeds](#) for new pages and blog posts.

Screenshot: The Global Reports macro



Related pages:

- [Subscribing to RSS Feeds within Confluence](#)
- [Working with Macros](#)
- [Confluence User's Guide.](#)

Using the Global Reports Macro

To add the Global Reports macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Width of Table	99%	Specify the width of the table in which the links are displayed, as a percentage of the window width.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

HTML Include Macro

The HTML Include macro allows you to include the contents of an external HTML file in a Confluence page.

 **CAUTION: Including unknown HTML inside a webpage is dangerous.**
HTML can contain active scripting components. This means that it would be possible for a malicious attacker to present a user of your site with script that their web browser would believe came from you. Such code could be used, for example, to steal a user's authentication cookie and give the attacker their Confluence login password.

Using the HTML Include Macro

To insert the HTML Include macro into a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Related pages:

- [HTML Macro](#)
- [Working with Macros](#)
- [Configuring a URL Whitelist for Macros](#)
- [Confluence User's Guide](#)

 The information on this page *does not apply* to Confluence OnDemand.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
HTML Page's URL	None	The URL of the page to include.

Troubleshooting

- The HTML Include macro will only be available if it has been [enabled](#) by your Confluence administrator. Also, your Confluence Administrator can define a [whitelist of trusted URLs](#). You will see an error message

on the Confluence page if the included URL is not in the whitelist.

- You can only use the HTML Include macro for pages with absolute links. If you use the macro to include an HTML page that has relative links, navigating those links in the wiki results in a 'Page Not Found' error. See [CONF-6567](#).

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

HTML Macro

The HTML macro allows you to add HTML code to a Confluence page.

 Note that the HTML macro will only be available if it has been [enabled](#) by your [System Administrator](#).

Using the HTML Macro

To add the HTML macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

There are no parameters for this macro.

Enter the HTML code into the body of the macro placeholder.

Related pages:

- [HTML Include Macro](#)
- [Working with Macros](#)
- [Enabling HTML macros](#)
- [Confluence User's Guide](#)

 The information on this page *does not apply* to Confluence OnDemand.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

IM Presence Macro

The IM Presence macro indicates graphically when a contact is signed into an Instant Messaging (IM) service. The IM Presence macro appears as a small icon on the page, like this image: .

Using the IM Presence Macro

To add the IM Presence macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Description
User ID/Screen Name	Identify the user by their ID, account name or screen name.
Service	aim – AOL Instant Messenger gtalk – Google Talk icq – ICQ jabber – Jabber msn – MSN Instant Messenger sametime – IBM Lotus Sametime skype – Skype skypeme – Skype wildfire – Openfire Server yahoo – Yahoo! Messenger
Show User ID	Shows or hides the User ID of the contact.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Related Topics

- [Working with Macros](#)
- [Confluence User's Guide](#)

Include Page Macro

You can use the Include Page macro to display the contents of one Confluence page or blog post in another page or blog post.

Using the Include Page Macro

To add the Include Page macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Page to Include	None	This is the name of the Confluence page or blog post that you want to include in the current page. • If the page or blog post is located in another space, add the space key and a colon in front of the page name. For example, DOC:My page name. • To include a blog post, specify the date as well as the title of the blog post. For example: /2010/12/01/My blog post. • The space key is case sensitive. • You can include pages from personal spaces using ~user name as the space key, where 'username' is the person's username. For example, ~jsmith:My page name.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Notes

- If you want to include part of a page rather than the whole page, use the [Excerpt](#) and [Excerpt Include](#) macros.
- To display a page's contents, you need 'View' permission for that page. Similarly, people who view the page will need 'View' permissions for the embedded page as well as the page into which it is embedded. See [space permissions](#) or contact your Confluence [space administrator](#) for more information.
- If someone changes the name of the included page after you have added the macro to your page, the page name does **not** change automatically in the macro. You will need to change the page name manually in the macro parameters.
- If you want to embed an external page into a Confluence page, you need the [HTML Include Macro](#).

Related Topics

Working with Macros

Take me back to the [Confluence User's Guide](#).

Sample Include Page

Start of sample page content

Lorem ipsum dolor sit amet, consectetur adipiscing elit. Aliquam fermentum vestibulum est. Cras rhoncus. Pellentesque habitant morbi tristique senectus et netus et malesuada fames ac turpis egestas. Sed quis tortor. Donec non ipsum. Mauris condimentum, odio nec porta tristique, ante neque malesuada massa, in dignissim eros velit at tellus. Donec et risus in ligula eleifend consectetur. Donec volutpat eleifend augue. Integer gravida sodales leo. Nunc vehicula neque ac erat. Vivamus non nisl. Fusce ac magna. Suspendisse euismod libero eget mauris.

End of sample page content

Info Macro

The Info macro allows you to highlight helpful information on a Confluence page. It creates a blue-coloured box surrounding your text, as shown below.



Info Macro Example

This text is rendered inside the info macro.

Using the Info Macro

To add the Info macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the Info Macro](#)
- [Parameters](#)
- [Code examples](#)

Related pages:

- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Optional Title	none	The title of the information box. If specified, the title text will be displayed in bold next to the icon.

Show Information Icon	true	If "false", the icon will not be displayed.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

JIRA Issues Macro

JIRA is the issue tracking and project management system supplied by Atlassian. The JIRA Issues macro allows you to display a list of issues from a JIRA site on a Confluence page. Using this macro, you can list publicly accessible issues from any JIRA site. Alternatively, you can allow users to see the issues that they have permission to see, based on their permissions on the JIRA site, assuming:

- The users are logged in to both the JIRA and Confluence sites, and
- Their usernames on both these sites match.

Note: You can also create, find and insert JIRA issues directly within text on a Confluence page or blog post. See [Inserting JIRA Issues](#).

Using the JIRA Issues Macro

To add the JIRA Issues macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type **{** and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the JIRA Issues Macro](#)
- [Displaying a List of JIRA Issues from any Accessible JIRA Site](#)
- [Parameters](#)
- [Displaying Issues which have Restricted Viewing \(Not applicable to Confluence OnDemand.\)](#)
- [Rendering HTML from JIRA](#)
- [Disabling the JIRA Issues macro](#)
- [Troubleshooting](#)
- [Code examples](#)

Related pages:

- [Inserting JIRA Issues](#)
- [Working with Macros](#)
- [Setting Up Trusted Communication between JIRA and Confluence \(Not applicable to Confluence OnDemand.\)](#)
- [Confluence User's Guide](#)

Refer to the [instructions below](#) for details on obtaining the URL of the XML view of a search. An example URL is:

```
http://jira.atlassian.com/sr/jira.issueviews:searchrequest-xml/temp/
SearchRequest.xml?jqlQuery=project+%3D+CONF+AND+%28summary
+%7E+jiraissues+OR+description+%7E+jiraissues+OR+comment+%7E+jiraissues%29&tempMax=
10
```

Screenshot: Example of JIRA issues shown on a Confluence page

Jira Issues		
Type	Key	Summary
	CONF-1181	Parse exception in jiraissues
	CONF-2746	jiraissues macro flaky
	CONF-4472	jiraissues macro is broken in Preview mode
	CONF-3729	robust (and safer) {jiraissues} macro authentication
	CONF-6878	jiraissue macro not including desired columns
	CONF-1415	jiraissues macro custom icons break
	CONF-854	ParseException when trying to use rss / jiraissues macro
	CONF-11829	jiraissues macro issues when multiple on page
	CONF-7322	Jiraissues macro doesn't show icons or timestamps
	CONF-2711	Better authentication method for jiraissues and jiraportlet macros


Page of 13

Displaying 1 to 10 of 125 items

Displaying a List of JIRA Issues from any Accessible JIRA Site

Step 1 — Obtain the URL of the Issue Filter

1. Log in to your JIRA system.
2. Go to the 'Issues' screen and create a new filter. Do not modify an existing filter.
3. Set up your search parameters and use 'View' to check the issues returned.
4. Once the filter is finished, go to the Filter's 'View' tab/section in the top-left area of the JIRA interface.
5. Copy the XML link. To do this, follow the appropriate step below:
 - If you are using JIRA 4.0.x or later, choose **Views**, right-click on **XML**, and choose **Copy Link Location**.



- If you are using **JIRA 3.13.x or earlier**, locate the 'Current View' links section, right-click on **XML**, and choose **Copy Link Location**.

Step 2 — Embed the Issue Filter URL onto your Confluence Page

1. Log in to your Confluence system.
2. Edit the page where you wish to display the list of JIRA issues.
3. Add the JIRA Issues macro to the page, as described above.
4. Edit the macro, and paste the JIRA filter URL from your clipboard into the **URL** box.
5. Customise the macro output using the optional parameters. See [below](#).
6. Save the Confluence page.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

The JIRA Issues macro allows the following parameters:

Parameter	Default	Description
URL	none	The URL of the XML view of your selected issues in the JIRA Issue Navigator. Note: If the URL in the URL parameter does not contain a tempMax argument, then the value of tempMax will default to 500. For JIRA 3.12 or earlier, the JIRA Issues macro will return a maximum of 500 issues. For JIRA 3.13 or later, the JIRA Issues macro will return a maximum of 500 issues per page.

JIRA Field Columns to Display	By default, the following columns are shown: • type • key • summary • assignee • reporter • priority • status • resolution • created • updated • due	A list of JIRA column names, separated by semi-colons (;). Example columns are: key, summary, type, created, fixversion, updated, due, assignee, reporter, priority, status and resolution. You can include any columns recognised by your JIRA site, including custom columns. See the JIRA documentation for a list of names.
Display Total Numbers Only	false	When selected, the issue list will only show the number of issues in JIRA. The count will be linked to your JIRA site.
Cache	on	• on – the macro maintains a cache of the issues which result from the JIRA query. • off – the relevant part of the cache is cleared each time the macro is reloaded.
Anonymous Retrieval	false	When selected, JIRA will return only the issues which allow unrestricted viewing i.e. the issues which are visible to anonymous viewers, as determined by JIRA's viewing restrictions. Otherwise, the results depend on how your administrator has configured the communication between JIRA and Confluence. By default, Confluence will show only the JIRA issues which the user is authorised to view. See more details below.
Width	100%	The width of the table displaying the JIRA issues. Can be indicated either as a percentage (%) or in pixels (px).

Height (pixel value only)	480	The height in pixels of the table displaying the JIRA issues. Note that this height specification is ignored in the following situations: • If you set the Render Mode parameter (see below) to static. • When the JIRA issues are displayed in a PDF or Word document, in an email message or in an RSS feed.
Title	JIRA Issues	You can customise the title text at the top of the JIRA issues table with this parameter. For instance, setting the title to 'Bugs-to-fix' will replace the default 'JIRA Issues' text. This can help provide more context to the list of issues displayed.
Render Mode	static – when the JIRA issues are displayed in a PDF or Word document, in an email message or in an RSS feed. dynamic – for all other formats.	• dynamic – dynamic issue display with the following features: • Click the column headers to sort the output. • Drag and drop the columns into a different order. • Temporarily remove a column from the display. • View a page of issues at a time, for faster response times. • static – disables the dynamic display features.

Displaying Issues which have Restricted Viewing (Not applicable to Confluence OnDemand.)

Maybe your JIRA instance is not visible to anonymous visitors — everyone has to log in before they can see JIRA issues. Or maybe some of the JIRA issues are restricted to viewing by certain users only. This section explains how to handle JIRA issues that have restricted viewing.

Using Confluence-to-JIRA Trusted Communication (Recommended)

For **Confluence 2.7.0 and later** and **JIRA 3.12 and later**, your administrator can set up trusted communication between Confluence and JIRA. The entire process is described in the [Confluence Administrator's Guide](#). Provided that your administrator has [set up trusted communication](#), you don't need to add any extra parameters. Confluence and JIRA will work out the security between them, ensuring that the user will see only the issues they are authorised to see. Read the section below if you want more detail.

The following options are available for determining the issues which will be retrieved from JIRA and displayed on

the Confluence page:

What you want to do	Macro parameter	URL parameter	Comments
Display the JIRA issues which the logged-in user is authorised to see. And if the user is not logged in, display only issues which allow unrestricted viewing.			Do not specify any authentication parameters. In this case, the behaviour depends on the way your administrator has set up trusted communication between JIRA and Confluence. Here is a summary of the behaviour. If trusted communication is enabled , the authorisation will work seamlessly. When a logged-in user views your page, they will see only the JIRA issues they are allowed to see. And if they are not logged in, they will see only the issues which allow unrestricted viewing. If trusted communication is disabled , the Confluence page will show only the JIRA issues which allow unrestricted viewing.
Ensure that Confluence will display only the JIRA issues which allow unrestricted viewing.	anonymous		Regardless of who the user is (logged in or not), the Confluence page will show only anonymously-visible issues. Confluence will not attempt to set up a trusted communication link with JIRA in this case.

Use a pre-determined username and password to access the JIRA issues.		&os_username=MYNAME&os_password=MYPASSWORD	Not recommended. Prior to Confluence 2.7, this was the only way of displaying issues with restricted viewing. For Confluence 2.7 and later, this method will still work. Confluence will not attempt to set up a trusted communication link with JIRA in this case.

Rendering HTML from JIRA

Formatted fields from JIRA can be displayed in Confluence if you set up a Confluence-to-JIRA Trust as described above. Otherwise, such formatted fields will be escaped within the JIRA issues macro output. This is to prevent the possibility of malicious HTML being served by an untrusted JIRA server. The most likely field where you will notice this is in the description field.

So, for example, without the trust relationship, a description column that rendered in JIRA like this -

Description
This is - the description - of my issue

- would actually appear in the JIRA issues macro like this -

Description
This is - the description - of my issue

Configuring Confluence-to-JIRA Trust as described above will enable the field to be rendered as expected.

Disabling the JIRA Issues macro

The functionality is provided by a plugin called the 'JIRA Macros Plugin'. To make the macro unavailable on your site, you can disable the plugin. See [Disabling or Enabling a Plugin](#).

Troubleshooting

HTTPS

The JIRA Issues macro can access a JIRA instance running under SSL as long as the Confluence server is set to accept the JIRA SSL certificate. Refer to the Confluence Knowledge Base article for more information about [problems connecting to SSL services](#).

And see also [Troubleshooting Trusted Communication between JIRA and Confluence](#). *Not applicable to Confluence OnDemand.*

Code examples

See:

- [Confluence Wiki Markup for Macros](#)

- [Confluence Storage Format for Macros](#)

JIRA Macro

See [Inserting JIRA Issues](#).

JUnit Report Macro

The JUnit Report macro displays a summary of JUnit test results from a directory accessible by the Confluence server. [JUnit](#) is a unit testing framework which allows programmers to ensure that individual units of Java source code are functioning correctly.

The JUnit Report macro appears as shown in the screenshot below.

Screenshot: The JUnit Report macro in Confluence

Test		Time	Messages
MoneyTest	100% 	00:03.391	Tests:Failures:Exceptions: 1 0 0
▶ testAdd		00:03.0	

Note:When generating reports from the JUnit Report macro, set the Apache Ant formatter to 'XML'.

Using the JUnit Report macro

To add the JUnit Report macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description

URL of the test result XML file	None	URL of a particular test result XML file. Is overridden by the Directory (URL) of your test result files parameter if you use both. Example, from a Confluence instance: <code>http://yourConfluenceInstance.com/download/attachments/<page id>/file.xml</code> For Confluence installations without anonymous user access, you can specify logon credentials as part of this parameter in the form of URL parameters: • <code>os_username</code> — The username of a Confluence user with permission to access to the JUnit test results. • <code>os_password</code> — The password of the Confluence user specified in the <code>os_username</code> parameter.
Directory (URL) of your test result files	None	URL of a directory containing your test result files. This must be a directory name and not the XML file itself. Overrides the URL of the test result XML file parameter if you use both. Example, for a local drive: <code>file:///C:/TEMP/</code> Example, for a network drive: <code>http://*host*/*path*</code>
Report Detail	all	Detail for the report. Can be all , fixture , summary or failuresonly .
Debug	None	Shows the content of failures, as well as the error messages.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Related topics

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Labels List Macro

The Labels List macro displays a hyperlinked alphabetical index of all labels within the current space.

The label index generated consists of numerous cells, each beginning with one or more letters of the alphabet or a number. Each label within the space is grouped alphanumerically into its appropriately headed cell.

Each label in the list links to a page that displays all the pages on which the label occurs within the current space.

Screenshot: Labels List Macro segment



Using the Labels List macro

To add the Labels List macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter name	Required	Default	Parameter description and accepted values
Restrict to this Space Key	No	Current space	The key of the space whose labels you want to display.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Related topics

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Livensearch Macro

The Livesearch macro allows you to add a search box to a Confluence page. When users enter a search term into the search box, Confluence will dynamically display matching results as they type.

Using the Livesearch macro

To add the Livesearch macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
ID	none	Uniquely identifies the Livesearch when there are multiple Livesearch macros in one page.
Restrict to this Space Key	all spaces	Specify a space key to limit the search to the given space. Case-sensitive.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Related topics

[Searching Confluence](#)

[Search Results Macro](#)

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Loremipsum Macro

The Loremipsum macro displays paragraphs of pseudo-Latin text ([more information](#)). You can use this macro to generate more-or-less meaningless text for demonstration purposes in pages showing a draft layout or arrangement of page elements. The text is deliberately non-meaningful so that it does not influence the viewer's perception of the page arrangement or design.

A basic example of the Loremipsum text:

Lorem ipsum dolor sit amet, consectetur adipiscing elit. Aliquam fermentum vestibulum est. Cras rhoncus. Pellentesque habitant morbi tristique senectus et netus et malesuada fames ac turpis egestas. Sed quis tortor. Donec non ipsum. Mauris condimentum, odio nec porta tristique, ante neque malesuada massa, in dignissim eros velit at tellus. Donec et risus in ligula eleifend consectetur. Donec volutpat eleifend augue. Integer gravida sodales leo. Nunc vehicula neque ac erat. Vivamus non nisl. Fusce ac magna. Suspendisse euismod libero eget mauris.

Using the Loremipsum macro

To add the Loremipsum macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type **{** and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Number of Paragraphs	3	Determines the amount of pseudo-Latin (space-filler) text to display. The macro will display a maximum number of 30 paragraphs.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Related topics

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Multimedia Macro

See [Embedding Multimedia Content](#).

Navigation Map Macro

The Navigation Map macro displays the list of pages associated with a specified label as a navigation map.

A label must be specified for this macro.

Using the Navigation Map Macro

To add the Navigation Map macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Label	none	Specify the label associated with the pages you want to show in the navigation map.
Map Title	none	Specify a title for the navigation map.
Number of Cells Per Row	5	Specify the number of cells in a row
Cell Width (Pixels)	90 px	Specify the cell width
Cell Height (Pixels)	60 px	Specify the cell height
Navigation Map Theme	Confluence	Define a theme for the navmap. If you want to create your own navmap 'look and feel' (for example, one with rounded corners), you need to add a customised navmap macro theme file to the WEB-INF/classes/templates/macros directory. The file name convention to use is navmap-mytheme.vm. Use the name of your choice for the mytheme part of the file name, which is also the value you use for this parameter. Hence, if your theme was called navmap-roundededges.vm, use the value of roundededges for this parameter.

Related Topics


[Related Labels Macro](#)
[Content by Label Macro](#)
[Recently Used Labels Macro](#)
[Working with Confluence Labels](#)
[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Network Macro

The Network macro displays a list of [Network](#) activity on a Confluence page or blog post. You can specify the user whose network activity you wish to show. These interactions include the users that the specified user is following or users who are following the specified user. The Network macro shows each listed user by their profile picture. It also provides a choice of two themes and the ability to limit the number of users in the list.

Screenshot: Network macro



On this page:

- [Using the Network macro](#)
- [Parameters](#)
- [Disabling the Network macro](#)

Related pages:

- [Working with Macros](#)
- [Confluence User's Guide](#)

Using the Network macro

To add the Network macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Username	Current user's username	The username of the Confluence user whose network interactions you wish to show. If no username is specified, then current user's (that is, your) network interactions are shown.

Mode	following	Determines which users are listed, with respect to the specified user: • following – those who the user is following. • followers – those who are following the user.
Theme	full	Determines how the user's network is displayed: • full – shows a large version of user's profile pictures and, if the following mode is set, provides an entry field function to follow more users. • tiny – shows only the small version of user's profile pictures.
Maximum Results	No limit imposed up to a maximum of 30	Restricts the number of users displayed. If the number of users exceeds the specified maximum, then a Show All link is provided. This link leads to the specified user's Network view, showing the complete list of network interactions.

Disabling the Network macro

The Network macro is provided by the 'network' module in the 'Profile Macros' plugin. To remove the macro from your site, you can disable the module in the plugin. See [Disabling and Enabling Add-ons](#).

Noformat Macro

The Noformat macro displays a block of text in monospace font with no other formatting.

Using the Noformat Macro

To add the Noformat macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Enter the content that is to be unformatted into the body of the macro placeholder.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
No Panel	False	Removes the panel around the content.

Related Topics

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Note Macro

The Note macro allows you to highlight a note on a Confluence page.

It creates a yellow-coloured box surrounding your text:



Note Macro Example

This text is rendered inside the Note macro.

Using the Note Macro

To add the Note macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type **{** and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Add the text of the note to the body of the macro placeholder.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Optional Title	none	If specified, the title is displayed in bold next to the icon.
Show Exclamation Mark Icon	true	• true – displays the warning icon • false – the icon is not displayed

Related Topics

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Page Index Macro

The Page Index macro creates a hyperlinked alphabetical index of all page titles within the current space.

The top section of the index contains a cell for each letter of the alphabet, with cells for numbers and symbols. Each cell indicates how many pages are in the corresponding list.

The lower section contains lists of page titles followed by the first few sentences of content on that page.

Each letter, number or symbol in the top section is hyperlinked to the corresponding cell in the lower section. Each page title in the lower section is hyperlinked to the page in the space.

Related pages:

- [Working with Macros](#)
- [Confluence User's Guide](#).

Screenshot: Page Index macro segment

Space Index

0-9 ... 1	A ... 1	B ... 1	C ... 1	D ... 0	E ... 0
F ... 0	G ... 1	H ... 0	I ... 1	J ... 0	K ... 0
L ... 0	M ... 0	N ... 0	O ... 1	P ... 0	Q ... 0
R ... 0	S ... 8	T ... 1	U ... 0	V ... 0	W ... 0
X ... 0	Y ... 0	Z ... 0	!@\$... 0		

0-9

25 reasons people like Confluence

Integration with JIRA Great product Its a wiki User experience design

A

Angry Nerds Home

Welcome to Angry Nerds, a sample Confluence space. We think you're gonna like it here!

B

Blog ideas

Do users need to be told left side / right side of screen Macros and what you can do with them

C

Confluence hints and tips

What hints and tips do you share with other Confluence users?

D

E

F

G

Games as a communication medium

Can we use games as a communication medium?

Using the Page Index Macro

To add the Page Index macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

This macro accepts no parameters.

Page Properties Macro

The Page Properties macro enables you to embed data on a page and then display that data in tabular form on another page. You can put the Page Properties macro on as many pages as you like and use the [Page Properties Report macro](#) to display the collected data on one page. You can also choose to hide the metadata on the pages that contain the Page Properties macro.

This macro was previously known as the Metadata Details macro.

On this page:

- [Basic usage of the Page Properties and Page Properties Report macros](#)
- [Using the Page Properties macro](#)
- [Parameters](#)
- [Examples](#)
- [Code examples](#)
- [Notes](#)
- [Other metadata macros](#)

Related pages:

- [Include Page Macro](#)
- [Excerpt Include Macro](#)
- [Using Label Macros to Categorise Wiki Content](#)
- [Working with Macros](#)
- [Working with Confluence Labels](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Basic usage of the Page Properties and Page Properties Report macros

The Page Properties macro is used in conjunction with the Page Properties Report macro.

To use the macros:

1. Add the **Page Properties** macro to your page and specify a label (for example, Status).
2. Add a two column table in the body of the macro placeholder for your metadata **keys** and **values**.
3. Repeat this process to add the **Page Properties** macro to other pages.
4. Create a new page to contain your report (for example, Status Report).
5. Add the **Page Properties Report** macro and specify the same label (for example, Status).
6. View your new status report page. The data contained in your **Page Properties** macros display in the report.

Screenshot: example 'Status' report

Status Report			
Added by Rachel Robins, last edited by Rachel Robins on Jan 31, 2013 (view change)			
Title	Current Status	Deadline	Team
Project ABC	In Progress	15 November	Green Parrots
Project DEF	Not Started	1 June	Purple Monkeys

7. Choose a column heading to sort the report.

When you insert the Page Properties macro on a page Confluence automatically adds the label to the page. You can add more than one Page Properties macro to the page, but they will inherit the same label (e.g. you cannot have two Page Properties macros with *different* labels on the same page).

Using the Page Properties macro

1. **Add the Page Properties macro to the page:**
 - a. In the Confluence editor, choose **Insert > Other Macros**.

- b. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.


2. Add a label to the macro, using the macro parameters.

In the macro browser, add a **Label**. For example, "Status".

3. Add metadata keys and values as rows in a table, in the body of the macro placeholder.

In the macro body add a two column table. In the left column specify the **keys** (these will be the column headings in your report). In the right column specify the **values** for each key.

Screenshot: The macro placeholder in the Confluence editor



Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Label	(None)	The label used to identify the metadata on this page. Confluence will add this label to the page. Any additional Page Properties macros will inherit this label.
Hidden	False	Determines whether the data in the Page Properties macro will be displayed on the current page. This setting does not affect the display of the detail in the Page Properties Report macro.

Examples

The following examples outline how you can use the Page Properties and Page Properties Report macros together to create a Status Report or a Risk Report.

▼ [Example 1 - Status Report](#)

In this example we wish to create a Status Report page that displays project status metadata from a number of pages.

The **label** in this example is 'status'

The **keys** in this example are:

- Deadline
- Project Status
- Team.

The **values** for each key are:

- Deadline: 1 June, 15 November and so on.
- Project status: Not started, In progress, Complete.
- Team: Purple Monkeys, Green Parrots.

The **Page Properties macro** on each page looks like this:

Screenshot: two examples of the Page Properties macro from different pages showing values for each key.

Project Status	Not started
Team	Purple Monkeys
Deadline	1 June

Project Status	In Progress
Team	Green Parrots
Deadline	15 November

The label keys are the same on each page. The values are different.

The **Page Properties Report macro** on the Status Report page looks like this:

Screenshot: Page Properties Report macro with the label 'Status'

The final Status Report **page** looks like this, with a row for each page:

Screenshot: Example of the Page Properties Report macro showing data

Page Properties Report for label "status"

Title	Deadline	Project Status	Team
Project ABC - Example Metadata	15 November	In Progress	Green Parrots
Project DEF - Example Metadata	1 June	Not started	Purple Monkeys

Want to see this example in action? The following pages were created in this documentation space to create this example.

- [Status and Risk Reports - example of Page Properties Report macro](#)
- [Project ABC - Example Metadata](#)
- [Project DEF - Example Metadata](#)

Example 2 - Risk Report

In this example we wish to create a Risk Report page that displays project risk metadata from a number of pages.

The **label** in this example is 'risk'

The **keys** in this example are:


- Impact
- Risk Level.

The **values** for each key are:

- Impact: critical, high, medium, low
- Risk Level: major, minor, trivial.


The **Page Properties macro** on each page looks like this:

Screenshot: example of the Page Properties macro from one page.



The **Page Properties Report macro** on the Risk Report page looks like this:

Screenshot: Page Properties Report macro with the label 'Risk'



The final Risk Report **page** looks like this, with a row for each page:

Screenshot: Example of the Page Properties Report macro showing data

Page Properties Report for label "risk"

Title	Impact	Risk level
Implementation Option A - Example Metadata	Major	Critical
Implementation Option B - Example Metadata	Trivial	High
Implementation Option C - Example Metadata	Major	High

Want to see this example in action? The following pages were created in this documentation space to create this example.

- [Status and Risk Reports - example of Page Properties Report macro](#)
- [Implementation Option A - Example Metadata](#)
- [Implementation Option B - Example Metadata](#)
- [Implementation Option C - Example Metadata](#)

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Notes

- If you add a label to the parameter in the Page Properties macro, Confluence adds the label to the page.
 - If you remove the label from the Page Properties macro, the label remains on the page.
 - If you remove the label from the page but leave it in the Page Properties macro, Confluence puts

the label back onto the page.

- You can add many Page Properties macros per page, however all Page Properties macros on the page will have the same labels applied to them. For example, if you add two Page Properties macros on a page, one with the label "risk" and the other with the label "status", both sets of metadata will appear in the Page Properties Report macro for the "status" label and for the "risk" label. This is true even if you have specified just one label in each Page Properties macro. It is the labels on the page that matter, not the labels in the macros.
- It is not possible to reference the metadata using the metadata key from within the page, or anywhere else on a Confluence page.

Other metadata macros

There are other metadata macros, which are not supported or documented on this page but which are worth mentioning:

- {metadata-list} – Adds metadata keys and values. See [Atlassian Answers](#).
- {metadata-values:pagename} – Displays the metadata values without the keys. You can use @self to get the metadata on the current page. See [Atlassian Answers](#).
- {metadata-report}
- Macros added by the [Confluence Metadata Plugin 2](#).

Status Report - Example of Page Properties Report Macro

This page contains examples of the Page Properties Report macro used to show a status report and a risk report.

Page Properties Report for label "status"

Title	Deadline	Project status	Team
Project ABC - Example Metadata	15 November	In Progress	Green Parrots
Project DEF - Example Metadata	1 June	Not Started	Purple Monkeys

Page Properties Report for label "risk"

Title	Impact	Risk level
Implementation Option A - Example Metadata	Major	Critical
Implementation Option B - Example Metadata	Trivial	High
Implementation Option C - Example Metadata	Major	High

Related pages:

- [Page Properties Report Macro](#)
- [Page Properties Macro](#)
- [Confluence User's Guide](#)

Implementation Option A - Example Metadata

This page contains an example of the Page Properties macro. The data in the macro is not hidden.

Risk level	Critical
Impact	Major

Related pages:

- [Page Properties Report Macro](#)
- [Page Properties Macro](#)
- [Confluence User's Guide](#)

Implementation Option B - Example Metadata

This page contains an example of the Page Properties macro. The data in the macro is not hidden.

Risk level	High
Impact	Trivial

Related pages:

- [Page Properties Report Macro](#)
- [Page Properties Macro](#)
- [Confluence User's Guide](#)

Implementation Option C - Example Metadata

This page contains an example of the Page Properties macro. The data in the macro is not hidden.

Risk level	High
Impact	Major

Related pages:

- [Page Properties Report Macro](#)
- [Page Properties Macro](#)
- [Confluence User's Guide](#)

Project ABC - Example Metadata

This page contains an example of the Page Properties macro. The data in the macro is not hidden.

Project Status	In Progress
Team	Green Parrots
Deadline	15 November

Related pages:

- [Page Properties Report Macro](#)
- [Page Properties Macro](#)
- [Confluence User's Guide](#)

Project DEF - Example Metadata

This page contains an example of the Page Properties macro. The data in this macro is hidden.

Related pages:

- [Page Properties Report Macro](#)
- [Page Properties Macro](#)
- [Confluence User's Guide](#)

Page Properties Report Macro

The Page Properties Report macro presents a tabulated summary of metadata that has been embedded, using the Page Properties macro, on any page or blog post in the current Confluence space. The Page Properties Report macro collects metadata from only those pages or blog posts that have a specific label.

The left-hand column of the report shows the name of the page that contains the metadata. Each page name is presented on a single row with a link to the page.

The other columns in the report represent the fields (keys) defined in the Page Properties macros. You can sort the table by choosing the column headers.

This macro was previously known as the Details Summary macro.

On this page:

- [Basic usage of Page Properties and Page Properties Report macros](#)
- [Using the Page Properties Report macro](#)
- [Parameters](#)
- [Examples](#)
- [Code examples](#)

Related pages:

- [Include Page Macro](#)
- [Excerpt Include Macro](#)
- [Using Label Macros to Categorise Wiki Content](#)
- [Working with Macros](#)
- [Working with Confluence Labels](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Basic usage of Page Properties and Page Properties Report macros

The Page Properties macro is used in conjunction with the Page Properties Report macro.

To use the macros:

1. Add the **Page Properties** macro to your page and specify a label (for example, Status).
2. Add a two column table in the body of the macro placeholder for your metadata **keys** and **values**.
3. Repeat this process to add the **Page Properties** macro to other pages.
4. Create a new page to contain your report (for example, Status Report).
5. Add the **Page Properties Report** macro and specify the same label (for example, Status).
6. View your new status report page. The data contained in your **Page Properties** macros display in the report.

Screenshot: example 'Status' report

Status Report			
Added by Rachel Robins, last edited by Rachel Robins on Jan 31, 2013 (view change)			
Title	Current Status	Deadline	Team
Project ABC	In Progress	15 November	Green Parrots
Project DEF	Not Started	1 June	Purple Monkeys

7. Choose a column heading to sort the report.

When you insert the Page Properties macro on a page Confluence automatically adds the label to the page. You can add more than one Page Properties macro to the page, but they will inherit the same label (e.g. you cannot have two Page Properties macros with *different* labels on the same page).

Using the Page Properties Report macro

1. Add the Page Properties Report macro to the page:

- a. In the Confluence editor, choose **Insert > Other Macros**.
- b. Find and select the required macro.


Speeding up macro entry with autocomplete: Type **{** and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

2. Add a label to the macro, using the macro parameters.

In the macro browser, specify a **Label**. For example, 'Status'.

Screenshot: Page Properties Report macro with label specified



Page Properties Report | label = Status

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Metadata Label	(None)	Identifies the label to be used in the Page Properties Report. The report will show data from all Page Properties macros with the same label on pages in the current space.

Examples

The following examples outline how you can use the Page Properties and Page Properties Report macros together.

The following examples outline how you can use the Page Properties and Page Properties Report macros together to create a Status Report or a Risk Report.

Example 1 - Status Report

In this example we wish to create a Status Report page that displays project status metadata from a number of pages.

The **label** in this example is 'status'

The **keys** in this example are:


- Deadline
- Project Status
- Team.

The **values** for each key are:

- Deadline: 1 June, 15 November and so on.
- Project status: Not started, In progress, Complete.
- Team: Purple Monkeys, Green Parrots.

The **Page Properties macro** on each page looks like this:


Screenshot: two examples of the Page Properties macro from different pages showing values for each key.



The label keys are the same on each page. The values are different.

The **Page Properties Report macro** on the Status Report page looks like this:

Screenshot: Page Properties Report macro with the label 'Status'



The final Status Report **page** looks like this, with a row for each page:

Screenshot: Example of the Page Properties Report macro showing data

Page Properties Report for label "status"

Title	Deadline	Project Status	Team
Project ABC - Example Metadata	15 November	In Progress	Green Parrots
Project DEF - Example Metadata	1 June	Not started	Purple Monkeys

Want to see this example in action? The following pages were created in this documentation space to create this example.

- [Status and Risk Reports - example of Page Properties Report macro](#)
- [Project ABC - Example Metadata](#)
- [Project DEF - Example Metadata](#)

Example 2 - Risk Report

In this example we wish to create a Risk Report page that displays project risk metadata from a number of

pages.

The **label** in this example is 'risk'

The **keys** in this example are:


- Impact
- Risk Level.

The **values** for each key are:

- Impact: critical, high, medium, low
- Risk Level: major, minor, trivial.


The **Page Properties macro** on each page looks like this:

Screenshot: example of the Page Properties macro from one page.



The **Page Properties Report macro** on the Risk Report page looks like this:

Screenshot: Page Properties Report macro with the label 'Risk'



The final Risk Report **page** looks like this, with a row for each page:

Screenshot: Example of the Page Properties Report macro showing data

Page Properties Report for label "risk"

Title	Impact	Risk level
Implementation Option A - Example Metadata	Major	Critical
Implementation Option B - Example Metadata	Trivial	High
Implementation Option C - Example Metadata	Major	High

Want to see this example in action? The following pages were created in this documentation space to create this example.

- [Status and Risk Reports - example of Page Properties Report macro](#)
- [Implementation Option A - Example Metadata](#)
- [Implementation Option B - Example Metadata](#)
- [Implementation Option C - Example Metadata](#)

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Page Tree Macro

The Page Tree macro displays a dynamic, hierarchical list of pages starting from a specified parent (root) page. It can act as a table of contents or a list of related topics. When viewing the page tree, your reader can click a link to view the relevant page. The page's current position is highlighted in the page tree.

Note: The Page Tree macro is used in the Confluence Documentation theme, to create a navigation panel showing a table of contents for your space. Read the instructions on [Configuring the Documentation Theme](#).

Using the Page Tree Macro

To add the Page Tree macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type **{** and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Click **Refresh** in the Macro Browser to see the effect of changes to the macro parameters.

On this page:

- [Using the Page Tree Macro](#)
- [Macro Parameters](#)

Related pages:

- [Page Tree Search Macro](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Macro Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description

Root Page	The home page of the space	Specify the parent page for the page tree. The tree will include all children of the given page, plus their children and grand-children etc. The tree will <i>not</i> include the root page itself. Specify the page title or a special value as follows: • Your page title — to specify a page name for the parent or root of the tree. The tree will include all children and grand-children of the specified root. The tree will <i>not</i> include the specified root page itself. • '@home' — will include all pages under the home page of the space (default). • '@self' — will include all pages under the current page. • '@parent' — will include all pages under the parent of the current page, including the current page. • '@none' — will include all pages in the space, including orphaned pages and the home page.

Sort Pages By	position	Specify the order to display the pages in the tree. This sort order is for display purposes only. It does not permanently re-arrange the page order. The value may be one of the following: • bitwise — sort alphabetically, for example: title1, title10, title2. • creation — sort by date of creation. • modified — sort by order of date last modified. • natural — sort in 'natural' alphabetical order, for example: title1, title2, title10. • position — sort by the default Confluence sorting rules. If your pages have been ordered manually, this sort will respect the defined order. Otherwise the pages will be displayed in the 'natural' alphabetical order, such as: title1, title2, title10.
Include Excerpts in Page Tree	false	Select if you want the page tree to show excerpts from each page. The excerpts must be defined on each page by the Excerpt macro .
Reverse Order	false	Select to show the pages in reverse (descending) natural order. Must be used in combination with the Sort Pages By parameter.
Include Search Box above Page Tree	false	Select if you want to include a search box above the page tree. The search box allows your readers to search within the page tree for the specified value.
Show Expand/Collapse Links	false	Select if you want to display the 'expand all' and 'collapse all' links at the top of your page tree. Your readers can click these links to open or close all branches of the tree at once.
Start Depth	1	Enter any number greater than 0 to set how many levels of children the tree should show when it opens for the first time.

Sample Page Tree

This page is a sample, used to demonstrate the Pagetree macro.

For more information, take a look at the main page on the [Page Tree Macro](#).

What you need to type	What you will get
<code>{pagetree:root=@parent expandCollapseAll=false}</code>	

Another Sample Page Tree

We're using this page to demonstrate the Pagetree macro.

For more information, take a look at the main page on the [Page Tree Macro](#).

What you need to type	What you will get
<code>{pagetree:root=@parent expandCollapseAll=true}</code>	Expand all Collapse all

Sample Page Tree 2

This is another sample page, used to demonstrate the Pagetree macro.

For more information, take a look at the main page on the [Page Tree Macro](#).

What you need to type	What you will get
<code>{pagetree:root=@parent expandCollapseAll=true}</code>	Expand all Collapse all

Page Tree Search Macro

Using the Page Tree Search macro, you can add a search box to your Confluence page. When a viewer enters a search term, Confluence will search a hierarchy of pages starting from a specified parent (root) page and return the search results.

You can also add a search box as part of a dynamic page tree, which looks like a table of contents. See the [Page Tree macro](#).

Using the Page Tree Search macro

To add the Page Tree Search macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Related pages:

- [Page Tree Macro](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Name of Root Page	none	The name of the root page whose hierarchy of pages will be searched by this macro. If this not specified, the root page is the current page. Note: Unlike the Page Tree macro, the Page Tree Search macro does not accept the special values that start with an @ sign, such as @home or @self.

Panel Macro

The Panel Macro allows you to display a block of text within a customisable panel, like a text box. Here is an example:



Using the Panel Macro

To add the Panel macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Panel Title	none	The title of the panel. If specified, this title will be displayed in its own title row.
Border Style	solid	The style of the panel's border. Accepted values are solid, dashed and other valid CSS border styles.
Border Colour		The colour of the panel's border.

Border Pixel Width (Value Only)		The width of the panel's border (in pixels).
Background Colour		The background colour of the panel.
Title Background Colour		The background colour of the title row of the panel.
Title Text Colour		The colour of the text in the title row of the panel.

Colours can be specified HTML colour names or hexadecimal codes.

Notes

- You can use panels within [columns](#) and table cells.

Related Topics

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Popular Labels Macro

The Popular Labels macro displays the most popular labels used throughout your Confluence site or within a space.

Using the Popular Labels Macro

To add the Popular Labels macro to a page:

- In the Confluence editor, choose **Insert > Other Macros**.
- Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Number of Labels to Display	100	Specifies the total number of labels to display in the heatmap.
Restrict Labels to this Space Key	none	Restricts the list of popular labels to the specified space.

Style of Labels	list	• list – displays the popular labels as a bulleted list, ordered by popularity (highest first). • heatmap – displays the popular labels using different font sizes for each label depending on the label's popularity, ordered by label names.

Related Topics

[Using Label Macros to Categorise Wiki Content](#)

[Related Labels Macro](#)


[User-contributed extension: Sortable Popular Labels](#)

Take me back to the [Confluence User's Guide](#).

Profile Picture Macro

The Profile Picture macro displays a user's profile picture on a page.

- When viewing the page, mouse-over the picture to see the [Hover Profile](#) for the user.
- When editing the page, click on the picture and choose **View User Profile** to see the [profile](#) for the user.



The Profile Picture macro is useful for such tasks as creating Team Pages that show all members of a project team.

On this page:

- [Using the Profile Picture Macro](#)
- [Parameters](#)
- [Related Topics](#)

Using the Profile Picture Macro

To add the Profile Picture macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description

User	none	The username, or real name, of a Confluence user.

Related Topics

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#)

Recently Updated Dashboard Macro

The Recently Updated Dashboard macro displays a list of the most recently changed content within Confluence. It is similar to the [Recently Updated macro](#) but is intended for use on the Confluence dashboard.

Using the Recently Updated Dashboard Macro

To add the Recently Updated Dashboard macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type **{** and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Space(s)	The space which contains the page on which the macro is added	Filter content by space. The macro will display only the pages etc which belong to the space(s) you specify here. You can specify one or more space keys, separated by commas. '*' means all spaces.
Include these Content Types Only	all types	Filter content by type. You can specify one or more types, separated by commas. Available types are: page, blogpost or news, spacedesc, attachment, comment, mail, userinfo.

Label(s)	none	Filter content by label. The macro will display only the pages etc which are tagged with the label(s) you specify here. You can specify one or more labels, separated by commas. <i>Note:</i> If there are no pages matching any of the specified labels, then Confluence will ignore the labels and will list all recently updated pages, as well as showing a message, "These labels don't exist and were ignored: xxx ". This unexpected behaviour is noted in issue  CONF-13860 - Authenticate to see issue details
User(s)	all users	Filter by username of the user who updated the content. The macro will only display content created and updated by the user(s) you specify here. You can specify one or more usernames separated by commas.
Width of Table	100%	Specify the width of the macro display, as a percentage of the window width.
Show User Profile Pictures	false	Select whether profile pictures of the users who updated the content are displayed.

Related Topics

[Recently Updated Macro](#)

[Viewing Recently Updated Content](#)

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Recently Updated Macro

The Recently Updated macro displays a list of the most recently changed content within Confluence.

Using the Recently Updated Macro

To add the Recently Updated macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open,

where you can edit the parameters of the macro.

On this page:

- [Using the Recently Updated Macro](#)
- [Parameters](#)
- [Notes](#)

Related pages:

- [Recently Updated Dashboard Macro](#)
- [Viewing Recently Updated Content](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Author(s) by username	None specified i.e. display all content	Filter the results by author. The macro will display only the pages etc which were last modified by the author(s) you specify here. You can specify one or more authors, separated by a comma or a space. For example: jsmith, jbrown
Space(s)	@self, i.e. the space which contains the page on which the macro is used	This parameter allows you to filter content by space. The macro will display only the pages etc which belong to the space(s) you specify here. You can specify one or more space keys, separated by a comma or a space.

- To exclude content in a specific space, put a minus sign (-) immediately in front of that space key. For example: If you specify a space key of -BADSPACE you will get only content which is not in the BADSPACE.
- To indicate that the results **must** come from a specific space, put a plus sign (+) immediately in front of that space key. For example: If you specify a space key of +GOODSPACE you will get only content in GOODSPACE. (Note that this is not particularly useful, because each content item belongs to one space only. If you put a plus sign next to one space key and list other space keys too, the other space keys will be ignored.)

Special values:

- @self — The current space.
- @personal — All [personal](#) spaces.
- @global — All [site](#) spaces.
- @favorite — The spaces you have marked as [favourite](#).
- @favourite — The same as @favorite above.
- @all — All spaces in your Confluence site.
- * — The same as @all above

When specifying a personal space, remember to use the tilde (~) sign in front of the username, such as ~jbloggs or ~jbloggs@example.com.

Label(s)	None specified i.e. display all content	Filter the results by label. The macro will display only the pages etc which are tagged with the label(s) you specify here. You can specify one or more label values, separated by a comma or a space. • To exclude content which matches a given label, put a minus sign (-) immediately in front of that label value. For example: If you specify a label value of -badpage you will get only content which is not labelled with 'badpage'. • To indicate that the results must match a given label value, put a plus sign (+) immediately in front of that label value. For example: If you specify a label value of +superpage, +goodpage you will get only content which has at least two labels, being 'superpage' and 'goodpage'.
Width of Table	100%	Specify the width of the macro display, as a percentage of the window width.

Include these Content Types Only	all types	This parameter allows you to filter content by content type. The macro will display only the content of the type you specify here. You can specify one or more types, separated by a comma or a space. To exclude content of a given content type, put a minus sign (-) immediately in front of that content type. For example: If you specify a content type of -blogpost you will get pages and all other content except for blog posts. Available values: • page — Pages. • blogpost or news — Blog posts, also known as news items. • comment — Comments on pages and blog posts. • attachment — Attachments. • status — Status updates made by other users.
Maximum Number of Results	15	Specify the maximum number of results to be displayed. If this parameter is omitted, then a maximum of 15 results are displayed. The theoretical maximum value that this parameter can accept is 2 to the power of 31, minus 1 (or 2147483647), though this has been limited to 200 in the code, for performance reasons. More details are here.

theme	'concise' with the heading 'Recently Updated'	Choose the appearance of this macro: • <code>concise</code> — the default list, showing the names of pages which were updated or commented on, the users who made the page modifications and time when the modifications occurred. • <code>social</code> — lists recent modifications in reverse chronological order, but groups them by user into short time segments. A 'sub' list appears within each user's time segment, showing the names of pages which they updated or commented on and time when these modifications occurred. • <code>sidebar</code> — lists recent updates in reverse chronological order, showing the names of pages which were updated or commented on and time when the page modifications occurred. This theme does not show authorship.
Show User Profile Pictures	false	Specify <code>showProfilePic=true</code> to display the profile pictures of the users who updated the content.

Notes

- The [Recently Updated Dashboard macro](#) is similar to this macro, but is intended for display on the Confluence dashboard.
- If you would like to change the wording displayed by the Recently Updated macro, please refer to the document on [modifying the Confluence interface text](#). *Not applicable to Confluence OnDemand.*

Recently Used Labels Macro

The Recently Used Labels macro displays a list of the labels that have been most recently added to a page, blog post or attachment. You can define the number of labels to be displayed and the scope (the current space, your personal space or site spaces, also known as 'global' spaces).

Using the Recently Used Labels Macro

To add the Recently Used Labels macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the Recently Used Labels Macro](#)
- [Parameters of this macro](#)

Related pages:

- [Related Labels Macro](#)
- [Content by Label Macro](#)
- [Recently Used Labels Macro](#)
- [Working with Confluence Labels](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Parameters of this macro

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Number of Labels to Display	10	Specifies the total number of labels to display in the list.
Scope for Retrieving Labels	global	Specifies the scope of labels to be displayed in the list. Valid values include: • global — covers all site spaces (non-personal) in the Confluence installation. • space — the current space. • personal — your own personal space.
List Style	list	• list — displays the list of labels horizontally. • table — includes additional information such as the page to which the label was added and the user who added it.
Table Title	none	Adds a title to the top of the list in table style. Titles are only visible when the List Style parameter has been set to table .

Related Labels Macro

The Related Labels macro lists all labels from every page which has one or more labels in common with the current page.

Using the Related Labels Macro

To add the Related Labels macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Restrict to these Labels	none	Specify the labels for which you want to view related labels. For example, documentation, my:stuff.

Related Topics

[Navigation Map Macro](#)

[Content by Label Macro](#)

[Recently Used Labels Macro](#)

[Working with Confluence Labels](#)

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

RSS Feed Macro

The RSS Feed macro embeds an [RSS feed](#) on a page. It can display the contents of external feeds, or of internal feeds generated by Confluence. To display blog posts or to list recently updated pages in a space, use the [Feed Builder](#) to create an internal feed, then render it using this macro.



CAUTION: Including unknown HTML inside a webpage is dangerous.

HTML inside an RSS feed can contain active scripting components. This means that it would be possible for a malicious attacker to present a user of your site with script that their web browser would believe came from you. Such code could be used, for example, to steal a user's authentication cookie and give the attacker their Confluence login password.

The RSS Feed macro will only be available if it has been enabled by your Confluence administrator. Also, your Confluence administrator can define a [whitelist of trusted URLs](#). You will see an error message on the Confluence page, if the included URL is not in the whitelist.

Using the RSS Feed macro

To add the RSS Feed macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of

suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the RSS Feed macro](#)
- [Parameters](#)
- [How up to date is the feed?](#)
- [What happens to a page containing a disallowed URL?](#)
- [Authentication](#)
- [Accessing internal HTTPS feeds](#)
- [Enabling and disabling the RSS Feed macro](#)

Related pages:

- [Subscribing to RSS Feeds within Confluence](#)
- [Managing Changes and Notifications and Tasks](#)
- [Working with Macros](#)
- [Configuring a URL Whitelist for Macros](#)
- [Confluence User's Guide](#)



The information on this page does not apply to Confluence OnDemand.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
RSS Feed URL	none	The URL of the RSS feed link you want to show.
Maximum Number of Entries	15	Limit the number of entries displayed.
Show Item Titles Only	false	Show only the titles of the news items, not the content.
Show Name/Title of RSS Feed	true	Hide the feeds title bar.

How up to date is the feed?

By default, the RSS Feed macro caches the feed results for 60 minutes before fetching the data again.

If you wish to change the default caching, use the [Cache macro](#) to define how often the RSS Feed macro fetches the feed updates. You will need to install the [Cache plugin](#) onto your Confluence site.

What happens to a page containing a disallowed URL?

Your Confluence Administrator can set up a whitelist of allowed URLs. If this is the case, you may see an error on the pages which contain the RSS Feed macro.

A user can add the [RSS Feed macro](#) or the [HTML-include macro](#) to a Confluence page. The macro code includes a URL from which the content is drawn. When the page is displayed, Confluence will check the URL against the whitelist. If the URL is not allowed, Confluence will display an error message on the page.

The error message says that Confluence "could not access the content at the URL because it is not from an allowed source" and displays the offending URL. If the person viewing the page is a Confluence Administrator, they will also see a link to the Administration page where they can configure the URL whitelist.

Here is an example of the error message, including the link shown only to Confluence Administrators:

Could not access the content at the URL because it is not from an allowed source.

<http://feathers.wordpress.com>

[Configure whitelist >>](#)

Here is an example of the error message, but without the link.

Could not access the content at the URL because it is not from an allowed source.

<http://feathers.wordpress.com>

You may contact your site administrator and request that this URL be added to the list of allowed sources.

Authentication

Privatefeeds from external sites

RSS feeds which require authentication cannot be accessed using the RSS Feed macro.

Accessing internal HTTPS feeds

This applies only to Confluence instances which have [enabled HTTPS for all content](#). If your site is fully HTTPS, the RSS Feed macro cannot access internal feeds. To enable the RSS Feed macro to access internal feeds without affecting your HTTPS setup, enable local-only HTTP access:

1. Shut down Confluence.
2. Consult the [SSL guide](#) to enable HTTP access to Confluence. You'll want to ensure that you have an HTTP connector and an SSL connector, both commented in. This means that Confluence will be accessible via both HTTP and HTTPS. However, you should *not* have a redirect port, nor rules in web.xml to redirect all traffic.
3. Instead of using web.xml to redirect traffic, insert a firewall rule to redirect all HTTP requests not from the Confluence server to the equivalent HTTPS URL. This ensures that users will only be able to access Confluence via HTTPS, as intended. If you have still left HTTP access for attachments enabled (to avoid the [IE download bug](#)) you must selectively enable those URLs as well.
4. Modify your Confluence RSS Feed macro feed link to use the HTTP URL, and restart Confluence.

Enabling and disabling the RSS Feed macro

The RSS Feed macro is a module of the Confluence HTML Macros plugin.

To enable or disable the RSS Feed macro:

1. Enable the **Confluence HTML Macros** plugin by following the instructions in [Enabling HTML macros](#).
2. In the plugin module list of the HTML macros, find the **RSS (rss-xhtml)** module and hover your cursor over it to enable or disable it.

Search Results Macro

The Search Results macro searches your Confluence site based on search terms specified in the macro code, and displays the results on the wiki page.

Using the Search Results Macro

To add the Search Results macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Search Terms	none	The search terms which this macro will use to generate its results. You can refine your search query by using operators such as 'AND' and 'OR'. For example: my_query 1 AND my_query2 For more information, take a look at the documentation on the Confluence search syntax.
Maximum Number of Results	10	Set a limit to the number of search results displayed.
Restrict to this Space Key	all	Specify the key of the space you want to search in. Note that this is case-sensitive.
Content Type	all	Specify the content type. The content types are: page , comment , blogpost , attachment , userinfo (the content of user profiles only) and spacedesc (the content of space descriptions only).

Last Modified	all	Specify a period of time in weeks, days, hours and/or minutes, to see the content modified within that time frame. For example: • 2h 35m • 3d 30m These are the values you can use: • w = weeks • d = days • h = hours • m = minutes If no time category is specified, Confluence assumes minutes. If you specify more than one time period (e.g. weeks and days), the periods must be separated by a space and they can come in any order. The time categories are not case sensitive e.g. '4d' is the same as '4D'.
Restrict to this Username	all	Specify the username of a Confluence user, to show only content created or updated by that user.

Permissions

When a user views the page containing the Search Results macro, the search results will show only pages and other content types for which the user has 'View' permission.

Related Topics

[Livesearch Macro](#)

[Searching Confluence](#)

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Section Macro

Used with the Column macro to define columns on a page. See [Working with page layouts and columns and sections](#).

Space Attachments Macro

See [Displaying a List of Attachments](#).

Space Details Macro

The Space Details macro renders the space's details in a table within the page.

Using the Space Details Macro

To add the Space Details macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Width of Table	100%	The width of the space details table, specified as a percentage (%) of the page width.

Related Topics

[Editing Space Details](#)

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Space Jump Macro

This page describes the Space Jump Macro, which is provided with the [Documentation theme](#). You can use space jumping to link from a page in one space to a page with the same name in another space, without knowing the name of the page when you create the link.



Advance warning of plans to merge Documentation theme with the default theme

This is an advance notice that we plan to merge the functionality of the Confluence Documentation theme with the Confluence default theme. We do not yet have a specific date for this plan, and we are interested in your feedback. The new default theme, to be introduced in Confluence 5.0, includes a sidebar with contextual navigation. (For a preview, see the [Confluence 5.0-m9 release notes](#).) Our plan is to include all the features of the Documentation theme into the default theme, and then remove the Documentation theme from Confluence.

If you are interested in this change and would like to give us feedback, please add a **comment on this blog post**: [Advance warning of plans to merge Documentation theme with the default theme](#). We are especially interested to know which features of the Documentation theme you use and value the most.

The Space Jump macro inserts a link onto the page. When the reader clicks the link, they will jump to a page that has the same name in another space. You specify the space when you insert the Space Jump macro.

Example: We use the Space Jump macro to put a standard message at the top of our archive spaces, telling people that they're reading an old version of the documentation and letting them jump quickly to the same page in the latest documentation. See the words '**this page in the current documentation**' in the screenshot below.


On this page:

- [Using the Space Jump macro](#)
- [Parameters](#)
- [Notes](#)

Related pages:

- [Configuring the Documentation Theme](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Screenshot: One way of using the Space Jump macro

**Using the Space Jump macro****To add the Space Jump macro to a page:**

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Space	None	The space key that contains a page with the same page title that you want the link to jump to. Space keys are case-sensitive.
Alias	None	The text to display as the hyperlinked text. If you do not supply an alias, Confluence will display the page name.

Notes

What happens if there is no page with the same name in the target space?

For the space jump to work, the target space must contain a page with the same name as the page that renders the Space Jump macro. If the target space does not contain such a page, you will see a broken link. Confluence

handles this in its usual manner: the link is coloured red. If you click the link, Confluence offers to create the page for you.

Can I use the Space Jump macro in any space?

Yes. You can use the Space Jump macro in any space, even if that space is not currently using the Documentation theme. Provided that the Documentation theme plugin and its components are installed and enabled on your Confluence site, the Space Jump macro is available in any space.

Spaces List Macro

The Spaces List macro is used to display a list of spaces within a page, similar to the list of spaces seen on the dashboard.

Using the Spaces List macro

To add the Spaces List macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type **{** and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Related pages:

- [Working with Spaces](#)
- [Creating Content](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Required?	Default	Description
Scope of spaces	no	all	Specify the view from which spaces are listed. Available options are: • all – All spaces in the Confluence installation. • category – Spaces grouped according to space categories. • favourite – Spaces which you have added to your favourites list. • new – New spaces which have been created within the last 7 days.

Width of List	no	100%	Specify the width of the table. The width of the spaces list table, specified as a percentage (%).

Notes

There is a bug in this macro that prevents people from selecting a space category. For details, please refer to this issue: [CONF-26597 - Authenticate](#) to see issue details

Status Macro

The Status macro displays a coloured lozenge (a rounded box) that is useful for reporting project status. You can choose the colour of the lozenge and the text that appears inside the lozenge. The macro also displays its current status in the editor, and you can change the status directly in the editor.

ALL GOOD!

Screenshot: Click on the Status macro lozenge to change the status.



On this page:

- [Using the Status Macro](#)
- [Parameters](#)
- [Related Topics](#)

Using the Status Macro

To add the Status macro to a page using the Macro Browser:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description

Colour	Grey	The colour of the lozenge and its border. The border will be a darker version of the same colour. The following colours are available: Grey , Red , Yellow and Green .
Title	The colour that you select.	The text that will appear inside the lozenge. If you do not specify any text, the title will be the colour of the lozenge, that is 'Grey', 'Red', 'Yellow' or 'Green'.

Related Topics

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#)

Table of Contents Macro

The Table of Contents macro scans the headings of the current Confluence page to dynamically create a table of contents from your page headings. This helps readers navigate lengthy pages by summarising the content structure and providing links to headings. Headings are indented progressively.

Using the Table of Contents Macro

Hint: For quick access from the editor toolbar, choose **Insert > Table of Contents**.

To add the Table of Contents macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the Table of Contents Macro](#)
- [Macro Parameters](#)
- [Examples](#)
- [Code examples](#)
- [Notes](#)

Related topics:

- [Table of Content Zone Macro](#)
- [Page Tree Macro](#)
- [Using the Documentation Theme](#)
- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Macro Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Output Type	list	• list — produces a typical list type TOC. • flat — produces a horizontal menu-type series of links.
Display Section Numbering	clear	Select the check box to apply outline numbering to your headings, for example: 1.1, 1.2, 1.3.
List Style	none	Select the style of bullet point for each list item. You can use any valid CSS style. For example: • none — no list style is displayed • circle — the list style is a circle • disc — the list style is a filled circle. This is the typical bullet list, and is used for this example list. • square — the list style is a square • decimal — the list is numbered (1, 2, 3, 4, 5) • lower-alpha — the list is lower-case, alphabetised (a, b, c, d, e) • lower-roman — the list style is lower roman numerals (i, ii, iii, iv, v, vi) • upper-roman — the list style is upper roman numerals (I, II, III, IV, V, VI)
Heading Indent		Sets the indent for a list according to CSS quantities. Entering 10px will successively indent heading groups by 10px. For example, level 1 headings will be indented 10px and level 2 headings will be indented an additional 10px.

Separator	brackets	This parameter applies to flat lists only. You can enter any of the following values: • brackets — Each item is enclosed by square brackets: []. • braces — Each item is enclosed by braces: { }. • parens — Each item is enclosed by parentheses: (). • pipe — Each item is separated by a pipe: • anything — Each item is separated by the value you enter. You can enter any text as a separator, for example "** *". If using a custom separator, be aware that text displays exactly as entered, with no additional white space to further separate the characters.
Minimum Heading Level	1	Select the highest heading level to start your TOC list. For example, entering 2 will include levels 2, and lower, headings, but will not include level 1 headings.
Maximum Heading Level	7	Select the lowest heading level to include. For example, entering 2 will include levels 1 and 2, but will not include level 3 headings and below.
Include Headings		Filter headings to include according to specific criteria. You can use wildcard characters. See Sun's Regex documentation for examples of constructing regular expression strings.
Exclude Headings		Filter headings to exclude according to specific criteria. You can use wildcard characters. See Sun's Regex documentation for examples of constructing regular expression strings.

Printable	checked	By default, the TOC is set to print. If you clear the check box, the TOC will not be visible when you print the page.
CSS Class Name		If you have custom TOC styles in your CSS style sheet, use this parameter to output the TOC inside <div> tags with the specified class attribute.

Examples

The examples below are based on this table of contents:

- [Places](#)
 - [Favourite Places](#)
 - [Unknown Places](#)
- [Foods](#)
 - [Favourite Foods](#)
 - [Unknown Foods](#)
- [Things](#)
 - [Favourite Foods](#)
 - [Unknown Foods](#)

Filtered Table of Contents

This example filters the headings to include those that contain 'Favourite', but excludes headings which end with 'Things'. The list is styled with Roman numerals.

Parameter	Value
List Style	upper-roman
Include Headings	Favourite.*
Exclude Headings	.*Things

The resulting table of contents is:

- I. [Favourite Places](#)
- II. [Favourite Foods](#)

Flat List

This example filters all headings to render a flat list of 'Unknowns' enclosed in square brackets (the default list style).

Parameter	Value
Output Type	flat

Maximum Heading Level	2
Include Headings	Unknown . *

The resulting table of contents is:

[[Unknown Places](#)] [[Unknown Foods](#)] [[Unknown Foods](#)]

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Notes

- When you use a Table of Contents macro in a **template**, you will see an error when you preview the template itself. But the Table of Contents macro works on the pages that people create from the template – the table of contents shows up after they have saved the page. (This is probably because the template is not defined as a page, and the Table of Contents macro works for pages only.)
- Due to an outstanding issue in the Table of Contents macro ([CONF-10619](#)), the macro browser's **Refresh** function does not render any parameter modifications. Currently, the rendering of parameter value modifications to the Table of Contents macro occurs only after the page is saved.
- **Using HTML Heading Markup with the Table of Contents Macro**
The Table of Contents macro cannot handle HTML heading markup on its own. Hence, if you use the [HTML](#) and [HTML Include](#) macros to render HTML heading markup in a Confluence page, the Table of Contents macro will not create a contents list out of these headings. (For more information about this issue, please refer to [TOC-93](#).)
However, if you insert an HTML anchor into each HTML heading on your page (based on the following syntax), the Table of Contents macro will incorporate these headings into your contents list.

```
<h2><a name="pagename-headingname"></a>Heading Name</h2>
```

The syntax for the anchor name is the page name and heading name separated by a hyphen, in which the page and heading names have all spaces removed and are converted to lowercase. If punctuation marks occur within a page or heading name, each mark should usually be converted to its URL escape code in the anchor name.

Table of Content Zone Macro

The Table of Content Zone macro enables you to mark out a 'page zone' from which to create a table of contents. Styling the headings as a flat list enables you to enclose the page text by top and bottom navigation bars similar to web navigation. When styled as a list, headings are indented progressively.

Using the Table of Content Zone Macro

To add the Table of Content Zone macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of

suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the Table of Content Zone Macro](#)
- [Parameters](#)
- [Examples](#)
- [Notes](#)

Related pages:

- [Table of Contents Macro](#)
- [Page Tree Macro](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
location	both	Specifies where in the zone the output list is displayed: top , bottom , or both , which encloses the page zone content.
Output Type	list	Specifies the layout for the table of contents: • list – produces a vertical list, typical of a TOC. • flat – produces a horizontal menu-type series of links, for example: [Heading 1] [Heading 2] [Heading 3].
Display Section Numbering	false	Select to apply outline numbering to your headings, for example: 1.1, 1.2, 1.3.

List Style	none	Specifies the style of bullet point for each list item. You can use any valid CSS style. For example: • none — no list style is displayed • circle --- the list style is a circle • disc — the list style is a filled circle. This is the typical bullet list, and is the one we're using for this example list • square — the list style is a square • decimal — the list is numbered (1, 2, 3, 4, 5) • lower-alpha — the list is lower-case, alphabetised (a, b, c, d, e) • lower-roman — the list style is lower roman numerals (i, ii, iii, iv, v, vi) • upper-roman — the list style is upper roman numerals (I, II, III, IV, V, VI)
Heading Indent		Sets the indent for a list output type, according to CSS quantities. Entering "10px" will successively indent list heading levels by 10px. For example, h1 headings will be indented 10px and h2 headings will be indented an additional 10px.

Separator	brackets	Only applies to the flat output type . Specifies the display style of the links. You can enter any of the following values: • brackets — Each item is enclosed by square brackets: []. • braces — Each item is enclosed by braces: { }. • parens — Each item is enclosed by parentheses: (). • pipe — Each item is separated by a pipe: • anything — Each is separated by the value you enter. You can enter any text as a separator, for example '***'. If using a custom separator, be aware that text displays exactly as entered, with no additional white space to further separate the characters.
Minimum Heading Level	1	Select the largest heading level to start your TOC list. For example, 2 will list h2, h3, and h4 headings, but will not include h1 headings.
Max Heading Level	7	Select the smallest heading level to include in the TOC. For example, 2 will list h1 and h2, but will not include h3 and below.
Include Headings		Filter the included headings according to specific criteria. You can use wildcard characters. See Sun's Regex documentation for examples of constructing regular expression strings.
Exclude Headings		Exclude headings according to specific criteria. You can use wildcard characters. See Sun's Regex documentation for examples of constructing regular expression strings.
Printable	true	By default, the TOC is set to print. If you clear this parameter, the TOC will not be visible when you print the page.

CSS Class Name		If you have a custom TOC in your CSS style sheet, you can use this parameter to output the TOC with the specified "class" attribute.

Examples

The examples are based on a page with the following headings:

- [Places](#)
 - [Favourite Places](#)
 - [Unknown Places](#)
- [Foods](#)
 - [Favourite Foods](#)
 - [Unknown Foods](#)
- [Things](#)
 - [Favourite Foods](#)
 - [Unknown Foods](#)

Filtered Table of Contents

This example will filter all headings to include those that contain "Favourite", but will exclude any heading which ends with the word "Things". The list is styled with upper-case Roman numerals.

Parameter	Value
Output Type	list
List Style	upper-roman
Include Headings	Favourite.*
Exclude Headings	.*Things

Screenshot: Filtered TOC 'zone' headings

I. Favourite Places
II. Favourite Foods

Flat List

This example will filter all headings to render a flat list of "Unknowns" enclosed in square brackets.

Parameter	Value
Output Type	flat
Separator	brackets
Max Heading Level	2
Include Headings	Unknown.*

Screenshot: Filtered TOC 'zone' headings displayed as a flat list

[[Unknown Places](#)] [[Unknown Foods](#)] [[Unknown Foods](#)]

Notes

- Due to an outstanding issue in the Table of Content Zone macro ([CONF-10619](#)), the Macro Browser's **Refresh** function does not render any parameter modifications. Currently, the rendering of parameter value modifications to the Table of Content Zone macro occurs only after the page is saved.
- Using HTML Heading Markup with the Table of Content Zone Macro — The Table of Content Zone macro cannot handle HTML heading markup on its own. Hence, if you used the [HTML](#) and [HTML Include](#) macros to render HTML heading markup in a Confluence page, the Table of Content Zone macro will not create a contents list out of these headings. (For more information on about this issue, please refer to [TOC-93](#).)

However, if you insert an HTML anchor into each HTML heading on your page (based on the following syntax), the Table of Content Zone macro will incorporate these headings into your contents list.

```
<h2><a name="pagename-headingname"></a>Heading Name</h2>
```

The syntax for the anchor name is usually the page name and heading name separated by a hyphen, in which the page and heading names have all spaces removed and are converted to lowercase. If punctuation marks occur within a page or heading name, each mark should usually be converted to its URL escape code in the anchor name.

Tasklist Macro

The Tasklist macro allows you to create and update a list of tasks on the wiki page. Users viewing the page can modify the tasks without having to edit the page, provided they have the required permissions to modify the page.

You may also be interested in the lightweight task list that you can add directly onto your page, via the editor insert menu. This method also allows you to notify users that tasks have been assigned to them. See [Managing Tasks in Confluence](#).

Using the Tasklist macro

To add the Tasklist macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type **{** and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the Tasklist macro](#)
- [Parameters](#)
- [Editing the task list while viewing a page](#)
- [Sorting the tasks](#)
- [Viewing the progress on tasks completed](#)
- [Notes](#)

Related pages:

- [Managing Tasks in Confluence](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Title	'Task List'	The name of the task list. This is displayed as the title above the list of tasks.
Width of List	530px	The width of the task list.
Enable Locking	clear	When selected, you can lock individual tasks so that they cannot be changed. See instructions below on editing the task list .
Prompt on Delete	clear	When selected, the user must confirm the deletion of a task in the list.

Editing the task list while viewing a page

While viewing a page, you can change the tasks in a task list as follows:

Action	Description
Adding a task	Type the task description in the box under the list title, and click Add .
Completing/uncompleting a task	Click the check box next to a task to mark the task as complete. The task name will become a lighter color and the progress bar will be updated. Clear the check box to mark the task as uncompleted. You can also click Uncheck all to mark all tasks as uncompleted.

Editing a task	Move your cursor over the task and click the edit icon (pencil) that appears to the right of the task. The task name will become editable and the edit icon will be replaced with a save icon. Make your change and press the 'Enter' key to save or click the save icon.
Deleting a task	Move your cursor over the task and click the delete icon (trash can) that appears to the right of the task.
Viewing details of a task	Click the arrow icon to the left of the task name. The task details will open in an expanded view.
Locking a task	Provided that the Enable Locking parameter has been selected, you can click the lock icon to prevent the task from being edited, deleted, or otherwise changed.
Changing the priority	When the task details are visible, click the appropriate option — High , Medium or Low .
Assigning the task	When the task details are visible, change the assignee of the task by typing in or searching for a username.

Screenshot: Task List showing task details

Planning a Holiday

▶ ☐ Book tickets

▼ ☐ Check passport expiry

Priority: ☒ High ☐ Medium ☐ Low

Assigned To:

Created: Mar 28, 2008

▶ ☐ Apply for visa

▶ ☐ Buy suitcases

Sort by: ▼

Sorting the tasks

There are two ways to sort the tasks in the list:

- Using the **Sort by** list.
- Using drag and drop.

Select one of the sort options from the 'Sort by' list:

Option	Description
Custom	This is the default option.
Priority	Sort the list in order of the priority you have allocated to each task.
Date Created	Sort the list in order of the dates upon which the tasks were created.
Completed	Move all completed tasks to the bottom or top of the list.
Name	Sort the list in order of the task names.
Assignee	Sort the list in order of the usernames assigned to the tasks.

Once you have selected a sort option, use the icon beside the **Sort by** box to reverse the sort order.

Dragging and dropping a task into a new position:

Drag a task up or down the list using the 'drag me' handle to the right of the task name. Make sure the task is positioned to the left of the existing tasks. A space will open and you will be able to drop the task into its new position.

Viewing the progress on tasks completed

The bar at the top of the task list displays two different colours, indicating the percentage of tasks completed.

Screenshot: Progress Bar on Task List

Notes

- It is not possible to add a due date to the task list. If you are interested in this improvement request, you can comment on or vote for this issue: [CONF-7371 - Authenticate to see issue details](#)
- The Tasklist macro does not notify users that a task has been assigned to them. But you can do that using the lightweight task list accessible from the editor tool bar. See [Managing Tasks in Confluence](#).

Tip Macro

Using the Tip macro, you can highlight a helpful tip on a Confluence page. The macro creates a green-coloured box surrounding your text as shown below.

**Tip Macro Example**

This text is rendered inside the tip macro.

Using the Tip macro**To add the Tip macro to a page:**

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the Tip macro](#)
- [Parameters](#)

Related pages:

- [Working with Macros](#)
- [Info Macro](#)
- [Note Macro](#)
- [Warning Macro](#)
- [Panel Macro](#)
- [Styling Confluence with CSS \(Not applicable to Confluence OnDemand.\)](#)
- [Error Box Macro - Example of a User Macro \(Not applicable to Confluence OnDemand.\)](#)
- [Confluence User's Guide](#)

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Optional Title	none	The title of the tip. If specified, it will be displayed in bold next to the icon.
Show Tip Icon	true	If cleared, the icon will not be displayed.

User List Macro

The User List macro displays a list of users registered in Confluence, based on their group membership.

Using the User List Macro**To add the User List macro to a page:**

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Group(s)	none	Specifies one or more groups whose Confluence users you want to list, using a comma-separated list of group names. To see all users registered in a Confluence installation, specify an asterisk (*) for this parameter's value.
Display Online/Offline Users	none	Select to generate a list of online users. Clear to generate a list of offline users. In order to make this feature functional, a System Administrator needs to enable the User Log In Listener for your Confluence site. <i>Not applicable to Confluence OnDemand.</i>

Related Topics

[Working with Macros](#)

[Configuring the User List Macro](#) *Not applicable to Confluence OnDemand.*


[Confluence User's Guide](#)

User Profile Macro

The User Profile macro displays a short summary of any Confluence user's profile on your Confluence page or blog. This is the same summary that appears in a [Hover Profile](#), which appears whenever you mouse-over any user's name in the Confluence interface.

 The information contained within your own summarised profile can be [edited](#) using your [User Profile](#) view.

Screenshot: Example of the User Profile Macro



On this page:

- [Parameters](#)

Related pages:

- [Working with Macros](#)
- [Confluence User's Guide](#).

Using the User Profile Macro

To add the User Profile macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Username	none	The username of the Confluence user whose profile summary you wish to show.

User Status List Macro

The User Status List macro displays a history of any Confluence user's status updates on your Confluence page or blog. This is the same history that appears in the user's [Status Updates view](#).

Screenshot: Example output of the User Status List macro

“ Time to look at networks Clear · Delete · Feb 15, 2013
“ Updating my profile picture Delete · Feb 15, 2013
“ Making Confluence sing... Delete · Feb 15, 2013

On this page:

- [Using the User Status List Macro](#)
- [Parameters](#)

Related pages:

- [Working with Macros](#)
- [User Status Updates](#)
- [Confluence User's Guide](#).

Using the User Status List Macro

To add the User Status List macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Username	none	The username of the Confluence user whose history of status updates you wish to show.



If you wish to list status updates made by more than just one user, you can use the [Recently Updated macro](#) with the following parameter-value combinations:

- **Include these Content Types Only** — status
- **Author(s) by username** — the user(s) whose status updates you want to include in the list. If you leave this field blank, the status updates of all users will be included.

View File Macro

The View File macro allows you to embed an Office or PDF document into your Confluence page. First attach the document to a wiki page and then use one of the View File macros to display the document's content.

When users view the page, they will see the content of the Office document. Users do not need to have Office installed in order to see the content of the Office document. If they do have Office installed, users will be able to open the document for editing in their Office application.

For a full list of Office Connector prerequisites and limitations, please refer to:

- [Office Connector Prerequisites](#)
- [Office Connector Limitations and Known Issue](#)

For an overview of all Office Connector features, please refer to [Working with the Office Connector](#).

On this page:

- [Displaying an Office or PDF Document in Confluence](#)
- [Parameters for the Office and PDF Macros](#)
- [Editing a Word Document or Excel Spreadsheet](#)
- [Troubleshooting](#)
- [Related Topics](#)

Displaying an Office or PDF Document in Confluence

To display an Office or PDF document in a page, use one of the following View File macros in the [macro browser](#):

- Office Excel

- Office Powerpoint
- Office Word
- PDF

To add one of the View File macros to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters for the Office and PDF Macros

Parameters are options that you can set to control the content or format of the macro output.

Macro	Parameter	Default	Description
All View File macros	Page Name	The page which contains the macro	Enter a page name, if you wish to display a document which is attached to another Confluence page.
	File Name	none	The file name of the Office or PDF document to be displayed. The document must be attached to a page on your Confluence site.
Office Excel	Show Grid?	true	Select to show grid lines around each cell of the Excel spreadsheet. Clear to hide these grid lines.
	Worksheet Name	Last worksheet viewed in the spreadsheet	The name of the worksheet that you want displayed.
	Last Row	Last row with content	The number of the last row you want displayed, starting from '0' as the first row.
	Last Column	Last column with content	The number of the last column you want displayed, starting from '0' as the first column.

Office Powerpoint	Height		Specify the height of the display, in pixels (default) or as a percentage of the window's height.
	Slide Number	none	Specify the number of the slide that you want displayed on the Confluence page, where the first slide is numbered zero. Instead of a slide show, the page will display just the single slide, represented as a JPEG image.
	Width		Specify the width of the display, in pixels (default) or as a percentage of the window's width.

✔ Reducing the size of the spreadsheet

Use the **Last Column** and **Last Row** parameters to reduce the size of the spreadsheet displayed on the wiki page. This is especially useful to prevent the display from showing empty cells. This will also help to prevent 'out of memory' errors.

✔ Presentation display options

By default, a presentation is displayed as a dynamic slide show, using Adobe Flash Player. However, you can use the **Slide Number** parameter to display just one of the slides as a static JPEG image.

Editing a Word Document or Excel Spreadsheet

When viewing a wiki page that displays an attached Office document, you can launch your Office editor directly from Confluence by clicking the title bar of the document.

You will find detailed instructions in [Editing an Office Document from Confluence](#).

Troubleshooting

Problems? Please refer to our guide to the [Office Connector limitations and known issues](#).

Related Topics

- [Working with the Office Connector](#)
- [Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Warning Macro

The Warning macro allows you to highlight a warning note on a Confluence page.

It creates a red-coloured box surrounding your text as shown below.



**Warning Macro Example**

This text is rendered inside the warning macro.

Using the Warning Macro**To add the Warning macro to a page:**

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Optional Title	none	The title of the warning note. If specified, will be displayed in bold next to the icon.
Show Warning Icon	true	If "false", the icon will not be displayed.

Related Topics[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Widget Connector Macro

The Widget macro, or Widget Connector, allows you to embed certain multimedia content from other web sites into your Confluence page.

It supports the following content:

- Gadgets and other widgets: [Google Gadgets](#), [Widgetbox](#).
- Videos: [YouTube](#), [MySpace Video](#), [Yahoo Video](#), [Dailymotion](#), [Episodic](#), [Vimeo](#), [Metacafe](#), [blip.tv](#), [Viddler](#).
- Photos and images: [Flickr](#), [Skitch.com](#).
- Micro-blogging: [Twitter](#), [FriendFeed](#), [BackType](#).
- Documents and presentations: [SlideShare](#), [SlideRocket](#), [Scribd](#), presentations on [Google Docs](#).
- Calendars: [Google Calendar](#).
- Forms and online databases: [Wufoo HTML Form Builder](#).
- Support and customer satisfaction: [Get Satisfaction](#).

There are live examples of many of these on the [widget examples page](#). If you wish to extend the functionality of this plugin, please see [Extending the Widget Connector](#).

On this page:

- [Using the Widget Connector](#)
- [Parameters](#)
- [Live Example of Flickr Photos](#)
- [Live Example of Google Gadget](#)
- [More Examples of Macro Code](#)
- [Troubleshooting](#)
- [Related Topics](#)

Using the Widget Connector**To add the Widget Connector to a page:**

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Description
Web Site's Widget URL	This is the URL provided by the external web site for embedding content from that web site onto another web page.
Pixel Height (Value Only)	Specify the height of the display, in pixels.
Pixel Width (Value Only)	Specify the width of the display, in pixels.

Live Example of Flickr Photos

This example displays all photos from Flickr with the tag 'Atlassian'. It uses this URL: <http://www.flickr.com/photos/tags/atlassian/>

Live Example of Google Gadget

This example lets you play with a Google Gadget, Gadzi's Monkey Virtual Pet. It uses this URL: <http://www.google.com/ig/directory?synd=open&num=24&url=http://www.gadzi.com/gadgets/monkey.xml&output=html>

More Examples of Macro Code**Google Gadgets**

You need to find the URL for the Google Gadget you want to display.

Here is one way to find a gadget's URL:

1. Go to the [Google Gadgets directory](#).
2. Find the gadget you want then click its name, such as 'Spider'.
3. The gadget's summary page will open. Copy the URL from your browser's address bar. The URL looks

something like this one:

```
http://www.google.com/ig/directory?synd=open&num=24&url=http://abowman.googlepages.com/spider.xml&output=html
```

You can also use the URL of the 'add gadget' page. The page is called 'Add "gadgetx" to your iGoogle page':

1. There are a couple of ways to get to the 'add gadget' page:
 - Click a '+Google' button underneath the gadget when displayed on a page somewhere.
 - Or click 'Add Stuff' on your iGoogle page.
2. Copy the URL from your browser's address bar. The URL would look something like this one:

```
http://www.google.com/ig/adde?synd=open&source=ggyp&moduleurl=abowman.googlepages.com/spider.xml
```

Widgetbox widgets

You will need to find the URL for the Widgetbox widget you want to display.

Here is one way to find a widget's URL:

1. Ensure you are logged in to Widgetbox and that you are viewing the [Widgetbox Gallery](#).
2. Find the widget you want then click its name, such as 'cyber-pet'.
3. The widget's summary page will open. Within the Get Widget section, click the Atlassian Confluence icon



. The Widgetbox **Add to Confluence** dialog box appears, containing the URL required for the Widget Macro.

 If you cannot see this icon, click the **more...** link to reveal it.

4. In the Widgetbox Add to Confluence dialog box, click **Copy**.
5. Copy the URL from your browser's address bar. The URL looks something like this one:

```
http://widgetbox.com/confluence/b8327e33-c8eb-4a38-b842-fba866ffdd28
```

YouTube

You will need to find the URL for the YouTube video that you want to display.

To find a YouTube video's URL:

1. Go to [YouTube](#) and search for the video you want.
2. Click the title of the video, such as 'Wikis in Plain English'.
3. The video's summary page will open on YouTube. Choose **Share**.
4. Choose **Options**, located under the video's URL.
5. Choose **Long link**, then copy the long URL. It looks something like this:

```
http://au.youtube.com/watch?v=-dnL00TdmLY
```

Note: You must use the long YouTube URL. The shortened URL (like this one: http://www.youtube.be/<video_key>) does not work in the widget connector.

MySpace Videos

You will need to find the URL for the MySpace video that you want to display.

To find a MySpace video's URL:

1. Go to [MySpace Video](#) and search for the video you want.
2. Click the title of the video, such as 'Glacier Creek Confluence Time Lapse'.
3. The video's summary page will open. Copy the URL from your browser's address bar. The URL looks something like this one:

```
http://vids.myspace.com/index.cfm?fuseaction=vids.individual&videoid=3376248&searchid=20c789f6-1ae9-459a-bfec-75efcfc2847c
```

Yahoo Video

You will need to find the URL for the Yahoo video that you want to display.

To find a Yahoo video's URL:

1. Go to [Yahoo Video](#) and search for the video you want.
2. Click the title of the video, such as 'Wiki Technology Trend: Past, Now and Future'.
3. The video's summary page will open. Copy the URL from the address bar of your browser. The URL looks something like this:

```
http://video.yahoo.com/watch/423158/2424140
```

 If you are unable to obtain a unique URL from your browser's address bar, click the envelope (Share) icon on the lower section of the video screen and copy the contents of the **Link** field.

Dailymotion Video

You will need to find the URL for the Dailymotion video that you want to display.

To find a Dailymotion video's URL:

1. Go to [Dailymotion](#) and search for the video you want.
2. Click the title of the video, such as 'Wiki Technology Trend: Past, Now and Future'.
3. The video's summary page will open. Copy the URL from the address bar of your browser. The URL looks something like this:

```
http://www.dailymotion.com/user/spacevidcast/video/x7zevj_spacevidcast-2009-promo-video_tech
```

 If you are unable to obtain a unique URL from your browser's address bar, click **Menu** at the lower right section of the video screen, select **URL & Embed Code** and copy the contents of the **Link** field.

Episodic

You will need an [Episodic](#) user account if you want to create and distribute videos via Episodic.

To embed an Episodic video onto a Confluence page:

1. Find the video and copy the URL from the address bar of your browser. The URL looks something like this:

```
http://app.episodic.com/shows/13/episodes/493
```

2. Paste the URL into the **Web Site's Widget URL** box in the Macro Browser.

Vimeo

You will need to find the URL for the Vimeo video that you want to display.

To find a Vimeo video's URL:

1. Go to [Vimeo](#) and search for the video you want.
2. Click the title of the video, such as 'The Wiki Show - Allison the Russian High Kicker'.
3. The video's summary page will open. Copy the URL from the address bar of your browser. The URL looks something like this one:

```
http://www.vimeo.com/909808
```

Metacafe

You will need to find the URL for the Metacafe video that you want to display.

To find a Metacafe video's URL:

1. Go to [Metacafe](#) and search for the video you want.
2. Click the title of the video, such as 'Wikis In Plain English (How To)'.
3. The video's summary page will open. Copy the URL from the address bar of your browser. The URL looks something like this one:

```
http://www.metacafe.com/watch/679493/wikis_in_plain_english_how_to/
```

blip.tv

This integration is currently broken. Please refer to [CONF-27266](#) for details of the issue .

Viddler

This integration is currently broken. Please refer to [CONF-27267](#) for details of the issue .

Flickr

You can embed a slide show of photos from [Flickr](#) by supplying a URL that specifies one of the following:

- Photos with a specific **tag**.
- Photos belonging to the photostream of a specific Flickr **user**.
- A **set** of photos as defined by the Flickr user.
- A user's photostream starting at a specific **photo**.

If you want to do something else, we suggest that you try any Flickr URL. It should work.

Below are some examples of the Widget macro code for embedding Flickr images.

Flickr Photos with a Specific Tag

This URL displays a slide show of Flickr photos that are tagged with the word 'Atlassian' <http://www.flickr.com/ph>

[otos/tags/atlassian/](#)

Flickr Photos from a Specific User

This URL displays a slide show of photos from the Flickr photostream of user 'Atlassian': <http://www.flickr.com/photos/atlassian/>

Flickr Photos from a Specific Set

This URL displays a slide show of Flickr photos from the set 'Melbourne Cup - November 2008' created by user 'Atlassian': <http://www.flickr.com/photos/atlassian/sets/72157608657271078/>

A Specific Flickr Photo

This URL displays a slide show of photos from the Flickr photostream of the user 'Atlassian', starting with a specific photo: <http://www.flickr.com/photos/atlassian/3003538919/>

Skitch.com

You will need to find the URL for the Skitch image that you want to display.

To embed a Skitch image onto a Confluence page:

1. Go to [Skitch.com](#).
2. Find the image and copy the URL from the address bar of your browser. The URL looks something like this:

```
http://skitch.com/atlassian/411g/example-image
```

Note: Skitch is now integrated with Evernote, as described in this blog post from *The Next Web*: [Evernote is bringing Skitch into its core service, Skitch.com will be archived](#). As a result, private images on Skitch.com are no longer accessible and will not work in the Confluence widget connector. Existing public images on Skitch.com will remain available.

Twitter

Use a [Twitter](#) link in the Widget macro to display a dynamic list of the latest tweets sent by a user or matching a Twitter search.

To display the latest messages from a Twitter user, add the user's Twitter link as the URL in the Widget macro.

```
http://twitter.com/username
```

This URL will display Mike Cannon-Brooke's Twitter messages: <http://twitter.com/mcannonbrookes>

To display the latest messages resulting from a Twitter search, add the Twitter search link as a URL in the Widget macro.

- Make sure you use the supported format of the search URL:

```
http://search.twitter.com/search?q=my search term
```

The following format is *not* supported:

```
http://twitter.com/#search?q=my search term
```

- The '#' tag is not supported (not even in its URL-encoded form %23).

This URL will display the most recent tweets containing the word 'AtlassianDragons': <http://search.twitter.com/search?q=AtlassianDragons>

FriendFeed

To display the latest messages from a [FriendFeed](#) user, add the user's FriendFeed link as the URL in the Widget macro. For example:

BackType

To display the latest blog or website comments from a [BackType](#) user, add the user's BackType widget link as the URL in the Widget macro. For example:

SlideShare

You will need to find the URL for the SlideShare presentation that you want to display.

To find a SlideShare presentation's URL:

1. Go to [SlideShare](#) and search for the presentation you want.
2. Click the title of the presentation, such as 'Using JIRA & Greenhopper for Agile Development'.
3. The presentation's summary page will open. Copy the URL from the address bar of your browser. The URL looks something like this one:

```
http://www.slideshare.net/jleyser/using-jira-greenhopper-for-agile-development-presentation
```

SlideRocket

You will need to find the URL for the SlideRocket presentation that you want to display.

To find a SlideRocket presentation's URL:

1. Log in to [SlideRocket](#) and go to your library of presentations.
2. Copy the 'web link' for the presentation you want to display. This will give you a URL that looks something like this one:

```
http://app.sliderocket.com/app/FullPlayer.aspx?id=132f9db7-b0fb-4f51-b974-36652774971b
```

3. Paste the URL into the Widget macro code on your Confluence page.

Scribd

You will need to find the URL for the Scribd presentation that you want to display.

To find a Scribd presentation's URL:

1. Go to [Scribd](#) and search for the presentation you want.
2. Click the title of the presentation, such as 'My Sea Friends Coloring Book'.
3. The presentation's summary page will open. Copy the URL from the address bar of your browser. The URL looks something like this one:

```
http://www.scribd.com/doc/5683554/My-Sea-Friends-Coloring-Book
```

4. Paste the URL into the Widget macro code on your Confluence page.

Google Docs Presentations

This integration is currently broken. Please refer to [CONF-24927](#) for details of the issue.

Google Calendar

You can embed a Google Calendar into your page and to do this, you will need to add the URL for the Google Calendar that you want to display.

To find the URL for a Google Calendar:

1. Log in to [Google Calendar](#).
2. In the calendar list on the left side of the page, ensure the appropriate calendar is selected, click the down-arrow button next to the calendar name and then select the **Calendar settings** option. (Alternatively, if available, click the **Manage Calendars** link at the bottom of the calendar list and then click the name of the appropriate calendar.)
3. In the **Calendar Address** section, click the **HTML** button. A pop-up message with your calendar's public URL appears.
4. Copy the URL from this pop-up message. The URL looks something like this:

```
http://www.google.com/calendar/embed?src=somebody%40example.com&ctz=Australia/Sydney
```

5. Paste the URL into the Widget macro code on your Confluence page.

Wufoo HTML Form Builder

To display an HTML form built in the [Wufoo HTML Form Builder](#), add the form's link as a URL to the Widget Macro. For example:

```
http://examples.wufoo.com/forms/contact-form/
```

Get Satisfaction social support application

To display a feedback form for a [Get Satisfaction](#) community, add the community or company link as a URL to the Widget Macro. For example:

```
http://getsatisfaction.com/atlassian
```

Troubleshooting

If the URL given in the Widget Connector macro does not work, the macro displays an icon and the base URL.

For example, the following code:

```
http://example.com/invalid
```

will result in an image like the one below:



example.com

Related Topics

[Working with Macros](#)

Take me back to the [Confluence User's Guide](#).

Widget Connector Examples

This page contains working examples of some services currently supported by the Widget Connector. This page lets you preview what each widget will look like and see how to interact with it. For detailed usage, see [Widget Connector Macro](#).

Flickr

```
http://www.flickr.com/photos/tags/atlassian
```

```
http://www.flickr.com/photos/atlassian/
```

```
http://www.flickr.com/photos/atlassian/sets/72157608657271078/
```

```
http://www.flickr.com/photos/atlassian/3003538919/
```

On this page:

- [Flickr](#)
- [Google Docs](#)
- [YouTube](#)
- [MySpace](#)
- [Vimeo](#)
- [BlipTV](#)
- [Viddler](#)
- [Skitch](#)
- [Twitter](#)
- [FriendFeed](#)
- [SlideShare](#)
- [SlideRocket](#)
- [Scribd](#)
- [Wufoo](#)
- [Example of widget error message](#)

Related pages:

- [Widget Connector Macro](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Google Docs

This integration is currently broken. Please refer to [CONF-24927](#) for details of the issue.

YouTube

```
http://au.youtube.com/watch?v=-dnL00TdmLY
```

Note: You must use the long YouTube URL, available under **Share > Options**. For detailed instructions, see [the user's guide to the widget macro](#).

MySpace

vids.myspace.com

```
http://vids.myspace.com/index.cfm?fuseaction=vids.individual&videoid=3376248&searchid=20c789f6-1ae9-459a-bfec-75efcfc2847c
```

Vimeo

```
http://www.vimeo.com/909808
```

BlipTV

This integration is currently broken. Please refer to [CONF-27266](#) for details of the issue.

Viddler

This integration is currently broken. Please refer to [CONF-27267](#) for details of the issue.

Skitch

Skitch is now integrated with Evernote, as described in this blog post from *The Next Web*: [Evernote is bringing Skitch into its core service, Skitch.com will be archived](#). As a result, private images on Skitch.com are no longer accessible and will not work in the Confluence widget connector. Existing public images on Skitch.com will remain available.

Twitter

```
http://twitter.com/mcannonbrookes
```

```
http://search.twitter.com/search?q=AtlassianDragons
```

FriendFeed

```
http://friendfeed.com/myname
```

SlideShare

```
http://www.slideshare.net/jleyser/using-jira-greenhopper-for-agile-development-presentation
```

SlideRocket

```
http://app.sliderocket.com/app/FullPlayer.aspx?id=132f9db7-b0fb-4f51-b974-36652774971b
```

Scribd

```
http://www.scribd.com/doc/28967704/How-did-Shakespeare-change-the-English-language|height=600px
```

Wufoo

```
http://examples.wufoo.com/forms/contact-form/
```

Example of widget error message

This is an example of the error message you will see, if the Widget connector cannot find the URL or service specified.



example.com

http://example.com/invalid

Working with Drafts

A draft is a 'snapshot' of unsaved page content, which Confluence creates automatically at regular intervals while you are editing a page or blog post. This can minimise the loss of work if your Confluence site experiences a problem, since you can retrieve the page content from your last saved draft.

How do drafts work in Confluence?

At regular intervals, Confluence automatically saves a draft of the page you are editing. If a network failure or system error prevents you from saving your page, you can retrieve its last saved draft and continue working on the page from the last saved draft.

Drafts are created while you are adding and editing a page or blog post. Each new draft replaces the previously saved draft. By default, Confluence saves a draft of your page once every thirty seconds. However, a [Confluence administrator](#) can [configure how often drafts are saved](#). In addition, whenever you edit a page and then move to another screen, Confluence will automatically save a draft.

When you edit the page again, Confluence will let you know that a version of the page you are editing was not saved and will give you the option to resume editing it.

Each time Confluence saves a draft, it displays a message and the time of the last save near the **Save** button on the edit screen.

On this page:

- [How do drafts work in Confluence?](#)
- [Viewing drafts](#)
- [Viewing your unsaved changes](#)

Related pages:

- [Resuming the Editing of a Draft](#)
- [Configuring the Time Interval at which Drafts are Saved](#)
- [Concurrent Editing and Merging Changes](#)
- [Confluence User's Guide](#)

Screenshot: Message displaying the time when the draft was last saved

☒ **Notify watchers**

Draft autosaved at 1:56 PM (view change)

More about drafts:

- A user only has access to the drafts of pages they have been working on and whose content has not yet been saved.
- A user cannot create a draft explicitly.

- A user's drafts are listed in the 'Drafts' tab of their [profile](#).
- Once a user has [resumed editing a draft](#), or chosen to discard it, the draft is removed from their drafts tab.

Viewing drafts

Your drafts are listed on the **Drafts** tab of your user profile.


To see your drafts:

Choose **your profile picture** at top right of the screen, then choose **Drafts**.

Viewing your unsaved changes

While editing a page or blog post, you can view any 'unsaved' changes you have made since the last automatically saved draft, by clicking **view change** (near the **Save** button).

Screenshot: Segment of the unpublished changes window



Configuring the Time Interval at which Drafts are Saved

By default, Confluence saves a draft of your page once every thirty seconds. [Confluence administrators](#) can configure how often drafts are saved.

As a [Confluence administrator](#), you can set the time interval at which drafts are saved as follows:

1. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
2. Click **General Configuration** in the left-hand panel.
3. Edit the setting for **Draft Save Interval**.

Related pages:

- [Working with Drafts](#)
- [Resuming the Editing of a Draft](#)

Concurrent Editing and Merging Changes


Sometimes, two or more people may edit a page at the same time. When this happens, Confluence will do its best to ensure that nobody's changes are lost.

How will I know if someone else is editing the same page as I am?


If another user is editing the same page as you, Confluence will display a message above your edit screen letting you know who the other user is and when the last edit was made.

Related pages:

- [Page History and Page Comparison Views](#)
- [Viewing Page Information](#)
- [Working with Drafts](#)
- [Confluence User's Guide](#).

Screenshot: Notification of Simultaneous Page Editing**What happens if two of us are editing the same page and the other user saves before I do?**

If someone else has saved the page before you, when you click 'Save', Confluence will check if there are any conflicts between your changes and theirs. If there are no conflicting changes, Confluence will merge both the edits successfully. If there are any conflicts, Confluence will display them for you and give you the option to either '**Overwrite**' the other user's changes, '**Merge your changes**' manually, or '**Discard**' them.

Screenshot: Notification of Page Editing Conflict*Example Scenario*

For example, Alice and Bob both edit the same page at the same time.

If Alice clicks save before Bob, Bob is now effectively editing an out-of-date version of the page. When Bob clicks save, Confluence will examine his changes to see if any overlap with Alice's. If the changes do not overlap (i.e. Alice and Bob edited different parts of the page), Bob's changes will be *merged* with Alice's automatically.

If Bob's changes overlap with Alice's, Confluence will display an error message to Bob showing where Alice has changed the page, and giving Bob the options to overwrite Alice's changes with his own, to re-edit the document to incorporate Alice's work, or to cancel his own changes entirely.

Resuming the Editing of a Draft

If you have typed some content into a Confluence page or blog post, Confluence will save a draft of it, even if you were not able to successfully save the page or blog post, or add a title to it.

There are two ways to resume editing an unsaved page or blog post:

A. Using your drafts view. To resume editing a draft from this view:

1. Choose **your profile picture** at top right of the screen, then choose **Drafts**.
2. Choose **Resume Editing** next to the appropriate draft to resume editing that draft.

Note: If you had not yet entered a page title, the draft will be listed with the title '*Untitled*'.

B. If you had created a new page or blog post but did not save it, then when you next [add a page](#) or blog post in that space, Confluence will ask you if you want to resume editing the page that was not saved. If you click **resume editing**, the draft and its unsaved content will be restored, allowing you to continue editing it.

Related pages:

- [Working with Drafts](#)

Screenshot: Resume Editing

 A version of this page you were editing at Feb 14, 2013 16:39 was saved as a draft. Do you want to [view the change](#), [resume editing](#) or [discard it](#)?

What happens if I am editing the draft of a page that has since been updated?

When this happens, Confluence will display a message informing you that you are editing an outdated page. If there are no conflicts between the two versions, Confluence will give you the option to **Merge and Resume editing**.

If there are any conflicts, Confluence will give you the option to **View the Conflict** or to **Discard** your changes.

Recording Change Comments

A 'change comment' is a short description that summarises the changes made to a page during an editing session. Change comments are a useful way of keeping track of the history of a page.

A change comment is not the same as a comment added to a page. Refer to [Commenting on pages and blog posts](#) for information about that type of comment.

Note that once a change comment has been added and the page has been saved, it is not possible to update or remove the change comment.

On this page:

- [Entering a Change Comment](#)
- [Viewing a Change Comment](#)
- [Viewing a History of Change Comments](#)

Related pages:

- [Viewing Page Information](#)
- [Page History and Page Comparison Views](#)
- [Confluence User's Guide](#)

Entering a Change Comment

You can enter change comments in the field located below the edit screen:

Screenshot: Entering change comments

What did you change?	☒ Notify watchers	Preview	Save	Cancel

Viewing a Change Comment

Once a comment has been added, it becomes visible in the view mode of the page, so that users are aware of the most recent changes made to a page. If a comment has been recorded, you will see a **show comment** link below the page title. Click the link to view the comment.

Screenshot: The 'show comment' link

Sample Page  1 Added by Rach Admin, last edited by Josh User on Feb 14, 2013 (view change) show comment

The **hide comment** link allows you to hide the comment again, so that it does not distract you from the content of the page.

Screenshot: The 'hide comment' link

Sample Page

@ 1 Added by Rach Admin, last edited by Josh User on Feb 14, 2013 (view change) hide comment
Comment: Added penguin image

Viewing a History of Change Comments

The change comments for a page are recorded under the 'Recent Changes' section of the page's 'Info' view and in the page's 'History' view.

Screenshot: History of change comments on Info view

Recent Changes

Since you last logged in:
Josh User, Sophie User made 2 changes. (view)

Since you last edited this page:
Josh User made 1 change. (view)

Time	Editor	
Feb 14, 2013 10:58	Josh User	View Changes
Added penguin image		
Feb 14, 2013 10:57	Sophie User	View Changes
Fixed a typo		
Feb 14, 2013 09:06	Rach Admin	

View Page History

Screenshot: History of change comments on History view

Pages / ... / Sample Page

View Tools

Page History

Compare selected versions


Version	Date	Changed By	Operations
☐ CURRENT (v. 3)	Feb 14, 2013 10:58	Josh User: Added penguin image	
☐ v. 2	Feb 14, 2013 10:57	Sophie User: (Fixed a typo)	Restore this version
☐ v. 1	Feb 14, 2013 09:06	Rach Admin	Restore this version

Return to Page Information

Creating Attractive and Dynamic Pages

Confluence has a number of features that help you build attractive pages to engage your readers and give them the opportunity to interact with up-to-date information. This page summarises those features and provides links to detailed instructions.

Adding visual appeal



Pictures, photographs and screenshots. Confluence pages can display images from your Confluence site and from other websites. To put an image into Confluence, you can upload it and attach it to a page or blog post, then display it on any page, blog post or comment. Alternatively, display an image from a remote location via the web address (URL). See [Displaying Images](#)

Galleries. Use the [Gallery Macro](#) to display a set of images. When viewing the page, people can click any of the pictures to zoom in and view the images as a slide show.

People. Add a [Profile Picture Macro](#) to show a picture of a Confluence user, or a [User Profile Macro](#) to show a summary of the person's profile as well as their avatar.

Multimedia. You can display movies, animations and videos, and embed audio files on your Confluence page. For example, Confluence supports Adobe Flash, MP3, MP4, and various other movie formats. See [Embedding Multimedia Content](#).

Social video and image sharing. The Widget macro displays live content from social sites such as [YouTube](#) and other video sharing sites, and [Flickr](#) for shared photographs. See the guide to the [Widget Connector Macro](#)

On this page:

- [Adding visual appeal](#)
- [Bringing numbers to life](#)
- [Displaying presentations and documents](#)
- [Pulling in content from your issue tracker](#)
- [Telling a story in pictures](#)
- [Varying the structure of your pages](#)
- [Integrating your content with social media](#)
- [Showing activity streams](#)

Related pages:

- [Working with Macros](#)
- [Using the Editor](#)
- [Confluence User's Guide](#)

Bringing numbers to life

The [Chart Macro](#) offers a variety of graphs and charts that you can use to illustrate statistics and other numerical data.

Illustration: A 3-dimensional bar chart produced by the Chart macro



Displaying presentations and documents

Display your Office documents and other presentations directly in Confluence.


- Attach your Office documents to a Confluence page then display them on the page, using the [View File Macro](#). This works for Excel spreadsheets, PowerPoint presentations and Word documents.
- Display PDF files in Confluence too, also with the [View File Macro](#).
- Use the [Widget Connector Macro](#) to show slide decks hosted on SlideShare and other online presentation sites.

Pulling in content from your issue tracker

Many project teams and customers have useful information on a JIRA issue tracker. Rather than copying and pasting it onto your Confluence page, you can display it directly from the source, thus ensuring that the information shown in Confluence is always up to date.

Link to a feature request in your issue tracker, or display a list of fixed issues – useful for release notes and project planning. See the [JIRA Issues Macro](#) and the [JIRA option in the Confluence editor](#).

Illustration: A PowerPoint slide deck



Telling a story in pictures

A number of Confluence add-ons provide sophisticated tools for creating diagrams and mockups.

For example:

- [Balsamiq Mockups for Confluence](#)
- [Creately for Confluence](#)
- [Gliffy Confluence Plugin](#)
- [Graphviz Plugin for Confluence](#)
- [Lucidchart for Confluence](#)

Search the [Atlassian Marketplace](#) for more add-ons.

Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#).

Varying the structure of your pages

Page layouts provide a fixed set of columns and panels for your page. Alternatively, try breaking up your page into a varied set of sections and columns, via the flexible Section and Column macros. See the detailed guidelines to [Working with Page Layouts and Columns and Sections](#).

Do you need to display tabular data, which your readers can sort when viewing the page? See [Working with Tables](#).

Use other macros to highlight and format sections of your page:

- [Panel](#)
- [Tip](#)
- [Info](#)
- [Note](#)
- [Warning](#)
- [Code block](#)
- [Noformat](#)

Illustration: A Gliffy diagram




Illustration: A Panel macro

Use a [macro](#) or add a [smiley](#) to brighten your page. 😊

Integrating your content with social media

People share information on various social sites. You can make Confluence a focal point where people collect their shared information and see what is happening in the areas that matter to them.

Use the [Widget Connector macro](#):

- Show a live stream of tweets from a Twitter user, or tweets matching a Twitter search.
- Display a video from YouTube or other online movie sites.
- Share photographs from Flickr.
- Display slide decks hosted on SlideShare and other online presentation sites.
- See what else the [Widget Connector macro](#) can do.

Showing activity streams

Make your Confluence pages dynamic and interactive with:

- An activity stream showing updates and comments on Confluence and other linked applications. See [Working with Confluence Gadgets](#).
- An RSS feed from within Confluence or an external site. See [Subscribing to RSS Feeds within Confluence](#).
- A list of recent blog posts from within Confluence. See [Blog Posts Macro](#).

Illustration: A Twitter stream via the Widget macro

Working with Templates

When you add a new page, you do not have to write the content from scratch. Instead, you can base your new page on a template. A template is a Confluence page with predefined content.

Some examples of where templates are useful:

- A software development project may have a template for use cases.
- A systems administration space may have a template for defining what information is kept about each server.

Global templates and space templates

In Confluence, there are two places to store your page templates:

- **Space templates:** These page templates are available in a specific space only. People who have [space administrator](#) permission can define templates via the space administration screen.
- **Global templates:** These page templates are available in every space on the site. People who have [Confluence Administrator permission](#) can define the global templates via the Confluence Administration Console.

Confluence administrators can also [download predefined templates](#).

On this page:

- [Global templates and space templates](#)
- [Creating a template](#)
- [Using a template](#)
- [System templates](#)
- [Useful plugins](#)

Related pages:

- [Adding a Template](#)
- [Administering Site Templates](#)
- [Importing Templates](#)
- [Creating a Page using a Template](#)
- [Confluence User's Guide](#)

Creating a template

You can write your template using the Confluence editor. You can also add special variables to the page, if you want to include fields that the author will complete when adding the page. See [Adding a Template](#) for more information.

Using a template

Page templates are used only when adding a page. It is not possible to apply a template to an already-existing page. Once a page has been added using a template, the template is no longer linked to the page. All further editing is performed as if the template was never used. Some plugins provide enhanced template functionality. You can search the [Atlassian Marketplace](#) for template add-ons.

See [Creating a Page using a Template](#) for more information.

System templates

Confluence also provides 'system templates' containing content like the site welcome message and default space content. See [Administering Site Templates](#).

Useful plugins

Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#).

Extended template functionality:

- [Scaffolding plugin](#)
- [Search the Atlassian Marketplace](#)

Adding a Template

A template is a predefined page that can be used as a framework when creating new pages. Templates are useful for setting a common style or format for a page.

In Confluence, there are two places to store your page templates:

- **Space templates:** These page templates are available in a specific space only. People who have [space administrator](#) permission can define templates via the space administration screen.
- **Global templates:** These page templates are available in every space on the site. People who have [Confluence Administrator permission](#) can define the global templates via the Confluence Administration

Console.

Adding a space template

Space templates are available in one space only.

To add a template for a space:

1. Go to the space and choose **Space Tools** on the sidebar.
2. Choose **Content Tools > Templates**.
3. Choose **Add New Space Template**.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Templates** from the space administration options.
3. Choose **Add New Space Template**.

The 'Create Template' screen will appear. Add content as described [below](#).

On this page:

- [Adding a space template](#)
- [Adding a global template](#)
- [A template illustration](#)
 - [Using the template editor](#)
 - [The resulting form when the template contains variables](#)
- [Adding content to your template](#)
 - [Labels](#)
 - [Images and other attachments](#)
 - [Variables used as form fields](#)
- [Converting an existing page to a template](#)
- [Notes](#)

Related pages:

- [Creating a Page using a Template](#)
- [Working with Templates](#)
- [Working with Confluence Labels](#)
- [Working with Macros](#)
- [Using the Editor](#)
- [Confluence User's Guide](#)

Adding a global template

Global templates are available in all spaces in your Confluence site.

To add a global template:

1. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
2. Choose **Global Templates** in the left-hand panel.
3. Choose **Add New Global Template**.

The 'Create Template' screen will appear. Add content as described [below](#).

A template illustration

Using the template editor

This illustration shows the template editor with an image, some text, styling, and variables.

The screenshot shows the 'Meeting minutes template' editor. At the top, the title 'Meeting minutes template' is displayed with a blue arrow pointing to it and the text 'Enter the template title'. Below the title is a rich text editor toolbar with various formatting options like Paragraph, Bold, Italic, Underline, and a 'Variables' dropdown menu. A blue arrow points to the 'Variables' menu with the text 'Insert a variable'. The main content area contains a form with several input fields: 'Minutes for' (with a green bug icon), '\$MeetingName', 'Date' (\$Date), 'Time' (\$Time), 'Location' (\$Location), 'Attendees' (with a dropdown menu showing 'Text', 'Multi-line Text', and 'List'), and 'Apologies'. A blue arrow points to the dropdown menu with the text 'Set the variable type'. Below the form is a section titled 'Minutes' with a bullet point 'Add the first item here...'. At the bottom, there is a blue arrow pointing to a label icon with the text 'Add labels'.

The resulting form when the template contains variables

This screenshot shows the form displayed when someone creates a page based on the template containing the above variables. (See [Creating a Page using a Template.](#))

Page Template Wizard

Step 2: Fill in template variables

The information you supply will become part of the content in your new page.

	Minutes for Status Meeting (MeetingName)
Date	15/02/2013 (Date)
Time	9:00 AM (Time)
Location	Meeting Room 1 (Location)
Attendees	
Apologies	

Minutes

- Add the first item here...

<< Back Next >>

Adding content to your template

Add a name for your template.

Enter text into the body of the template, and use the editor toolbar to apply styles, layout and formatting. You can add links and macros. In general, you can use the Confluence editor in the same way as on a page. In addition, you can add variables which will produce a form for data collection when someone adds a page based on the template.

Below are some points of special interest in templates.

Labels

Choose **Labels** to add one or more labels to the template. These labels will be included in all pages created using this template.

Images and other attachments

You cannot attach an image or other file to a template. Instead, attach the file to another page, and insert it into the body of the template.

For example:

- You can attach an image to a page and then choose **Insert > Image** to embed the image into the template.
- You can attach a PDF file to a page and then choose **Insert > Other Macros > PDF** to embed the PDF file into the template.

Variables used as form fields

You can add variables to your template, to act as form fields. When someone creates a page based on the template, Confluence will display a text entry box for each field. The user can enter data into each field, and the data is inserted onto the new page.


Every variable must have a unique name. If you add the same variable more than once in the same template, Confluence will make sure that they have the same value when the user saves the page. This is useful if you need the same information in more than one place in the page.



To insert a variable into a template:

1. Place your cursor on the template where you want the variable to appear.
2. Choose **\$ Variables** from the editor toolbar.
3. Choose **Add New Variable**. Alternatively, you can choose the name of an existing variable if you want the same variable to appear more than once in the template.
4. Enter the variable name.
5. Press **Enter**. By default this will create a single-line text input field.
6. To change the variable type, click the variable placeholder. The variable's property panel will appear.
Choose one of the variable types: **Text**, **Multi-line Text**, or **List**. See [below](#) for a description of each type.

Speeding up variable entry with autocomplete: Type **\$** and the variable name, then press Enter, to add a new variable or to select an existing variable from a list of suggestions. The suggestions are drawn from variables already defined in this template.

These are the types of variable available:

Variable type	Description
Text	Creates a single-line text input field. <i>Screenshot: A template variable called \$purpose and its property panel</i>  The screenshot shows a text input field with the placeholder text "This tutorial helps you to \$purpose". Below the input field is a property panel with three tabs: "Text", "Multi-line Text", and "List". The "Text" tab is currently selected.

Multi-line text	Creates a text box that allows more than one line of text. By default, the text area is 5 rows depth and 100 characters wide. You can change the size by typing over the digits in the variable property panel. <i>Screenshot: A multi-line variable and its property panel</i> 
List	Creates a dropdown list. You must specify the values that will appear in the dropdown list. The values: • Must be separated by commas. • Can include letters, numbers, special characters, and spaces. • Cannot include commas (except as the list separation character). <i>Screenshot: A list variable and its property panel</i> 

Converting an existing page to a template

If you would like to convert an existing page to a template, you can copy the content from the page and paste it into the template editor. There is no automated way of doing this.

Please note the section [above](#) about images and other attachments in templates.

Notes

- You cannot insert variables via the 'Insert wiki markup' option in the editor toolbar.
- Page templates are used only when adding a page. It is not possible to apply a template to an already-existing page. Once a page has been added using a template, the template is no longer linked to the page. All further editing is performed as if the template was never used. Some plugins provide enhanced template functionality. You can search the [Atlassian Marketplace](#) for template add-ons.
- When you use a [Table of Contents macro](#) in a template, you will see an error when you preview the template itself. But the Table of Contents macro works on the pages that people create from the template – the table of contents shows up after they have saved the page. (This is probably because the template is not defined as a page, and the Table of Contents macro works for pages only.)
- The editor for templates is available only in **Confluence 4.3 and later**. Please refer to the [earlier documentation](#) for a description of the wiki markup editor templates.

- Confluence also provides 'system templates' containing content like the site welcome message and default space content. See [Administering Site Templates](#).

Creating a Page using a Template

You can create a page based on a global template (available to all spaces) or a space template (available only to that space). Before reading this page, make sure that someone has already [created a template](#) on your Confluence site.

Information copied from the template to the page

When you create a page based on a template, Confluence will copy the following content and information from the template to the new page:

- Labels
- Text and styles
- Layouts and formatting
- Macros
- Embedded images and other files. Note that you cannot attach an image or other file to a template. But if the template displays an image or file from another page, the new page will display that image or file too.

Form fields displayed by the template

If the template author included variables in the template, Confluence will display a form prompting you to supply values for the variables when you add the page.

On this page:

- [Information copied from the template to the page](#)
- [Form fields displayed by the template](#)
- [Using a template to create a page](#)
- [Notes](#)

Related pages:

- [Adding a Template](#)
- [Using the Editor](#)
- [Working with Confluence Labels](#)
- [Confluence User's Guide](#)

Using a template to create a page

To create a page based on a template:

1. Choose **Create** on the header
2. Select a **space** and the **template** you want to use and choose **Next**
3. If the template contains variables, you will now see a form. Type the relevant information into the form fields, and choose **Next**.
4. Now you will see a new page based on the template. If you added information in the form fields, the page content will include that information.
5. Type a name for the page where you see 'New Page'.
6. Add more content or make any other changes required.
7. Choose **Save**.

Screenshot: Form showing template variables when creating a page from a template

Page Template Wizard

Step 2: Fill in template variables

The information you supply will become part of the content in your new page.

	Minutes for Status Meeting (MeetingName)
Date	15/02/2013 (Date)
Time	9:00 AM (Time)
Location	Meeting Room 1 (Location)
Attendees	
Apologies	

Minutes

- Add the first item here...

<< Back Next >>

Notes

Page templates are used only when adding a page. It is not possible to apply a template to an already-existing page. Once a page has been added using a template, the template is no longer linked to the page. All further editing is performed as if the template was never used. Some plugins provide enhanced template functionality. You can search the [Atlassian Marketplace](#) for template add-ons.

Editing a template

A template is a predefined page that can be used as a prototype when creating new pages. Templates are useful for giving pages a common style or format. This page is about changing an existing template.

Note: Page templates are used only when adding a page. It is not possible to apply a template to an already-existing page. Once a page has been added using a template, the template is no longer linked to the page. All further editing is performed as if the template was never used. Some plugins provide enhanced template functionality. You can search the [Atlassian Marketplace](#) for template add-ons.

In Confluence, there are two places to store your page templates:

- **Space templates:** These page templates are available in a specific space only. People who have [space administrator](#) permission can define templates via the space administration screen.
- **Global templates:** These page templates are available in every space on the site. People who have [Confluence Administrator](#) permission can define the global templates via the Confluence Administration

Console.

Confluence also provides 'system templates' containing content like the site welcome message and default space content. See [Administering Site Templates](#).

Related pages:

- [Adding a Template](#)
- [Creating a Page using a Template](#)
- [Working with Template](#)
- [Working with Pages](#)
- [Confluence User's Guide](#)

To edit a space template:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Content Tools > Templates**.
3. A list of templates for the space displays. Choose **Edit** next to the template that you want to modify.
4. Make changes, or add new content, as you would when [adding a template](#).
5. Choose **Save**.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.

Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Templates** from space administration options.
3. A list of templates for the space displays. Choose **Edit** next to the template that you want to modify.
4. Make changes, or add new content, as you would when [adding a template](#).
5. Choose **Save**.

To edit a global template:

1. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
2. Choose **Global Templates** in the left-hand navigation panel.
3. A list of templates for the Confluence site displays. Choose **Edit** next to the template that you want to modify.
4. Make changes, or add new content, as you would when [adding a template](#).
5. Choose **Save**.

Removing a Template

A template is a predefined page that can be used as a prototype when creating new pages. Templates are useful for giving pages a common style or format. This page is about deleting an existing template, at space level or at site (global) level.

Templates are used only when adding a page. Once a page has been added, the template is no longer linked to the page. You can therefore remove the template without affecting any existing pages.

You need to be a [space administrator](#) to remove a space template, and you need [Confluence Administrator permissions](#) to remove a global template.

Note: Deleted templates cannot be restored.

Related pages:

- [Working with Templates](#)
- [Confluence User's Guide](#)

To remove a space template:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Content Tools > Templates**
3. A list of templates for the space displays. Choose **Remove** next to the template that you want to delete.
4. Confirm the deletion when prompted.

If your space uses the Documentation Theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Templates** from the space administration options.
3. A list of templates for the space displays. Choose **Remove** next to the template that you want to delete.
4. Confirm the deletion when prompted.

To remove a global template:

1. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
2. Choose **Global Templates** in the left-hand navigation panel.
3. A list of templates for the Confluence site displays. Choose **Remove** next to the template that you want to delete.
4. Confirm the deletion when prompted.

Working with the Office Connector

The Office Connector is bundled with Confluence 2.10 and later. It allows you to:

- Import an Office document into Confluence format
- Attach an Office document to a Confluence page and display its content in Confluence, without converting the content.
- Edit the attached document in the Office application, directly from the Confluence page.

 Please be aware that source code is currently not available for the Confluence Office Connector.

Table of Contents

- [Office Connector Prerequisites](#)
- [Displaying Office Files in Confluence](#)
- [Importing a Word Document into Confluence](#)
- [Editing an Office Document from Confluence](#)
- [Editing an Office Spreadsheet from Confluence](#)
- [Editing an Office Presentation from Confluence](#)
- [Installing the Firefox Add-On for the Office Connector](#)

Related Topics

[View File Macro](#)

[Configuring the Office Connector](#) *(Not applicable to Confluence OnDemand.)*

[Confluence User's Guide](#)

Office Connector Prerequisites

The page describes the software and setup you need to use the [Office Connector](#).

Your [System Administrator](#) can enable or disable the Office Connector or parts of it. The Office Connector options can appear in different places on your Confluence page, depending on the themes and configuration of your Confluence site. Please refer to [Configuring the Office Connector](#) in the *Confluence Administration Guide* and discuss any configuration problems with your administrator. *(Not applicable to Confluence OnDemand.)*

Overall prerequisites

- Ensure that Java 5 (JDK 1.5) or higher is installed on your Confluence server.
- The **WebDAV plugin** must be enabled, because the Office Connector uses WebDAV to transfer information to and from Office documents. Note that the WebDAV plugin is bundled with Confluence, and can be enabled or disabled by the [System Administrator](#). If necessary, refer to the instructions on [enabling plugins](#) and [configuring the WebDAV options](#).
- Ensure that your Confluence server's **base URL** is set correctly. (Check it by going to the 'General Configuration' screen in the Confluence Administration Console, as described in [Configuring the Server Base URL](#).) When a user edits a wiki page in Word and then uploads the page back to the Confluence server, the base URL determines where the document will be saved. If the base URL is incorrect, the documents may be saved to a different Confluence server.

Prerequisites for viewing Office and PDF files in Confluence

If you want to use the [View File macro](#), or to [view Office files](#) attached to a Confluence page, you need the setup described below.

Browsers and Flash Player

You can use any browser to view an Office file on a wiki page or attachment view, provided that you have installed [Adobe Flash Player](#) version 9 or later. You do not need to have an Office desktop application installed on your computer in order to view Office files in Confluence.

File Types

Confluence can display files compatible with Microsoft Office 97-2007, and PDF files, of the following types:

- .doc and .docx
- .xls and .xlsx
- .ppt and .pptx
- .pdf

On this page:

- [Overall prerequisites](#)
- [Prerequisites for viewing Office and PDF files in Confluence](#)
- [Prerequisites for importing Word documents into Confluence](#)
- [Prerequisites for editing Office files directly from Confluence](#)

Related pages:

- [Working with the Office Connector](#)
- [Configuring the Office Connector](#) (Not applicable to Confluence OnDemand.)
- [Confluence User's Guide](#)

 The information on this page *does not apply* to Atlassian OnDemand sites with multiple apps. If you are using Confluence-only OnDemand, the information does apply.

Prerequisites for importing Word documents into Confluence

- Document import can import Microsoft Word documents of the file types .doc and .docx. These must be valid Word 97-2007 format documents.

Prerequisites for editing Office files directly from Confluence

The Office Connector allows you to edit Office files embedded in a wiki page or from the page's attachments view.

To make use of these editing capabilities, you will need the setup described below.

Browsers

- If you are using Firefox, you will need to install a Firefox add-on. Firefox will prompt you to do this, the first time the add-on is required. You will find instructions in [Installing the Firefox Add-On for the Office Connector](#).
- **Note: No Chrome support.** Chrome does not support WEBDAV clients, so this feature will not work. Please refer to this issue for more information: [CONF-23322](#).

Office editors

To edit Office files, you will need to have [Microsoft Office](#) or [OpenOffice](#) installed. (See the configuration matrix below.)

- If you are using Firefox, you can choose which of the above editors you want to use. The Firefox add-on allows you to configure this option for each file type. See [Installing the Firefox Add-On for the Office Connector](#).
- If you are using Internet Explorer, you will need Microsoft Office. You cannot edit Office files in OpenOffice when using Internet Explorer.

Configuration matrix

You need one of the following software combinations to edit Office files from your wiki page:

Operating System	Office Version	Browser
• Windows 7, • Windows Vista, or • Windows XP with Service Pack 2 or 3	• OpenOffice 2.x – 3.x, or • Microsoft Office XP, 2003, 2007 or 2010	• Internet Explorer 8.x – 9.x, or • Firefox – latest stable version

Mac OS X 10.5 and 10.6	OpenOffice 2.x – 3.x - The "Edit in Word" feature is known to work in OpenOffice 3 .2.0.	Firefox – latest stable version
Linux	OpenOffice 2.x – 3.x The only known supported Office editor for Linux is OpenOffice. But in theory it should work with any WebDAV-aware application.	Firefox – latest stable version

Displaying Office Files in Confluence

Confluence can display Office files that are attached to a page. If you have an Office application installed, you will also be able to edit these Office files in your Office application.

These are two of the ways that Confluence can interact with Office files. For an overview of all Office Connector features, please refer to [Working with the Office Connector](#).

i Your [System Administrator](#) can enable or disable the Office Connector or parts of it. The Office Connector options can appear in different places on your Confluence page, depending on the themes and configuration of your Confluence site. Please refer to [Configuring the Office Connector](#) in the *Confluence Administration Guide* and discuss any configuration problems with your administrator. *(Not applicable to Confluence OnDemand.)*

On this page:

- [Prerequisites](#)
- [Attaching and Displaying Office Files and PDF Files](#)
- [Viewing and Editing the Attached Office Files](#)
- [Troubleshooting](#)
- [Related Topics](#)

Prerequisites

If you want to use the [View File macro](#), or to [view Office files](#) attached to a Confluence page, you need the setup described below.

Browsers and Flash Player

You can use any browser to view an Office file on a wiki page or attachment view, provided that you have installed [Adobe Flash Player](#) version 9 or later. You do not need to have an Office desktop application installed on your computer in order to view Office files in Confluence.

File Types

Confluence can display files compatible with Microsoft Office 97-2007, and PDF files, of the following types:

- .doc and .docx
- .xls and .xlsx
- .ppt and .pptx
- .pdf

Attaching and Displaying Office Files and PDF Files

There are two ways to do this in Confluence:

- Attach Office files to a page and display them in a Confluence page [using the View File or Attachments macros](#)

- Attach an Office or PDF file to a page and embed its contents onto the page by simply [dragging and dropping it into the editor window](#)

To attach and display Office files in Confluence using macros:

1. Attach the Office file(s) to a Confluence page:
 - View the Confluence page on which you want to display your document.
 - Choose **Tools > Attachments**.
 - Browse for your Office files and upload them to the Confluence page.
Refer to detailed instructions in [Attaching Files to a Page](#).
2. Now you have two options for displaying the attached document:
 - You can embed the document into the Confluence page, using one of the Office Word, Office Excel, Office PowerPoint or View PDF macros. These macros can be found using the macro browser. Refer to the detailed instructions in the [View File macro](#) topic.
 - You can display a list of page attachments using the [Attachments macro](#). People viewing the page will be able to click the **View** link to see the Office or PDF document in Confluence.

To attach and display an Office file on a Confluence page using 'drag and drop':

- Drag the Office file from your computer and drop it into the editor window. Only one file can be dragged and dropped at a time. The appropriate [View File macro](#) placeholder will appear in the position where you dragged the file. However, the contents of the file will be rendered in full when you preview, or save and view, the page.
 Older browser versions may not support drag and drop - refer to [Using Drag-and-Drop in Confluence](#).

Viewing and Editing the Attached Office Files

If an Office document is [attached to a Confluence page](#), you can view the attached Office document from within Confluence. View the Office document in one of the following ways:

- Search for the Office document by file name, then click **View** next to the Office document on the Search results page. (See [Searching Confluence](#).)
- View the list of attachments for a specific Confluence page, then click **View** next to the Office document on the Attachments page. (See [Viewing Attachment Details](#).)
- View a list of attachments displayed on a page via the Attachments macro, then click **View** next to the Office document in the list of attachments. (See [Displaying a List of Attachments](#).)
- View a Confluence page which has the Office document embedded in the page via the View File macro. (See [View File Macro](#).)

Any Confluence user who has an Office application installed will also be able to launch their Office editor from within Confluence:

- [Editing an Office Document from Confluence](#).
- [Editing an Office Presentation from Confluence](#).
- [Editing an Office Spreadsheet from Confluence](#).

Troubleshooting

Problems? Please refer to our guide to the [Office Connector limitations and known issues](#).

Related Topics

[View File Macro](#)

[Working with the Office Connector](#)

- [Office Connector Prerequisites](#)

- [Displaying Office Files in Confluence](#)
- [Importing a Word Document into Confluence](#)
- [Editing an Office Document from Confluence](#)
- [Editing an Office Spreadsheet from Confluence](#)
- [Editing an Office Presentation from Confluence](#)
- [Installing the Firefox Add-On for the Office Connector](#)

Confluence User's Guide

Importing a Word Document into Confluence

The Office Connector in Confluence allows you to import a Word document into Confluence, so that the document's content is copied onto one or more Confluence pages.

This is just one of the ways Confluence can interact with Office documents. For an overview of all Office Connector features, please refer to [Working with the Office Connector](#).

i Your [System Administrator](#) can enable or disable the Office Connector or parts of it. The Office Connector options can appear in different places on your Confluence page, depending on the themes and configuration of your Confluence site. Please refer to [Configuring the Office Connector](#) in the *Confluence Administration Guide* and discuss any configuration problems with your administrator. *(Not applicable to Confluence OnDemand.)*

The simplest way to import a Word document is to import the entire content of the document into a single wiki page. By default, the content of the document will be created as a new wiki page.

More advanced options allow you to import the content into a new page, to split a single document into more than one wiki page, and to resolve conflicts in the titles of your pages.

These options are described below.

Prerequisites

Prerequisites for the Office Connector's document import feature:

- Document import can import Microsoft Word documents of the file types .doc and .docx. These must be valid Word 97-2007 format documents.

For a full list of Office Connector prerequisites and limitations, please refer to:

- [Office Connector Prerequisites](#)
- [Office Connector Limitations and Known Issues](#)

On this page:

- [Prerequisites](#)
- [Importing a Word Document](#)
- [Splitting a Word Document into Multiple Wiki Pages](#)

Related pages:

- [Working with the Office Connector](#)
- [Office Connector Prerequisites](#)
- [Displaying Office Files in Confluence](#)
- [Importing a Word Document into Confluence](#)
- [Editing an Office Document from Confluence](#)
- [Editing an Office Spreadsheet from Confluence](#)
- [Editing an Office Presentation from Confluence](#)
- [Installing the Firefox Add-On for the Office Connector](#)
- [Confluence User's Guide](#)

Importing a Word Document

The simplest way to import a Word document is to import the entire content of the document into a single wiki page.

This method will replace any existing content on the wiki page.

To import a Word document onto a single wiki page:

1. Create a page in Confluence (see [Creating Content](#)) or go to an existing page whose content you want replaced. View the page in view mode (not edit mode).
2. Choose **Tools > Import Word Document**.
3. Click **Browse** and find the Word document on your local drive or network.
4. Click the **Open** or **Upload** button provided by your browser. The path and file name of the document will now appear in the text box on the Office Connector import screen.
5. Click **Next** on the Office Connector import screen. The import document options screen will display.
6. The import document options are:

Option	Description
Root page title	The title of the wiki page that will contain the information from your imported document.
Import as a new page in the current space	A new wiki page will be created with the page title specified above.
Replace <pagename>	The contents of the existing page will be replaced. The page will be renamed to the page title specified above.
Delete existing children of <pagename>	The existing child pages of the page you are replacing will be deleted.
Rename imported pages if page name already exists	Assign new names to any new page which would otherwise have a duplicate name. The content of existing pages will remain unchanged.
Replace existing pages with imported pages of the same title	If imported pages have titles equal to existing pages, then the content of the Word document will overwrite the content on the existing page. Page history will be preserved.
Remove existing pages with the same title as imported pages	If imported pages have titles equal to existing pages, then the existing pages will be deleted. This will remove the page history as well as the content.
Split by heading	The content of the Word document will be split over multiple wiki pages. If you don't want to split your document into multiple wiki pages, leave the default Don't split option selected. For more information on splitting your document, please see below .

7. Click **Import**.

When the upload has finished, the content of the Word document will have been transformed into Confluence


page content. You can now view and edit this page in the usual way. There is no connection between the original Word document and this wiki page.

Screenshot: Empty page ready for import




The screenshot shows a Confluence page header for a page titled "Chocolate". The breadcrumb is "Pages / Test Space Home". To the right of the title are links for "Edit", "Share", and "Tools". Below the title, it says "Added by Rach Admin, last edited by Rach Admin on Feb 20, 2013 (view change)".

Screenshot: Selecting Word document to import



The screenshot shows the "Import Word Document: Upload" dialog. It has a text input field for "Upload:" containing the file path "C:\Users\Rachel\Desktop\Chocolate.doc". To the right of the input field is a "Browse..." button. Below the input field is a "Next" button.


Screenshot: Importing a Word document



The screenshot shows the "Import Word Document: Configuration" dialog. It contains several configuration options:

- Root page title:** A text input field containing "Chocolate".
- Where to import:** Three radio buttons:
 - ☐ Import as a new page in the current space
 - ☒ Replace Chocolate
 - ☐ Delete existing children of Chocolate
- Title conflicts:** Three radio buttons:
 - ☒ Rename imported pages if page name already exists
 - ☐ Replace existing pages with imported pages of the same title
 - ☐ Remove existing pages with the same title as imported pages
- Split by heading:** A dropdown menu currently showing "Don't split".
- Document Outline:** A list containing "Chocolate" with a document icon.
- Import:** A button at the bottom.

Screenshot: Page after import



Splitting a Word Document into Multiple Wiki Pages

When importing a Word document, you can split a single document into more than one wiki page, based on the heading styles in the document.

By default, the page names will be the same as the heading text. This may result in a conflict, if a page already exists with the same title. You can instruct the importer how to handle such conflicts.

To import a Word document into multiple wiki pages:

1. Import a Word document as [described above](#). On the import document options screen, choose how to split your document in the '**Split by heading**' field:
 - '**Split by heading**' — If you want to split the content under each heading in your document into separate child pages, select the desired heading level to split by. A preview of the page hierarchy that will be created by the split will be displayed under '**Document Outline**'. Each bullet point in 'Document Outline' represents a new page after import into Confluence.
2. Click '**Import**' to import your document.
3. When the upload has finished, the content of the Word document will have been transformed into Confluence page content. You can now view and edit this page in the usual way. There is no connection between the original Word document and this wiki page.

Screenshot: Splitting a single Word document into multiple wiki pages

Import Word Document: Configuration

Root page title:

Where to import: ☐ Import as a new page in the current space
☒ Replace Chocolate
☐ Delete existing children of Chocolate

Title conflicts: ☒ Rename imported pages if page name already exists
☐ Replace existing pages with imported pages of the same title
☐ Remove existing pages with the same title as imported pages

Split by heading:

Document Outline:

- Chocolate
 - Overview
 - Survey Results
 - Conclusions

Editing an Office Document from Confluence

When viewing a wiki page that displays an attached Office document, you can launch your Office editor directly from Confluence. This allows you to edit a Word document from within Confluence and save it back to Confluence.

This is just one of the ways Confluence can interact with Office documents. For an overview of all Office Connector features, please refer to [Working with the Office Connector](#).

i Your [System Administrator](#) can enable or disable the Office Connector or parts of it. The Office Connector options can appear in different places on your Confluence page, depending on the themes and configuration of your Confluence site. Please refer to [Configuring the Office Connector](#) in the *Confluence Administration Guide* and discuss any configuration problems with your administrator. (Not applicable to Confluence OnDemand.)

Prerequisites for Editing an Attached Office Document

The Office Connector allows you to edit Office files embedded in a wiki page or from the page's attachments view.

To make use of these editing capabilities, you will need the setup described below.

Browsers

- If you are using Firefox, you will need to install a Firefox add-on. Firefox will prompt you to do this, the first time the add-on is required. You will find instructions in [Installing the Firefox Add-On for the Office Connector](#).
- Note: No Chrome support.** Chrome does not support WEBDAV clients, so this feature will not work. Please refer to this issue for more information: [CONF-23322](#).

Office editors

To edit Office files, you will need to have [Microsoft Office](#) or [OpenOffice](#) installed. (See the configuration matrix below.)

- If you are using Firefox, you can choose which of the above editors you want to use. The Firefox add-on allows you to configure this option for each file type. See [Installing the Firefox Add-On for the Office Connector](#).

- If you are using Internet Explorer, you will need Microsoft Office. You cannot edit Office files in OpenOffice when using Internet Explorer.

Configuration matrix

You need one of the following software combinations to edit Office files from your wiki page:

Operating System	Office Version	Browser
• Windows 7, • Windows Vista, or • Windows XP with Service Pack 2 or 3	• OpenOffice 2.x – 3.x, or • Microsoft Office XP, 2003, 2007 or 2010	• Internet Explorer 8.x – 9.x, or • Firefox – latest stable version
• Mac OS X 10.5 and 10.6	• OpenOffice 2.x – 3.x • The "Edit in Word" feature is known to work in OpenOffice 3 .2.0.	• Firefox – latest stable version
• Linux	• OpenOffice 2.x – 3.x The only known supported Office editor for Linux is OpenOffice. But in theory it should work with any WebDAV-aware application.	• Firefox – latest stable version

On this page:

- [Prerequisites for Editing an Attached Office Document](#)
- [Editing an Office Document in your Office Application](#)
- [Troubleshooting](#)

Related pages:

- [Office Connector Prerequisites](#)
- [Displaying Office Files in Confluence](#)
- [Importing a Word Document into Confluence](#)
- [Editing an Office Document from Confluence](#)
- [Editing an Office Spreadsheet from Confluence](#)
- [Editing an Office Presentation from Confluence](#)
- [Installing the Firefox Add-On for the Office Connector](#)
- [Confluence User's Guide.](#)

Editing an Office Document in your Office Application

To edit an Office document in your Office application:

1. There are two ways to do this:

- **From an Office document embedded on a page:**
 - a. Go to a Confluence page with an Office document embedded on it.
 - b. Choose **Edit Document** above the embedded document.

Screenshot: Page with an embedded Word document showing the 'Edit Document' link

[Pages](#) / [Test Space Home](#)

 [Edit](#)  [Share](#)  [Tools](#)

Chocolate

@ 1 Added by Rach Admin, last edited by Rach Admin on Feb 20, 2013 ([view change](#))

[Edit Document](#) 

Overview

It has been previously noted that the Atlassian technical writing team like chocolate. A lot. We set out to test this theory.

Survey Results

Of the technical writers surveyed, all agreed that chocolate is awesome, in all its many forms.

Conclusions


Chocolate is popular.

- **From an Office document in a list of attachments:**
 - If an Office file is [attached to a Confluence page](#), you can edit this file directly in your compatible Office application, in one of the following ways:
 - View the list of attachments for a specific Confluence page, then click **Edit in Office** next to the Office file on the Attachments page. (See [Viewing Attachment Details](#).)
 - View a list of attachments displayed on a page via the Attachments macro, then click **Edit in Office** next to the Office file in the list of attachments. (See [Displaying a List of Attachments](#).)


Attachments						
Name	Size	Creator	Creation Date	Labels	Comment	
>  Chocolate.doc	11 kB	Rach Admin	Feb 20, 2013 15:16	No labels 	Properties Remove Edit in Office	

2. A window will pop up, asking you to confirm that you want to open this document.

Screenshot: Confirmation window in Firefox



Screenshot: Confirmation window in Internet Explorer



3. Click 'OK'. Now you may be asked to log in to your Confluence server.
4. Enter your Confluence username and password, then choose 'OK'.
5. The Office document will open in your Office application.
6. Make the necessary changes, then save the document. It will be saved back into Confluence.

Troubleshooting

Problems? Please refer to our guide to the [Office Connector limitations and known issues](#).

Editing an Office Spreadsheet from Confluence

When viewing a wiki page that displays an attached Office document, you can launch your Office editor directly from Confluence. This allows you to edit an Excel spreadsheet from within Confluence and save it back to Confluence.

This is just one of the ways Confluence can interact with Office documents. For an overview of all Office Connector features, please refer to [Working with the Office Connector](#).

i Your [System Administrator](#) can enable or disable the Office Connector or parts of it. The Office Connector options can appear in different places on your Confluence page, depending on the themes and configuration of your Confluence site. Please refer to [Configuring the Office Connector](#) in the *Confluence Administration Guide* and discuss any configuration problems with your administrator. (Not applicable to Confluence OnDemand.)

On this page:

- [Prerequisites for Editing an Attached Office Spreadsheet](#)
- [Editing an Office Spreadsheet in your Office Application](#)
- [Troubleshooting](#)

Related pages:

- [Office Connector Prerequisites](#)
- [Displaying Office Files in Confluence](#)
- [Importing a Word Document into Confluence](#)
- [Editing an Office Document from Confluence](#)
- [Editing an Office Spreadsheet from Confluence](#)
- [Editing an Office Presentation from Confluence](#)
- [Installing the Firefox Add-On for the Office Connector](#)

Prerequisites for Editing an Attached Office Spreadsheet

The Office Connector allows you to edit Office files embedded in a wiki page or from the page's attachments view.

To make use of these editing capabilities, you will need the setup described below.

Browsers

- If you are using Firefox, you will need to install a Firefox add-on. Firefox will prompt you to do this, the first time the add-on is required. You will find instructions in [Installing the Firefox Add-On for the Office Connector](#).
- **Note: No Chrome support.** Chrome does not support WEBDAV clients, so this feature will not work. Please refer to this issue for more information: [CONF-23322](#).

Office editors

To edit Office files, you will need to have [Microsoft Office](#) or [OpenOffice](#) installed. (See the configuration matrix below.)

- If you are using Firefox, you can choose which of the above editors you want to use. The Firefox add-on allows you to configure this option for each file type. See [Installing the Firefox Add-On for the Office Connector](#).
- If you are using Internet Explorer, you will need Microsoft Office. You cannot edit Office files in OpenOffice when using Internet Explorer.

Configuration matrix

You need one of the following software combinations to edit Office files from your wiki page:

Operating System	Office Version	Browser
• Windows 7, • Windows Vista, or • Windows XP with Service Pack 2 or 3	• OpenOffice 2.x – 3.x, or • Microsoft Office XP, 2003, 2007 or 2010	• Internet Explorer 8.x – 9.x, or • Firefox – latest stable version
• Mac OS X 10.5 and 10.6	• OpenOffice 2.x – 3.x • The "Edit in Word" feature is known to work in OpenOffice 3 .2.0.	• Firefox – latest stable version
• Linux	• OpenOffice 2.x – 3.x - The only known supported Office editor for Linux is OpenOffice. But in theory it should work with any WebDAV-aware application.	• Firefox – latest stable version

Editing an Office Spreadsheet in your Office Application

To edit an Office spreadsheet in your Office application:

1. There are two ways to do this:
 - **From an Office spreadsheet embedded on a page:**
 - a. Open a Confluence page with an Office document embedded on it.
 - b. Choose **Edit Document** above the embedded content.

Screenshot: The title bar showing 'spreadsheet.xls' above an embedded Excel spreadsheet

Pages / Test Space Home / Chocolate

Spreadsheet  Edit  Share  Tools

@ 1 Added by Rach Admin, last edited by Rach Admin on Feb 20, 2013

[Edit Document](#) 


	Monday	Tuesday	Wednesday	Thursday	Friday
Planning	3	4	1	1	0
Design	5	3	4	2	2
Development	0	0	2	5	6
Testing	0	1	0	1	0
Admin	1	1	1	1	1

- **From an Office spreadsheet in a list of attachments:**
 - If an Office file is [attached to a Confluence page](#), you can edit this file directly in your compatible Office application, in one of the following ways:
 - View the list of attachments for a specific Confluence page, then click **Edit in Office** next to the Office file on the Attachments page. (See [Viewing Attachment Details](#).)
 - View a list of attachments displayed on a page via the Attachments macro, then click **Edit in Office** next to the Office file in the list of attachments. (See [Displaying a List of Attachments](#).)


Attachments						
Name	Size	Creator	Creation Date	Labels	Comment	
>  Spreadsheet.xls	11 kB	Rach Admin	Feb 20, 2013 15:16	No labels 	Properties Remove Edit in Office	

2. A window will pop up, asking you to confirm that you want to open this document.

Screenshot: Confirmation window in Firefox



Screenshot: Confirmation window in Internet Explorer



3. Click 'OK'. Now you may be asked to log in to your Confluence server. Enter your Confluence username and password, then click 'OK'.
4. The Office spreadsheet will open in your Office application.
5. Make the necessary changes, then save the spreadsheet. It will be saved back into Confluence.

Troubleshooting

Problems? Please refer to our guide to the [Office Connector limitations and known issues](#).

Editing an Office Presentation from Confluence

When viewing a wiki page that displays an attached Office document, you can launch your Office editor directly from Confluence. This allows you to edit a PowerPoint presentation from within Confluence and save it back to Confluence.

This is just one of the ways Confluence can interact with Office documents. For an overview of all Office Connector features, please refer to [Working with the Office Connector](#).

i Your [System Administrator](#) can enable or disable the Office Connector or parts of it. The Office Connector options can appear in different places on your Confluence page, depending on the themes and configuration of your Confluence site. Please refer to [Configuring the Office Connector](#) in the *Confluence Administration Guide* and discuss any configuration problems with your administrator. (*Not applicable to Confluence OnDemand.*)

On this page:

- [Prerequisites for Editing an Attached Office Presentation](#)
- [Editing an Office Presentation in your Office Application](#)
- [Troubleshooting](#)

Related pages:

- [Office Connector Prerequisites](#)
- [Displaying Office Files in Confluence](#)
- [Importing a Word Document into Confluence](#)
- [Editing an Office Document from Confluence](#)
- [Editing an Office Spreadsheet from Confluence](#)
- [Editing an Office Presentation from Confluence](#)
- [Installing the Firefox Add-On for the Office Connector](#)

Prerequisites for Editing an Attached Office Presentation

The Office Connector allows you to edit Office files embedded in a wiki page or from the page's attachments view.

To make use of these editing capabilities, you will need the setup described below.

Browsers

- If you are using Firefox, you will need to install a Firefox add-on. Firefox will prompt you to do this, the first time the add-on is required. You will find instructions in [Installing the Firefox Add-On for the Office Connector](#).
- **Note: No Chrome support.** Chrome does not support WEBDAV clients, so this feature will not work. Please refer to this issue for more information: [CONF-23322](#).

Office editors

To edit Office files, you will need to have [Microsoft Office](#) or [OpenOffice](#) installed. (See the configuration matrix below.)

- If you are using Firefox, you can choose which of the above editors you want to use. The Firefox add-on allows you to configure this option for each file type. See [Installing the Firefox Add-On for the Office Connector](#).
- If you are using Internet Explorer, you will need Microsoft Office. You cannot edit Office files in OpenOffice when using Internet Explorer.

Configuration matrix

You need one of the following software combinations to edit Office files from your wiki page:


Operating System	Office Version	Browser
• Windows 7, • Windows Vista, or • Windows XP with Service Pack 2 or 3	• OpenOffice 2.x – 3.x, or • Microsoft Office XP, 2003, 2007 or 2010	• Internet Explorer 8.x – 9.x, or • Firefox – latest stable version
• Mac OS X 10.5 and 10.6	• OpenOffice 2.x – 3.x • The "Edit in Word" feature is known to work in OpenOffice 3.2.0.	• Firefox – latest stable version
• Linux	• OpenOffice 2.x – 3.x The only known supported Office editor for Linux is OpenOffice. But in theory it should work with any WebDAV-aware application.	• Firefox – latest stable version

Editing an Office Presentation in your Office Application

To edit an Office presentation in your Office application:

1. There are two ways to do this:
 - **From an Office presentation embedded on a page:**
 - a. Open a Confluence page with an Office presentation embedded on it.
 - b. Click the 'Edit' icon  on the bottom frame of the slide show.

Screenshot: PowerPoint presentation displayed on a Confluence page




- **From an Office document in a list of attachments:**

- If an Office file is [attached to a Confluence page](#), you can edit this file directly in your compatible Office application, in one of the following ways:
 - View the list of attachments for a specific Confluence page, then click **Edit in Office** next to the Office file on the Attachments page. (See [Viewing Attachment Details](#).)
 - View a list of attachments displayed on a page via the Attachments macro, then click **Edit in Office** next to the Office file in the list of attachments. (See [Displaying a List of Attachments](#).)


Attachments						
Name	Size	Creator	Creation Date	Labels	Comment	
> Presentation.ppt	11 kB	Rach Admin	Feb 20, 2013 15:16	No labels	Properties Remove Edit in Office	

2. A window will pop up, asking you to confirm that you want to open this document.

Screenshot: Confirmation window in Firefox



Screenshot: Confirmation window in Internet Explorer



3. Click 'OK'. Now you may be asked to log in to your Confluence server. Enter your Confluence username and password, then click 'OK'.
4. The presentation will open in your Office application.
5. Make the necessary changes, then save the presentation. It will be saved back into Confluence.

Troubleshooting

Problems? Please refer to our guide to the [Office Connector limitations and known issues](#).

Installing the Firefox Add-On for the Office Connector

If you are using Firefox as your browser, you will need to install an add-on into Firefox (the [Firefox WebDAV Launcher](#)) in order to use some features of the Office Connector. You will be prompted to install the add-on the first time you try to use a function which requires it.

For an overview of all Office Connector features, please refer to [Working with the Office Connector](#).

Note about supported web browsers: Please ensure that you are using one of the web browsers supported by Confluence. If you are using an unsupported browser or browser version, some features may not work correctly. You can find the list of supported web browsers and browser versions on this page: [Supported Platforms](#).

On this page:

- [Installing the Firefox Add-On](#)
- [Configuring the Add-On](#)
- [Security Risks](#)
- [Information about this Firefox Add-On](#)
- [Related Topics](#)


Related pages:

- [Office Connector Prerequisites](#)
- [Displaying Office Files in Confluence](#)
- [Importing a Word Document into Confluence](#)
- [Editing an Office Document from Confluence](#)
- [Editing an Office Spreadsheet from Confluence](#)
- [Editing an Office Presentation from Confluence](#)
- [Installing the Firefox Add-On for the Office Connector](#)
- [Confluence User's Guide.](#)

Installing the Firefox Add-On


You will be prompted to install the add-on the first time you try to use a function which requires it. The add-on is required for editing a wiki page in Office, or for editing an Office document which is displayed on a wiki page.

1. When you choose an option which requires the Firefox add-on, you will see a popup window like this one:




2. Click 'OK'. Some browsers may now ask you to confirm the download with a message bar across the top of the page, beneath the browser's address bar.

- You may see a message like the one shown here:




Click 'Allow'.

- Or you may see a similar message with an 'Edit Options' button like this:




- If you see the above message, click '**Edit Options**'. You will then see an 'Allowed Sites' window like this one:




This window lets you tell Firefox that your Confluence server is allowed to install add-ons into Firefox. The '**Address of web site**' box should already contain the address of your Confluence server.


- Click the '**Allow**' button to add your Confluence server to the list.
 - Go back to your Confluence page and try to edit your Office document again, e.g. by clicking '**Edit in Word**' again. Now you will see the option to install the add-on.
3. A 'Software Installation' window will appear, asking you to confirm the installation. The window will look something like the one below, but the URL will be the address of your own Confluence server:



4. Click 'Install Now'. The installation will happen and a window will pop up asking you to restart Firefox:



5. Make sure you have saved all your Confluence pages and any other work in your browser, then restart Firefox.
6. If Firefox asks you to confirm the restart, confirm it.
7. Firefox will close all the browser windows and will then start up again. You will see a window confirming that a new add-on has been installed, like this:



Configuring the Add-On


After you have installed the add-on into Firefox, you will need to configure it. Basically, you will associate a desktop application (editor) with each relevant file type. This tells the Office Connector which application to launch when it encounters a link to an editable file. The configuration is slightly different for each operating system, as described below.

Configuring the Add-On in Windows


The add-on can will automatically configure itself on Windows via the system registry. The first time you edit a new file type, the add-on will look up the default editor for that file type and make that the permanent setting.

If you want to override the registry settings, or if for some reason the automatic configuration is not working, you can configure the Firefox add-on manually.

1. In Firefox, go to the '**Tools**' menu and select '**WebDAV Launcher Options**', as shown in this screenshot:



2. A 'WebDAV Launcher Options' window will appear, allowing you to associate a specific file type (file extension) with a desktop application (editor). The window looks like this one:




3. In the '**File Extension**' box, enter the extension for a particular file type. For example, you may want to associate the 'doc' file extension with Microsoft Word 2003 or earlier. To do this, you would type 'doc' in the File Extension text box.

i If you use or have recently upgraded to Office 2007

In addition to the original Office 2003 file extensions (that is, 'doc', 'ppt' and 'xls'), you *should additionally* configure the WebDAV launcher to handle the new Office 2007-specific file extensions for Microsoft Word ('docx'), Microsoft Excel ('xlsx') and PowerPoint ('pptx').


Screenshot: Configuring the WebDAV Launcher - adding the 'doc' file extension.



4. Enter the '**Application Path**' — Use one of the following methods to specify the associated application for editing the given file type:

- Click the '**Auto**' button to load the associated application from the Windows registry.
- Alternatively, you can click the '**Browse**' button to find the application on your computer.
- Or you can manually type in the path to the application's executable file.

Screenshot: Configuring the WebDAV Launcher - adding the 'Application Path' for the 'doc' file extension.




i If you use or have recently upgraded to Office 2007

Follow the instructions in this step to add the path to the relevant Office 2007 application for the Office 2007 file extension you configured [above](#). For example, if you had a typical default installation of Office 2007, you would add the application path 'C:\Program Files\Microsoft Office\Office12\WINWORD.EXE' to the 'docx' extension.

- Click the **Add** button. The file extension association will be added to the list. For example, in the picture below you can see that the 'doc' extension has been associated with 'C:\Program Files\Microsoft Office\OFFICE11\WINWORD.EXE'. This is the path to the Microsoft Word 2003 executable on a specific Windows machine.

Screenshot: Configuring the WebDAV Launcher - configuration of the 'doc' file extension complete.



Configuring the Add-On in Mac OS X

The configuration procedure is similar to Windows, as shown above. Note that there is no 'Auto' button in Mac OS X.

Configuring the Add-On in Linux

The only known supported Office editor for Linux is [OpenOffice](#). (See [Office Connector Prerequisites](#).)

There is no automatic configuration on Linux. You will need to associate each file type with your Office editor in Firefox. Note that there is no 'Auto' button in Linux.

The configuration procedure is similar to Windows, as shown above.

For both Ubuntu and OpenSUSE, the configuration will look something like this:

File Extension	Application Path
doc and docx	/usr/bin/oowriter
ppt and pptx	/usr/bin/ooimpress
xls and xlsx	/usr/bin/oocalc

Security Risks


 Please be aware that there are security risks in installing this add-on to Firefox. Internet Explorer is exposed to the same risks, because it can directly open Office documents. By installing the add-in into Firefox, you are exposing Firefox to the same risks.

Summary of the risks:


- Office documents can contain macro viruses. Before opening an Office document, make sure that you trust the source of the document.
- There are known flaws in the Office file formats and Microsoft Office that an attacker can exploit to gain control of your machine. Microsoft has fixed the known exploits in the latest Service Packs for all Microsoft Office versions. But new exploitations may arise at any time. Again, be sure that you trust the source of a document before opening it.

The add-on tries to reduce the risk by supporting the following:

- **Same origin policy** — The add-on can only open documents from the same host that initiated the action.
- **Digital signature** — The add-on is digitally signed. When you install the add-on please verify that it is signed by *Benryan Software Inc.*



- **Prompt the user for confirmation** — You will always be warned before a file is opened. **Please read these warnings carefully before opening a file.** The warning tells you the complete URL of the file as well as the complete application path of the application opening the file.



Information about this Firefox Add-On

Add-on name:	WebDAV Launcher
Description:	Adds the ability to launch a WebDAV URL directly in a WebDAV-aware client.
Latest version:	See the WebDAV Launcher add-on page at Mozilla

Compatible with:	All versions of Firefox, up to and including the latest stable version.
Author:	Atlassian Pty Ltd

Related Topics

[Working with the Office Connector](#)

Importing Content Into Confluence

This page describes how to get text, pages, images and other content into Confluence, by converting the content from another storage format and importing it into the Confluence wiki.

Importing content from other Confluence sites

For content originating from other instances of Confluence:

- If the Confluence major versions are the same, [export the space](#) from the originating Confluence site and [import](#) it into the destination Confluence site.
- If the Confluence major versions are different, you can use an intermediate server to [migrate versions](#).

Page history, attachments, and page content will be preserved and you will be able to do multiple pages at once. The drawbacks are that it may be inconvenient if the Confluence versions differ, and you cannot have a duplicate space key on the destination instance. (You cannot import a space with the same space key as a space that already exists.)

On this page:

- [Importing content from other Confluence sites](#)
- [Importing content from other wikis](#)
- [Importing content from a Microsoft Word document](#)
- [Importing web content](#)
- [Importing other non-wiki content](#)
- [Note about add-on support](#)

Related pages:

- [Working with the Office Connector](#)
- [Data Import and Export](#)
- [Confluence User's Guide](#)

Importing content from other wikis

Check whether the [Universal Wiki Converter](#) can import the content. See [Importing Content from Another Wiki](#).

Importing content from a Microsoft Word document

The Office Connector in Confluence allows you to import a Word document into Confluence. The document's content is copied onto one or more Confluence pages. See [Importing a Word Document into Confluence](#).

Importing web content

Here are some options for importing or displaying web content on a Confluence page:

- Use the [Widget Connector Macro](#) to display videos, slide shows, twitter chats, documents and more, sourced from other web sites and displayed on your Confluence page.
- Convert a HTML file to a Confluence page using the [HTML To Confluence Converter plugin](#).

- Embed an external web page into Confluence with the [HTML Include macro](#).
- Use HTML code in a page with the [HTML macro](#).

Importing other non-wiki content

Importing non-wiki markup into Confluence requires a conversion process:

- Text with basic formatting can be pasted directly into the editor. This includes simple Word documents or web pages.
- Files such as Microsoft Excel documents can be imported using a [content converter plugin](#).
- Confluence pages saved to disk can be [imported from disk](#).
- Files can be uploaded in bulk using the [Confluence WebDav Plugin](#).
- Full featured customisation is available using the [Confluence remote APIs](#).

Note about add-on support

Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#).

Importing Content from Another Wiki

The Universal Wiki Converter (UWC) allows you to import content from other wikis into Confluence. The Confluence Administration Console offers a link to the Universal Wiki Converter documentation and download sites.

Note: You need to install and run the UWC separately from Confluence. The UWC is a standalone application that communicates with Confluence remotely. You cannot install the UWC directly into Confluence. Instead, download the UWC separately and run it according to the instructions below.

The UWC supports many wiki dialects. In addition, the UWC is an extensible framework, which means that developers can continue writing new conversion modules for other wikis.

- Download the latest version of the UWC from the [Atlassian Marketplace](#).
- For information on installation and usage, see the [UWC User Documentation](#).
- For information on developing your own converter module, see the [UWC Developer Documentation](#).
- For information about a specific wiki, including a list of currently supported wikis, see the [UWC documentation - what wikis are currently supported?](#).
- To ask a question, see the [UWC discussions on Atlassian Answers](#).

Related pages:

- [Importing Content Into Confluence](#)
- [Data Import and Export](#)
- [Confluence Administrator's Guide](#)



*The information on this page **does not apply** to Confluence OnDemand.*

Importing Pages from Disk

Confluence allows you to import text files from a directory on the Confluence server, and convert them into Confluence pages. Each file will be imported as a separate Confluence page with the same name as the file.

Notes:

- The text file may contain plain text, HTML or [Confluence Storage Format](#).

- You need to be logged in as a [System Administrator](#) to import text files.
- You can import pages from disk into site spaces, but not into personal spaces. Please see [Working with Spaces](#) for information about differences between site spaces and personal spaces.

Related pages:

- [Importing Content Into Confluence](#)
- [Confluence User's Guide](#)

 The information on this page *does not apply* to Confluence OnDemand.

To import text files:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.


Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Content Tools > Import**
3. Type the your directory path into the **Import directory** box.
4. Select **Trim file extensions** to remove file extensions from the page titles when converting the files to Confluence pages. Note that the Confluence pages will take their titles from the files' names (including their extensions). To avoid having page titles with a suffix like '.txt' check this box.
5. Select **Overwrite existing pages** if you want to replace existing Confluence pages that have the same page title as one you are importing.
6. Choose **Import**.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Import** from the space administration options.
3. Follow the steps above.

Confluence will place the new pages at the root of the space.

Screenshot: Importing text files

You can use this action to import text files from a directory on the Confluence server.

These text files become pages in Confluence, with the following features:

- The page title is taken from the filename
- The content is the entire page body

Import directory

Trim file extensions ☐

Overwrite existing pages ☐

Sharing Content

Confluence provides a number of ways for you to notify other people about content that may be of interest to them:

- You can [share a page link](#) with them.
- You can [mention](#) a user when you write a page, blog post or comment. Mentioning a user automatically emails a notification to them about that content.
- You can [broadcast a message](#) that appears in Confluence activity streams.
- You can [like](#) a page, blog post or comment. The author will receive a notification. If enough people like the content, it will appear in the list of popular content on the dashboard and in the recommended updates email message.

Other users can also find out about changes to content in Confluence by [watching](#) pages and spaces.

You may also be interested in [exporting Confluence content](#) to other formats such as XML, HTML, Microsoft Word and PDF.

Related pages:

- [Creating Content](#)
- [Managing Changes and Notifications and Tasks](#)
- [Organising Content](#)
- [Confluence User's Guide](#)

Network Overview

The 'network' feature provides notifications on the activity of users that you choose to follow. This compares with Confluence's other [content tracking](#) features, which provide notifications on specified types of content updates, made by any user.

The types of activities tracked by the network feature include:

- Additions or edits to [pages](#) or [blog posts](#)
- [Comments](#) added to a page or blog post or edits to existing comments
- Updates to a user's [User Status Updates](#)
- Updates to a user's [User Profile](#)

On this page:

- [Accessing Your Network View](#)
- [Following Another User](#)
- [Stop Following a User](#)
- [Notes](#)

Related pages:

- [Network Macro](#)
- [Subscribing to a Network RSS Feed](#)
- [Subscribing to Email Notifications of Updates to Confluence Content](#)
- [Confluence User's Guide.](#)


Accessing Your Network View

To see your network view:

- Choose **your profile picture** at top right of the screen, then choose **Network**.
(Alternatively, choose **More** in the 'Network' section of your profile sidebar.)

You can access another user's Network view using the [Hover Profile](#).

Screenshot: Example of the Network view



Following Another User

You can follow another user by using either the Hover Profile or your Network view.

To follow a user with the Hover Profile:

1. Open the user's hover profile popup:
 - Log in to Confluence, if you have not already done so.
Note: If a Confluence Administrator has granted the 'View User Profiles' permission to anonymous users, you can access people's hover profile popups without logging in. However, the hover profile features available to anonymous users are restricted.
 - Move your mouse pointer over a user's linked name or profile picture. The hover profile popup will appear.
2. Choose **Follow**.

To follow a user from your Network view:

1. Choose **your profile picture** at top right of the screen, then choose **Network**.
(Alternatively, choose **More** in the 'Network' section of your profile sidebar.)
2. Enter the first few characters of the name (or username) of the user you wish to follow in the **Following** field and choose the user from the list of suggestions.
3. Choose **Follow**.

If you now refresh or revisit your Network view, the profile picture(s) of the user(s) you just followed will appear within the 'Following' list on the right. Additionally, their tracked activities will start appearing in the 'Recent Activity' list on this page.

Stop Following a User

To stop following a user by using the Hover Profile:

1. Open the user's hover profile popup:
 - Log in to Confluence, if you have not already done so.
Note: If a Confluence Administrator has granted the 'View User Profiles' permission to anonymous users, you can access people's hover profile popups without logging in. However, the hover profile features available to anonymous users are restricted.
 - Move your mouse pointer over a user's linked name or profile picture. The hover profile popup will

appear.

2. Choose **Stop Following**.

You can also stop following a user by going to their Profile view.

If you now refresh or revisit your Network view, the profile picture(s) of the user(s) you just stopped following are removed from the 'Following' list on the right. Additionally, their tracked activities will stop appearing in the 'Recent Activity' list on this page.

Notes

Once you are following a user, you can see their activity in a number of ways:

- Your Network view: your Network view shows all the tracked activities that you have permission to view for all the users that you are following. In the same way, people who follow you will be able to see all your Confluence-based activities on their network views, provided they have permission to view the content. See below for instructions on accessing your network view.
- RSS feeds: you can subscribe to any Confluence user's network RSS feed and receive summaries on the activities of other users they are following in their network. See [Subscribing to a Network RSS Feed](#).
- Email notifications: you can request email notifications of any activity in your network. See [Subscribing to Email Notifications of Updates to Confluence Content](#).

Note that it is not possible to stop another user from following you. If you are interested in the ability to block followers, please watch [CONF-16285](#) for updates on the feature request.

Likes and Popular Content

Has someone written a good blog post or page on Confluence? Or has someone added a comment that you agree with? Click the **Like** button to them know.  **Like**

Confluence has like buttons on every page, blog post and comment. If enough people like a page or post, it will show on the dashboard's 'Popular' tab. The information in the 'Recommended Updates' email message is based on the number of people who have liked the content.

Liking a page, blog post or comment

Click the **Like** button to let people know that you agree with or enjoy a page, blog post or comment. Click **Unlike** to remove your name from the list of people who like the content.

You can also see:

- Up to three names of people in your network who have most recently liked the content.
- A link showing the number of people who have liked the comment. For example, **19 people like this**. Click the link to see the names. At the top of the list are people in your network, sorted with the most recent likes first. Then follow other people, also sorted chronologically with the most recent first.


On this page:

- [Liking a page, blog post or comment](#)
- [Effects of liking content](#)
- [Disabling the 'like' feature](#)
- [Disabling notifications when your content is 'liked'](#)

Related pages:

- [Dashboard](#)
- [Subscribing to Email Notifications of Updates to Confluence Content](#)
- [Network Overview](#)

Screenshot: The Like button at the bottom of a page and on comments



Effects of liking content

When you like a page, blog post or comment:

- The author of the content receives a notification.
- People in your network receive a notification. They will receive the notification only if they do not already know about the content. Let's assume Arthur is in your network. Arthur will **not** receive a notification if:
 - Someone else in his network has already liked the content.
 - Arthur himself has already liked the content.
 - Arthur has already commented on it.
 - In the case of a threaded comment, Arthur has already replied to the comment.
- If enough people like the content, it will appear on the 'Popular' tab of the [dashboard](#).
- Similarly, if the content is popular enough it will appear in the 'Recommended Updates' summary sent out by [email](#).

Disabling the 'like' feature

The functionality is provided by a plugin called the 'Confluence Like Plugin'. To remove the 'like' functionality from your site, you can disable the plugin. See [Disabling or Enabling a Plugin](#).

Disabling notifications when your content is 'liked'

There are two ways to turn the 'someone likes your page' notifications off:

1. Open an email notification of a like, and click Manage Notifications
2. Go to `_<your confluence URL>/plugins/likes/view-notifications.action_`

User Status Updates

You can use your 'user status' to broadcast a short message, which other users can see on various activity

streams in Confluence. These short messages could include:

- A description about what you are working on.
- A question you may want answered quickly.
- A hyperlink that you share immediately with other users.
- Any other message you may want to share quickly with other users.
- Another person's Confluence username, in the format [~username], to send that person an email message about your status.

Your 'Status Updates' view shows a history of updates you have made to your status. Your latest status message is shown on the profile popup that appears when people hover over your username, and in various other places in Confluence.

On this page:

- [Setting or updating your status](#)
- [Mentioning another person in your status update](#)
- [Viewing status updates](#)
- [Clearing your current status](#)
- [Deleting a status update](#)
- [More about user status updates](#)
- [Enabling and disabling status updates](#)

Related pages:


- [User Profile Overview](#)
- [User Status List Macro](#)
- [Confluence User's Guide](#)

Setting or updating your status

To set or update your status:

1. Log in to Confluence.
2. Choose **your profile picture** at top right of the screen, then choose **Update Status**. The 'What are you working on' dialog will open.
3. Enter a short message (140 characters maximum) that describes your current status or what you are working on.
4. Choose **Update** to publish your new or updated status.

Screenshot: User status



What are you working on?

Making Confluence sing... | 115

Last update:

Update Cancel

Mentioning another person in your status update

You can include another person's Confluence username in your status update, using square brackets and the

tilde sign in the format [~username]. Confluence will send that person an email message containing your status update. For example, let's assume another Confluence user has the username 'charlie'. You could put this message in your status update, and Charlie will receive an email message:

| *Enjoying all the blog posts that [~charlie] has written recently!*

Note: Mentions in status updates do **not** appear as notifications in the Confluence workbox.


Viewing status updates

To view your status updates:

- Choose **your profile picture** at top right of the screen, then choose **Status Updates**.

You can also view another user's status by going to their profile.

Screenshot: Status updates view




Clearing your current status

Clearing a message is not the same as deleting it. If you clear a message, it is still shown in your status updates view until it is deleted.

To clear your current status:

1. Choose **your profile picture** at top right of the screen, then choose **Status Updates**.
2. Choose **Clear** in the status message at the top of the page.

Screenshot: Clearing your current status message



Deleting a status update

To delete your current or a previous status message:

1. Choose **your profile picture** at top right of the screen, then choose **Status Updates**.
2. Choose **Delete** next to the appropriate status message. Your status updates view will be refreshed and the message you deleted will be removed from the list.

More about user status updates

There are a number of activity streams in Confluence that show different types of status updates. These include:

- The 'Recently Updated' list on the [Confluence Dashboard](#), which shows all status updates (when the **All** tab is selected).
- Your [Network page](#), which shows the status updates of Confluence users you are following.
- The [Network page](#) of Confluence users who are following you, which shows your status updates.
- The [Recently Updated](#) and [Recently Updated Dashboard](#) macros, which shows all status updates (provided that these macros' space parameters have been set to '@all').

Enabling and disabling status updates

The functionality is provided by a plugin called 'User Status'. To remove the status updates functionality from your site, you can disable the plugin. See [Disabling or Enabling a Plugin](#).

You can also set the Confluence site permissions to determine which users can use status updates. By default, users will not have permission to use this feature. See [Global Permissions Overview](#).

Using Mentions

You can mention a person in a special way that prompts Confluence to send that person an email message and a workbox notification. This way of mentioning someone is called an @mention. It works on Confluence pages, blog posts and comments.

When you save the page, Confluence sends an email message to the user letting them know that they have been mentioned on the page (if they have permission to view the page) with a link to the relevant page. Confluence also adds a notification to the person's workbox.

Note: Use the person's full name. The user mention feature recognises the full name only, not the username.

There are two ways to mention someone:

- The quickest way is to start typing '@' and the person's name, then choose from the suggestions that Confluence offers. This is called autocomplete.
- Alternatively, you can choose **Insert** > **User Mention** from the editor toolbar.


Each of these methods is described in more detail below.

Using autocomplete to mention someone

To mention someone using '@':

1. Edit the page.
2. Click where you want to insert a mention and type '@' and then the first few characters of the user's full name.
3. Choose the user's name from the list of suggestions.

Screenshot: Autocomplete for mentions



On this page:

- [Using autocomplete to mention someone](#)
- [Accessing the user mention option in the editor toolbar](#)
- [Seeing your mentions in the Confluence workbox](#)
- [Notes](#)

Related pages:


- [Using the Editor](#)
- [Using Autocomplete](#)
- [Keyboard Shortcuts](#)
- [Confluence User's Guide](#)

Accessing the user mention option in the editor toolbar

To add a user mention via the editor toolbar:

1. Edit the page.
2. Choose **Insert > User Mention**. Confluence will add an '@' sign to the page, and display a dropdown list of suggested users for you to choose from.
3. Start typing the person's name, to refine the list of suggestions.
4. Choose the person from the list of names.

Screenshot: The user mention option in the editor toolbar



Seeing your mentions in the Confluence workbook

When someone mentions you, you will receive a notification in the Confluence workbook. See [Managing Notifications in Confluence](#).

Notes

- **Disabling the user mention feature.** The functionality is provided by a plugin called the 'Confluence Mentions Plugin'. To remove the user mention functionality from your site, you can disable the plugin. See [Disabling or Enabling a Plugin](#).
- **Mentioning groups.** It is not possible to mention a group and then have the email sent to the entire group. You can only mention individual users. There is a feature request to allow mentions for groups: [CONF-23015 - Authenticate to see issue details](#)
- **Mentioning people in status updates.** See [User Status Updates](#).
- **Linking to a user profile.** You can use a square bracket '[' and a person's name to trigger Confluence autocomplete and link to a person's user profile or personal space. See [Linking to Personal Spaces and User Profiles](#). Confluence will send the person a notification just as if you had used @mention (unless the administrator has disabled the user mention feature).

Emailing a Page

You can share a Confluence page or blog post by emailing a link to recipients of your choice. The recipients can be Confluence users or any email addresses.

To email a link to a Confluence page or blog post using the Share button:


1. Go to the page or blog post you wish to share.
2. Choose **Share** at the top right of the page.
Note: The **Share** button will only be visible if your Confluence administrator has configured an outgoing mail server for your Confluence site. See [Configuring a Server for Outgoing Mail](#). *Not applicable to Confluence OnDemand.*
3. Enter the name or username of a Confluence user or any email address. As you start typing a name or username, or when you have typed a valid email address, an autocomplete dropdown will appear.
4. Select the appropriate user or email address from the dropdown. You can add multiple recipients to the list.
5. Enter an optional message into the **Note** box.
6. Choose **Share** to send the link via email.

If you chose one or more Confluence usernames (not email addresses) the recipients will also receive a notification in their Confluence workbox. See [Managing Notifications in Confluence](#).

Related pages:

- [Managing Notifications in Confluence](#)
- [Working with Pages](#)
- [Working with Blog Posts](#)
- [Confluence User's Guide](#)

Screenshot: Sharing a page

**Notes**

To remove a recipient from the list, choose the bin icon to the right of the recipient.

Exporting Confluence Pages and Spaces to Other Formats

You can convert a part of, or the entire contents of a space to various formats, including Microsoft Word, HTML, PDF and XML. This is called 'exporting' the space.

What would you like to do?

- [Exporting Confluence Pages and Spaces to HTML](#)
- [Exporting Confluence Pages and Spaces to PDF](#)
- [Exporting to a Word document](#)
- [Exporting Confluence Pages and Spaces to XML](#)

Related topics

- [Working with Spaces](#)
- [Confluence User's Guide](#)

Exporting Confluence Pages and Spaces to HTML

In Confluence, you can export part of, or the entire contents of, a space into a zipped archive of HTML files. This is useful if you want convert your space into a static website.

To use the space export functionality, you need the 'Export Space' permission. See the guide to [space permissions](#).

To export pages to HTML:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Content Tools > Export**

Note: This option will only be visible if you have the 'Export Space' permission.

3. Select **HTML** then choose **Next**

4. Decide whether you need to customise the export:

- Select **Normal Export** to produce an HTML file containing all the pages that you have permission to view.
- Select **Custom Export** if you want to export a subset of pages, or to exclude comments from the export.

5. Select the **Include Comments** check box if you want to include comments for the pages you are exporting.

6. Select the pages you want to export.

- You have the option to **Select All** or **Deselect All** pages.
- When you select a page, all its child pages will also be selected. Similarly, when you deselect a page all its child pages will also be deselected.

7. Choose **Export**. This will create a zipped archive of HTML files.

8. When the export process has finished, download the zipped archive as prompted, and extract the files into a folder.

If your space uses the Documentation theme:

1. Choose **Browse > Space Operations**
2. Choose **HTML Export** from the left menu
3. Follow the steps above to export the Space.

Related pages:

- [Exporting Confluence Pages and Spaces to PDF](#)
- [Exporting Confluence Pages and Spaces to XML](#)
- [Confluence User's Guide](#)

Screenshot: Selecting pages to export

Export HTML Options

Export content within this space as HTML.

☐ Normal Export

Generates a HTML file of all pages and blog posts in this space, including comments and attachments.

☒ Custom Export

Generates a HTML file of selected pages based on options that you choose from below.

Includes:

☒ Include comments

Choose pages to export:

[Select All](#) · [Deselect All](#)

☒ Crowd Documentation

☒ Crowd 101

☒ Crowd Administration Guide

☒ Getting Started

[Select All](#) · [Deselect All](#)

Export

Notes

- In the zip file, page attachments are placed in individual folders with names in the following format:
... \download\attachments\xxxxxxx
where 'xxxxxxx' is the page ID of the page containing the attachments.
- By default, the 'Space Details' page is exported as `index.html` and displays the space's details as well as a list of all available pages within it.
- Blog posts are not included in the HTML export. See the feature request: [CONF-14684](#).
- To customise the HTML output, you will need to modify the file `confluence-x.y.z-jar/com/atlassian/confluence/pages/Page.htmllexport.vm`. To learn how to repackage this file, see [How to Edit Files in Confluence JAR Files](#)

Exporting Confluence Pages and Spaces to PDF

This page explains how you can export individual Confluence pages, blog posts, entire spaces or selections of pages into a single PDF file.

Exporting single pages

You can export a Confluence page to PDF. This option exports a single page and is available to all users who have permission to view the page.

- Go to a page in the space and choose **Tools > Export to PDF**. Follow the prompts to export the page.

Note that the export of a single page to PDF applies any PDF stylesheet customisations, but does not apply any PDF layout customisations. To make your PDF layout customisations apply to a single page exported to PDF, use the 'multiple page' method described below to export that single page only. See [Customising Exports to PDF](#).

Exporting a blog post

You can export a Confluence blog post to PDF. This option exports a single blog post and is available to all users who have permission to view the page.

- Go to a blog post and choose **Tools > Export to PDF**. Follow the prompts to export the page.

Blog posts can only be exported individually. Blogs cannot be exported at the space level.

Exporting multiple pages or the entire space

Using Confluence's space export functionality, you can convert multiple pages or an entire space to PDF.

To use the space export functionality, you need the 'Export Space' permission. See the guide to [space permissions](#).

To export a space or selected pages to PDF:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Content Tools > Export**

Note: This option will only be visible if you have the 'Export Space' permission.

3. Select **PDF** then choose **Next**

4. Decide whether you need to customise the export:

- Select **Normal Export** to produce a PDF file containing all the pages that you have permission to view.
- Select **Custom Export** if you want to export a subset of pages.

5. Select the pages you want to export.

- You have the option to **Select All** or **Deselect All** pages.
- When you select a page, all its child pages will also be selected. Similarly, when you deselect a page all its child pages will also be deselected.

6. Choose **Export**.

7. When the export process has finished, download and save the PDF file as prompted.

If your space uses the Documentation theme:

1. Choose **Browse > Space Operations**
2. Choose **PDF Export** from the left menu
3. Follow the steps above to export the Space.

On this page:

- [Exporting single pages](#)
- [Exporting a blog post](#)
- [Exporting multiple pages or the entire space](#)
- [Customising the appearance of PDF exports](#)
- [Notes](#)

Related pages:

- [Customising Exports to PDF](#)
- [Advanced PDF Stylesheet Customisations](#)
- [Creating PDF in Another Language](#)
- [Exporting Confluence Pages and Spaces to HTML](#)
- [Exporting Confluence Pages and Spaces to XML](#)
- [Confluence User's Guide](#)

Screenshot: Selecting pages to export

Export PDF Options

Export content within this space as PDF. You can customise the layout and styling of this exported PDF in the [PDF Stylesheet](#) page.

☐ Normal Export
Generates a PDF file of all pages and blog posts in this space, including comments and attachments.

☒ Custom Export
Generates a PDF file of selected pages based on options that you choose from below.

Choose pages to export:
[Select All](#) · [Deselect All](#)

☒ Crowd Documentation

- ☒ Crowd 101
- ☒ Crowd Administration Guide
 - ☒ Getting Started

[Select All](#) · [Deselect All](#)

Customising the appearance of PDF exports

You can add a title page, a table of contents and customised headers and footers to the PDF output. For more advanced customisations, you can apply Cascading Style Sheet (CSS) modifications. These customisations are specific to each space. You need the 'Space Administrator' permission to be able to apply these customisations. For more information, see [Customising Exports to PDF](#).

Notes

- Comments on the page are not exported to the PDF file.
- Only image attachments that have been inserted into a page are included when exporting to PDF.
- To export a PDF containing international text, you need to [install a Unicode font in Confluence](#).

- Blog posts can be individually exported, but are not included when you export a space to PDF.
- If you have 'Space Administrator' permissions, the link to customise the PDF Stylesheet is provided at the top of the page tree, as shown in the screenshot above.
- Confluence's PDF export feature is designed to handle a wide variety of content. However, on rare occasions the PDF Export process may fail due to an unrecognised customisation. If that happens the PDF export screen will indicate the title of the page in which the problem occurred, to help you diagnose the cause of the failure.

Customising Exports to PDF

Confluence administrators and space administrators can customise the PDF exports for individual spaces.

Please note:

- PDF customisations are unique to each space.
- Confluence's PDF customisations use a combination of HTML and CSS (Cascading Style Sheets).
- To achieve a particular requirement in the exported PDF file, you make changes in one or both of the following:
 - The **PDF Layout**, where HTML is used to define the structure of the exported content, including features such as the title page, headers and footers.
 - The **PDF Stylesheet**, where CSS is used to define the style of elements in the exported content, such as page size and margins, font, colour, and list numbering.

For further customisations, see the [Advanced PDF Export Customisations](#) page.

Customising the PDF Layout

You can add your own HTML to customise the title page, page headers and page footers in the PDF output.

Setting a global PDF layout

1. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
2. Choose **PDF Layout**. You can enter HTML and CSS that will be rendered on the PDF title page, as well as page headers and footers.

Setting the PDF layout at space level

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Look and Feel > PDF Layout**.
3. Choose **Edit**.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.

Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **PDF Layout** in space administration options.
3. Choose **Edit**.

You can customise the HTML that is generated for the following areas when the space is exported to PDF:

- **PDF Space Export Title Page** – title page.
- **PDF Space Export Header** – page headers.

- **PDF Space Export Footer** – page footers.

Enter your customisations into each text box as required. The PDF layout section accepts HTML code. You can include inline CSS in the HTML too.

On this page:

- [Customising the PDF Layout](#)
 - [Setting a global PDF layout](#)
 - [Setting the PDF layout at space level](#)
- [Customising the PDF Stylesheet](#)
 - [Setting a global PDF Stylesheet](#)
 - [Setting a space PDF stylesheet](#)
- [Example Customisations](#)
 - [Page Size](#)
 - [Page Orientation: Landscape or Portrait](#)
 - [Page Margins](#)
 - [Page Breaks](#)
 - [Title Page](#)
 - [Table of Contents](#)
 - [Headers and Footers](#)
 - [Page Numbering](#)
 - [Wrapping Long Words](#)
 - [General Formatting](#)
- [Notes](#)
- [Related Topics](#)

Related pages:

- [Advanced PDF Export Customisations](#)

Customising the PDF Stylesheet

You can adjust the appearance of the PDF pages by customising the CSS in the PDF Stylesheet screen.

To get started, download the default CSS rules for the PDF stylesheet - [confluencedefaultpdf.css](#).

Any rule defined in this file can be customised and added to the PDF Export Stylesheet section. Your customisations override any default CSS rule. If no customisations are defined, the default CSS rules will be applied.

By default, the export does not include a title page, headers or footers. You can define these in the PDF layout.

To customise the PDF Stylesheet:

Setting a global PDF Stylesheet

1. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
2. Choose **Look and Feel > PDF Stylesheet**. The following screen allows you to enter and save CSS code that will render content on each page.

Setting a space PDF stylesheet

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Look and Feel > PDF Stylesheet**
3. Choose **Edit**.
4. Enter your customisations.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **PDF Stylesheet** in the space administration options.
3. Choose **Edit**.
4. Enter your customisations.

The PDF Export Stylesheet field accepts Cascading Style Sheets (CSS) rules. The 'PDF Export Stylesheet' page shows the current (e.g. customised) contents of your PDF stylesheet.

Example Customisations

This section provides examples of typical customisations that you can add. See also [Advanced PDF Customisations](#).

Page Size

The default page size is based on the location of your Confluence server. For example, if this server is located in the US then the default paper size of your PDF export will be US Letter (8.5 inches wide by 11 inches long). If the server is located in Australia, the default paper size will be A4 (210 mm wide by 297 mm long). More information about paper sizes can be found on [Wikipedia](#).

To modify the page size to A4, edit the PDF Stylesheet to add a size property to the CSS@page rule, like this:

CSS - PDF Stylesheet

```
@page
{
/*The A4 paper size is 210 mm wide by 297 mm long*/
size: 210mm 297mm;
}
```

Page Orientation: Landscape or Portrait

To change the page orientation of your PDF document, simply reverse the order of the values declared in the @page rule's size property. The first and second values of this property represent the width and height of the page, respectively.

For example, to generate PDF space exports in A4-sized landscape orientation, your @page rule might look like this:

CSS - PDF Stylesheet

```
@page
{
/*A4-sized pages in landscape orientation are 297 mm wide by 210 mm long*/
size: 297mm 210mm;
}
```

Page Margins

To set all margins to 15 mm, with a paper size of A4, edit the CSS `@page` rule in the PDF Stylesheet, like this:

CSS - PDF Stylesheet

```
@page
{
size: 210mm 297mm;
margin: 15mm;
}
```

To set the margins independently, edit the `@page` rule as follows:

CSS - PDF Stylesheet

```
@page
{
margin-top: 2.54cm;
margin-bottom: 2.54cm;
margin-left: 1.27cm;
margin-right: 1.27cm;
}
```

To set margins to provide a gutter for binding a printed document, use the `:left` and `:right` pseudo-classes, as follows:

CSS - PDF Stylesheet

```
@page :left
{
margin-left: 4cm;
margin-right: 3cm;
}
@page :right
{
margin-left: 3cm;
margin-right: 4cm;
}
@page :first
{
margin-top: 10cm /* Top margin on first page 10cm */
}
```

Note the use of the `:first` pseudo-class in the example above to define distinct margins for a cover or title

page.

Page Breaks

By default, Confluence pages are exported without page breaks, so that shorter pages will appear on the same PDF page.

To make each Confluence page appear on a separate page in the PDF file, add the following rule in the PDF Stylesheet:

CSS - PDF Stylesheet

```
.pagetitle
{
  page-break-before: always;
}
```

Title Page

You can add a title page to your PDF document by adding HTML to the Title Page section of the PDF Layout screen. The following example creates the title page and adds a title:

HTML - PDF Layout: Title Page Section

```
<div class="fsTitlePage">
  
  <div class="fsTitle">Planning for Confluence 4.0</div>
</div>
```

Use CSS rules in the PDF Stylesheet to control the appearance of the title page and the title text:

CSS - PDF Stylesheet

```
.fsTitlePage
{
  margin-left: auto;
  margin-top: 50mm;
  margin-right: auto;
  page-break-after: always;
}

.fsTitle
{
  font-size: 42px;
  font-weight: bold;
  margin: 72px 0 4px 0;
  text-align: center;
}
```

Adding an Image to the Title Page

In the example above, the title page includes an image called 'titlepage.png', centred in the middle of the page. The "590719" in the src attribute is the ID number of the page to which the image is attached.

Follow these instructions to include an image on your title page:

1. Attach the image to a Confluence page.
2. View the list of attachments on that page, then right-click the image and copy its location.
3. Paste the link into the appropriate `src=""` attribute in your PDF Stylesheet, as shown above.
4. Edit the image URL so that it is relative, by removing the first part of the URL before `/download/ . . .`

Table of Contents

By default, a table of contents will be generated after the title page, or at the beginning of the PDF document if no title page is defined in the PDF Layout. To see the default CSS rules applied to the table of contents, download the default CSS rules ([confluencedefaultpdf.css](#)) and examine the specific rules with `toc` in their name.

To make changes to the appearance of the table of contents, define CSS rules in the PDF Stylesheet.

Disabling the Table of Contents

To prevent the table of contents from being generated in your PDF document, add the `div.toc` rule to the PDF Stylesheet and set its `display` property to `none`:

CSS - PDF Stylesheet

```
div.toc
{
display: none;
}
```

Changing the Leader Character in the Table of Contents

The leader character is used to link a heading in the table of contents with its page number. By default, the leader character is the '.' (dot) character. Leader values of `dotted`, `solid` and `space` are allowed. You can also use a string, for example `leader(". . . ")`.

To change the leader character to a solid line, modify the `leader()` value on the `content` property of the CSS rule as follows:

CSS - PDF Stylesheet

```
span.toclead:before
{
content: leader(solid);
}
```

Headers and Footers

You can add headers and footers to your PDF pages using the 'Header' and 'Footer' sections of the PDF Layout screen. By default, headers and footers only apply to a space export and not to exports of single pages (however, see [Advanced PDF Export Customisations](#)). The following example adds a simple copyright notice.

HTML - PDF Layout: Footer Section

Copyright © 2013, Atlassian Pty Ltd.

Page Numbering

To add page numbering, you need to combine customised HTML in the PDF Layout with customised CSS in the PDF Stylesheet.

1. **PDF Layout HTML:** In the Footer section (or the Header section), use an empty span element with a unique ID, for example `pageNum`, to act as a place holder for the page number.

HTML - PDF Layout: Footer Section

```
<span id="pageNum"/>
```

2. **PDF Stylesheet CSS:** Create the following CSS selector rule for the empty span:

CSS - PDF Stylesheet

```
#pageNum:before  
{  
  content: counter(page);  
}
```

Analysing the above CSS selector rule in more detail:

- The `#pageNum` rule selects the HTML element with the specified ID of "pageNum", which is the span element we created for the header or footer.
- The `:before` part of the selector is a pseudo class that allows the insertion of content before the span element is processed.
- The `counter(page)` is a function that returns the current page number as its content.
- The `content` property tells the CSS processor that dynamic content (that is, an incrementing page number) is to be inserted at the span tag.

Wrapping Long Words

In order to break long words or words that are not separated by whitespace, add a selector to the PDF stylesheet containing the `word-wrap` property with a value of `break-word`:

CSS - PDF Stylesheet

```
div  
{  
  word-wrap: break-word;  
}
```

General Formatting

You can use the stylesheet to customise the output of just about anything else that will influence the look and feel of the final document. This includes fonts, tables, line spacing, macros, etc. The export engine works directly from the HTML output produced by Confluence. Therefore, the first step in customising something is to find a selector for the HTML element produced by Confluence or the Confluence macro. Then add a CSS rule to the PDF stylesheet. Your customisation will appear in the PDF export.

Notes

- **Demotion of heading elements: h1, h2, and so on.** Due to the hierarchical manner in which a space is exported, Confluence will modify the heading elements to generate a uniform appearance for the entire

space export. This means that headings will be demoted. This will affect the application of custom PDF Stylesheets. It is possible to calculate the amount by which a heading will be demoted in order to have the correct CSS styling applied. A heading will be demoted by the value of its depth in the export tree. A page at the first level will be demoted by 1 (all <h1> elements will become <h2> elements, and so on). A page at the second level will be demoted by 2, and so on.

- **Atlassian support for PDF customisation is limited.** We support the mechanism for customising the PDF layout with HTML and CSS, and we will help if the mechanism is broken or does not work as we say it should in our published examples. But, since custom HTML and CSS offer potentially limitless possibilities, Atlassian will not support issues that are caused by or related to PDF customisations.

Related Topics

[Advanced PDF Export Customisations](#)

Advanced PDF Export Customisations

This page provides information about 'advanced' PDF export customisations. These expand upon the regular customisations described in [Customising Exports to PDF](#).

 The information below is for advanced users. Customisations are not supported by Atlassian. Be aware that the advanced customisations described below require knowledge of certain parts of Confluence, and of CSS and HTML. This documentation is intended for advanced users. Some of the suggestions below are moderately complex, or irregular in nature. If you are having trouble understanding them we strongly suggest you ask an expert. We do not support any of the customisations described below. This means that the Atlassian support engineers will not be able to help you with these modifications.

On this page:

- [Header and Footer](#)
 - [Adding Headers and Footers to Single Page Exports](#)
 - [Adding Images to Headers and Footers](#)
- [Incorporating Other Fonts](#)
- [Adding a Dynamic Title to the Title Page](#)
- [Hiding Text from the PDF Output \(*Not applicable to Confluence OnDemand.*\)](#)
- [Indexing](#)
- [Notes](#)

Related pages:

- [Customising Exports to PDF](#)
- [Confluence User's Guide](#)

Header and Footer

Adding Headers and Footers to Single Page Exports

By default, custom headers and footers set up in the PDF Layout screen (see [Customising Exports to PDF](#)), only apply to space exports and not to exports of single pages. However, it is possible to add CSS rules to your PDF Stylesheet that produce headers and footers in single page exports as well as space exports.

For custom headers, define @top-left, @top-center and @top-right rules within your @page rule. These rules apply respectively to content that appears on the left-hand side, centre and right-hand side of your page's header area.

For custom footers, define @bottom-left, @bottom-center and @bottom-right rules within your @page rule.

For example, the following rules add a document title at the centre of the header and a page number at the centre of the footer:

CSS - PDF Stylesheet

```
@page
{
    @top-center
    {
        content: "Document Title Goes Here";
        font-family: ConfluenceInstalledFont, Helvetica, Arial, sans-serif;
        font-size: 8pt;
    }
    @bottom-center
    {
        content: "Page " counter(page);
        font-family: ConfluenceInstalledFont, Helvetica, Arial, sans-serif;
        font-size: 8pt;
    }
    /* Any other page-specific rules */
}
```

Notes:

- The `font-family` and `font-size` properties ensure that the header and footer text is rendered in the same default font style used for the body text, based on the default CSS rules.
- It is not possible to use this method to insert images (stored as attachments within your Confluence instance) into the headers and footers of single page exports.

Adding Images to Headers and Footers

To insert an image into the header or footer, add HTML to the Header or Footer section of the PDF Layout screen.

The following example uses an HTML `img` element with `src` attribute to add an image to the left of the header. The `src` attribute refers to an image attached to a Confluence page. The image element is usually placed within a `div` element container.

HTML - PDF Layout: Header Section

```
<div style="margin-top:10mm">
  
</div>
```

In the example above, the header includes an image called 'header-image.png'. The "12346" in the `src` attribute is the ID number of the page to which the image is attached.

Follow these instructions to include an image on your page:

1. Attach the image to a Confluence page.
2. View the list of attachments on that page, then right-click the image and copy its location.
3. Paste the link into the appropriate `src=""` attribute in your PDF Stylesheet, as shown above.
4. Edit the image URL so that it is relative, by removing the first part of the URL before `/download/...`

Notes:

- This example uses an inline CSS property `margin-top` in the `style` attribute to force the image away from the top of the page by 10mm. This comes in handy when your header image is large enough to touch or spill over the top of the page.

- Likewise, for footers, you can use the `margin-bottom:XXmm` property to force an image away from the bottom of the page by 'XX' mm.
- Very large images can spill over into the body of a page or alter the position of text or other elements used within a header or footer. In such situations, it is recommended that you reduce the size of the image and then attach it to your Confluence page again. If you prefer to keep the image size and want to move the content lower instead, you can do so by configuring the `margin-top` properties in the `@page` CSS rule.
- By default, a header or footer image is aligned to the left-hand side of the page. However, you can align this image to the centre or right-hand side of a page by adding either the `text-align:center` or `text-align:right` properties to your style attribute. For example, to align the header image to the right-hand side of the page, your style attribute would look similar to this: `style="margin-top:10mm ; text-align:right"`.

Incorporating Other Fonts

By default, Confluence provides Times New Roman, Helvetica or Courier fonts for use in PDF exports. You can use your own fonts for PDF exports by declaring them in a `@font-face` CSS rule in your PDF Stylesheet.

The following CSS rule example shows how to declare the Consolas font and apply it to some elements for your PDF export:

CSS - PDF Stylesheet

```
@font-face
{
  src: url(file:///usr/share/fonts/Consolas.ttf);
  -fs-pdf-font-embed: embed;
}

.code pre, .preformatted pre, tt, kbd, code, samp
{
  font-family: Consolas, monospace;
  font-size: 9pt;
}
```

The font path specified in the CSS must be the path to the font on the Confluence server.

Adding a Dynamic Title to the Title Page

When you export an arbitrary set of pages from Confluence, you may like to have a corresponding title added to the cover (or title) page automatically. This can be done (in a somewhat irregular way) by using the top level item from the default table of contents as the title. This method relies on having the exported pages structured as sub-pages of the top-level page. In other words, the pages to be exported should consist of a page (at the top-level) and all of its child pages. The result is that the title that appears on the cover page changes depending on the top-level page that is used for the export.

The CSS below moves, and styles, the top-level TOC item for use as the title on the cover page, and turns off the leader and page number normally associated with this item in the TOC.

CSS - PDF Stylesheet

```
.fsTitlePage
{
position:relative;
left:0px;
}

/* Turn off the default section numbering for this TOC item */
.toclvl0:before
{
content: " ";
counter-reset: chapter 0;
}

/* Hide the default page numbering for this TOC item */
.toclvl0 .tocnum
{
display: none;
}

/* Move and style this TOC item */
.toclvl0
{
position:absolute;
top:250px;
font-size: 42px;
font-weight: bold;
margin: 72px 0 4px 0;
text-align:center;
}
```

Hiding Text from the PDF Output (Not applicable to Confluence OnDemand.)

This section describes a way to hide text from your PDF export. In other words, you can have text on the Confluence page that will not appear in the PDF export.

There are three steps:

1. Follow the instructions to [define the NoPrint user macro](#). *Not applicable to Confluence OnDemand.*
2. Use the NoPrint macro to mark some text on a Confluence page.
3. Add the following CSS to your PDF stylesheet to make the PDF export recognise the NoPrint macro:

CSS - PDF Stylesheet

```
.noprnt
{
display: none ;
}
```

Indexing

To obtain an index at the end of the exported PDF file, consider using the [Scroll Wiki PDF Exporter plugin](#) that is produced by K15t Software GmbH.

Notes

If styling is not working as expected, it is useful to look at the intermediary HTML source to which the CSS is applied. This intermediary HTML is created whenever you create an [HTML export](#) that contains **multiple pages**, and is stored in the temp directory in Confluence's home directory. For example:

```
<confluence-home>/temp/htmllexport-20110308-154047-1/export-intermediate-154047-2.html
```

Creating PDF in Another Language

To export a Confluence page written in a language other than English, you need to install the necessary font for that language. This means that you need to upload the font file to Confluence, as described below.

Uploading a Font File to Confluence

1. Find the appropriate font file:

- **Windows users:** All font files in Windows are stored in a directory called:

```
C:\WINDOWS\Fonts
```

- **Unix users:** All font files in Unix are stored in:

```
/usr/share/fonts
```

- Microsoft True Type core fonts such as Verdana can be downloaded from this page: <http://corefonts.sourceforge.net/>

2. Copy the font file into a temporary folder, for example a folder on your desktop.

3. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**. then choose **PDF Export Language Support**.

Note: If you are using *Confluence OnDemand*, go to this URL instead:

```
https://<account_name>.atlassian.net/wiki/admin/flyingpdf/configurepdflanguagesupport.action
```

4. Upload the file you copied in step 2.

5. Choose **Install**.

Related pages:

- [Exporting Confluence Pages and Spaces to PDF](#)
- [Confluence Administrator's Guide](#)

Notes

- The only font files supported are *true type fonts* and *true type collections*. The accepted file extensions are *.ttf and *.ttc.
- We recommend that you use Unicode font Verdana for correct character encoding and exporting to PDF.
- If the font file size is bigger than your [current attachment size limit](#), you will not be able to upload it. Please increase the [attachment size limit](#) temporarily and re-upload again. An improvement of the error messaging is tracked at  **CONF-24706** - [Authenticate](#) to see issue details .

Exporting to a Word document

Confluence allows you to export a single page into a Word document. By default, this will create a Word document with the same name as the Confluence page. This is useful for emailing content to people who do not have access to Confluence.

Anyone who has permission to view the page will be able to export it to Word.

To export a page to a Word document:

Go to the page and choose **Tools > Export to Word**.

Useful plugins

Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#).

This plugin provides extended functionality for exporting Confluence pages to Microsoft Word: [Scroll Office](#).

Exporting Confluence Pages and Spaces to XML

You can export part of, or the entire contents of, a Confluence space into a zipped archive of XML files. This is useful if you want to make a backup of the space, import the space into another Confluence site, or use the data from the space in another application.

To export a space or pages to XML, you will need the 'Export Space' permission. See [Space Permissions](#).

Notes:

- There are some restrictions when **importing** a space. See:
 - [Restoring a Space](#) (Not applicable to Confluence OnDemand.)
 - [Importing wiki data](#) (For Confluence OnDemand.)
- If you are doing the export for backup purposes, consider another means of backup. See [Production Backup Strategy](#) (Not applicable to Confluence OnDemand.)

To export pages or an entire space to XML:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Content Tools > Export**

Note: This option will only be visible if you have the 'Export Space' permission.

3. Select **XML** then choose **Next**

4. Decide whether you need to customise the export:

- Select **Full Export** to produce an XML file containing all the pages in the space, including those that you do not have permission to view.
- Select **Custom Export** if you want to export a subset of pages, or to exclude comments from the export.

5. Select **Include Comments** if you want to include comments made on the pages you are exporting.

6. Select the pages you want to export.

- You have the option to **Select All** or **Deselect All** pages.
- When you select a page, all its child pages will also be selected. Similarly, when you deselect a page all its child pages will also be deselected.

7. Choose **Export**. This will create a zipped archive of XML files.

8. When the export process has finished, download and save the zipped archive file as prompted.

If your space uses the Documentation theme:

1. Choose **Browse > Space Operations**
2. Choose **XML Export** from the left menu
3. Follow the steps above to export the Space.

On this page:

Related pages:

- [Restoring a Space](#) (Not applicable to Confluence OnDemand.)
- [Importing wiki data](#) (For Confluence OnDemand.)
- [Exporting Confluence Pages and Spaces to PDF](#)
- [Exporting Confluence Pages and Spaces to XML](#)
- [Working with Spaces](#)
- [Confluence User's Guide](#)

Screenshot: Exporting a space

Export XML Options

Export content within this space as XML.

☐ Full Export (includes pages not visible to you)
Generates a XML file of all pages and blog posts (including ones not visible to you) in this space, including comments and attachments.

☒ Custom Export
Generates a XML file of selected pages based on options that you choose from below.

Includes:

☒ Include comments

Choose pages to export:
[Select All](#) · [Deselect All](#)

☒ Crowd 101
☒ Crowd Administration Guide
☒ Getting Started

[Select All](#) · [Deselect All](#)

Notes

If you are running Confluence behind Apache HTTP Server and are facing timeout errors, please consider creating the export directly from Tomcat, instead of going through Apache. This will speed up the process and prevent timeouts.

Commenting on pages and blog posts

A comment is a remark, question, or any other additional information you wish to add to a page or blog post. People can use comments to interact with each other on your Confluence site.

You can add a comment to any page or blog post, provided that you have the 'Add Comments' permission in the space. You can also show that you agree with or enjoyed someone else's comment, by [liking](#) it.

Comments are displayed at the bottom of the page, below the page content. They appear in one of two views, configured globally by a [site administrator](#):

- **Threaded** – This view shows the comments in a hierarchy (tree) of responses. The replies are indented to indicate the relationships between the comments.
- **Flat** – This view displays all the comments in a single list and does not indicate the relationships between comments.

On this page:

- [Adding a comment](#)
- [Editing a comment](#)
- [Deleting a comment](#)
- [Disabling comments](#)
- [Notes](#)

Related pages:

- [Linking to Comments](#)
- [Working with Pages](#)
- [Working with Blog Posts](#)
- [Sharing Content](#)
- [Confluence User's Guide](#)
- [Enabling Threaded Comments](#)

Adding a comment

You can add a comment on pages and blog posts in Confluence.

To add a comment, you need the 'Add Comments' permission. See [Space permissions](#).

To add a new comment:

1. Position your cursor in the comment box, next to your [profile picture](#) at the bottom of the page.
2. Type in your comment.
3. Choose **Preview** to see how your comment will appear.
4. By default, **Watch this page** is ticked. This means that you will start receiving [notifications](#) about this page. Remove the tick if you do not want to watch the page.
5. Choose **Save**.

If the Confluence site displays comments in the threaded view, you can respond to previous comments.

To respond to a comment:

1. Choose **Reply** located below the text of a comment.
2. Type in your response.
3. Choose **Save**.

Editing a comment

To edit a comment, you need the 'Add Comments' permission. See [Space permissions](#). Space administrators can edit all comments within their space. The date on a comment always indicates the time the comment was last edited.

To edit a comment:

1. Go to the comment and choose **Edit**.
2. Make changes to the comment just as if you were adding a comment.
3. Choose **Save**.

Deleting a comment

To delete a comment from a page, you need the 'Remove Comments' permission. See [Space permissions](#).

Note: Deleted comments cannot be restored.

To delete a comment:

1. Go to the page that contains the comment.
2. Choose **Delete** at the bottom of the comment box.

Disabling comments

To prevent all users from adding comments in a space, remove the 'Add Comments' permission from the 'confluence-users' group, anonymous users and all other users and groups. See [Space permissions](#). The option to add comments will no longer appear on pages or blog posts. You need to be a space administrator to change the space permissions.

There is no permission that controls comments across the entire site.

Notes

- You can choose **Tools** > **Watch** to receive an email notification whenever anyone edits the page or adds a comment to the page.
- Your [profile picture](#) will appear next to each comment that you have added. (This is true if your space uses the Confluence Default [theme](#).)
- On blog posts only, an 'Author' lozenge will appear on any comments made by the original author of the post. 
- Comments are not auto-saved. See feature request:  **CONF-12978** - [Authenticate](#) to see issue details
- It is not possible to delete all comments for a page simultaneously.

Linking to Comments

You can add a link to a comment by making use of the permalink (permanent link) associated with each comment. Alternatively, using wiki markup you can link directly to the ID of a comment.

Linking to a comment via the permalink

To link to a comment from within Confluence:

1. Right-click the **date/time** at the lower right of the comment box.
2. Use your browser's 'copy link location' function to copy the link on the date/time text. That link is the URL of the comment.
3. Edit the page from which you want to link to the comment.
4. Choose **Insert** > **Link** in the editor toolbar.
5. Choose the **Web Link** tab.
6. Paste the comment's URL into the address field.
7. Provide link text if required.
8. Choose **Insert**.
9. Save the page.

To link to a comment from outside Confluence:

1. Right-click the **date/time** at the lower right of the comment box.
2. Use your browser's 'copy link location' function to copy the link on the date/time text. That link is the URL of the comment.
3. Use this URL to link to the comment from your web page.

On this page:

- [Linking to a comment via the permalink](#)
- [Linking to a comment via the comment ID](#)

Related pages:

- [Commenting on pages and blog posts](#)
- [Working with Links](#)
- [Confluence User's Guide](#)

Linking to a comment via the comment ID

You can enter wiki markup into the Confluence editor, either via **Insert > Wiki Markup**, or by typing the full wiki markup into the editor and allowing Confluence to autoconvert it.

Here is the wiki markup syntax for linking to a comment, where the comment ID is '12345'.

Without an alias:

```
[$12345]
```

With an alias:

```
[alias text|$12345]
```

To find the ID of a comment, right-click the **date/time** at the lower right of the comment box and examine the URL of the comment.

- The comment URL looks something like this:

```
https://confluence.atlassian.com/display/DOC/Linking+to+Comments?focusedCommentId=302812339#comment-302812339
```

- The comment ID is a number, something like this: 302812339.

Sample Page

Start of sample page content

Lorem ipsum dolor sit amet, consectetur adipiscing elit. Aliquam fermentum vestibulum est. Cras rhoncus. Pellentesque habitant morbi tristique senectus et netus et malesuada fames ac turpis egestas. Sed quis tortor. Donec non ipsum. Mauris condimentum, odio nec porta tristique, ante neque malesuada massa, in dignissim eros velit at tellus. Donec et risus in ligula eleifend consectetur. Donec volutpat eleifend augue. Integer gravida sodales leo. Nunc vehicula neque ac erat. Vivamus non nisl. Fusce ac magna. Suspendisse euismod libero eget mauris.

End of sample page content

child page

Printing Confluence Pages

You can print one or more Confluence pages:

- To print a single page, use your browser's 'Print' option.
- Confluence allows you to export a single page, single blog post, part of a space, or an entire space into a

single PDF file. See [Exporting Confluence Pages and Spaces to PDF](#).

Managing Changes and Notifications and Tasks

Confluence provides several ways in which you can watch for changes to single pages, entire spaces, and all spaces on the site. You can also follow the updates made by specific people. You can only track updates to content that you have permission to see.

Personal tasks appear in the task-and-notification dialog, and you can assign team tasks via a task list on a page.

Making yourself a watcher of pages or spaces

You can 'watch' a page, blog post or space that you have permission to view. Confluence will then send you an email notification whenever someone adds or updates content on, or adds a comment to, that page or space. See:

- [Watching a Page or Blog Post](#)
- [Watching a Space](#)

If you have space administrator permissions, you can [manage watchers of pages and spaces](#).

Requesting other notifications

You can configure Confluence to send you various digest reports via email. See [Subscribing to Email Notifications of Updates to Confluence Content](#).

On this page:

- [Making yourself a watcher of pages or spaces](#)
- [Requesting other notifications](#)
- [Tracking updates by specific people](#)
- [Managing your notifications and tasks](#)
- [Using Confluence RSS feeds](#)

Related pages:

- [Page History and Page Comparison Views](#)
- [Viewing Space Activity](#)
- [Contributors Macro](#)
- [Confluence User's Guide](#)

Tracking updates by specific people

You can also follow the activity of people who interest you (see [Network Overview](#)) and receive a notification when someone follows you (see [Subscribing to Email Notifications of Updates to Confluence Content](#)).

Managing your notifications and tasks

There are a few ways to manage notifications and tasks in Confluence:

- You can manage your email notification settings via the options in your user profile. See [Subscribing to Email Notifications of Updates to Confluence Content](#).
- The Confluence workbox displays all notifications collected from Confluence page watches, shares and mentions. See [Managing Notifications in Confluence](#).
- You can manage your personal tasks in the Confluence workbox, and also create a list of tasks on a page. See [Managing Tasks in Confluence](#).

Using Confluence RSS feeds

You can build RSS feeds to monitor content changes in Confluence.

- Create a customised RSS feed using the [RSS Feed Builder](#).
- Subscribe to one of the [pre-specified feeds](#) generated by Confluence.

Watching a Page or Blog Post

You can 'watch' a Confluence page, blog post or space. Confluence will then send you a notification by email whenever anyone updates the watched content.

You will receive email notifications for:

- Edits (unless the user clears the **Notify watchers** check box).
- Deletions.
- Attachments, including new versions or deletions of an existing attachment.
- Comments, including new comments, edits of existing comments or deletions of existing comments.

By default, Confluence will assign you as a watcher of any page or blog post that you create or edit. This behaviour is called 'autowatch'. You can [control autowatch](#).

There is no daily digest for email notifications. You will receive an email notification every time someone makes a change.

You will **not** receive email notifications for content changes due to the output of a macro, because the page content itself has not been edited.



You need 'View' permission for the page, blog post or space to receive notifications.

On this page:

- [Watching a Page or Blog Post](#)
- [Setting Autowatch and Other Notification Options](#)
- [Watching an Entire Space](#)
- [Watching for New Blog Posts](#)
- [Managing Watches from your User Profile](#)
- [Managing Watches from the Email Message](#)

Related pages:

- [Watching a Space](#)
- [Subscribing to Email Notifications of Updates to Confluence Content](#)
- [Managing Changes and Notifications and Tasks](#)
- [Updating Email Address](#)
- [Confluence User's Guide](#)

Watching a Page or Blog Post

To start watching a page or blog post:

1. Go to the page or blog post.
2. Choose **Tools** > **Watch**.

To stop watching a page or blog post:

1. Go to the page or blog post.
2. Choose **Tools** > **Stop watching**.

Setting Autowatch and Other Notification Options

By default, Confluence will assign you as a watcher of any page or blog post that you create or edit. This behaviour is called 'autowatch'. You can turn autowatch on or off, and set other notification options, in the email

settings section of your user profile. See [Setting User Settings](#).

Watching an Entire Space

You can choose to watch all the pages and blog posts in a given space. See [Watching a Space](#).

Watching for New Blog Posts

You can choose to watch for:

- New blog posts in a given space. See [Watching a Space](#).
- All new blog posts in the Confluence site. See [Subscribing to Email Notifications of Updates to Confluence Content](#).

Managing Watches from your User Profile

The '**Watches**' page in your user profile displays a list of all pages and spaces you are currently watching.

To manage your watches:


1. Choose **your profile picture** at top right of the screen, then choose **Watches**.
2. Choose **Stop Watching** for any unwanted spaces or pages.

Managing Watches from the Email Message

The email notifications that you receive from Confluence have some useful links at the bottom of the email message. The links in each message vary, depending on the context. In general, the links allow you to view the page online, reply to a comment, and so on. In particular with respect to setting your notification preferences, you will see one or more of the following links:

- **Stop watching page** – Click this link to stop watching the page that triggered the email notification.
- **Stop watching space** – Click this link to stop watching the space that triggered the email notification.
- **Stop following this user** – Click this link to stop following the user whose update triggered the email notification.
- **Manage Notifications** – Click this link to go to the email settings page in your user profile.

Screenshot: Email notification footer showing links



Watching a Space

You can 'watch' a Confluence page, blog post or space. Confluence will then send you a notification by email whenever anyone updates the watched content.

You will receive email notifications for:

- Edits (unless the user clears the **Notify watchers** check box).
- Deletions.
- Attachments, including new versions or deletions of an existing attachment.
- Comments, including new comments, edits of existing comments or deletions of existing comments.

By default, Confluence will assign you as a watcher of any page or blog post that you create or edit. This behaviour is called 'autowatch'. You can [control autowatch](#).

There is no daily digest for email notifications. You will receive an email notification every time someone makes a change.

You will **not** receive email notifications for content changes due to the output of a macro, because the page

content itself has not been edited.

 You need 'View' permission for the page, blog post or space to receive notifications.

On this page:

- [Watching all pages in a space](#)
- [Watching for new blog posts in a space](#)
- [Watching all Spaces on the Site](#)
- [Managing watches from your user profile](#)
- [Managing watches from the email message](#)
- [Managing watchers](#)
- [Notes](#)

Related pages:

- [Watching a Page or Blog Post](#)
- [Subscribing to Email Notifications of Updates to Confluence Content](#)
- [Managing Changes and Notifications and Tasks](#)
- [Updating Email Address](#)
- [Managing Watchers](#)
- [Confluence User's Guide](#)

Watching all pages in a space

If you want to receive notifications of updates to any content in the space you can watch all pages.

To start watching a space:

1. Choose **Pages** in the space sidebar.
2. Choose **Watch this space** at the top right.

If your space uses the Documentation theme:

1. Choose **Browse > Space Operations**.
2. Choose **Watch this space** in the left-hand menu.

To stop watching a space:

1. Choose **Pages** in the space sidebar.
2. Choose **Stop watching this space** at the top right.

If your space uses the Documentation theme:

1. Choose **Browse > Space Operations**.
2. Choose **Stop watching this space** in the left-hand menu.

Watching for new blog posts in a space

You can choose to receive a notification whenever someone adds a blog post in the space. You will not receive notification of updates to or deletions of blog posts, nor of comments on the blog posts.

To start watching for new blog posts in a space:

1. Choose **Blog** in the space sidebar.
2. Choose **Watch this blog** at the top right.

If your space uses the Documentation theme:

1. Choose **Browse > Space Operations**.

2. Choose **Watch this blog** in the left-hand menu.

To stop watching for new blog posts in a space:

1. Choose **Blog** in the space sidebar.
2. Choose **Stop watching this blog** at the top right.

If your space uses the Documentation theme:

1. Choose **Browse > Space Operations**.
2. Choose **Stop watching this blog** in the left-hand menu.

Watching all Spaces on the Site

You can receive notifications about changes to the content of pages, blog posts and comments from across all spaces on a Confluence site.

To start watching for content changes across the whole site:

1. Choose **your profile picture** at top right of the screen, then choose **Settings**.
2. Choose **Email**.
3. Choose **Edit** then choose **Subscribe to daily updates**.
4. Choose **Submit**.

Managing watches from your user profile

The '**Watches**' page in your user profile displays a list of all pages and spaces you are currently watching.

To manage your watches:


1. Choose **your profile picture** at top right of the screen, then choose **Watches**.
2. Choose **Stop Watching** for any unwanted spaces or pages.

Managing watches from the email message

The email notifications that you receive from Confluence have some useful links at the bottom of the email message. The links in each message vary, depending on the context. In general, the links allow you to view the page online, reply to a comment, and so on. In particular with respect to setting your notification preferences, you will see one or more of the following links:

- **Stop watching page** – Click this link to stop watching the page that triggered the email notification.
- **Stop watching space** – Click this link to stop watching the space that triggered the email notification.
- **Stop following this user** – Click this link to stop following the user whose update triggered the email notification.
- **Manage Notifications** – Click this link to go to the email settings page in your user profile.

Screenshot: Email notification footer showing links



Managing watchers

Space administrators can view the watchers of a page or space, and manage the watchers of a page. See [Managing Watchers](#).

Notes

If your space administrator has removed the Pages and Blogs options from the space sidebar, it will not be possible to access the **Watch this space** and **Watch this blog** options.

Managing Watchers

If you are a [space administrator](#) for a space, you can manage the watchers for all pages and blog posts in that space. This means that you can:

- View a list of the watchers of a page/blog post.
- View a list of the watchers of the space for that page/blog post.
- Add users as watchers of the page/blog post.
- Remove existing watchers of the page/blog post.

i It is not possible to remove watchers of the space.

On this page:

Related pages:

- [Watching a Space](#)
- [Watching a Page or Blog Post](#)
- [Subscribing to Email Notifications of Updates to Confluence Content](#)
- [Managing Changes and Notifications and Tasks](#)
- [User Profile Overview](#)
- [Confluence User's Guide.](#)

To manage your watchers for a page/blog post:

1. Navigate to the page or blog post for which you want to manage the watchers. Note, you must be a space administrator for the space that the page is in.
2. Choose **Tools > Manage Watchers**. The 'Manage Watchers' screen will be displayed (see screenshot below). The left-hand column of the 'Manage Watchers' screen will contain the users watching the page/blog post, the right-hand column will contain the users watching the space.
 - To remove an existing page watcher, click the icon (trash can) next to the user's name.
 - To add a user as a watcher of the page, type in the box and choose the user's name from the list.
3. Click **Done** to save your changes.

Screenshot: Managing Watchers

Manage Watchers

Watching this page

These people are notified when the page is changed. You can add or remove people from this list.

 Sarah Maddox (smaddox) 

 Glenn Martin (gmartin) 

Watching this space

These people are notified when any content in the space is changed. You cannot modify this list.

 Rachel Robins (rrobins)

Subscribing to Email Notifications of Updates to Confluence Content

You can 'watch' a page, blog post or space. Confluence will then send you a notification by email whenever anyone adds or updates content on that page or space. You can also subscribe to daily email reports and other notifications of various updates, as described below.

You will only receive notifications for content that you have permission to view. Users that have been [disabled](#) by an administrator will not receive email notifications.

Subscribing to email notifications

You can subscribe to the following email summary reports:

- A daily report of updates to all spaces that you have permission to view.
- An immediate report of all blog posts added or changed, in all spaces that you have permission to view.
- An immediate report of all updates made by the people you are following, in all spaces that you have permission to view.
- An immediate report when someone follows you.
- A daily or weekly report of recommended updates, in all spaces that you have permission to view.

To edit your email notification settings:

1. Choose **your profile picture** at top right of the screen, then choose **Settings**.
2. Click **Email** in the left-hand panel.
3. Click **Edit**.

On this page:

- [Subscribing to email notifications](#)
 - [Subscribe to daily updates](#)
 - [Subscribe to all blog posts](#)
 - [Subscribe to network](#)
 - [Subscribe to new follower notifications](#)
 - [Subscribe to recommended updates](#)
- [Notes for administrators](#)

Related pages:

- [Managing Changes and Notifications and Tasks](#)
- [Subscribing to RSS Feeds within Confluence](#)
- [User Profile Overview](#)
- [Editing User Settings](#)
- [Confluence User's Guide](#)

Below is an explanation of all the email settings is explained below.

Setting	Description	Content	Frequency
Autowatch	Option: Do you want Confluence to automatically add you as a watcher on each page or blog post that you add or update? If you are a watcher of a page or a post, you will receive notification of future changes.	• Pages and blog posts that you create, edit or comment on.	(Not applicable)

Subscribe to daily updates	Receive email reports showing changes to content in all spaces that you have permission to view. <i>Note: Daily email reports do not include information about attachments on a page or blog post that are added, edited or deleted.</i>	• Pages and blog posts that are added, edited or deleted. • Comments on a page or blog post that are added, edited or deleted. • Updates by users who have changed their personal profile.	Daily
Subscribe to all blog posts	Receive email notifications for changes to blogs in your Confluence installation that you have permission to view.	• Blog posts added, edited or deleted.	Immediately
Subscribe to network	Receive email notifications for changes to content by all users that you are following, which you have permission to view.	• Pages being added, edited or deleted. • Blog posts being added, edited or deleted. • Comments being added, edited or deleted. • Status updates by the user.	Immediately
Subscribe to new follower notifications	Receive an email message when anyone chooses to follow you.		Immediately
Notify on my actions	Option: Do you want to receive email notifications for your own changes? <i>Note: If you have not subscribed to any email notifications and are not watching any pages/spaces, then selecting 'Notify on my actions' will not do anything.</i>	• All pages and spaces that you are watching. • This affects all subscriptions set.	(Not applicable)

Show changed content	Option: Do you want your notifications to include details of the changes made to the content? • If you do not select this option, your notifications will include only the title of the page, and any comment the author made when updating the page. • If you do select this option, your notifications will show the differences between the current and previous versions of the page. See Page History and Page Comparison Views.	• Edits to pages and blog posts.	(Not applicable)

Subscribe to recommended updates	Receive an email message showing the top content that is relevant to you from spaces that you have permission to view. How do you set the frequency of the mail message? A link in the email message allows you to choose daily or weekly notifications. How do you enable and disable the notification? You can turn off the notification by clicking a link in the email message. You can also turn the notification on or off by setting the 'Subscribe to recommended updates' option in your user profile.	Confluence chooses the content to display, based on: • Pages and blog posts that people have recently liked. • Pages and blog posts that people have recently commented on. • Pages and blog posts that have recently been created. 'Recent' means any activity that occurred since the last recommended updates message was sent to you. The activities are listed in order of popularity, with the most popular at the top. Likes, comments and content creations are scored equally. Activity that involves people in your network ranks higher than activity not involving your network. Content in your favourite spaces also ranks higher than content in other spaces. The recommended updates summary does not include any content that you created yourself, and it gives a lower ranking to content that you have participated in, for example by adding a comment or updating the page. If there is no activity to report, Confluence will not send the email message.	Daily (weekdays at 1pm) or weekly

Notes for administrators

- To enable Confluence to send email notifications, a System Administrator must configure an email server. See [Configuring a Server for Outgoing Mail](#). *Not applicable to Confluence OnDemand*.
- Confluence Administrators can set the default options for the recommended updates notification. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**. Click **Recommended Updates Email** in the left-hand panel. See [Configuring the Recommended Updates Email Notification](#).

Subscribing to RSS Feeds within Confluence

An RSS feed is a format for delivering summaries of regularly changing web content. Subscribing to an RSS feed allows you to stay informed of the latest content from sites that you are interested in.

RSS is not designed to be read in a regular web browser. Specialised RSS newsreader programs can check RSS files every so often, and tell you what's new on a site. Your reader may be on a website, an add-on to your browser, part of your email program, or a stand-alone program.

Confluence works with RSS in two ways:

- Confluence generates its own RSS feeds for tracking updates to content within Confluence. You will need an RSS reader which can grab the RSS feeds from Confluence and display them for you.
- Confluence's [RSS macro](#) allows you to display the contents of an RSS feed on a Confluence page. The feeds may come from a Confluence feed generator or from external sites. In this way, Confluence can act as an RSS reader.

For a technical description of RSS, read [Mark Pilgrim's "What is RSS?" article](#) on XML.com.

Confluence RSS feeds

RSS feeds allow you to track updates to content within Confluence. You will need an RSS newsreader to read a feed.

You can create a customised RSS feed using the RSS Feed Builder or subscribe to one of the pre-specified feeds generated by Confluence.

What would you like to do?

- [Create and subscribe to customised RSS feeds using the RSS Feed Builder](#) – Create a customised RSS feed. For example, you can filter your feed using a label, specify the number of items and days to include in your feed, and so on.
- [Subscribe to pre-specified RSS feeds](#)  – Generate an RSS feed automatically in a minimal number of steps.
- [Subscribe to a feed of any Confluence user's network](#) – Track the activities of users the selected person is following.

On this page:

- [Confluence RSS feeds](#)
- [RSS newsreaders](#)
- [Removing an RSS feed](#)

Related pages:

- [Managing Changes and Notifications and Tasks](#)
- [RSS Feed Macro](#)
- [Confluence User's Guide](#)

RSS newsreaders

The following are some popular RSS readers for various operating systems. You can find a more comprehensive list on [Google's open directory](#).

Windows

- [SharpReader](#)
- [NewsGator](#)
- [Syndirella](#)
- [FeedDemon](#)
- [NewzCrawler](#)

Mac OS X

- [Safari](#)
- [NetNewsWire](#)
- [NewsFire](#)
- [Shrook](#)

Multi-platform

- [NewsMonster](#) (Runs in the Mozilla web browser)
- [Radio Userland](#) (Windows and MacOS)
- [AmphetaDesk](#) (Windows, Unix, Mac OS X)

Removing an RSS feed

There is no need to try to delete or remove an RSS feed built by the Confluence [RSS feed builder](#).

Explanation: The feeds generated by the RSS Feed Builder are dynamically generated via the parameters included in the feed URL (address). For example, take a look at the following feed URL:

```
http://confluence.atlassian.com/createrssfeed.action?types=page&sort=modified&showContent=true...
```

The above feed URL will generate a list of pages ('types=page'), sorted by the modification date and showing the page content. The feed is generated at the time when the URL is fetched and there is no RSS feed information stored on the database. For that reason, there is no need to remove anything.

Using pre-specified RSS feeds

This page tells you how to get hold of an RSS feed which Confluence has predefined for you.

To subscribe to predefined RSS feeds for a particular space:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Content Tools > RSS Feeds**
3. Copy and paste the link for one of the feeds into your RSS newsreader:

If your space uses the Documentation theme:

1. Choose **Browse > Space Operations**

2. Choose **RSS Feeds** in the space operations options.
3. Copy and paste the link for one of the feeds into your RSS newsreader.

Feeds include:

- Pages
- Blog
- Mail
- Comments
- Attachments
- All content

To subscribe to predefined RSS feeds for a particular page (where available):

Note that the word 'page' here means a part of the Confluence user interface, rather than a page that contains Confluence content. For example, your [Network](#) view offers an RSS feed.

1. Go to the page.
2. Locate the following icon, which is available in the top-right corner of certain pages: 
3. Copy and paste the icon's link into your RSS newsreader.

Related pages:

- [Using the RSS Feed Builder](#)
- [Managing Changes and Notifications and Tasks](#)
- [RSS Feed Macro](#)
- [Confluence User's Guide](#)

Notes

If you want to customise your Confluence RSS feed (for example, use a label to filter your feed), use the [RSS Feed builder](#) instead of the above instructions.

Using the RSS Feed Builder

Using the RSS feed builder, you can create customised RSS feeds to subscribe to changes within Confluence.

Wondering what an RSS feed is? See [more information about RSS Feeds](#).

Building an RSS feed

Follow the steps below to build your feed, choosing the type of content and the time period you want to monitor.

To create a customised RSS feed:

1. Choose the help icon  at top right of the screen, then choose **Feed Builder**.
2. Select the content types you want in your feed.
Check **Mail** if you want to know when the email archive is updated. (See the [overview of mail archives in Confluence](#). *Not applicable to Confluence OnDemand.*)
3. Select one or more spaces from the list.
4. Click **Advanced Options** to set the following:

Option	Description
Feed Name	The default name is based on the name of your Confluence installation. For example, 'Extranet RSS Feed'.

With these labels	Enter one or more labels separated by spaces or commas. Confluence returns all content (of the selected types) that matches one or more of the labels. See the hint below about using labels to customise your feeds.
Exclude these spaces	Exclude specific spaces from those already selected.
Sorted by	Sort content by either the date or creation or the date they were last updated.
Limit to	Specify the number of items returned in your feed.
Within the last	Specify how old items returned can be.
Include content for pages	Specify whether the entire page is displayed in the feed.

5. Choose **Create RSS Feed**.
6. Drag or copy the link into your RSS reader.

On this page:

- [Building an RSS feed](#)
- [Hints](#)
- [Notes](#)

Related pages:

- [Managing Changes and Notifications and Tasks](#)
- [Subscribing to RSS Feeds within Confluence](#)
- [Confluence User's Guide](#)

Hints

- **Separate feeds.** Try building separate feeds, one for pages only and one that includes comments as well. This allows you to monitor only pages if you are short of time, and to read the comments when you have more time.
- **Labels to customise your feed.**

You can use the RSS feed builder to track updates to labelled pages and comments on those pages. Here is an idea for customising your RSS feed by using your own personal label(s). This is useful if you want to track updates to specific pages or blog posts, and you do not want to deal with emails. You can use this method as an alternative to watching pages.

- Build an RSS feed that returns pages, blog posts and comments labelled with a personal label, such as '**my:feed**'.
- Each time you want to 'watch' a page, just label it with '**my:feed**'.
- All updates and comments will automatically come through your RSS feed.

Notes

- **Removing an RSS feed:**

There is no need to try to delete or remove an RSS feed built by the Confluence [RSS feed builder](#).

Explanation: The feeds generated by the RSS Feed Builder are dynamically generated via the parameters included in the feed URL (address). For example, take a look at the following feed URL:

```
http://confluence.atlassian.com/createrssfeed.action?types=page&sort=modified&showContent=true...
```

The above feed URL will generate a list of pages ('types=page'), sorted by the modification date and showing the page content. The feed is generated at the time when the URL is fetched and there is no RSS feed information stored on the database. For that reason, there is no need to remove anything.

- **Feed authentication options:** Confluence can offer you the option of an anonymous feed or a feed that requires authentication.
 - An **anonymous** feed will show only the content that is visible to anonymous users. The feed URL does not contain the `&os_authType` parameter mentioned below. This feed is useful only if your Confluence site allows anonymous access. If a feed is anonymous, you only get anonymously-viewable content in the feed regardless of whether you are a Confluence user or not.
 - An **authenticated** feed requires you to log in to Confluence before you can retrieve the content. The feed URL contains the following parameter: `&os_authType=basic`.
 - The option to choose between an anonymous and an authenticated feed is currently not available on the feed builder screen. The feed builder offers only **authenticated** feeds. See [CONF-21601](#) for details and a workaround.

Subscribing to a Network RSS Feed

You can create an RSS Feed from any user's [network](#) view, allowing you to receive summaries on the activities of users they are following in their network. The types of activities tracked in these RSS feed summaries include:

- Additions or edits to [pages](#) or [blog posts](#)
- [Comments](#) added to a page or blog post or edits to existing comments
- Updates to a user's [status updates](#)
- Updates to a user's [profile](#)

Subscribing to a user's network feed

To subscribe to a user's network RSS feed:

1. Locate the RSS icon , which is available from the top-right of:
 - The 'Recent activity of the users you are following' section of your network page, or
 - The 'Activity of followed users' section of another user's network page.
2. Copy and paste the icon's link into your RSS newsreader.

On this page:

- [Subscribing to a user's network feed](#)
- [Customising your network RSS feed](#)
- [Notes](#)

Related pages:

- [Network Overview](#)
- [Subscribing to RSS Feeds within Confluence](#)
- [Confluence User's Guide](#)

Customising your network RSS feed

Confluence does not provide a way of customising a network RSS feed via the user interface. However, you can modify the maximum number of results and type of content displayed in these feeds by directly editing the RSS feed link in your RSS newsreader.

To modify the maximum number of results displayed in your RSS feed:

1. Edit the RSS feed link in your RSS newsreader.
2. Change the value of the max parameter from its default value of 40 to a value of your choice. Example:
`http://confluence.atlassian.com/feeds/network.action?username=MYNAME&max=60&publicFeed=false&os_authType=basic&rssType=atom`
3. Save the modified link in your RSS newsreader.

To modify the type of content displayed in your RSS feed:

1. Edit the RSS feed link in your RSS newsreader.
2. Append the parameter contentType to the end of the link, followed by an equals sign (=) and then add the appropriate content type value of your choice:
 - USER_STATUS — restricts the RSS feed to user status updates.
 - PAGE — restricts the RSS feed to page additions or updates.
 - BLOG — restricts the RSS feed to blog post additions or updates.
 - ATTACHMENT — restricts the RSS feed to attachment additions or updates.
 - COMMENT — restricts the RSS feed to comment additions or updates.

Content type values are case-sensitive. Ensure that each parameter is separated from the other by an ampersand (&).

Example:

`http://confluence.atlassian.com/feeds/network.action?username=ggaskell&max=40&publicFeed=false&os_authType=basic&rssType=atom&contentType=USER_STATUS`

3. Save the modified link in your RSS newsreader.

Notes

It is not possible to filter for more than one type of content by adding multiple values to the contentType parameter.

Managing Notifications in Confluence

This page is about the notification-and-task dialog, known as the Confluence 'workbox', which drops down when you choose the  icon on the Confluence page header.

Do you want to manage your notification email messages instead? See [Subscribing to Email Notifications of Updates to Confluence Content](#).

Managing your notifications in the Confluence workbook

The workbook displays all notifications collected from Confluence page watches, shares, mentions, and tasks. If your Confluence site is linked to a [JIRA issue tracker](#), you will also see JIRA notifications in your workbook.

You can view your notifications and convert them to personal tasks. Use the inline actions to reply to comments, like a comment or page, or watch a page. Follow the links in a notification to open the relevant page or blog post. With JIRA integration, you can watch or unwatch issues, comment on issues, or follow the link to open the issue in JIRA.

The workbook displays your notifications and your personal tasks in separate tabs.

To manage your notifications:

1. Choose the workbook icon  in the Confluence page header.
 - A number may appear on the workbook icon, indicating the number of unread notifications waiting for your attention.

- You can use the keyboard shortcut: Type **g** then **n**. (When in the Confluence editor, click outside the editor pane before pressing the keyboard shortcut keys.)



2. Choose the notifications icon:

3. Choose a notification from the list, to see the notification details. Now you can do the following:

- Choose a link or **Open** to open the related page, blog post, or comment. The page will open in a new tab in your browser.
- Choose **Like** or **Unlike** to let people know that you like, or have stopped liking, a page, blog post, or comment.
- Choose **Watch** or **Stop Watching** to receive notifications, or stop receiving notifications, about a page or blog post.
- Choose **Reply** to respond to a comment inline, within the workbox.
- Choose the 'add task' icon  to flag a notification as a task. The notification will remain in the notification list too.


On this page:

- [Managing your notifications in the Confluence workbox](#)
- [Which notifications are included?](#)
- [Keyboard shortcuts](#)
- [Managing notifications with Confluence mobile](#)
- [Notes](#)

Related pages:

- [Configuring Workbox Notifications](#)
- [Subscribing to Email Notifications of Updates to Confluence Content](#)
- [Watching a Page or Blog Post](#)
- [Likes and Popular Content](#)
- [Managing Tasks in Confluence](#)
- [Confluence User's Guide](#)

Screenshot: Your Confluence notifications in the workbox



Which notifications are included?

The workbox displays a notification when someone does one of the following in Confluence:

- [Shares](#) a page or blog post with you.
- [Mentions](#) you in a page, blog post or comment.
- Assigns you a task by mentioning you in a [task list](#).
- Comments on a page or blog post that you are [watching](#).
- [Likes](#) a page or blog post that you are watching.

The workbox does **not** show notifications triggered because you are watching a space. Only watches on pages and blog posts are relevant here.

If your Confluence site is linked to JIRA, you will also see the following JIRA notifications in your workbox:

- Comments on issues that you are watching.
- Mentions.
- Shares of issues, filters and searches.

Keyboard shortcuts


Key	Action
g then n	Open the Confluence workbox.
j	Move down to the next entry in the notification list.
k	Move up to the previous entry in the notification list.

n	Move down to the next notification for a particular page or blog post.
p	Move up to the previous notification for a particular page or blog post.
Enter	Open the selected notification.
u	Return to the notification list after opening a particular notification.

Note: The above keyboard shortcuts are available for notifications only, not for tasks, inside the Confluence workbox.

Managing notifications with Confluence mobile

You can view and respond to your notifications on your phone or other mobile device too. See [Using Confluence on a Mobile Device](#) for more about mobile platforms.



Notes

- Read notifications are automatically deleted after 2 weeks.
- Unread notifications are automatically deleted after 4 weeks.
- You cannot delete your notifications yourself.
- If a new notification arrives while you have workbox open, the count appears on the workbox icon  but the notification is not added to the workbox. You need to close workbox and re-open it to see the new notification.
- The ability to receive notifications from JIRA or another Confluence site is available in **Confluence 4.3.3 and later**. To receive JIRA notifications, you need **JIRA 5.2 or later**.
- Administrators can enable and disable the workbox on your Confluence site. They can also connect a JIRA site or another Confluence site, so that notifications from those sites appear in your workbox too. See [Configuring Workbox Notifications](#).
- The Confluence workbox is provided by a set of plugins. To remove the personal notifications and tasks functionality from your site, you can disable the following plugins. See [Disabling or Enabling a Plugin](#) for instructions. Disabling these plugins will disable the entire workbox . It is not possible to disable only tasks or only notifications:
 - Notifications and Tasks - Common Plugin
 - Notifications and Tasks - Host Plugin

- Notifications and Tasks - Confluence Provider Plugin
- If you want to re-enable the plugins, do so in the following order: Common Plugin, Host Plugin, Confluence Provider Plugin.
- There is no option to disable the workbox for an individual user.
- The workbox is not available in [clustered](#) environments. The plugin will be installed and enabled, but it will detect that the site is in clustered mode and will not display the dialog.

Managing Tasks in Confluence

You can manage your personal tasks in the notification-and-task dialog, known as the Confluence 'workbox', which drops down when you choose the icon  in the Confluence page header.

You can also create a list of tasks on a page, and assign them to your colleagues via [@mention](#). Changes made in the workbox are reflected in the task list on the page, and changes made on the page are reflected in the workbox too.

Creating personal tasks and having tasks assigned to you

There are a few ways that you and other people can assign tasks to you:

- You can add a personal task via the workbox.
- You can add a notification to your task list, via the notification workbox. This is useful if you want to get back to it later.
- Someone can assign you a task from a task list on a Confluence page.
- Other Confluence actions may create a task for you. For example, your Confluence site may be running a plugin that creates and assigns tasks.

On this page:

- [Creating personal tasks and having tasks assigned to you](#)
- [Managing your personal tasks in the workbox](#)
- [Adding your notifications to your task list](#)
- [Creating task lists and managing tasks on a page](#)
- [Managing tasks with Confluence mobile](#)
- [Notes](#)


Related pages:

- [Tasklist Macro](#)
- [Managing Notifications in Confluence](#)
- [Subscribing to Email Notifications of Updates to Confluence Content](#)
- [Confluence User's Guide](#)

Managing your personal tasks in the workbox

The workbox displays your notifications and your personal tasks in separate tabs. The task tab shows the tasks assigned to you. When you update a task that originated in a task list on a page, the update is reflected in the task list too.

Screenshot: Your personal tasks in the workbox



To manage your tasks:

1. Choose the workbox icon  in the Confluence page header.
 - You can use the keyboard shortcut: Type **g** then **n**. (When in the Confluence editor, click outside the editor pane before pressing the keyboard shortcut keys.)
 - The icon indicates the number of unread notifications.

2. Choose the personal tasks icon: 
3. To add a task and assign it to yourself, type the task summary in the text box and choose **Add task**.
4. To prioritise tasks, drag and drop them into your chosen order. (Click a task, hold down your mouse button to drag the task into position, then release the mouse button.)
5. To complete a task, or mark it as incomplete, choose the check box next to the task.
6. To add notes to a task and see further information (for example, a related page) choose the task item. The task details dialog will open.
7. To see the tasks that are marked as complete, choose **View completed**.

Adding your notifications to your task list

You can flag a notification as a task. This is useful if you want to take action on the notification later.

To add a notification to your task list:

1. Choose the workbox icon  in the Confluence page header.
 - You can use the keyboard shortcut: Type **g** then **n**. (When in the Confluence editor, click outside


the editor pane before pressing the keyboard shortcut keys.)

- The icon above shows that you have 3 unread notifications.

2. Choose the notifications icon: 
3. Choose the notification that you want to add to your task list. The notification details dialog will open.
4. Choose the 'add task' icon  to add this notification to your tasks. The notification will remain in the notification list too.

See [Managing Notifications in Confluence](#) for a full description of notifications.

Screenshot: The notification details dialog



Creating task lists and managing tasks on a page

Task lists on a page are useful for assigning and managing tasks in a team.

To add a task list on a page:

1. Edit the page.
2. Choose the task-list icon  in the editor toolbar, or press [and then] on your keyboard.
3. Type the description of the task.
4. If you want to assign a task to someone, type '@' and the person's name in the task description. (For more information about @mentions, see [Using Mentions](#).) That person will receive a notification, and the task will appear in their personal task list in the workbox. If you @mention yourself, the task will appear in your personal task list.
5. To end the list, press Enter twice.

Keyboard shortcuts:

- To add a task list, press press [and then] on your keyboard.
- To indent a task, press Tab.
- To undo an indent, press Shift+Tab.

Managing tasks on a page:


- When viewing a page, you and other viewers can mark tasks as complete or incomplete. Updates to a task on the page will be transferred to the workbox too. (See [above](#).)
- To be able to update a task list when in view mode, you need permission to edit the page:
 - You need the 'Create page' permission in the space. See [Space Permissions Overview](#).
 - There must not be any page restrictions that prevent you from editing the page. See [Page Restrictions](#).

What if the update fails?

This section describes what you should do if Confluence displays an error message saying that your change to a task list could not be saved. The cause is probably one of the following:


- Your session has expired. **Resolution:** Log in and update the task list again.
- You do not have permission to update the task list. **Resolution:** Check your permissions. You need 'Create page' permission in the space. Please check also that there are no page restrictions that prevent you from editing the page.
- The network is down. **Resolution:** Please try again when the network is available.

Screenshot: A task list on a page



Managing tasks with Confluence mobile

You can view and manage your tasks on your phone or other mobile device too. See [Using Confluence on a Mobile Device](#) for more about mobile platforms.



Notes

- Administrators can enable and disable the workbox on your Confluence site. They can also connect a JIRA site or another Confluence site, so that notifications from those sites appear in your workbox too. See [Configuring Workbox Notifications](#).

- The Confluence workbox is provided by a set of plugins. To remove the personal notifications and tasks functionality from your site, you can disable the following plugins. See [Disabling or Enabling a Plugin](#) for instructions. Disabling these plugins will disable the entire workbox . It is not possible to disable only tasks or only notifications:
 - Notifications and Tasks - Common Plugin
 - Notifications and Tasks - Host Plugin
 - Notifications and Tasks - Confluence Provider Plugin
- If you want to re-enable the plugins, do so in the following order: Common Plugin, Host Plugin, Confluence Provider Plugin.
- There is no option to disable the workbox for an individual user.
- The workbox is not available in [clustered](#) environments. The plugin will be installed and enabled, but it will detect that the site is in clustered mode and will not display the dialog.
- Completed tasks in the workbox are automatically deleted after 7 days.
- You cannot disable the functionality that provides task lists on a page.
- There is no link between the tasks in a [Tasklist Macro](#) and the tasks described above. The tasks from the macro do not appear in the workbox.
- **Have a feature request?** If you are interested in expanding the functionality of tasks in Confluence, you can collaborate with other customers, vote and view all the open feature requests for this feature in the [workbox component of the Confluence issue tracker](#).
For example, here are some of the feature requests on the issue tracker:
 - Ability to get a list of tasks from content: [CONF-26688](#)
 - Ability to see other users tasks: [CONF-26615](#)

Finding Content

Where does a page or blog post go when you create it, and how can you find it again? How can you find content that is most relevant to your team or project, or search for pages that cover the topic you are interested in?

Hint for space administrators: Help your team members and colleagues find important pages and other content, by adding links to the space's sidebar. See [Configuring a Sidebar](#).

A space is an area within Confluence, containing your pages, blog posts and other content. You can think of each space as a sub-site, or mini-site, each with its own home page.

Finding pages and blog posts

These are the quickest ways to find your content:

- Use the links in the **sidebar** to find your pages, blog posts, and other parts of the space. See [more details below](#).
- Go to the **pages** view for a list of pages in the space. You can see recently updated pages or browse through a hierarchical (tree) view. See [Viewing All Pages in a Space](#).
- Type the page name or key words into the **search box** at the top right of the Confluence screen. See [Searching Confluence](#).

More about the sidebar

The sidebar appears on the left of every page in spaces that use the default Confluence theme. You can:

- Choose a different type of content, or perform various operations, via the links on the sidebar.
- Use the contextual navigation options that appear at the bottom of the sidebar, based on the type of content you are viewing.
- Collapse or expand the sidebar.
- Access the sidebar options via slide-out menus even when the sidebar is collapsed.

- Configure the links that appear in the 'Shortcut links' section, if you are a space administrator.


On this page:

- Finding pages and blog posts
- More about the sidebar
- Collapsing the sidebar
- Where does Confluence put your pages and blog posts?
- Can you change the location of a page?
- Can you change the location of a blog post?

Related pages:

- Creating Content
- Organising Content
- Giving People Access to Content
- Using the Documentation Theme
- Confluence User's Guide

Screenshot: Sidebar in the default theme




Section or option	Explanation

Link to the space home page	This link appears next to the space logo at the top of the sidebar. It takes you to the home page for this space. Clicking on the space logo will also take you to the home page for the space.
Pages and Blog	This section can contain the links to the following locations: • Pages: An index of all pages in the space. See Viewing All Pages in a Space. Note that space administrators can hide the 'Pages' link. • Blog: An index of all blog posts in the space. See Working with Blog Posts. Note that space administrators can hide the 'Blog' link. • Other links added by add-ons.
Space shortcuts	This area contains links to important pages and other locations for your project or team. Space administrators can add and remove links here. See Configuring a Sidebar .
Space Tools	The 'Advanced' option gives access to space administration and advanced operations like space exports and space watches.
Configure sidebar	The 'Configure sidebar' option is available to space administrators for setting up shortcut links, changing the space name and logo, and other configuration options. See Configuring a Sidebar .
Contextual navigation	The links in this area change, depending on the section of the space that you are viewing. • For pages, you will see the child pages (if any) of the current page, and a quick link to create a child page. • For blogs, you will see links to blog posts in the current month, and an expandable list of previous months. • If you are viewing the space tools option, you will see content tools, space administration, and other advanced options. Add-ons can add options here too.

Collapsing the sidebar

Advanced users will find it useful to collapse the sidebar and gain more space on the page.

- Grab and drag the border, or use the keyboard shortcut **[** to collapse and expand the sidebar.
- Access the sidebar options via slide-out menus even when the sidebar is collapsed.



Where does Confluence put your pages and blog posts?

When you create a new page, that page will be a child of another page, in the space that you selected in the 'Create' dialog. The parent page depends on where you are when you create the page.

Your location when creating the page	Location of new page
You are viewing a page in the same space where you will put the new page – that is, the space that you select in the 'Create' dialog.	A child of the page you are currently viewing.
You are viewing any other Confluence screen. For example: - You are on the dashboard. - You are on the 'Pages' view of a space. - You are viewing a blog post. - You are viewing a page in a space, and choose to add your new page in a different space.	A child of the home page in the space you select in the 'Create' dialog.

A blog post is part of a chronological sequence of posts, linked from the space's 'Blog' index page.

Can you change the location of a page?

Yes. See [Moving a Page](#).

Can you change the location of a blog post?

No.

Searching Confluence

Quick guide to searching in Confluence:

1. Use the search box at the top right of your Confluence screen. It offers you a quick navigation aid as well as a full site search.
2. You can search Confluence directly from your browser's search box. Just add your Confluence site as a search provider using the dropdown menu in your browser's search box.
3. While editing a page or a blog post, you can find and replace text on the page. See [Using the Editor](#).


Using the Quick Navigation Aid

The quick navigation aid automatically offers a dropdown list of pages and other items, matched by title to your search query. You can select one of the offered items or ignore them altogether.

To use the quick navigation aid:

1. Start typing your query into the search box located at the top right-hand corner of every screen. Confluence matches titles as you type, showing a quickly-adjusting dropdown list of pages, blog posts, personal profiles, attachments and so on.
 Press the Enter key if you want to bypass the quick navigation aid and perform a full search, as described [below](#).
2. To see the space to which an item belongs, let your mouse pointer hover over the item in the dropdown list.
3. Use the up- and down-arrows on your keyboard to move up and down the list of matching titles and select an item.
4. Press the Enter key to open the selected item.
5. If you do not find what you are looking for, click **Search for** at the bottom of the list to do a full search. This has the same effect as pressing Enter immediately after typing your search query. The full search is described [below](#).

Screenshot: The quick navigation aid showing titles matching the query 'sta'



Here is more information about how the quick navigation feature works:

- Confluence will truncate any titles that are too long to be displayed.
- The matching items are grouped by content type so that you can quickly find the type you want. Confluence shows a maximum of 6 pages and/or blog posts, 2 attachments, 3 people and 2 spaces. If no matches are found in a particular category, then that category does not appear in the list.
- Items are ordered with the most recent updates first.

- When the matching item is a person's name, their profile picture appears next to their name in the list.
- The part of the title that is matched by the search query is highlighted in bold text.
- Your [Confluence Administrator](#) can enable or disable the quick navigation feature using the Confluence Administration Console.

On this page:

- [Using the Quick Navigation Aid](#)
- [Performing a Full Search](#)
- [Viewing Attached Office Documents](#)
- [Accepting 'Did you mean' Suggestions from Confluence](#)
- [Filtering your Search Results](#)
- [Using Labels in the Search](#)
- [Searching the Content of Attachments](#)
- [Search Options When Using the Documentation Theme](#)
- [Advanced Search Syntax](#)
- [Searching Confluence from your Browser's Search Box](#)
- [Useful plugins \(*Not applicable to Confluence OnDemand.*\)](#)
- [Notes](#)

Related pages:

- [Confluence Search Syntax](#)
- [Confluence Search Fields](#)
- [Ranking of Search Results](#)
- [Text Tokenisation and Filtering](#)
- [Search Results Macro](#)
- [Livesearch Macro](#)
- [Page Tree Macro \(includes an optional search box\)](#)
- [Viewing Labels and Labelled Content](#)
- [Searching the People Directory](#)
- [Confluence User's Guide](#)

Performing a Full Search

When you perform a full search, Confluence will search all content in all spaces (site and personal), mail, personal profiles, attachments and the space description. The results will appear on a new screen.

To use the full search:

1. Type your query into the search box located at the top right-hand corner of every screen (or type it into the text box at the top of the Search screen).
2. Press the Enter key. (This means that you will ignore the dropdown list of titles offered by Confluence's quick navigation aid, described [above](#).)
3. The Search screen appears, as shown below. If any Confluence pages or items match your search query, the Search screen shows a list of the matching items.
4. Click an item's title to open the Confluence page or other item.

Screenshot: Results of searching for 'permissions'

The screenshot shows a search results page in Confluence. At the top, there is a search bar with the text 'permissions' and a 'Search' button. Below the search bar, it says 'Showing 1-10 of 566 for permissions'. The main content area on the left lists search results. The first result is a document titled 'Assigning Space Permissions' with a document icon, followed by 'Image Preview (5)' and 'View All (5)'. The snippet describes assigning space permissions to groups or individual users. The second result is 'Space Permissions Overview' with a document icon, followed by 'Space Permissions Overview' and a snippet about space permissions. The third result is an image file named 'pagepermission.jpg' with a thumbnail, followed by '12 kB - 631x160 Download' and a breadcrumb trail 'Confluence Latest > Space Attachments Directory > Attachments Nov 28, 2005'. On the right side, there are filter options under the heading 'Where' (Confluence Latest), 'What' (All Content), 'When' (Any date), and 'Who' (empty). Below these are 'Filter' and 'Clear Filter' buttons. At the bottom right, there is a 'Browse Labels' section with links for 'permissions', 'bamboo', 'access', 'security', and 'space'.

On the left of the screen you will see a text block for each item that matched the search criteria, with the following information for each item:

- An icon representing the content type (user profile, space, page, blog post, etc).
- The title or name of the content item.
- For attachments: The size and type of file, with a link to download or view the attachment where relevant. See information on [viewing Office attachments](#) below.
- For image files: A thumbnail of the image will display to the right of the file name.
- The most relevant few lines of content from within the item. Any words that match your search query are highlighted within the content.
- For personal profile items: The email address.
- The space to which the item belongs, displayed on the last line of the item's text block.
- The date when the content item was last modified.

You will see only search results which you have permission to view.

On the right of the screen are further options which allow you to tailor or filter your search results. See [below](#).

Viewing Attached Office Documents

When the search results include an attached Office document, you will see a **View** link as shown in the screen snippet below.

Screenshot: Search results include an attached Office document with 'View' link

The screenshot shows a search results page in Confluence. At the top, there is a search bar with the text 'spreadsheet' and a 'Search' button. Below the search bar, it says 'Showing 1-1 of 1 for spreadsheet'. The main content area on the left lists search results. The first result is a document titled 'Sales Spreadsheet' with a document icon, followed by '11 kB Excel Spreadsheet View Download' and a snippet 'Sales Spreadsheet Quarterly sales figures for MyCompany. Sample Space Feb 19, 2013'.

Click the **View** link to view the content of the Office document within Confluence. If you have an Office application installed, you will also be able to launch your Office editor from within Confluence. See [Displaying Office Files in Confluence](#) and [Working with the Office Connector](#).


Accepting 'Did you mean' Suggestions from Confluence

When you perform a full Confluence search, as described [above](#), Confluence may offer you an alternative spelling of your search query. The alternative spelling will appear next to the words '**Did you mean**', as shown in the example below.

To accept an alternative spelling suggestion:

1. Type your query into the search box.
2. Press the Enter key.
3. Confluence will analyse the wiki content, to determine whether an alternative spelling of your search query occurs more often in the wiki content. If this is the case, the words '**Did you mean**' will appear on the screen, along with an alternative spelling for your search query.
4. If you want to try the alternative spelling, click the word showing the suggested spelling. In the example below, you would click **confluence**.

Screenshot: The Search screen with 'Did you mean' offering a corrected spelling



cnofluence Search

Did you mean: **confluence**

No results found for **cnofluence**. Please try one of the following suggestions:

- Use more general search terms
- If you are filtering by space, content, last modification date or contributor, try removing or adjusting the filter

Here is more information about how the 'Did you mean' feature works:

- Confluence uses both a dictionary (bundled with Confluence) and words mined from the content on your system to work out the best alternative spellings of your search terms. Practically, this means that Confluence can provide spelling corrections for specialised jargon that may not appear in a standard dictionary. In general, when deciding between alternative spellings, Confluence will favour words that appear more often in your content.
- In some cases, the 'Did you mean' suggestion may appear even when there are Confluence pages, etc, which match your search query. In other cases, there will be no items which match your search criteria. In both cases, Confluence will offer a 'Did you mean' suggestion if there is a word which will help you find more relevant content.
- The 'Did you mean' feature may offer more than one suggestion.
- The 'Did you mean' suggestion may even offer an incorrect spelling. This would happen if the incorrect spelling occurs many times within your Confluence site. This is intentional, because the aim of the 'Did you mean' feature is to help you find content, not to correct your spelling.
- Your [Confluence Administrator](#) can enable or disable the 'Did you mean' feature using the Confluence Administration Console.

Filtering your Search Results

The Search screen, [pictured above](#), appears when you do your first search. By default, Confluence will search all content across your Confluence site, including all spaces, mail archives, attachments and all other content

types.

On the right of the screen are options which allow you to tailor or filter the search results.

Where

Confluence Latest ▼

☐ Include archived spaces

What

All Content ▼

When

Any date ▼

Who

Content the user has created or edited.

Filter Clear Filter

Enter your filter criteria as described below, then click **Filter**.

- **Where** — Restrict your search results to a particular space, or to your favourite spaces, site spaces or personal spaces.
- **What** — Restrict your search results to a particular content type (pages, blog posts, mail, etc).
- **When** — Restrict your search results to content modified within a particular period of time (today, yesterday, within the last week or within the last month).
- **Who** — Restrict your search results to content last modified by a particular user. You can start typing the person's username or part of their name into the text box as follows:
 - Type the username (e.g. 'jsmith').
 - Or start typing the person's first name (e.g. 'john')
 - Or their last name (e.g. 'smith').
 - Or another part of their name, such as a middle name.

Confluence will offer you a list of possible matches. Use your mouse to select the person you want, then press the Enter key to filter the search results.

More information about the user-matching filter:

- The user-matching filter is *not* case sensitive. You can enter upper or lower case letters and will receive the same results.
- When looking for users to match the name you entered, Confluence divides a person's name into logical units corresponding to first name, middle name (one or more) and last name. It matches the letters of each unit in the name you entered against the letters of each unit in the user directory. For example, you can enter 'jo sm' to look for John Smith. The search is triggered after you have entered at least two letters.
- For each part of the name, you need to enter at least two letters. For example, if you enter just 'john s', the filter will look for users called 'john' and will ignore the 's'. Similarly, if you enter 'j smith' you will see everyone with the name 'smith' even if their first name does not start with a 'j'.
- You are not forced to use the auto-complete list. You can just type 'jsmith' or 'jo sm' and filter on that without choosing a match from the dropdown list. Confluence will warn you if there is more than one user corresponding to the name you have entered.

Click **Clear Filter** if you want to remove all your filters and perform the same search again but without the filter.

Using Labels in the Search

Searching for Labels

Use the 'labelText:' prefix to search specifically for content that has a specific label. The table below gives examples of search terms that you can enter into Confluence's search box, and the search results that you can expect.

Searching for ...	Returns content that ...
recipe labelText:chocolate	contains the word 'recipe' or has the label 'chocolate'
recipe AND labelText:chocolate	contains the word 'recipe' and has the label 'chocolate'
labelText:cake labelText:chocolate	has the label 'cake' or the label 'chocolate'
labelText:cake AND labelText:chocolate	has both labels 'cake' and 'chocolate'

The 'labelText:' prefix is an example of a search field. See more about [Confluence Search Fields](#).

Browsing Related Labels

On the right of the search screen, Confluence offers a list of labels which are related to your search query. See the screenshot [above](#). You can click a label to see all pages and blog posts tagged with that label. See [Viewing Labels and Labelled Content](#).

Searching the Content of Attachments

When you search Confluence, by default the search will include the content of the following types of attachments:

- Word
- Text
- PowerPoint
- Excel
- PDF
- HTML

To search the content of other attachment types, you will need to use an attachment content extractor plugin. (*Not applicable to Confluence OnDemand*.) For more information, take a look at the following:

- Existing extractor plugins which you can install on your Confluence site. See this [search on Atlassian Marketplace](#).
- Guidelines on developing your own attachment content extractor plugin. See our [developer documentation on extractor plugins](#).

Search Options When Using the Documentation Theme

When using the Documentation theme, the Confluence search offers a few options as described below.

Using the search box at the top right of the page:

- By default, the main Confluence search is configured to search the entire Confluence site.

- You will see the words '**Search Confluence**' in the search box at top right of the page.
- The Confluence search will look for matches in the entire Confluence site. This is the default behaviour for other themes too.
- A space administrator can configure the Documentation theme to restrict the search to the current space.
 - You will see the words '**Search this space**' in the search box at top right of the page.
 - The search will return results from the current space only.
 - You can override the search restriction. Enter '**all:**' and your search term to search the entire site. For example, enter the following into the search box at top right of the page to search the entire site for 'technical writing':

```
all: technical writing
```

Using the search box in the left-hand panel:

- By default, the Documentation theme's left-hand panel includes a search box. Enter your search term there, to restrict the search to the current space. Specifically, this will search only the pages that are children of the space's home page.
- If your administrator has restricted the main search to the current space, there will not be a search box in the left-hand panel.

For screenshots and a full description, see [Using the Documentation Theme](#).

Advanced Search Syntax

See [Confluence Search Syntax](#) for more ways to refine the text you enter into the search box.


Additionally, see [Confluence Search Fields](#) for special parameters you can use in the search box to search on various metadata.

Searching Confluence from your Browser's Search Box

If you are using Firefox or Internet Explorer 7 or later, you can add your Confluence site as a search provider, using the dropdown menu next to the browser's search box.

The example below shows the 'Extranet' Confluence site offered for inclusion as a search engine in the browser's search box.

Screenshot: Adding your Confluence site to your browser's search box



Information about OpenSearch:

- Confluence supports the autodiscovery part of the [OpenSearch](#) standard, by supplying an [OpenSearch description document](#). This is an XML file that describes the web interface provided by Confluence's search function.
- Any [client applications](#) that support OpenSearch will be able to add Confluence to their list of search engines.
- Your [Confluence Administrator](#) can enable or disable the Open Search feature using the Confluence Administration Console.

Useful plugins (*Not applicable to Confluence OnDemand.*)

Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#).

This plugin extends the Confluence search, so that you can search for macro parameter names and values: the [Confluence Macro Indexer plugin](#).

Notes

For developers: The rendering of search results in Confluence is pluggable. If you are a developer, you may wish to write your own search result renderer to change how the search results are displayed. For more information, please refer to the following developer document: [Writing a search result renderer](#).

Text Tokenisation and Filtering

When searching for content based on search terms entered by the user, Confluence splits the text of the content into tokens, and then filters and modifies those tokens according to the following rules.

Tokenisation

Confluence uses Lucene's [Standard Tokenizer](#). This splits the text into tokens as follows:

- Splits words at punctuation characters, removing punctuation. However, a dot that's not followed by white space is considered part of a token.
- Splits words at hyphens, unless there's a number in the token, in which case the whole token is interpreted as a product number and is not split.
- Recognises email addresses and internet host names as one token.

 An example: The string 'foo-bar5' won't be split into 'foo' and 'bar5', so a search for 'bar5' or 'bar*' will not find any results.

Filtering

Confluence then:

- Removes "'s" from the ends of words.
- Removes the dots from acronyms, e.g. I.B.M. becomes IBM.
- Converts everything to lower case.
- Removes common words like 'the' and 'or' are removed.
- Converts words to their stems. For example, 'fishing' and 'fishes' both become 'fish'.

Note

At this moment, the query string for search with wildcards have issues with case sensitive words. We have an open [bug](#), kindly have a look.

Related Topics

[Searching Confluence](#)

Confluence Search Syntax

This page describes how you can refine your search. Confluence will ignore common words like 'the' unless you place your query within quotes.

Exact phrase search

To search for content that contains the exact phrase "chalk and cheese"

```
"chalk and cheese"
```

i Confluence will ignore common words ([stop words](#)) like "and" above. [This](#) is the default list of stop words used by lucene. Please cast your vote towards [this](#) improvement request.

For eg:

1. Searching for "The One" returns all pages containing "One" because "The" is a stop word.
2. Searching for "Cheese One" would only return pages in which "One" appears as the first word (other than stop words) after "Cheese". So it would return "Cheese for One" or "Cheese to One" or "Cheese One". It would not match "One Cheese" or "Cheese Flamingo One"

OR search

To search for content that contains one of the terms, "chalk" OR "cheese"

```
chalk OR cheese
```

Please note that the operator OR must be typed in capitals.

On this page:

- [Exact phrase search](#)
- [OR search](#)
- [AND search](#)
- [NOT search](#)
- [Excluded term search](#)
- [Grouping search](#)
- [Title search](#)
- [Wild card searches](#)
- [Proximity searches](#)
- [Range search](#)
- [Fuzzy search](#)
- [Combined search](#)
- [Searching for macros](#)
- [Searching for labels](#)

Related pages:

- [Searching Confluence](#)
- [Confluence Search Fields](#)
- [Confluence User's Guide](#)

AND search

To search for content that contains both the terms "chalk" AND "cheese"


```
chalk AND cheese
```

Please note that the operator AND must be typed in capitals.

NOT search

To search for content that contains "chalk" but NOT "cheese"

```
chalk NOT cheese
```

Please note that the operator NOT must be typed in capitals.

Excluded term search

Similar to the NOT search, to search for content that contains "chalk" and "butter" but NOT "cheese"

```
chalk butter -cheese
```

Grouping search

To search for content that MUST contain "chalk" but CAN contain either "cheese" or "butter" use the search:

```
(cheese OR butter) AND chalk
```

Title search

To search for content with "chalk" in its title, where *title* is the field keyword.

```
title:chalk
```

Wild card searches

Single character

To search for "butter" or "batter" you can use the search:

```
b?tter
```

To search for "chicken" or "chickpea" you can use the search:

```
chick*
```

 Wildcards can be used anywhere within a word, except at the very beginning.
For example:

```
*chick
```

is an invalid search term.

Multiple characters

To search for "chick" or "chickpea":

```
c*c*
```

You can also combine search characters to get the exact word. For example the search term below will return "chick" yet not "chickpea":

```
c*c?
```

Case Sensitivity in wildcard searches

Since the fix for [CONF-13846](#) Confluence is case sensitive for wildcard searches.

You should note that all the example searches given previously search across the default set of fields which are stored as lower case and therefore all searches of that style should be given lower case search terms (as shown in the examples).

However, if you were to search one of the case sensitive fields, such as 'content-name-untokenized' the case of your search term would need to match the document you are searching for.

Proximity searches

This search ensure that the two words specified must be within a certain number of words of each other to be included.

```
"octagon post"~1
```

will return "Octagon blog post".

```
"octagon post"~0
```

is an invalid search term.

Range search

Searches for names that fall alphabetically within the specified range.

```
[adam TO ben]
```

Note: You can't use the **AND** keyword inside this statement and that TO must be written in capitals to form a

valid search.

Fuzzy search

This search looks for words spelled similarly.

To search for octagon, if unsure about spelling:

```
octogan~
```

will correctly return "octagon"

Combined search

You can also combine various search terms together:

```
o?tag* AND past~ AND ("blog" AND "post")
```

Searching for macros

You can search Confluence content for anywhere a macro is used. To do this, just add `macroName:` to your search and append the macro name after the colon. For example, search for all excerpt-include macros:

```
macroName:excerpt-include*
```

For more information about `macroName` and other search fields, see [Confluence Search Fields](#).

Searching for labels

Use the `'labelText:'` prefix to search specifically for content that has a specific label. The table below gives examples of search terms that you can enter into Confluence's search box, and the search results that you can expect.

Searching for ...	Returns content that ...
<code>recipe labelText:chocolate</code>	contains the word 'recipe' or has the label 'chocolate'
<code>recipe AND labelText:chocolate</code>	contains the word 'recipe' and has the label 'chocolate'
<code>labelText:cake labelText:chocolate</code>	has the label 'cake' or the label 'chocolate'
<code>labelText:cake AND labelText:chocolate</code>	has both labels 'cake' and 'chocolate'

The `'labelText:'` prefix is an example of a search field. See more about [Confluence Search Fields](#).

Confluence Search Fields

This page gives an overview of the [Apache Lucene](#) search fields used in Confluence.

Searching for content in specific fields

Confluence data is stored in fields which can be specified in the search. To search a specific field, type the name of the field followed by a colon `:` and then the term you are looking for.

Preliminary examples:

```
title:"Some Title"
```

```
labelText:chalk
```

The field specification applies only to the term directly preceding the colon. For example, the query below will look for "Some" in the title field and will search for "Heading" in the default fields.

```
title:Some Heading
```

On this page:

- [Searching for content in specific fields](#)
- [Confluence search fields](#)
 - [Personal Information](#)
 - [Pages](#)
 - [Blog](#)
 - [Attachments](#)
 - [Mail items](#)
- [More examples](#)
 - [Searching for labels](#)
- [Useful plugins](#)

Related pages:

- [Searching Confluence](#)
- [Confluence Search Syntax](#)
- [Ranking of Search Results](#)
- [Text Tokenisation and Filtering](#)
- [Confluence User's Guide](#)

Confluence search fields

Below are the fields which can be searched, listed by content type.

Personal Information

Name	Indexed	Stored	Tokenised	Notes
handle	true	true	false	
type	true	true	false	
urlPath	true	true	false	
fullName	true	true	true	
username	true	true	true	
title	true	true	false	
labelText	true	true	true	
modified	true	true	false	

created	true	true	false	
userpermission	true	true	false	
contentBody	true	true	true	

Pages

Name	Indexed	Stored	Tokenised	Notes
handle	true	true	false	
type	true	true	false	
urlPath	true	true	false	
title	true	true	true	
spacekey	true	true	false	
labelText	true	true	true	
modified	true	true	false	
created	true	true	false	
userpermission	true	true	false	
contentBody	true	true	true	
lastModifiers	true	true	false	Username of the user who last updated the page.
creatorName	true	true	false	Username of the user who added the page.
macroName	true	true	false	The name of a macro used on the page

Blog

Name	Indexed	Stored	Tokenised	Notes
handle	true	true	false	
type	true	true	false	
urlPath	true	true	false	
title	true	true	true	
spacekey	true	true	false	
labelText	true	true	true	
modified	true	true	false	

created	true	true	false	
userpermission	true	true	false	
contentBody	true	true	true	
lastModifiers	true	true	false	Username of the user who last updated the blog post.
creatorName	true	true	false	Username of the user who created the blog post.
macroName	true	true	false	The name of a macro used in the blog

Attachments

Name	Indexed	Stored	Tokenised	Notes
handle	true	true	false	
type	true	true	false	
urlPath	true	true	false	
filename	true	true	true	
title	true	true	false	
comment	true	true	true	
spacekey	true	true	false	
modified	true	true	false	
created	true	true	false	
userpermission	true	true	false	
contentBody	true	true	true	

Mail items

Name	Indexed	Stored	Tokenised	Notes
handle	true	true	false	
type	true	true	false	
urlPath	true	true	false	
title	true	true	true	
spacekey	true	true	false	
messageid	true	true	false	

inreplyto	true	true	false	
recipients	true	true	true	
labelText	true	true	true	
modified	true	true	false	
created	true	true	false	
userpermission	true	true	false	
contentBody	true	true	true	
lastModifiers	true	true	false	The username of the user who did the mail import, not the person who sent the email message.
creatorName	true	true	false	The username of the user who did the mail import, not the person who sent the email message.

More examples

Searching for labels

Use the 'labelText:' prefix to search specifically for content that has a specific label. The table below gives examples of search terms that you can enter into Confluence's search box, and the search results that you can expect.

Searching for ...	Returns content that ...
recipe labelText:chocolate	contains the word 'recipe' or has the label 'chocolate'
recipe AND labelText:chocolate	contains the word 'recipe' and has the label 'chocolate'
labelText:cake labelText:chocolate	has the label 'cake' or the label 'chocolate'
labelText:cake AND labelText:chocolate	has both labels 'cake' and 'chocolate'

The 'labelText:' prefix is an example of a search field. See more about [Confluence Search Fields](#).

Useful plugins

Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our [guidelines on add-on support](#).

This plugin extends the Confluence search, so that you can search for macro parameter names and values: the

[Confluence Macro Indexer plugin](#).

Ranking of Search Results

When you perform a [search](#) in Confluence, it is likely that there will be many pages or other content items that match your search terms. Confluence will rank the matching items by evaluating their relevance. This should mean that the items most relevant to you will appear at the top of the search results list, so that you can quickly select the item you need.

Below is an overview of the method Confluence uses to determine the relevance of the items returned by the search, that is, to rank the search results.

Philosophy behind the Ranking

Confluence gives highest priority to personal information i.e. documents which take you to a user's profile when you click on them. Collaboration is a primary function of a wiki, so Confluence makes it easy to find people.

For example, if you search for 'John Smith', the first results you see will be for John Smith's user profile and personal space. There may also be other content (wiki pages, email messages, etc) which contain the words 'John Smith'. These other content types may even have 'John Smith' as the page title and repeated multiple times in the content, but they will still appear lower down in the list of search results.

Matching terms found in the title of a page, or in the title of any content type, are considered a strong match. So are matches found in labels, because when someone applies a label it means that they think the content is particularly relevant to the labelled term.

Matches found in the content body are of average importance. If the matched term appears more than once, the document will be given a proportionately higher ranking.

We also assume that information created recently is slightly more relevant than older information.

Summary of the Ranking Method

When displaying the results of a search, Confluence applies a weighting to each of the content items returned.

To determine the weighting:

1. For each content item, Confluence first applies three weightings based on the following:
 - a. The content type of the item returned — user profile, page, blog post, attachment, etc. (More details [below](#).)
 - b. The type of field in which the search term was found — title, name, label, or content body. (More details [below](#).)
 - c. The age of the item returned. (More details [below](#).)
2. Confluence then combines the three weightings to arrive at a single weighting for the content item.

The item with the heaviest weighting will appear at the top of the list of search results, and the other items will appear below in descending order of weighting.

On this page:

- [Philosophy behind the Ranking](#)
- [Summary of the Ranking Method](#)
- [Weighting of Content Types](#)
- [Weighting of Fields](#)
- [Weighting Based on Age](#)
- [Simplified Example](#)

Related pages:

- [Searching Confluence](#)
- [Confluence Search Syntax](#)
- [Confluence Search Fields](#)
- [Text Tokenisation and Filtering](#)
- [Search Results Macro](#)
- [Livesearch Macro](#)
- [Page Tree Macro](#) (includes an optional search box)
- [Confluence User's Guide](#)

Weighting of Content Types

Content Type	Weighting
User Profile	9
Page	8
Blog	7
Attachment	6
Comment	5
Mail	0.5
Space Description	0.4

**Simple example**

If the search returns 7 matching items, and each item is one of the above types, then the items will be presented in the above order on the results screen. (This example assumes that the search term is found in the same field in each item — see more about fields [below](#).)

Weighting of Fields

Field Name	Weighting
Title	9
Full name	8
Label text	7
Content	5

Note that 'content' above could be the content of a page, or the content of a comment, or the body of any other

content type. See more about content types [above](#).



Simple example

A match for a search term in the title of a document is 1.8 times (9/5) more important than a match in the content.

Weighting Based on Age

This weighting is based on the age of the item returned in the search results. The age of the item is calculated from the creation date of the item. The age intervals are quite coarse-grained, as shown in the table below.

When the Item was Created	Weighting
Today	1.5
Yesterday	1.3
Up to 1 week ago	1.25
Up to 1 month ago	1.2
Up to 3 months ago	1.15
Up to 6 months ago	1.10
Up to 1 year ago	1.05
Beyond a year	1

The weighting is fairly small, so will not have a large effect. When an item is more than a year old, the age weighting is just '1' i.e. it has no effect.



Simple example

- If two documents match in all other ways then the newer one will be presented first.
- If the two documents being compared are both older than a year then their relative age does not matter.

Simplified Example

Let's assume you search for a single term.

Confluence finds a match in the title of an email message created today:

Weighting for the content type (email)	0.5
Weighting for field (title)	9
Weighting for age (today)	1.5
Total weighting	6.75

Confluence also finds a match in the content of a comment created three weeks ago:

Weighting for the content type (comment)	5

Weighting for field (content)	5
Weighting for age (up to 1 month ago)	1.2
Total weighting	30

Result: The comment (weighting 30) will appear higher in the search results than the e-mail (6.75).

i Confluence uses the [Apache Lucene](#) search engine library. Lucene's score calculation has a number of additional terms, not mentioned in the above example. We have simplified above, for purposes of illustration. If you are interested, you can see more information in the [Lucene documentation](#).

Searching the People Directory

The people directory displays a list of people who are authorised to log in to your Confluence site.

The people directory includes anybody who has logged into Confluence or who has had a user account created for them in Confluence. The people directory does not include users who can log into Confluence using [external user management](#) if they have never yet logged in.

Viewing the people directory

Choose **People** at the top of the screen.

Searching for people

To search for a particular person, type their first name and/or last name into the search box and choose **Search**.

- To see everyone who uses your Confluence site, choose **All People**.
- To see just those people who have set up a [personal space](#), choose **People with Personal Spaces**.

Following people's activities

Confluence's network features allow you to 'follow' (that is, keep track of) other people's activities in your Confluence site. For more information, please refer to [Network Overview](#). You can use the [hover profile](#) feature in the people directory to start following other people.

- To start following someone, move your mouse over their name or profile picture and choose **Follow** in their profile popup.
- To stop following someone, move your mouse over their name or profile picture and choose **Stop Following** in their profile popup.

Once you start following another person, their activities will start appearing in your [network view](#).


On this page:

- [Viewing the people directory](#)
- [Searching for people](#)
- [Following people's activities](#)
- [Notes](#)

Related pages:

- [Setting Up your Personal Space](#)
- [Editing your User Profile](#)
- [Choosing a Profile Picture](#)
- [Confluence User's Guide](#)

Screenshot: The people directory



Notes

- The Confluence administrator can [hide the people directory](#). If it is hidden, you will not see the **People Directory** option. *Not applicable to Confluence OnDemand.*
- The [people directory](#) uses the hCard microformat for simple integration with a variety of microformat-enabled tools. hCard is an open data format for representing people, companies, organisations, and places. Read more about [microformats](#) and [hCard](#).
- By default, [deactivated users](#) (disabled user accounts) are excluded from the people directory. You can include them by adding the `showDeactivatedUsers` parameter to the URL. For example:

```
http://my.confluence.com/dopeopledirectorysearch.action?showDeactivatedUsers=true
```

- By default, externally deleted users (for example, users deleted from an LDAP repository) are excluded from the people directory. You can include them by adding the `showExternallyDeletedUsers` parameter to the URL. For example:

```
http://my.confluence.com/dopeopledirectorysearch.action?showExternallyDeletedUsers=true
```

Organising Content

Confluence provides a number of ways for organising and structuring content in the wiki:

- [Spaces](#) allow you to group content according to major categories.
- [Pages](#) are used for discrete topics, and can be structured into [page trees](#) to show the relation between them.
- [Favourites](#) are particular pages or spaces that have been bookmarked by a user, to make them easy to find again.
- [Labels](#) are user-defined tags that are added to related pages in order to categorise them in some way.
- [Attachments](#) to a page can include images, multimedia, Office and PDF files, and provide a way to include other forms of content in the wiki.
- The [sidebar](#) is a good place to display important links for your team or project.
- [Email](#) can be collected and archived within each space, to manage all mail related to a project. *Not applicable to Confluence OnDemand.*

Related pages:

- [Changing the Sequential Order of Pages](#)
- [Creating Content](#)
- [Searching Confluence](#)
- [Confluence User's Guide](#)

Working with Pages

Pages are the primary means of storing and sharing information in Confluence. Pages are contained within [spaces](#).

- Use **spaces** to organise your wiki content into your primary logical groups. For example, you could have a space per team, per product, or per department.
- Use **pages** to organise your content into lower-level groups. For example, you could have a page for a particular team activity, or for a feature in a product, or for a chapter in a book. Add more child pages to contain lower-level details if necessary.

Things you can do with pages in Confluence:

- [Create a new page](#) from anywhere within the site.
- Write content [using the editor](#).
- [Rename](#) a page.
- [Copy](#) a page.
- [Delete](#) a page or remove a specific version of a page.
- Move pages and organise them hierarchically [while editing a page](#) or [while viewing the space's Tree view](#).
- Navigate within and between spaces through flexible [linking](#).
- Collaborate via [comments](#) on a page.
- Control access through [page security restrictions](#).
- Monitor page updates and other activity through [page notifications](#).
- View [page history](#), and manage and compare versions of a page.
- [Search](#) page content, including attachments.
- Export pages to [PDF](#), [WORD](#), [HTML](#) or [XML](#).
- [Email](#) page content.
- [Like](#) a page.

Related pages:

- [Creating Content](#)
- [Working with Drafts](#)
- [Working with the Office Connector](#)
- [Viewing Recently Visited Content](#)
- [Confluence User's Guide](#)

Moving a Page

This guide describes how to change a page's location. You can:

- Change the default location of a new page.
- Move an existing page to a different space.
- Move an existing page to a different parent page within the same space.
- Reorder pages that are children of the same parent.

When you move a page, attachments and comments will be moved with the page. All child and descendent pages will also be moved.

Notes about permissions:

To move a page, you need the following permissions:

- 'Add' permission on the page you are moving, and
- 'View' permission on the page's parent page. So if you are moving the page to a different parent, you need 'View' permission on the new parent.

To move a page into a different space, you also need:

- 'Remove' permission on the space you are moving from, and
- 'Add' permission on the space you are moving to.

To move a page while keeping its page restrictions, you will also need:

- Space administrator permission on the space you are moving to. Alternatively, remove the page restrictions before performing the move.

On this page:

- [Setting the location of a new page](#)
- [Moving a page to a different space](#)
- [Moving a page within a space](#)
- [Notes](#)

Related pages:

- [Moving an Attachment](#)
- [Copying a Page](#)
- [Deleting a Page](#)
- [Changing the Sequential Order of Pages](#)
- [Overview of Pages](#)
- [Confluence User's Guide](#)

Setting the location of a new page

While you are creating a **new** page, you can set the page's location before saving the page.

To set the location for a new page:

1. While editing the page, choose **Location**.
2. Use the tabs on the left of the 'Set Page Location' dialog to help you find the new space and parent page for your page. They determine the location of your page. The 'Current location' and 'New location' breadcrumb trails at the bottom of the dialog indicate the current parent page and new parent page.
3. If you want to move a page to a different position amongst the child pages, select **Reorder**. (When you choose **Move** in the next step, you will be able to reorder the page.)
4. Choose **Move**.
5. If you are reordering the child pages, position the pointer in the list to set the new position for the page and choose **Reorder**.

Screenshot: Setting the location of a new page

Set Page Location

Advanced

[Search](#)

[Recently Viewed](#)

[Browse](#)

Specify the new parent page for this page and its children by space and title.

New space:

New parent page:

Start typing a page title to see a list of suggestions.

Current location: Chocolate > Chocolate Home > Blank page added from home page

New location: Chocolate > Chocolate Home

Moving a page to a different space

You can move a page, along with its child pages, to a different space. Confluence will automatically adjust all links to the moved pages, to point to the pages in the new space.

To move a page to another space in your Confluence site:

1. Go to the page and choose **Tools > Move**.
2. Use the tabs on the left to help you find the new space and parent page for your page. They determine the location of your page. The 'Current location' and 'New location' breadcrumb trails at the bottom of the dialog indicate the current parent page and new parent page.
3. If you want to move a page to a different position amongst the child pages, select **Reorder**. (When you choose **Move** in the next step, you will be able to reorder the page.)
4. Choose **Move**.
5. If you are reordering the child pages, position the pointer in the list to set the new position for the page and choose **Reorder**.

Moving a page within a space

You can move a page to a different position in the page tree. This allows you to:

- Move a single page, or a family of pages, to a different parent within the space.
- Reorder pages that are children of the same parent.

All links to the page are maintained. When you move a parent page, the entire hierarchy of child pages will move too.

To move a page:

1. Go to a page in the space and choose **Pages** in the sidebar. For more options, choose **Browse and reorder all pages**.
Or, if you are using the Documentation theme, choose **Browse > Pages** at the top of the screen.
2. Choose **Browse and reorder all pages** (default theme).

3. Expand the branches to locate the page you want to move.
4. Drag the page to a new position in the tree.
5. While dragging the page, you see one of the following:
 - A thin line between existing pages — this indicates the potential new position for the page. Release the mouse button when the page is where you want it.
 - A wide highlight over one or more existing pages — this indicates that you can drop the page into a page family. Release the mouse button to add the page to the family. The page will appear either in alphabetical sequence or as the last page in the family, depending on the family's [sequential order](#).

Notes

- The new position of the page is saved as soon as you release the mouse button.
- To cancel the move, press the 'Esc' key before releasing the mouse button.

Copying a Page

You can copy a page, to create a duplicate of the page content. You will need to rename the page, because a page name must be unique within a space.

You need 'Create Pages' permission, which is assigned by a [space administrator](#) from the Space Administration screens. See [space permissions](#) or contact a space administrator for more information.


To copy a page:

1. Go to a page in the space and choose **Tools > Copy**. Confluence will open a copy of the page in the editor. By default, Confluence will name the page 'Copy of <<original page name>>'.
 2. Rename the page and make any other changes required in the body of the page.
 3. If you need to move the new page to a different space or a different parent, you can edit the **Location**. Refer to the [instructions on moving a page](#).
 4. Click **Save**.

Related pages:

- [Working with Pages](#)
- [Moving a Page](#)
- [Confluence User's Guide](#)

Screenshot: Copying a page



Notes

- Copying a page will duplicate all of the original page's attachments and labels, but will not copy comments from the original page.
- This method of copying a page does not copy the child pages. Please add your vote to issue [CONF-2814](#) if you'd like to see this improvement.
- You can copy an entire space, including all pages in the space (parents and children) — refer to [these instructions on copying a space](#).
- Consider using [WebDAV](#) to move or copy a page hierarchy from one space to another, provided that

none of the page names already exist in the target space.

Renaming a Page

To rename an existing page, you require 'Edit Pages' permission which is assigned by a [space administrator](#) from the Space Administration screens. See [Space permissions](#) or contact a space administrator for more information.

To rename a page:

1. Go to a page in the space, and click **Edit** at the top to view the page in 'Edit' mode.
2. Change the page title as required.
3. Click **Save**.

Notes

- Confluence will automatically update all [internal links](#) to point to your new page title. This only works for page links that use the relative link syntax, for example [Renaming a Page].
- In [macros](#), page links will not be updated. You need to update these manually.
- Links from external sites will be broken, unless they use the page's [permanent URL](#).

Related Topics

[Linking Pages](#)

[Working with Pages](#)

Take me back to [Confluence User's Guide](#)

Deleting a Page

By default, when you delete a page in Confluence, this will remove all versions of the page. To do that, you need the 'Remove Pages' permission. See [Space permissions](#). If someone has applied [page restrictions](#) to the page, the restrictions may prevent you from deleting the page too.

If you want to delete a specific version of a page, you need to be a [space administrator](#).

Deleting all versions of a page

To delete a page:

Go to the page and choose **Tools > Remove**. Confirm the action as prompted.

Note: The 'Remove' option will only appear if you have permission to remove this page.

Deleting a specific version of a page

To delete just one version of a page:

1. Go to the page and choose **Tools > Page History**.
2. Choose **Remove** next to the version you want to delete, and confirm the action as prompted.

On this page:

- [Deleting all versions of a page](#)
- [Deleting a specific version of a page](#)
- [Deleting a page and all its children](#)
- [Notes](#)

Related pages:

- [Restoring a Deleted Page](#)
- [Purging Deleted Pages](#)
- [Creating Content](#)
- [Editing or Deleting a Page That Won't Render](#)
- [Confluence User's Guide](#)

Deleting a page and all its children

If the page you are deleting has any child pages, they will be moved to the root of the space. The child pages will not be deleted.

Hint: If you need to remove a parent page and a large number of child pages:

- Create a temporary new space.
- Move the parent page to the new space. The child pages will move too.
- Remove the space.

Notes

- When you delete a page, Confluence moves it to the trash. Space administrators can recover pages from the trash.
- Purge the trash to remove the page permanently.
- When you delete a version of a page, the version is not stored in the trash. The deletion of a version is therefore permanent and cannot be undone.
- Attachments attached to a deleted page will remain in the database (allowing potential retrieval) until the trash is purged. When the trash is purged, all attachments on that page are permanently removed.
- When you remove a version of a page, the version numbers of the later versions will change accordingly. For example, if a page has four versions and you remove version 2, then version 3 will become version 2 and version 4 will become version 3.

Purging Deleted Pages

When a user deletes a page from a Confluence space, the page is not permanently removed. Instead, Confluence places the deleted page into the 'Trash'. The page will remain in 'Trash' until a space administrator purges the page.

Purging deleted pages permanently clears them from 'Trash'.

You need to be a [space administrator](#) to purge deleted pages for a space.

Related pages:

- [Deleting a Page](#)
- [Restoring a Deleted Page](#)
- [Confluence User's Guide](#)

To purge deleted pages:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space**

Admin.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Content Tools > Trash**
3. A list of deleted pages and blog posts for the space displays. Choose **Purge** for a specific page or **Purge All** to permanently clear all deleted pages and news items.

If your space is using the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Trash** from the space administration options
3. A list of deleted pages and blog posts for the space displays. Choose **Purge** for a specific page or **Purge All** to permanently clear all deleted pages and news items.

 When the trash is purged, all attachments on purged pages are permanently removed as well.

Restoring a Deleted Page

When you restore a page, you are moving it from 'Trash' to the root of the space where it existed before it was deleted.

You need to be a [space administrator](#) to restore deleted pages.

Related pages:

- [Deleting a Page](#)
- [Purging Deleted Pages](#)
- [Confluence User's Guide](#)

To restore a deleted page:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Content Tools > Trash**
3. A list of deleted pages and blog posts for the space displays. Choose **Restore** for the page you wish to restore.

If your space is using the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Trash** from the space administration options
3. A list of deleted pages and blog posts for the space displays. Choose **Restore** for the page you wish to restore.

Note

If a new page has already been created in that space with the same name as the deleted page, you will be given an option to rename the page before it is restored.

Viewing All Pages in a Space

All Confluence pages are contained within a space. You can use the 'Pages' view to see a list of recently updated pages and all pages within a space.

To access the 'Pages' view:

1. Go to a page in the space and choose **Pages** in the sidebar. For more options, choose **Browse and reorder all pages**.
Or, if you are using the Documentation theme, choose **Browse** > **Pages** at the top of the screen.
2. Recently updated pages and a hierarchical (tree) view of all pages in the space display.

Screenshot: The pages view

The screenshot shows the 'Pages' view in Confluence. At the top left, the title 'Pages' is displayed. To the right of the title is a button labeled 'Stop Watching this Space'. Below the title, there are two main sections: 'Recently Updated' and 'Tree Browser'. The 'Recently Updated' section lists several pages with their update status and creator. The 'Tree Browser' section shows a hierarchical view of the pages, with 'Status Reports' expanded to show its sub-pages. A link 'Browse and reorder all pages' is located to the right of the 'Tree Browser' section.

Recently Updated	Tree Browser
- Status Reports less than a minute ago • updated by Rachel Robins • view change - Status Report - March less than a minute ago • created by Rachel Robins - Status Report - February a minute ago • created by Rachel Robins - Status Report - January 2 minutes ago • created by Rachel Robins - Project ABC Feb 01, 2013 • updated by Rachel Robins • view change - Project DEF Jan 31, 2013 • updated by Rachel Robins • view change - Status and Risk Reports Jan 31, 2013 • created by Rachel Robins	- Project ABC - Project DEF - Status and Risk Reports ▼ Status Reports - Status Report - February - Status Report - January - Status Report - March

Related pages:

- [Moving a Page](#)
- [Changing the Sequential Order of Pages](#)
- [Working with Pages](#)
- [Confluence User's Guide](#)

Viewing an alphabetical list of pages

To view an alphabetical list of all pages in a space:

1. Go to a page in the space and choose **Pages** in the sidebar. For more options, choose **Browse and reorder all pages**.
Or, if you are using the Documentation theme, choose **Browse** > **Pages** at the top of the screen.
2. Choose **Browse and reorder all pages** (*default theme*)
3. Choose **Alphabetical**
4. Choose a letter to view all pages starting with that letter.

Hint: If you know the title of a page, you might find it faster using the [Confluence search](#).


Viewing a hierarchical list of pages

The hierarchical (tree) view is a useful way to see the parent-child relationships between the pages.

To view an alphabetical list of all pages in a space:

1. Go to a page in the space and choose **Pages** in the sidebar. For more options, choose **Browse and reorder all pages**.
Or, if you are using the Documentation theme, choose **Browse** > **Pages** at the top of the screen.
2. Choose **Browse and reorder all pages** (*default theme*)
3. Choose **Tree**
4. Expand the branches of the tree to view pages.

Screenshot: Tree view



Changing the Sequential Order of Pages

Confluence allows you to present your pages in any order (sequence) you choose. The position of a page is reflected in the following places:

- The navigation area of the space sidebar. (See [Finding Content](#).)
- The pages [Tree](#) on the 'Pages' view in the space.
- Pages exported to [PDF](#), [HTML](#) and [XML](#).
- The [Page Tree](#) macro.
- The [Children](#) macro.

Alphabetical versus manual order

By default, Confluence will present your pages in alphabetical order. When you move a page to a different position, the order becomes manual for the affected page family. When we say 'page family' we mean the immediate children of the parent page, not including the grand-children.

When ordering pages alphabetically, Confluence applies a more sophisticated 'natural' order rather than a straight alphabetical order. The natural order handles numeric values correctly when doing string comparisons.

Now let's consider what happens when you add a page to a page family, by creating a new page or by moving or copying a page into the family:

- If the page family's order is alphabetical, the new page will appear in alphabetical order too.
- If the page family's order is manual, the new page will appear at the bottom of the list of pages in the family.

On this page:

- [Alphabetical versus manual order](#)
- [Changing the page order manually](#)
- [Changing the page order to alphabetical](#)

Related pages:

- [Finding Content](#)
- [Working with Pages](#)
- [Confluence User's Guide](#)

Changing the page order manually

To change the order of pages in the space:

1. Go to a page in the space and choose **Pages** in the sidebar. For more options, choose **Browse and reorder all pages**.
Or, if you are using the Documentation theme, choose **Browse > Pages** at the top of the screen.
2. Choose **Browse and Reorder Pages** (*default theme only*).
3. Expand the branches of the tree to find the page family you wish to sort.
4. Drag each page to a new position in the tree.

When you drag a page to a new position, the order of the page family changes to Manual. Newly added pages will not be sorted alphabetically, but will appear at the bottom of the list.

Changing the page order to alphabetical

If the pages in a page family have been ordered manually, you can change the page order back to alphabetical.


To set the page order to alphabetical:

1. Go to a page in the space and choose **Pages** in the sidebar. For more options, choose **Browse and reorder all pages**.
Or, if you are using the Documentation theme, choose **Browse > Pages** at the top of the screen.
2. Choose **Browse and Reorder Pages** (*default theme only*).
3. Expand branches of the tree to find the page family you wish to sort.
4. Choose the **Sort Alphabetically** (A-Z) icon beside the parent page.

The **Sort Alphabetically** (A-Z) icon only appears next to the parent page if the page family is currently sorted manually.

If you change your mind, you can use the **Undo Sorting** icon to revert back to the previous manual page order for that page family. This option is only available immediately after sorting the page (while you are still on the 'Reorder Pages' tab and have not performed any other action).

Screenshot: Page tree showing the Sort Alphabetically and Undo Sorting icons.



Sort Alphabetically only sorts the immediate children of the parent page. The grandchildren will not be re-ordered, sorting happens for one node at a time. If you want to re-order grandchildren, you need to click the **Sort Alphabetically** icon next to the parent of those pages.

Managing Orphaned Pages

An orphaned page is a page without any incoming links. This means that, unless you know that the page exists, you are not likely to come across it in the space during the natural course of navigation.

When you are working in a large space with a number of pages, it is difficult to keep track of all of them. An orphaned page may be redundant or may need to be referred to from another page. Confluence allows you to view all the orphaned pages in a space so you can tidy up the space by either deleting pages or reorganising them.

To view the orphaned pages in a space:

- If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

- Choose **Content Tools > Orphaned Pages**.

If your space uses the Documentation theme:

- Choose **Browse > Space Operations** at the top of the screen.
- Choose **Orphaned Pages** in the space operations options.

You can do the following:

- Delete an orphaned page by choosing the 'trash can' icon next to the page name.
- Edit a page by choosing the 'pencil' icon next to the page name.
- Give an orphaned page a parent — see [Moving a Page](#).

Related pages:

- [Managing Undefined Pages](#)
- [Working with Pages](#)
- [Confluence User's Guide](#)

Screenshot: Managing orphaned pages

Templates

Reorder Pages

Orphaned Pages

Undefined Pages

Attachments

Trash

Export

Import

RSS Feeds

This report shows all the 'orphaned' pages which are not linked to by other pages.

1

2

3

4

5

Next >>

Title (Space)	Creator	Created	Last Updated By	Updated	Operations
Decision Register (Confluence Development)	Rach Admin	Feb 15, 2013	Rach Admin	Feb 15, 2013	
What's in OD-29 (Confluence Development)	Rach Admin	Feb 14, 2013	Ewan User	Feb 14, 2013	
Requirements (Confluence Development)	Ewan User	Dec 12, 2012	Sophie Staunton	Dec 12, 2012	

Managing Undefined Pages

In Confluence, you can add links to pages that you intend to create later. These are links to 'undefined pages'. This is useful because it allows you to create links first and enter content for those pages later.

For example, this [link to new page](#) is a link to a non-existent page, also called an undefined page. The link is shown in dark red. If someone clicks the link, Confluence will create a new page called 'link to new page'.

The 'Undefined Pages' view gives a consolidated report of all undefined pages so that you can manage your space better. The undefined page links are badged with this icon to remind you that those pages need to be created.

To view a list of the undefined links in a space:

- If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Content Tools > Undefined Pages**

If your space uses the Documentation theme:

1. Choose **Browse > Space Operations** at the top of the screen.
2. Choose **Undefined Pages** in the space operations options.

You can choose the link for an undefined page to create the page and add content to it.

Related pages:

- [Managing Orphaned Pages](#)
- [Working with Pages](#)
- [Confluence User's Guide](#)

Using the Documentation Theme

The Documentation theme is one of the themes bundled with Confluence. It provides an inbuilt table of contents for your wiki space, a configurable header and footer, and text styles suited to documentation. You can also configure it to restrict the search results to the current space, rather than searching the entire Confluence site.

**Advance warning of plans to merge Documentation theme with the default theme**

This is an advance notice that we plan to merge the functionality of the Confluence Documentation theme with the Confluence default theme. We do not yet have a specific date for this plan, and we are interested in your feedback. The new default theme, to be introduced in Confluence 5.0, includes a sidebar with contextual navigation. (For a preview, see the [Confluence 5.0-m9 release notes](#).) Our plan is to include all the features of the Documentation theme into the default theme, and then remove the Documentation theme from Confluence.

If you are interested in this change and would like to give us feedback, please add a **comment on this blog post**: [Advance warning of plans to merge Documentation theme with the default theme](#). We are especially interested to know which features of the Documentation theme you use and value the most.

This page tells you how to view pages in your Confluence space when your space uses the Documentation theme. For the full list of features and instructions on applying the theme to a space, see the [guide to configuring the Documentation theme](#).

Quick guide to using the Documentation theme:

- The left-hand panel contains a page tree. This is a table of contents that shows the pages in the space.
- Click the plus signs in the page tree to see the child pages.
- Drag the thick vertical bar to change the width of the panels.
- Show/hide the left-hand panel: Click the sidebar icon  at top right, next to the search box, to remove the left-hand panel altogether. Click the icon again to restore the panel.
- Alternatively, press '[' on your keyboard to show/hide the left-hand panel.
- Overriding a space-restricted search: If your theme is configured to restrict the search to the current space, you can enter 'all:' and your search term to search the entire site.

The rest of this page gives more details of the above guidelines.

On this page:

- [Using the Documentation theme](#)
- [Searching the space or the site](#)
- [Hints and tips](#)
- [Notes](#)


Related pages:

- [Configuring the Documentation Theme](#)
- [Space Jump Macro](#)
- [Changing the Sequential Order of Pages](#)
- [Confluence User's Guide](#)

Using the Documentation theme

By default in a space that uses the Documentation theme, the left-hand panel contains a search box and a table of contents (page tree) showing all the pages in your space. Specifically, it shows the pages that are children of the space's home page.


Diagram: The Documentation theme with default settings



A [space administrator](#) can customise the Documentation theme as follows:

- Change the content in the left-hand panel and add a header and footer to the page. This means that your own pages may look different from the screenshot above.
- Restrict the search so that it will show results from the current space only, not from the entire Confluence site.

Diagram: The Documentation theme with space-restricted search



Here is a summary of the things you can do on a page that uses the Documentation theme:

- Click the plus signs to open and close the branches of the page tree (table of contents) in the left-hand panel.
- Drag the thick bar between the left-hand panel and the content, to increase or decrease the width of the panel.

- Click the sidebar icon  at top right, next to the search box, to remove the left-hand panel. This will remove the panel for you only. Other people will still see it.
- Click the sidebar icon  again to restore the left-hand panel.
- Alternatively, press '[' on your keyboard to show/hide the left-hand panel.
- Use the scroll bars to scroll the left-hand and right-hand panels independently of each other.
- Search the content of the space or the site. See below.

Searching the space or the site

When using the Documentation theme, the Confluence search offers a few options as described below.

Using the search box at the top right of the page:

- By default, the main Confluence search is configured to search the entire Confluence site.
 - You will see the words '**Search Confluence**' in the search box at top right of the page.
 - The Confluence search will look for matches in the entire Confluence site. This is the default behaviour for other themes too.
- A space administrator can configure the Documentation theme to restrict the search to the current space.
 - You will see the words '**Search this space**' in the search box at top right of the page.
 - The search will return results from the current space only.
 - You can override the search restriction. Enter '**all:**' and your search term to search the entire site. For example, enter the following into the search box at top right of the page to search the entire site for 'technical writing':

```
all: technical writing
```

Using the search box in the left-hand panel:

- By default, the Documentation theme's left-hand panel includes a search box. Enter your search term there, to restrict the search to the current space. Specifically, this will search only the pages that are children of the space's home page.
- If your administrator has restricted the main search to the current space, there will not be a search box in the left-hand panel.

Hints and tips

Below are some hints that you may find useful when using the Documentation theme.

Where can I see a working example of the Documentation theme?

The Confluence documentation uses the Documentation theme. If you are reading this documentation online on [the Atlassian documentation wiki](#), you are seeing a working version of the Documentation theme.

Which pages will appear in the Documentation theme's table of contents?

The theme constructs the page tree in the left-hand panel from all pages that are child pages of the space's home page. Each space has a single page designated as the 'Home' page. You can specify the home page in the [space administration section](#).

Help, my pages do not appear in the Documentation theme table of contents

Cause 1: Your pages are not under the space's home page. The most probable reason why your pages do not appear in the page tree in the left-hand panel is this: The theme constructs that table of contents from all pages that are child pages of the space's home page. If your pages are above the home page in the page tree, they will not appear in the left-hand panel.

There are two ways to fix the problem:

- You can change the designated space home page in the [space administration section](#).
- Or you can drag and drop all your pages to make them children of the current home page. You can drag and drop pages in the 'Pages' section of the space 'Browse' screen. See [Moving a Page](#).

Cause 2: Problem with upgrade from Confluence 3.1, with Documentation theme as plugin, to Confluence 3.2 or later with Documentation theme bundled. If your existing Confluence installation already has the Documentation theme plugin installed, you may find that after upgrading to Confluence 3.2 the left-hand navigation bar is empty in the spaces that use the theme. The fix is to enable all modules of the Documentation theme plugin. See the [knowledge base article](#).

Help, my left-hand panel has disappeared

If your entire left-hand panel has disappeared when using the Documentation theme, this is probably because you have clicked the sidebar icon  at top right, next to the search box. Click the icon again to restore the panel.

Can I change the default width of the left-hand navigation panel?

The Confluence user interface does not offer a way to change the default width of the left-hand navigation panel supplied by the Documentation theme. Users can change the width by dragging the middle bar, but the default width is not configurable. This post on Atlassian Answers gives a way to do it with CSS: [Documentation Theme - Default Width \(in px\) of left panel](#).

Notes

- The Confluence default theme supplies a **sidebar**, which is different to the left-hand panel in the Documentation theme. For information about the sidebar, see [Finding Content](#) and [Configuring a Sidebar](#).
- The Documentation theme supplies a **Browse** menu in the Confluence header, which gives access to the space administration and advanced options.

Viewing Page Information

The 'information' view for a page shows you various bits of useful information about the page.

To see the information view for a page:

1. View the page.
2. Choose **Tools** > **Info** to go to the 'Information' view for the page.

You will see the following information:

1. Page details: Title, author, date of creation, date of last modification and the [tiny link](#) of the page.
2. Page hierarchy: Parent-child relationships of the page.
3. Labels: Any labels (tags) that have been applied to this page. See [Working with Confluence Labels](#).
4. Page Permissions: Displays page-level security restrictions that apply to the page (if present). See [Page Restrictions](#).
5. Hot Referrers: The external website pages which send the most viewers to the page. See [Managing External Referrers](#).
6. Recent Changes: Links to the five most recent versions of the page along with the name of the editor and the date of modification. See [Page History and Page Comparison Views](#). Choose **View page history** to see the page history view, all the versions of the page in reverse chronological order and allows you to compare versions or to restore a previous version.
7. Outgoing links: A summary of the links contained on this page, pointing to other pages on the Confluence site or to external websites.

Related pages:

- [Working with Pages](#)
- [Confluence User's Guide](#)

Screenshot: A page's information view

Chocolate / Chocolate Home View Tools

All about chocolate

Title:	All about chocolate	
Author:	Administrator	Dec 24, 2012
Last Changed by:	Administrator	Dec 24, 2012
Tiny Link: (useful for email)	http://localhost:8090/x/A4AW	
Export As:	Word · PDF	
Operations:	Copy	

Recent Changes

Time	Editor	
Dec 24, 2012 10:24	Administrator	View Changes
Dec 24, 2012 10:10	Administrator	

[View Page History](#)

Hierarchy

Parent Page

- Chocolate Home

Children (1)

- Chocolate is the new black

Outgoing Links

External Links (1)

- en.wikipedia.org/wiki/Chocolate

Chocolate (2)

- Chocolate Home
- Meeting Notes

Labels

There are no labels assigned to this page.

Page Permissions

Page restrictions:

- Only **admin** can **view** this page. (set by Anonymous at Dec 24, 2012 10:17)
- Only **joe** can **view** this page. (set by Administrator at Dec 24, 2012 10:17)

Hot Referrers

(3) smaddox-pc:8090/display/CHOC/All+about+chocolate	[ban]
(2) smaddox-pc:8090/display/CHOC/Chocolate+Home	[ban]
(2) smaddox-pc:8090/dashboard.action	[ban]
(2) smaddox-pc:8090/pages/viewinfo.action?pagelid=1474563	[ban]
smaddox-pc:8090/pages/createpage.action?spaceKey=CHOC&fromP...	[ban]
(1) smaddox-pc:8090/display/CHOC/Chocolate+is+the+new+black	[ban]
(1) smaddox-pc:8090/pages/editpage.action?pagelid=1474563	[ban]

Viewing Recently Visited Content

Confluence keeps track of pages you have recently visited in Confluence. You can view 20 of your recent pages and navigate back to them using the **Recently Viewed** list.

To view the list of recently viewed pages:


1. Choose **your profile picture** at top right of the screen, then choose **Recently Viewed**.
2. Choose the title of the page you wish to revisit.

To filter the list type part of a page title or user's name in the Filter field.

Related pages:

- [Working with Pages](#)
- [Confluence User's Guide](#)

Screenshot: Recently viewed content



Page History and Page Comparison Views

Confluence tracks the history of changes to each page by creating a new version of the page each time it is modified. You can view the changes between different versions, and roll back to a previous version if required.

Accessing the page history

To view the history of a page:

Go to the page and choose **Tools > Page History**.

You can choose a version number to view the content of that version.

On this page:

- [Accessing the page history](#)
- [Viewing an older version of a page](#)
- [Restoring an older version of a page](#)
- [Removing a specific version of a page](#)
- [Viewing the changes made to a page](#)
- [Comparing two versions of a page](#)

Related pages:

- [Viewing Page Information](#)
- [Working with Pages](#)
- [Tracking Updates](#)
- [Confluence User's Guide](#)

Screenshot: Page history

Compare selected versions

	Version	Date	Changed By	Operations
	CURRENT (v. 6)	Jul 02, 2010 15:46	Andrew Lui: Migrated to Confluence 4.0	
	v. 5	Jul 02, 2010 15:46	Andrew Lui: (Migrated to Confluence 4.0)	Restore this version · Remove
	v. 4	Jul 02, 2010 15:46	Andrew Lui	Restore this version · Remove
	v. 3	Mar 06, 2010 14:41	Sarah Maddox ▾	Restore this version · Remove
	v. 2	Sep 29, 2008 12:23	Sarah Maddox ▾	Restore this version · Remove
	v. 1	May 06, 2008 14:33	Sarah Maddox ▾	Restore this version · Remove

Viewing an older version of a page

To view a specific version of a page:

1. Go to the page and choose **Tools > Page History**.
2. Choose a version number to view the contents of that version of the page. You will see a header like this, at the top of the old version of the page:



You are viewing an old version of this page. View the **current version**.

[Compare with Current](#) ·
 [Restore this Version](#) ·
 [View Page History](#)

[« Previous](#) **Version 2** [Next »](#)

If you want to send this page version to someone, copy and paste the URL from your browser. The link will look something like this: `http://confluence.atlassian.com/pages/viewpage.action?pageId=12345`.

When you are viewing a specific version of the page, the following functions are available:

Function	Description
current version	View the latest version of the page.
Compare with Current	Compare the differences between the version of the page you are viewing and the current version.
Restore this Version	Roll back the content of the page to the previous version that you are viewing.
View Page History	Return to the list of page versions.
<< Previous and Next >>	View the previous or next version of the page.

Restoring an older version of a page

You can roll back the content of the page to a specific version.

To restore an older version of a page:

1. Go to the page and choose **Tools > Page History**.
2. Choose **Restore this version** beside the version you want to restore.

3. Change the default comment if necessary, and choose **OK**.

Notes

- All page history is retained. Restoring an older version creates a copy of that version. For example, if you restore version 39, Confluence will create a copy of version 39. This copy will become the new, current version.
- If you are viewing a specific version of a page, you can restore that version of the page by choosing **Restore this Version** at the top of the page.

Removing a specific version of a page

Choose **Remove** next to a version, to delete that version. See [Deleting a Page](#).

Viewing the changes made to a page

Using the page history view or the [page information view](#), you can see the recent changes made to a page.

To view recent changes made to a page:

1. Choose **view change** at the top of the page below the page title. The page comparison view is displayed, showing the differences between the current version and the previous version.
Or:
2. Choose **Tools > Info** to go to the 'Information' view for the page.
 - In the section titled 'Recent Changes' you will see the most recent versions of the page, along with the date of their modification and the name of the modifying author.
 - Choose **View Changes** beside the required version. The page comparison view is displayed, showing the differences between the selected and previous versions.

Comparing two versions of a page

To compare two versions of a page:

1. Go to the page and choose **Tools > Page History**.
2. Choose the versions you want to compare by selecting the check boxes beside them.
3. Choose **Compare selected versions**. The page comparison view is displayed, showing the differences between the selected versions.

Changes are highlighted in different colours, as shown in this table:

Highlighted colour	Meaning
Green	Added content
Red	Deleted content
Blue	Changed formatting

Screenshot: Comparing changes

Versions Compared

6

Administrator

less than a minute ago

Current

Administrator

less than a minute ago

Key

This line was added.

~~This line was removed.~~

Formatting was changed.

[View Page History](#)

Add this line.

~~Remove this line.~~

Reformat this line,

More options on the comparison view

When a page comparison view is first displayed, all large sections of unchanged text are hidden and reduced to an ellipsis, like this: . . .

You can view page changes between versions which are adjacent to your current page comparison view. Click the link containing:

- << to view the page comparison with the earlier adjacent version
- >> to view the page comparison with the more recent adjacent version.

For example, if your page comparison view is between v. 30 and v. 34 of a page, you can view changes between:

- v. 29 and v. 30 by clicking << **Changes from 29 to 30**
- v. 34 and v. 35 by clicking **Changes from 34 to 35** >>

Using a WebDAV Client to Work with Pages

You can access Confluence content via a WebDAV client, such as 'My Network Places' in Microsoft Windows. Provided that you have permission, you will be able to read and write to spaces, pages and attachments in Confluence. You will be asked to log in and the standard Confluence content access permissions will apply to the equivalent content available through the WebDAV client.

Please refer to the page on [configuring and setting up a WebDAV client](#).

Working with Blog Posts

You can publish a blog post from any space in Confluence, provided you have permission. Blog posts may be announcements, journal entries, status reports, or any other timely information.

To view the blog posts within a space: Go to a page in the space and choose **Blog** in the sidebar. Or, if you are using the Documentation theme, choose **Browse > Blog** at the top of the screen.

Confluence lists the latest blog posts. You can click through to earlier posts via the navigation area in the sidebar.

Creating and editing a blog post is just as easy as creating and editing any other page in Confluence. You can also let people know you care by [liking](#) a blog post.

Creating a blog post

To create a blog post, you need the 'Add Blog' permission. See [Space Permissions](#), and [Creating Content](#).

You can create attractive, engaging content in a blog post in the same way as in a page. See [Creating Attractive and Dynamic Pages](#).

On this page:

- [Creating a blog post](#)
- [Editing a blog post](#)
- [Deleting a blog post](#)
- [Exporting a blog post](#)

Related pages:

- [Linking to Blog Posts](#)
- [Subscribing to RSS Feeds within Confluence](#)
- [Managing Changes and Notifications and Tasks](#)
- [Blog Posts Macro](#)
- [Sharing Content](#)
- [Exporting Confluence Pages and Spaces to PDF](#)
- [Confluence User's Guide](#)

Editing a blog post

To edit a blog post, you need the 'Add Blog' permission. See [Space Permissions](#).

To edit a blog post:

1. Go to a page in the space and choose **Blog** in the sidebar.
Or, if you are using the Documentation theme, choose **Browse > Blog** at the top of the screen. You will see the most recent blog posts within the space, and you can find earlier posts via the navigation area in the sidebar.
2. Go to the blog post and choose **Edit**.
3. Make changes to the blog post.
4. *(optional)* Add a comment, in the text box below the editing pane, to describe your changes.
5. **Preview** your changes if desired, and choose **Publish**.

Editing a blog post is similar to [editing](#) any other page in Confluence. However, there are a few things to keep in mind:

- You cannot change the date of an existing blog post. You can only backdate when adding a blog post.
- You cannot move a blog post to another space.
- A blog post has no parent.

Deleting a blog post

By default, when you delete a blog post in Confluence, this will remove all versions of the post. To do that, you need the 'Remove Blog' permission. See [Space permissions](#). If someone has applied [page restrictions](#) to the blog post, the restrictions may prevent you from deleting the post too. Deleted blog posts are stored in the space's trash and can be recovered by a space administrator.

If you want to delete a specific version of a blog post, you need to be a [space administrator](#). When you delete a version of a blog post, the version is not stored in the trash. The deletion of a version is therefore permanent and cannot be undone.

To delete all versions of a blog post:

Go to the page and choose **Tools > Remove**. Confirm the action as prompted.

Note: The 'Remove' option will only appear if you have permission to remove this page.

To delete just one version of a blog post:


1. Go to the page and choose **Tools > Page History**.
2. Choose **Remove** next to the version you want to delete, and confirm the action as prompted.

Exporting a blog post

You can export individual blog posts to PDF format. This is useful, for example, if you want to email an internal blog post to people outside your organisation.

See [Exporting Confluence Pages and Spaces to PDF](#) for more information on exporting blog pages to PDF.

Screenshot: A blog within a Confluence space



Working with Spaces

In Confluence, content is organised into spaces. There are two types of space:

- Site spaces, sometimes called 'global' spaces, are areas on your site into which you can group content items (pages, attachments, news, etc) based on any subject or topic of your choice. For example, you may want separate areas on your site for each team or project within your organisation.
- Personal spaces belong to specific users. You can keep your personal space private, or open it up so the whole world can view or edit it. Personal spaces are listed in the [People Directory](#). They are not listed on the 'Spaces' tab on the dashboard.

What is a Space?

A space is an area within Confluence, containing your pages, blog posts and other content. You can think of

each space as a sub-site, or mini-site, each with its own home page.

Each space:

- Has its own [pages](#), [blog posts](#), [comments](#), [RSS feeds](#) and [mail](#) (*mail applies to site spaces only*).
- Has its own [access control settings](#). You can set different levels of access for different spaces.
- Can be separately exported to [PDF](#), [HTML](#) or [XML](#). The XML export provides a way of [backing up and restoring a space](#).

There is no limit to the number of site spaces you can create in Confluence.

On this page:

- [What is a Space?](#)
- [Viewing the spaces in a Confluence site](#)
- [Guidelines for dividing content into spaces and pages](#)
- [Example: Favourite spaces as shown on the dashboard](#)
- [Notes](#)

Related pages:

- [Creating a Space](#)
- [Configuring a Sidebar](#)
- [Setting Up your Personal Space](#)
- [Viewing All Confluence Spaces](#)
- [Archiving a Space](#)
- [Deleting a Space](#)
- [Backing Up and Restoring a Space](#)
- [Viewing Space Activity](#)
- [Using Labels to Categorise Spaces](#)
- [Administering a Space](#)
- [Confluence User's Guide](#)

Viewing the spaces in a Confluence site

Confluence displays a list of spaces in the following locations:

- The **dashboard** displays a list of all the spaces in the Confluence site that you have permission to see. You can make a space as a [favourite](#), or [categorise the space](#), to get easy access to the content that is most relevant to you. See [Customising your Personal Dashboard](#).
- The **space directory** displays a list of all the site and personal spaces in the Confluence site that you have permission to see. You can choose to see all spaces, the spaces you have marked as favourite, or the spaces in a given space category. You can further restrict the number of spaces displayed, by entering a word or words in the **Filter** box. Confluence will display only the spaces that have the matching words in the space name or description. See [Viewing All Confluence Spaces](#).
- The **people directory** displays a list of all Confluence users, including those who have personal spaces. See [Searching the People Directory](#).

Guidelines for dividing content into spaces and pages

To ensure maintainable and logical spaces, consider the following points when allocating your content to pages and spaces:


- Group the content by topic, subject, project or team.
- Evaluate permissions across the wiki content. If members require conflicting access, for example John must access content on topics A and B, while Jane must access content for topics B and C, then the topics should be separated into three spaces.

Useful notes about spaces and pages:

- Spaces cannot be nested. You cannot have parent and child spaces, but you can have parent and child pages within a space.
- Page permissions can prevent users from accessing a specific page, even though they have permission to access the space.
- Page permissions alone cannot keep the existence of a page secret. The page should be in a restricted space instead.
- Pages can be moved between spaces.
- You can group related spaces, using [space categories](#).

Example: Favourite spaces as shown on the dashboard

The screenshot below shows the area of the Confluence dashboard that displays the spaces that you have marked as favourite:



Notes

A **space key** is a short, unique identifier for a space. For example, you might give your documentation space a key of "DOC". To find the key of an existing space, look at the Confluence URL for a page in the space. The standard Confluence URL has this format:

```
http://my.confluence.site.com/display/SPACEKEY/Page+Name
```

Viewing All Confluence Spaces

Quick guide to viewing spaces:

- The **dashboard** displays a list of all the spaces in the Confluence site that you have permission to see. You can make a space as a [favourite](#), or [categorise the space](#), to get easy access to the content that is most relevant to you. See [Customising your Personal Dashboard](#).
- The **space directory** displays a list of all the site and personal spaces in the Confluence site that you have permission to see. You can choose to see all spaces, the spaces you have marked as favourite, or the spaces in a given space category. You can further restrict the number of spaces displayed, by

entering a word or words in the **Filter** box. Confluence will display only the spaces that have the matching words in the space name or description. See [Viewing All Confluence Spaces](#).

- The **people directory** displays a list of all Confluence users, including those who have personal spaces. See [Searching the People Directory](#).

On this page:

- [Viewing spaces on the dashboard](#)
- [Viewing spaces in the space directory](#)
- [Viewing personal spaces in the people directory](#)
- [Notes](#)

Related pages:

- [Working with Spaces](#)
- [Archiving a Space](#)
- [Confluence User's Guide](#)

Viewing spaces on the dashboard


The Confluence dashboard displays a list of spaces that you have permission to view. Remember to log in, so that you can see the complete list of spaces based on your username's permissions.

The **Spaces** tab displays all the global spaces on the site that you have permission to view, and the spaces you have marked as your [favourites](#).

To see the spaces on the dashboard:

1. Choose the **site logo** at the top left of your Confluence screen.
2. Scroll down and choose the **Spaces** tab.

Screenshot: Viewing spaces on the dashboard



Viewing spaces in the space directory

The space directory displays a list of site and personal spaces that you have permission to view. Remember to log in, so that you can see the complete list of spaces based on your username's permissions. The order of

spaces is random.

Categorising the spaces: The spaces are displayed on a number of tabs, each showing a different set of spaces, as follows:

- **All Spaces** – Shows all the global and personal spaces on the site. The list excludes spaces that you do not have permission to view, and spaces that have been [archived](#).
- **Site Spaces** – Excludes personal spaces.
- **Personal Spaces** – Shows only personal spaces.
- **Favourite Spaces** – Shows the spaces that you have marked as your [favourites](#).
- *Various categories* – You will see a number of tabs showing spaces categorised by label. You can add any space category you like. See [Using Labels to Categorise Spaces](#).
- **Archived Spaces** – Shows all the global and personal spaces on the site that have been [archived](#), and that you have permission to view.

Filtering the list of spaces: To restrict the number of spaces displayed, enter a word or words in the **Filter** box. Confluence will display only the spaces that have the matching words in the space name or description.

To see the spaces in the space directory:

1. Choose **Spaces** at the top of the screen.
2. Choose one of the tabs to see the spaces you want.
3. If you want to restrict the number of spaces shown, entering a word or words in the **Filter** box.

Screenshot: Viewing favourite spaces in the space directory

The screenshot shows the 'Space Directory' interface. On the left is a sidebar with tabs: 'All Spaces', 'Site Spaces', 'Personal Spaces', 'Favourite Spaces' (selected), 'Development', 'Documentation', and 'Archived Spaces'. The main area is titled 'Favourite Spaces' and contains a table of spaces. At the top right of the main area is a 'Filter' input box. The table has three columns: 'Space', 'Description', and 'Categories'. Two spaces are listed: 'Angry Nerds' with a description 'What do you do when you have bugs in your code? Send in the Angry Nerds.' and a 'development' category; and 'Documentation' with a description 'Documentation for the latest version of Confluence.' and a 'documentation' category. Both spaces have a star icon next to them. At the bottom of the table is a hint: 'Hint: Your space administrator can organise spaces into categories. [Learn more.](#)'

Space	Description	Categories
Angry Nerds	What do you do when you have bugs in your code? Send in the Angry Nerds.	development ★
Documentation	Documentation for the latest version of Confluence.	documentation ★

Hint: Your space administrator can organise spaces into categories. [Learn more.](#)

Viewing personal spaces in the people directory

The people directory displays a list of Confluence users, including those who have personal spaces. See [Searching the People Directory](#). It excludes spaces that have been [archived](#).

To see the personal spaces in the people directory:

1. Choose **People** at the top of the screen.
2. Choose **People with Personal Spaces**.

Screenshot: The people directory

People Directory

[All People](#)
[People with Personal Spaces](#)

People with Personal Spaces



Adrien Ragot
 aragot@atlassian.com



Rachel Robins
 rrobins@atlassian.com



Alexander Dickson
 adickson@atlassian.com



David Chui
 dchui@atlassian.com

Notes

- If you do not log in, you will be treated as an 'anonymous user'. Confluence will display only those spaces that anonymous users have permission to see.
- Permission to access a space is granted by a [space administrator](#). See the overview of [space permissions](#).
- You can use the [Spaces List macro](#) to display a list of spaces on a Confluence page.

Creating a Space

There are two types of space in Confluence: 'site' spaces and 'personal' spaces. This page is about site spaces. For help with personal spaces, see [Setting Up your Personal Space](#).

Site spaces, sometimes called 'global' spaces, are areas on your site into which you can group content items (pages, attachments, news, etc) based on any subject or topic of your choice. For example, you may want separate areas on your site for each team or project within your organisation.

To set up a new site space, you need the 'Create Space' permission. 'Create Space' is one of the [global permissions](#) that can be assigned by a Confluence administrator.

To create a new space:


1. Choose **Add Space** located above the list of spaces on the [dashboard](#), or at the top right of the dashboard, or at the top right of the [space directory](#). The 'Create Space' dialog appears.
2. Enter the following information about your new space:
 - **Space name:** A name for the space. Space names do not have to be unique.
 - **Space key:** A simple key to identify your space (A-Z, a-z, 0-9). This key is a shorthand name for the space, used when linking content between spaces, for web URLs and for reports. For example, a 'Development Space' might have a space key of 'DEV'. The space key must be unique within the entire Confluence site.
 - **Make this space private:** A private space will be visible only to the person who created it. If you do not make it private, the space will have the default [space permissions](#). The creator will have space administrator permissions on the new space, and can change the permissions at any time after creating the space.
3. Choose **Create**. The home page for your new space is displayed. Note that the home page will automatically contain any [default space content](#) as defined by your Confluence administrator.

Next, you can choose a [theme](#) and start [adding pages](#) to your space. You can also [add links to the sidebar](#), to help people find important content.

Related pages:

- [Setting Up your Personal Space](#)
- [Configuring a Sidebar](#)
- [Editing Space Details](#)
- [Deleting a Space](#)
- [Working with Spaces](#)
- [Confluence User's Guide](#)

Screenshot: Adding a space to Confluence

**Notes**

A space administrator can change the [permissions](#) at any time after creating the space.

Setting Up your Personal Space

Your personal [space](#) is a place where you can publish your own pages and blog posts. Once you have set up your personal space, Confluence users can reach it by clicking your name in the [People Directory](#). You can get to your personal space by clicking your name at the top of the page and choosing 'Personal Space'.

Creating your personal space

To set up your personal space, you need the 'Personal Space' permission which is assigned by a [Confluence administrator](#). See [Giving People Access to Content](#) and [Global Permissions Overview](#).

To create your personal space:

1. Choose **your profile picture** at top right of the screen, then choose **Add Personal Space**.
2. Indicate whether your space should be private or not. A private space will be visible only to you. If you do not make it private, the space will have the default [space permissions](#). Note that you can change these settings again later. You will have space administrator permissions on your space.
3. Choose **Create**.
4. The home page of your new space will appear. Your home page will contain any [default space content](#) as defined by your Confluence administrator. You can change this content at any time.


On this page:

- [Creating your personal space](#)
- [Adding and changing content in your space](#)
- [Changing the look and feel of your space](#)
- [Granting access to your space](#)
- [Watching updates made in your space](#)

Related pages:

- [Configuring a Sidebar](#)
- [User Profile Overview](#)
- [Linking to Personal Spaces and User Profiles](#)
- [Working with Spaces](#)
- [Confluence User's Guide](#)

Screenshot: Adding a personal space

**Adding and changing content in your space**

Now you can start [adding pages](#) to your personal space. You may also want to [upload your photo](#).

Changing the look and feel of your space

If you like, you can apply a different [theme](#) to your personal space, or [modify its colour scheme](#). You can also [add and arrange links in the sidebar](#).

Granting access to your space

When you created the space, you set the option to make your space private, or to allow other people to view and contribute content to your space. You can change the [permissions on your space](#) at any time.

Watching updates made in your space

By default, Confluence assigns you as a watcher of your space. This means that you will receive an email notification each time someone adds or updates content in your space. You can stop watching the space (see [Watching a Space](#)) and change your [notification settings](#) at any time.

Administering a Space

This page gives an overview of the administration functions available in site and personal spaces. You need to be a [space administrator](#) to perform space administration functions.

Space administrators can also add and remove links in the space sidebar. See [Configuring a Sidebar](#).

Administering a space

To view the space tools page:

1. Go to the space you wish to manage.
2.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

3. The 'Space Permissions' page displays.

On this page:

- [Administering a space](#)
- [Administering a space that uses the Documentation theme](#)

Related pages:

- [Configuring a Sidebar](#)
- [Working with Spaces](#)
- [Confluence User's Guide](#)

The administration options are divided into the following categories. Some options may not be applicable for personal spaces or Confluence OnDemand.

- **Overview**
 - Space Details - see [Editing Space Details](#).
 - Space Labels - see [Using Labels to Categorise Spaces](#).
 - Remove Space - see [Deleting a Space](#).
- **Permissions**
 - Permissions - see [Assigning Space Permissions](#).
 - Restricted Pages - see [Viewing Restricted Pages](#).
- **Content Tools**
 - Templates - see [Working with Templates](#).
 - Orphaned Pages - see [Managing Orphaned Pages](#)
 - Undefined Pages - see [Managing Undefined Pages](#)
 - Attachments - see [Viewing Attachment Details](#)
 - Trash - see [Purging Deleted Pages and Restoring a Deleted Page](#).
 - Export - see [Exporting Confluence Pages and Spaces to Other Formats](#)
 - Import - see [Importing Pages from Disk](#). *Not applicable to Confluence OnDemand. Not available for personal spaces.*
 - RSS Feeds - see [Using pre-specified RSS feeds](#)
- **Look and Feel**
 - Themes – see [Applying a Theme to a Space](#).
 - Colour Scheme – see [Editing a Space's Colour Scheme](#).
 - Layout - see [Customising Space Layouts](#)
 - Stylesheet - see [Styling Confluence with CSS](#)
 - PDF Layout – see [Customising Exports to PDF](#).
 - PDF Stylesheet – see [Customising Exports to PDF](#).

- **Integrations**

- Application Links – see [Configuring Application Links](#). *Not applicable to Confluence OnDemand.*
- Mail Accounts – see [Working with Mail Archives](#). *Not applicable to Confluence OnDemand. Not available for personal spaces.*
- Mailbox Import – see [Importing Mail](#). *Not applicable to Confluence OnDemand. Not available for personal spaces.*
- Mail – see [Working with Mail Archives](#). *Not applicable to Confluence OnDemand. Not available for personal spaces.*

You can also customise the sidebar, including changing the space logo and adding shortcuts to other spaces - see [Configuring a Sidebar](#) for more information.

Administering a space that uses the Documentation theme

In this theme the standard Confluence sidebar is replaced by a page navigation sidebar. As a result the layout of the space administration options are slightly different.

To view the space admin page:

1. Go to the space you wish to manage.
2. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
3. The 'Space Details' page displays.

For spaces using the Documentation theme, the administration options are divided into the following categories:

- **General**

- Space Details – see [Editing Space Details](#).
- Space Labels – see [Using Labels to Categorise Spaces](#).
- Templates – see [Working with Templates](#).
- Remove Space – see [Deleting a Space](#).
- Trash – see [Purging Deleted Pages](#) and [Restoring a Deleted Page](#).

- **Security**

- Permissions – see [Assigning Space Permissions](#).
- Restricted Pages – see [Viewing Restricted Pages](#).
- Application Links – see [Configuring Application Links](#). *Not applicable to Confluence OnDemand.*

- **Mail**

- Mail Accounts – see [Working with Mail Archives](#). *Not applicable to Confluence OnDemand.*
- Mailbox Import – see [Importing Mail](#). *Not applicable to Confluence OnDemand.*

- **Look and Feel**

- Themes – see [Applying a Theme to a Space](#).
- Colour Scheme – see [Editing a Space's Colour Scheme](#).
- PDF Layout – see [Customising Exports to PDF](#).
- PDF Stylesheet – see [Customising Exports to PDF](#).
- Change Space Logo – see [Changing a Space's Logo](#).

- **Import**

- Import Pages from Disk – see [Importing Pages from Disk](#). *Not applicable to Confluence OnDemand.*

Editing Space Details

To edit the details of a space you need to be a [space administrator](#) for the space.

To edit the details of a space:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Overview > Edit Space Details**
3. The 'Edit Space Details' page displays.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. The 'Edit Space Details' page displays.

On the 'Edit Space Details' page you can:

- Change the name of the space (you can also do this via the sidebar - see [Configuring a Sidebar](#)).
- Change the description of the space.
- Change the status of the space from 'Current' to 'Archived' or back again - see [Archiving a Space](#).
- Select a new home page for the space. The home page is the default page that users see when they navigate to the space.

Note: If you set this field to blank (no selection) the default home page will be the 'Pages' page.

Related pages:

- [Configuring a Sidebar](#)
- [Working with Spaces](#)
- [Archiving a Space](#)
- [Confluence User's Guide](#)

Notes

- You cannot edit the space key or the space creator's name.
- The space fields do not accept wiki markup. Any wiki markup entered in these fields will be displayed as plain text.

Deleting a Space

Deleting a space permanently removes the space and all of its contents. To delete a space you must be the [space administrator](#) for the space.

Note: Deleting a space is permanent. Always create an XML backup of the space before proceeding. Once you have deleted the space, there is no way to restore it unless you have made an XML space backup.

To delete a space:

1. Go to a page in the space you wish to delete.
2.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a

member of the confluence-administrators group).

3. Choose **Overview > Remove Space**
4. Choose **OK**.

If your space is using the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Remove Space** in the space administration options.
3. Choose **OK**.

Related pages:

- [Working with Spaces](#)
- [Archiving a Space](#)
- [Copying or Renaming a Space](#)
- [Confluence User's Guide](#)

Notes

There is a problem in some versions of Confluence, where space deletion does not work. See issue

 [CONF-26122 - Authenticate](#) to see issue details. If you like, you can watch that issue to be informed of progress.

Backing Up and Restoring a Space

Confluence can back up all the content, comments and attachments for a space. The process involves converting the data in the space into XML format. The end product is a zip file that contains XML file(s) that define the content of the space, and optionally a folder containing the attachments in the space. To transfer this data to another Confluence site, you can upload the zip file.

Creating a space backup

See [Exporting Confluence Pages and Spaces to XML](#).

Restoring (importing) a space backup

See:

- [Restoring a Space](#) (*Not applicable to Confluence OnDemand.*)
- [Importing wiki data](#) (*For Confluence OnDemand.*)

Archiving a Space

You can archive a space, so that its content is less visible but still available on your Confluence site. You need to be a [space administrator](#) to archive a space. You can change a space's status from archived to current at any time.

The effect of archiving a space

If a space is archived:

- The pages and other content do not appear in the Confluence quick navigation aid, which drops down when you enter text in the search box.
- By default, the pages and other content do not appear in the Confluence search results. If a Confluence site contains any archived spaces, the search screen will provide an option to include them in the search results.
- The space and its pages do not appear on the dashboard.
- Updates to the space's content do not appear in activity streams, such as the recent updates section of the dashboard.

- The space does not appear in space-selection dropdown menus. Similarly, its pages and other content do not appear in any dropdown menus in the Confluence user interface.
- In the space directory, the archived space will no longer appear in the general space lists. Archived spaces will appear on the 'archived spaces' tab. They will also appear on the category tabs, as determined by their labels.

These functions remain available for archived spaces:

- People can view the content as usual, by following a link or typing in a URL belonging to the archived space.
- People can edit the content as usual, as determined by the [space permissions](#).
- [RSS feeds](#), [watches](#) and [notifications](#) remain active.

On this page:

- [The effect of archiving a space](#)
- [Archiving a space](#)
- [Notes](#)

Related pages:

- [Working with Spaces](#)
- [Deleting a Space](#)
- [Confluence User's Guide](#)

Archiving a space

To archive a space:

1. Go to a page in the space you wish to archive.
2.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.


Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the `confluence-administrators` group).

3. The 'Edit Space Details' screen appears. Select **Archived** in the **Status** dropdown menu.
4. Choose **Save**.

Notes

Archiving a space has no effect on search results of external search engines. For example, the space will still appear in Google search results.

Screenshot: An archived space



Edit Space Details

Name:

Description:

Status:

Home Page:

The page that displays when users navigate to this space.

Viewing Space Activity

Space activity information is **disabled by default**.

If enabled, the space activity screen displays statistics on the activity in each space. These include:

- How many pages and blog posts have been viewed, added or updated over a given period.
- Which content is the most popular (most frequently viewed).
- Which content is the most active (most frequently edited).
- Which people are the most active contributors/editors of content.

The 'Activity' tab will not be visible unless the Space Usage Stats plugin is enabled. See notes [below](#).

To view the activity in a space:

1. Choose **Space Tools** in the space sidebar.
2. Choose the **Activity** tab.

Confluence will show a graphic display of the number of pages and blog posts that have been viewed, added and edited, showing trends over a period of time.

Related pages:

- [Page History and Page Comparison Views](#)
- [Managing Changes and Notifications and Tasks](#)
- [How Do I Get More Statistics from Confluence?](#)
- [Finding Unused Spaces](#) *Not applicable to Confluence OnDemand.*
- [Viewing Site Statistics](#) *Not applicable to Confluence OnDemand.*
- [Confluence User's Guide](#)

Screenshot 1: The Space Activity tab

Space Activity

- Overview
- Permissions
- Content Tools
- Look and Feel
- Integrations
- Activity**

Activity

Activity for week starting 10 February 2013

Period: [month](#) | **[week](#)** | [day](#) Week: [<< Previous](#) | [Now](#) | [Next >>](#)

See also: [Global Confluence activity](#)

In addition to the graphical representation of Views and Edits, the top ten most popular and most active pages and/or blog posts will be listed, with a link to each.

Screenshot: Popular content, active content and active contributors.

Most popular content (Views)	Most active content (Edits)	Most active contributors (Edits)
1. Angry Nerds Home (6) 2. Which nerd are you? (3) 3. Step 1 - download the game (2) 4. Why I loved Angry Nerds (2) 5. Step 2 - Play (2) 6. Ideas for Angry Nerds 2 - revenge of the... (2) 7. Status update (1) 8. Games as a communication medium (1)	1. Ideas for Angry Nerds 2 - revenge of the... (2) 2. Why I loved Angry Nerds (1) 3. Which nerd are you? (1) 4. Step 2 - Play (1) 5. Status update (1) 6. Games as a communication medium (1)	1. Josh User (5) 2. Ewan User (3) 3. Rach Admin (1)

Notes

- The Confluence Usage Stats plugin, which provides the 'Space Activity' screen, is known to cause performance problems on large installations. This plugin is **disabled by default**. Your Confluence system administrator can enable the plugin, but please be aware of the possible impact upon your site's performance.
- The plugin is sometimes called 'Confluence Usage Tracking'.
- If your Confluence site is clustered, the space activity information will not be available.

Viewing Recently Updated Content

The 'Recently Updated' view is a useful way of keeping track of the changes being made in a space. It displays links to the most recently added or modified content within the space including pages, blog posts, mail messages and comments.

Are you looking for a way to display a list of recently updated pages on a page? Try the [Recently Updated Macro](#).

To view the recently updated content in a space:

1. Go to a page in the space and choose **Pages** in the sidebar. For more options, choose **Browse and reorder all pages**.
Or, if you are using the Documentation theme, choose **Browse > Pages** at the top of the screen.
2. Choose **Recently Updated**. A list of the most recently added or modified content in the space is displayed. Choose a link to open the corresponding document.

Related pages:

- [Recently Updated Macro](#)
- [Viewing All Pages in a Space](#)
- [Viewing Space Activity](#)
- [Confluence User's Guide](#)

Working with Mail Archives

Confluence allows you to collect and archive mail within each space. This is useful for storing the email messages that relate to a particular project – you can put them in the same Confluence space as the content for that project.

You can download mail from one or more POP or IMAP accounts. You can also import mail from mbox files either on your local system or on the Confluence server.

You need space administration permissions to manage the mail archives. See [Space Permissions Overview](#).

To see archived mail:

- Go to a space and choose **Space Tools > Integration > Mail**
Or, if your space uses the Documentation theme, choose **Browse > Mail** at the top of the screen.
- Choose a message to see its contents, or choose **Next**, **Previous** and other options to navigate around the mail archives.

Managing mail archives:

- [Adding a Mail Account](#)
- [Deleting Mail](#)
- [Fetching Mail](#)
- [Importing Mail](#)
- [Managing Mail Accounts](#)

Related pages:

- [Working with Spaces](#)
- [Confluence User's Guide](#)

 *The information on this page does not apply to Confluence OnDemand.*

Screenshot: Viewing a message in the mail archive

[Confluence Development](#) / [Browse Space](#) / [Mail Archive](#)

Tom's on annual leave today (Monday)

[Add ▾](#)

Subject: **Tom's on annual leave today (Monday)** ([find more](#))

From: Tom Davies <tomd Davies@exemail.com.au> ([find more](#))

Date: Oct 22, 2006 16:12

I'll see you all on Tuesday.

Tom

Mail Operations

- [Next By Date](#)
- [Previous By Date](#)
- [Remove Mail](#)
- [Mail Archive](#)

Notes

- Only **site spaces** can store mail archives. Personal spaces cannot. See [Working with Spaces](#) for an explanation of site spaces and personal spaces.
- You can also search the mail messages and their attachments. See [Searching Confluence](#).

- Confluence mail archiving is an optional feature. This means that the 'Mail' options may be disabled and will therefore not appear in the Confluence user interface. Mail archiving features are contained in a bundled plugin. To activate mail archiving features in Confluence, enable the plugin – choose **Confluence Admin > Manage Add-ons > Show System Add-ons**, then enable the **Confluence Mail Archiving Plugin**.

Adding a Mail Account

When you add a mail account, you are configuring Confluence to download mail from that account and archive the mail within the space.

You need space administration permissions to add a mail account. See [Space Permissions Overview](#).

 **Note:** Confluence will remove email messages from an email account when it transfers them to the mail archive. You must therefore configure Confluence to poll a **clone** email account rather than the actual account. For example, to archive the actual account sales@company.com to your Confluence Sales space, you must first create a clone account such as conf-sales@company.com that contains the same email content.

Step 1. Create a clone email account on the mail server

1. Add a new email account on the mail server with the clone email address.
2. Copy all existing email messages from the actual account to the clone account.
3. Set up the actual account to bcc sent email messages to the clone account.
4. Set up the actual account to forward received email messages to the clone account.

Related pages:

- [Working with Mail Archives](#)
- [Managing Mail Accounts](#)
- [How Do I Check Which Spaces Have Email Accounts?](#)
- [How Do I Disable Automatic Mail Polling?](#)
- [Confluence User's Guide](#)

 The information on this page *does not apply* to Confluence OnDemand.

Step 2. Configure Confluence to archive the clone account

1. Go to the 'Mail Accounts' view:
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

- Choose **Integration > Mail Accounts**

If your space uses the Documentation theme:

- Choose **Browse > Space Admin** at the top of the screen.

Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

- Choose **Mail Accounts** in the space administration options.

2. Choose **Add mail account**.

3. Enter configuration details for the account.

- **Account Name:** Enter a name for this account by which it will be known in Confluence.
- **Description:** Provide a description for this account (optional).

- **Protocol:** Choose from POP, IMAP, POPS or IMAPS.
 - **Hostname:** Enter the host name of the mail server on which the account resides.
 - **Port:** Do not edit this field. The mail server's port number will be displayed by default.
 - **Username:** Enter a username that has permission to retrieve mail from this account.
 - **Password:** Enter the account's password.
4. Choose **Test Connection** to verify the details.
 5. Choose **Create** to add the account to Confluence.

Notes

- Only **site spaces** can store mail archives. Personal spaces cannot. See [Working with Spaces](#) for an explanation of site spaces and personal spaces.
- Confluence mail archiving is an optional feature. This means that the 'Mail' options may be disabled and will therefore not appear in the Confluence user interface. Mail archiving features are contained in a bundled plugin. To activate mail archiving features in Confluence, enable the plugin – choose **Confluence Admin > Manage Add-ons > Show System Add-ons**, then enable the **Confluence Mail Archiving Plugin**.

Deleting Mail

To delete mail from a space, you need 'Remove Mail' permission. See [Space Permissions](#).

Only a space administrator can delete all email messages for the space simultaneously.

To delete mail from a space:

1. Go to a space and choose **Space Tools > Integration > Mail**
Or, if your space uses the Documentation theme, choose **Browse > Mail** at the top of the screen. A list of email messages in the space is displayed in reverse chronological order.
2. Delete an individual email message by choosing the trash  icon beside it.
3. If you are a space administrator, you can delete all email messages within a space at once by choosing **Delete All**.

Space administrators can restore deleted email messages, provided they were deleted individually.

Note: Email messages deleted using the 'Delete All' option cannot be restored.

To restore mail that has been deleted:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose Content Tools > **Trash**.
3. You will see a list of email messages and other content deleted from the space. Choose **Restore** beside the email message you want to restore.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Trash** in the left-hand panel.
3. You will see a list of email messages and other content deleted from the space. Choose **Restore** beside the email message you want to restore.

Related pages:

- [Working with Mail Archives](#)
- [Confluence User's Guide](#)

 The information on this page *does not apply* to Confluence OnDemand.

Fetching Mail

Confluence fetches mail from the server once every 30 minutes. If necessary, you can manually retrieve new mail from the configured mail accounts.

You need to be a space administrator to manually retrieve mail. See [Space Permissions](#).

To manually retrieve mail:

1. Go to a space and choose **Space Tools > Integration > Mail**
Or, if your space uses the Documentation theme, choose **Browse > Mail** at the top of the screen.
2. Choose **Fetch new mail**. Any new messages will be displayed in order of most recent first.

Notes

- Confluence mail archiving is an optional feature. This means that the 'Mail' options may be disabled and will therefore not appear in the Confluence user interface. Mail archiving features are contained in a bundled plugin. To activate mail archiving features in Confluence, enable the plugin – choose **Confluence Admin > Manage Add-ons > Show System Add-ons**, then enable the **Confluence Mail Archiving Plugin**.
- Once mail is fetched, it will be removed from the server.

Related pages:

- [Adding a Mail Account](#)
- [Working with Mail Archives](#)
- [How Do I Disable Automatic Mail Polling?](#)
- [Confluence User's Guide](#)

 The information on this page *does not apply* to Confluence OnDemand.

Importing Mail

Confluence allows you to import mail from mbox files located either on your local system or on the Confluence server. Confluence will store the imported email messages in the space's mail archive.

You need to be a space administrator to import mail for a space. See [Space Permissions](#).

NB: You may need to enable the **Confluence Mail Archiving Plugin** as it is disabled by default.

To import mail from an mbox file:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Integrations > Mailbox Import**.
 - To import from a location on your file system: Browse to the location of the mbox file, select the file and then choose **Import**.
 - To import from the Confluence server: Enter the location of the mbox file on the server, then choose **Import**.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.

Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Mailbox Import** in the space administration options.

- To import from a location on your file system: Browse to the location of the mbox file, select the file and then choose **Import**.
- To import from the Confluence server: Enter the location of the mbox file on the server, then choose **Import**.

Related pages:

- [Working with Mail Archives](#)
- [Adding a Mail Account](#)
- [Confluence User's Guide](#)



The information on this page *does not apply* to Confluence OnDemand.

Notes

- Only **site spaces** can store mail archives. Personal spaces cannot. See [Working with Spaces](#) for an explanation of site spaces and personal spaces.
- Confluence mail archiving is an optional feature. This means that the 'Mail' options may be disabled and will therefore not appear in the Confluence user interface. Mail archiving features are contained in a bundled plugin. To activate mail archiving features in Confluence, enable the plugin – choose **Confluence Admin > Manage Add-ons > Show System Add-ons**, then enable the **Confluence Mail Archiving Plugin**.

Managing Mail Accounts

You need to be a space administrator to manage mail accounts for a space. See [Space Permissions](#).

Confluence will import mail from these POP/IMAP mail accounts into the space's mail archive.

To manage mail accounts:

1. Go to the 'Mail Accounts' view:

- If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
- If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

- Choose **Integration > Mail Accounts**

If your space uses the Documentation theme:

- Choose **Browse > Space Admin** at the top of the screen.

Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

- Choose **Mail Accounts** in the space administration options.

2. Add an account if required. See [Adding a Mail Account](#).

3. For each of the existing mail accounts listed, you can:

- **Edit:** Change the configuration settings for the mail account.
- **Remove:** Remove the account permanently.
- **Disable/Enable:** Temporarily disable the account, or enable a disabled account.

Related pages:

- [Working with Mail Archives](#)
- [Importing Mail](#)
- [Confluence User's Guide](#)



*The information on this page **does not apply** to Confluence OnDemand.*

Notes

Confluence mail archiving is an optional feature. This means that the 'Mail' options may be disabled and will therefore not appear in the Confluence user interface. Mail archiving features are contained in a bundled plugin. To activate mail archiving features in Confluence, enable the plugin – choose **Confluence Admin > Manage Add-ons > Show System Add-ons**, then enable the **Confluence Mail Archiving Plugin**.

Working with Confluence Labels

Labels are key words or tags that you can add to pages, blog posts, attachments and spaces. You can define your own labels and use them to categorise, identify or bookmark content in Confluence.

For example, you could assign the label 'accounting' to all accounts-related pages on the site. You can then browse all pages with that label in a single space or across the site, or display a list of pages with that label. You can search based on the label, or use it to filter items when you subscribe to a Confluence RSS feed.

Because labels are user-defined, you can add any word that helps you identify the content in the site.

You can add or remove labels without affecting the page content.

Content labels

You can add labels to pages, blog posts and attachments. Any user with permission to view the page can also view its labels. See [Adding Labels](#).

Space categories

You can also apply labels to spaces and use them to categorise your spaces. These are known as **space categories**. See [Using Labels to Categorise Spaces](#).

On this page:

- [Content labels](#)
- [Space categories](#)
- [Advantages of labels](#)
- [Using labels](#)
- [Notes](#)

Related pages:

- [Using Label Macros to Categorise Wiki Content](#)
- [Viewing Labels and Labelled Content](#)
- [Using Labels in the Search](#)
- [Using Labels to Categorise Spaces](#)
- [Using the RSS Feed Builder](#)
- [Confluence User's Guide](#)

Advantages of labels

Here are some of the advantages of using labels:

- Labels are user-defined which means that you decide what information is relevant to you and how you are

going to label it.

- You can group pages and spaces without having to restructure the site.
- Labels are easy to add and edit, and do not affect the content of the page.
- You can add as many labels as you like to a page or space.

Using labels

- [Adding Labels](#)
- [Using Labels to Categorise Spaces](#)
- [Removing Labels](#)
- [Using Label Macros to Categorise Wiki Content](#)
- [Viewing Labels and Labelled Content](#)
- [Viewing Personal Labels](#)

Notes

Note: Personal labels are deprecated: Earlier versions of Confluence recognised a special type of label called a 'personal' label. A personal label starts with 'my:' and is only visible to the user who created it. We are removing personal labels from Confluence, as announced in the [Confluence 4.1 Upgrade Notes](#). The functionality for personal labels is still in Confluence, but we recommend that you stop using them. In a future release, we plan to remove the functionality altogether.

Adding Labels

Labels are key words or tags that you can add to pages, blog posts, attachments and spaces. You can define your own labels and use them to categorise, identify or bookmark content.

Labelling a page or blog post

Any user with permission to edit a page can add a label to a page.

To add a label to a page or blog post:

1. Go to the page. If the page already has labels, these will be listed at the bottom of the page, below the page content.
2. Choose the edit icon  beside the list of labels, or press L on your keyboard.
3. Type in a new label. Existing labels are suggested as you type.
4. Choose **Add**.


On this page:

- [Labelling a page or blog post](#)
- [Labelling an attachment](#)
- [Notes](#)

Related pages:

- [Removing Labels](#)
- [Viewing Labels and Labelled Content](#)
- [Using Label Macros to Categorise Wiki Content](#)
- [Using Labels to Categorise Spaces](#)
- [Confluence User's Guide](#)

Screenshot: Labels as they are displayed on a page



Screenshot: Adding a label to a page or blog post

Labelling an attachment

If you have permission to view or edit the page that contains the attachment, you can add a label to the attachment.

To add a label to an attachment:

1. Go to the page that contains the attachment. Choose **Tools > Attachments**.
2. Alternatively, go to the attachments view of the space:
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

- Choose **Content Tools > Attachments**
3. You will see a list of attachments, with columns for attachment name and other details. If the attachment already has labels, these will be listed in the **Labels** column.
 4. Choose the edit icon  beside the list of labels.
 5. Type in a new label. Existing labels are suggested as you type.
 6. Choose **Add**.

You can also add labels in a list of attachments displayed by the [Attachments macro](#), by choosing the edit icon  beside each label.

Screenshot 2: Adding a label to an attachment

The screenshot shows the 'Attachments' section of a Confluence page. It contains a table with the following data:

Name	Size	Creator	Creation Date	Labels
> iBugs.gif	22 kB	Josh User	Feb 15, 2013 14:51	No labels
> sitelogo.png	2 kB	Josh User	Feb 15, 2013 14:51	logo confluence
> penguin.png	5 kB	Josh User	Feb 14, 2013 10:58	penguin chocolate

Below the table, there is a 'Download' link. A 'Labels' dialog box is open, showing a text input field with 'logo', an 'Add' button, and a list of existing labels: 'useful' with a close icon. At the bottom of the dialog, there is a 'Shortcut tip: In page view, pressing l also opens this dialog box' and a 'Close' button.

Notes

- **Note: Personal labels are deprecated.** Earlier versions of Confluence recognised a special type of label called a 'personal' label. A personal label starts with 'my:' and is only visible to the user who created it. We are removing personal labels from Confluence, as announced in the [Confluence 4.1 Upgrade Notes](#). The functionality for personal labels is still in Confluence, but we recommend that you stop using them. In a future release, we plan to remove the functionality altogether.
- If you add a label to a template, that label will be copied to the page when someone adds a page based on that template. See [Adding a Template](#).

Using Labels to Categorise Spaces

A **space category** is a label that you can apply to a whole space for the purpose of categorising your spaces in the [space directory](#), and in the recent activity area of the [dashboard](#).

You need to be a space administrator to add space categories.

Using space categories

Here is an example of using space categories. Let's assume that you have one or more spaces that your Sales team may be interested in. You can use the category 'sales' to group those spaces together.

1. First add the 'sales' category to the relevant spaces, as described below.
2. Then, in the space directory, you can click the relevant tab to see only the spaces with the chosen label. See [Viewing All Confluence Spaces](#).
3. And, you can see updated content in those spaces by choosing the 'sales' category under the **Space Categories** tab in the recent activity area of the dashboard. See [Customising your Personal Dashboard](#).

On this page:

- [Using space categories](#)
- [Categorising a space](#)
- [Removing a space from a category](#)
- [Removing an entire space category](#)
- [Notes](#)

Related pages:

- [Working with Confluence Labels](#)
- [Viewing All Confluence Spaces](#)
- [Confluence User's Guide](#)

Categorising a space

When you categorise a space, you add a 'space category' to the space. A category does not exist if there are no spaces labelled with that category.

To add a space category to a space:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Overview** > Space Categories: **Edit**.
3. Under 'Space Categories', enter your category name and choose **Add**.
Alternatively, choose a category in the list of 'Suggested Space Categories'
4. Choose **Done**.

If your space is using the Documentation theme:

1. Choose **Browse** > **Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Space Labels** in the space administration options.
3. Under 'Space Categories', enter your category name and choose **Add**.
Alternatively, choose a category in the list of 'Suggested Space Categories'.
4. Choose **Done**.

Removing a space from a category

Removing a space from a category is the same as removing the category from the space.

To remove a space category from a space:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Overview** > Space Categories: **Edit**.

3. Choose the **x** next to the space category.

If you are using the Documentation theme:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the `confluence-administrators` group).

2. Choose **Space Labels** in the space administration options.
3. Choose the **x** next to the space category.

Removing an entire space category

To remove a whole space category from Confluence, just remove that category from all spaces, as described above. A category cannot exist if there are no spaces labelled with that category. The space category will disappear from the dashboard and space directory.

To remove an entire space category from Confluence:

1. Choose **Spaces** at the top of the screen.
2. Choose the space category that you want to remove.
3. You will see a list of all spaces in that category. Choose the spaces one by one, and remove the category from each space, as described [above](#).

Screenshot: Space categories

Notes

The ability to add space labels has been removed in [Confluence 5.0](#) in order to simplify the way labels are used in spaces. Existing space labels will be preserved, but you will be unable to add new space labels. Space categories are unaffected by this change.

Removing Labels

Labels are key words or tags that you can add to pages, blog posts and attachments. You can define your own labels and use them to categorise, identify or bookmark content in Confluence. You can see the existing labels, and the pages which contain the labels, by [viewing labels and labelled content](#).

Removing labels in Confluence

To remove a label from a page or blog post:

1. Go to the page that contains the label. You will see the labels at the bottom of the page below the page content.
2. Choose the edit icon  beside the list of labels, or press L on your keyboard.

3. In the 'Labels' dialog, choose the **X** next to a label to remove that label.
4. Choose **Close**.

Related pages:

- [Working with Confluence Labels](#)
- [Confluence User's Guide](#)

To remove a label from an attachment:

1. Go to the page that contains the attachment. Choose **Tools > Attachments**.
2. Alternatively, go to the attachments view of the space:
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

- Choose **Content Tools > Attachments**
3. You will see a list of attachments, with columns for the attachment name and other details. If the attachment already has labels, these will be listed in the **Labels** column.
 4. Choose the edit icon  beside the list of labels.
 5. In the 'Labels' dialog, choose the **X** next to a label to remove that label.
 6. Choose **Close**.

When you have removed the label from all content, the label will disappear from the labels view in the space too.

Notes

- **Deleted pages containing labels:** If you have deleted pages that contain a label, you may need to [purge](#) the deleted pages from the space's trash to ensure that the label disappears too.
- **Bulk removal of labels:** There is no way to remove a number of labels at once, via the Confluence user interface. Instead, we suggest that you use the [Confluence Command Line Interface](#). See the 'removeLabels' action described in the [CLI documentation](#). For an introduction to the CLI, see this blog post: [Confluence CLI for bulk actions like deleting or publishing pages](#).

Using Label Macros to Categorise Wiki Content

Using labels, you can categorise pages and refer to content across multiple categories, pages and even spaces.

Example

For the purpose of this example, imagine we have a space with pages of content on various type of vehicles. Pages are shown in **bold** text, while the labels are in [blue](#).

- **Cars** [vehicle-type](#)
 - **Toyota Prius** [vehicle car](#)
 - **Honda Civic** [vehicle car](#)
 - **Porsche Carrera** [vehicle car](#)
- **Motorbikes** [vehicle-type](#)
 - **Harley Davidson Sportster** [vehicle motorbike](#)
 - **Suzuki GSX-R** [vehicle motorbike](#)

This page hierarchy can then be categorised using labels, with pages referenced using the [Content by Label Macro](#).

If you want to list...	You would use this label:	These would be the pages that you would get:
Vehicle types	vehicle-type	Cars, Motorbikes
All vehicles	vehicle	Toyota Prius, Honda Civic, Porsche Carrera, Harley Davidson Sportster, Suzuki GSX-R
All cars	car	Toyota Prius, Honda Civic, Porsche Carrera

Related pages:

- [Working with Confluence Labels](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Label macros

Navmap macro

The [Navigation Map macro](#) renders the list of pages associated with a specified label as a navigation map.

Related Labels macro

The [Related Labels macro](#) lists labels commonly associated with the current page's labels.

Content by Label macro

The [Content by Label macro](#) displays a list of content marked with specified labels.

Content Report Table macro

The [Content Report Table macro](#) displays a set of pages and blog posts in tabular format, based on the specified labels.

Labels List macro

The [Labels List macro](#) lists all labels of a space, grouped alphabetically.

Recently Used Labels macro

The [Recently Used Labels macro](#) lists labels most recently used in a specified scope - global (site), space, or personal.

Popular Labels macro

The [Popular Labels macro](#) displays popular labels in a list or in a heatmap (also called a cloud).

Viewing Labels and Labelled Content

Labels are key words or tags that you can add to pages, blog posts, attachments and spaces. You can define your own labels and use them to categorise, identify or bookmark content in Confluence. This page describes a few ways of viewing labels and labelled content. The focus of this page is on labels that are visible to everyone. You may also be interested in [viewing personal labels](#).

Finding the labels view

Global labels are visible to all users with 'view' permission on the page, and personal labels are visible only to the person who added them.

- Any page or blog post that has labels will have them listed together in a block at the bottom of the page.
- You will also see labels in the 'Attachments' view or in a listing of attachments provided by the Attachments macro. (See [Displaying a List of Attachments](#).)

To find the labels view by choosing a label:

If you are in a page that has labels, choose a label.

- If it is a **personal** label (starts with 'my:') you will go to the personal labels page in your user profile. See [Viewing Personal Labels](#).
- If it is a global label, you will go to the 'Labels' tab of the space. Choose **Popular Labels** or **All Labels** to see all labels in the space.

Screenshot: Labels as they are displayed on a page



To find the labels view via URL:

Visit the following URL:

```
<MY.CONFLUENCE.SITE>/labels/listlabels-alphaview.action?key=MYSPEACEKEY
```

For example: <https://confluence.atlassian.com/labels/listlabels-alphaview.action?key=DOC>

To find the labels view from the menu (Documentation theme only):

If the space is using the Documentation theme, you can access the labels view directly via the menu:

- Go to a page in the space and choose **Browse > Labels**.
- Choose **Popular Labels** or **All Labels** to see all labels in the space.

On this page:

- [Finding the labels view](#)
- [Using the labels view](#)
- [Searching for labels](#)
- [Navigating pages by URL and label](#)

Related pages:

- [Viewing Personal Labels](#)
- [Searching Confluence](#)
- [Confluence User's Guide](#)

Using the labels view


The labels view in a space offers the following options:

- **Popular Labels:** Choose this option to see a list of the most frequently used labels in that space. From here, you can also view the most popular labels across the site. The bigger the font size, the more popular the label.
- **All Labels:** View all labels in the space. From this view, you can choose a link to view an alphabetical

listing of all labels across the site. Choosing a label will list all content in the space with that label. It will also display any related labels if they exist. **Related labels** are labels that frequently appear on pages together. For example, if pages labelled with 'sales' also tend to have the label 'marketing', these will be displayed as related labels.

- **See content from all spaces:** Expand the list of labels to include pages and other labelled content from all spaces.


Screenshot: The labels view, showing all 'logo' labels



Searching for labels

A quick way to find labelled content is to search for it. If there is a label matching your query, you will see it in the panel titled **Browse Labels** in the search results. Choose a label to see all content in the site with that label.

Screenshot: Searching for labelled content



Advanced label searching

Use the 'labelText:' prefix to search specifically for content that has a specific label. The table below gives examples of search terms that you can enter into Confluence's search box, and the search results that you can expect.

Searching for ...	Returns content that ...
recipe labelText:chocolate	contains the word 'recipe' or has the label 'chocolate'
recipe AND labelText:chocolate	contains the word 'recipe' and has the label 'chocolate'
labelText:cake labelText:chocolate	has the label 'cake' or the label 'chocolate'
labelText:cake AND labelText:chocolate	has both labels 'cake' and 'chocolate'

The 'labelText:' prefix is an example of a search field. See more about [Confluence Search Fields](#).

Navigating pages by URL and label

This section describes how to move around your Confluence pages by adding and subtracting labels from the list of labels that you want to match. You can search for matching labels by entering a URL. You can also add and subtract labels from the search.

To search labelled pages by typing a URL:

1. Open a new web browser window.
2. In the address bar of your web browser, type an URL such as:
`http://CONFLUENCE_HOSTNAME/label/foo+bar`
3. Press Enter.
4. The 'View Labels' page will load, showing search results for pages with the labels 'foo' and 'bar'.

Adding a label to your results:

- Choose a label from the **Related Labels** list (at the top *left*).
- A new page loads, showing pages that contain all of the labels selected so far. You can continue to add labels to the results in this way.

Subtracting a label from your search results:

When two labels are in use, links to subtract a label from the search appear at the end of the labels list. These are easily identified because these links have a preceding minus sign, like this:

```
- education
```

Viewing Personal Labels

Any page that has labels (global or personal) will have them listed at the bottom of the page. Personal labels start with 'my:', and are only visible to the user that created them.

Note: Personal labels are deprecated. The functionality for personal labels is still in Confluence, but we recommend that you stop using them. In a future release, we plan to remove the functionality altogether.

To view your personal labels:

- If you are on a page that has personal labels, click one of those labels to get to the screen showing all your personal labels.

- Alternatively, visit the URL: <your Confluence site>/users/viewmylabels.action. For example: <http://confluence.atlassian.com/users/viewmylabels.action>

You will see a list of your personal labels along with the pages that contain the label.

Related pages:

- [Adding Labels](#)
- [Viewing Labels and Labelled Content](#)
- [Confluence User's Guide](#)

Working with Favourites

You can mark pages and spaces as favourites and then access them quickly from the Confluence dashboard and from your user profile.

Adding favourites

To add a page as a favourite:

1. Go to the page.
2. Choose **Tools** > **Favourite**.

The menu item will change to 'Remove Favourite' to indicate the page is a favourite.

To add a space as a favourite:

1. Choose **Spaces** at the top of the screen.
2. Choose the star icon next to the space name in the list of spaces.

The star icon will change colour to indicate that you have added this space as a favourite.

To add someone's personal space as a favourite:

This option is only available for personal spaces. You cannot mark a person's profile as favourite, so this option is not available if the person has not yet created a personal space.

1. Choose **Spaces** at the top of the screen.
2. Choose **Personal Spaces**.
3. Choose the star icon next to the space name in the list of spaces.

The star icon will change colour to indicate that you have added this space as a favourite.

On this page:

- [Adding favourites](#)
- [Removing favourites](#)
- [Viewing favourites](#)

Related pages:

- [User Profile Overview](#)
- [Likes and Popular Content](#)
- [Working with Spaces](#)
- [Searching the People Directory](#)
- [Confluence User's Guide](#)

Removing favourites

To remove a page as a favourite:

1. Go to the page.
2. Choose **Tools** > **Remove Favourite**.

This will change to 'Favourite' to indicate that you have removed this page from your favourites.

To remove a space as a favourite:

1. Go to the [dashboard](#) or choose Spaces in the header.
2. Choose the star icon beside the space in the list of spaces.
The star icon will change colour to indicate that you have removed this space as a favourite.

To remove a personal space as a favourite:

1. Choose **Spaces** in the header.
2. Choose **Personal Spaces**.
3. Choose the star icon beside the space in the list of personal spaces.
The star icon will change colour to indicate that you have removed this space as a favourite.


Viewing favourites

You can see your favourite pages via your user profile and on the dashboard.

To view your favourites via your profile:

1. Log in to Confluence, if you have not already done so.
2. Choose **your profile picture** at top right of the screen, then choose **Favourites**.

Screenshot: Viewing your favourites in your profile


**Viewing your favourites via the dashboard**

On the [dashboard](#), you can see:

- your favourite spaces on the **Spaces** tab.
- your most recently added favourite pages on the **Pages** tab.

Recently updated content in your favourite spaces will be listed on the **Favourite Spaces** tab on the dashboard.

Screenshot: Viewing your favourites on the dashboard



Working with Attachments

An attachment is any file that is included with your page. Examples of attachments are screenshots, photographs, other images, Word documents, presentations, PDF documents, videos and sound files. Attachments are useful when you want to share information that exists in another file format. You can attach files to any page or blog post, provided you have permission to do so.

When a page you are viewing contains attachments, a small paperclip icon  appears next to the page byline, under the page name. Clicking the paperclip will take you to the 'Attachments' view, where you will see the full list of attachments.

A quick guide to attachments

Choose **Tools > Attachments** to view and attach files to a Confluence page. (See [Attaching Files to a Page](#).) If you attach a file with the same name as an existing attachment, Confluence will create a [new version](#) of the existing attachment.

Once you have attached the relevant files, you can [display attached images](#) and [multimedia content](#) on the page. If the attachment is an Office document, use the [View File macro](#) to display the content of the document on the Confluence page. If you have an Office application installed, you will also be able to launch your Office editor from within Confluence. See [Displaying Office Files in Confluence](#) and [Working with the Office Connector](#).

Your page can display a [list of attachments](#) – these may be the files that are attached to the page or to any page in the space. You can also [display a link to an attachment](#). When a user clicks the link, the attachment will open, provided that the user has the software application needed to open the attachment.

You can [label an attachment](#), and then use labels to categorise your content.

On this page:

- [A quick guide to attachments](#)
- [Working with attachments](#)
- [Notes](#)

Related pages:

- [Configuring Attachment Size](#)
- [Configuring your Attachment Storage](#) (*Not applicable to Confluence OnDemand.*)
- [Confluence User's Guide](#)

Working with attachments

- [Using Drag-and-Drop in Confluence](#)
- [Attaching Files to a Page](#)
- [Attachment Versions](#)
- [Deleting an Attachment](#)
- [Displaying a List of Attachments](#)
- [Downloading Attachments](#)
- [Editing Attachment Properties](#)
- [Embedding Multimedia Content](#)
- [Embedding PowerPoint Presentations in a Page](#)
- [Moving an Attachment](#)
- [Viewing Attachment Details](#)

Notes

If you want an attachment to be displayed on more than one page, you may wish to consider creating a special page to hold such attachments. This special page could be part of an '[inclusions library](#)'.

Using Drag-and-Drop in Confluence

This page describes the drag-and-drop functionality in Confluence, and the browser configurations needed to support that functionality.

Overview of the drag-and-drop features

Confluence supports these forms of drag-and-drop:

- **Drag-and-drop within the editor.** Working inside the editor panel, you can drag an image or a macro and drop it into a different location on the page.
- **Drag-and-drop for external images and files.** You can drag a file from a location outside Confluence, and drop it directly into the editor. For example, try it with images, video files, audio files, Office documents, and PDF files. The contents of the file will be embedded into the page or blog post.

Drag-and-drop within the editor

Working within the editor panel, you can drag an image or a macro from one location on the page and drop it into a different location on the page. Hover your cursor over the image or the macro placeholder. The cursor changes to a drag-and-drop icon  and you can click the image or macro and drag it to a new location.

If you want to abandon the drag-and-drop action, press Escape. The image/macro will return to its original position.

Requirements for internal drag-and-drop

For the drag-and-drop of images and macros in the editor, Confluence supports the following browsers: Chrome, Firefox, and Internet Explorer 9. (Drag and drop in the editor does not work in Internet Explorer 8.)

On this page:

- [Overview of the drag-and-drop features](#)
- [Drag-and-drop within the editor](#)
 - [Requirements for internal drag-and-drop](#)
- [Drag-and-drop for external images and files](#)
 - [Requirements for external drag-and-drop](#)
 - [Disabling drag-and-drop for external files](#)

Related pages:

- [Attaching Files to a Page](#)
- [Using the Editor](#)
- [Displaying Images](#)
- [Confluence User's Guide](#)

Drag-and-drop for external images and files

You can drag files from your computer or file system onto your browser and attach them to your Confluence pages or blog posts. You can drag and drop:

- multiple files at once.
- [image](#), [multimedia](#) and PDF files, and [Office documents](#).

When you drag and drop files onto the different Confluence views, you get the following results:

Confluence View	Result
Attachments	Files are attached
Page	Files are attached
Edit	Files are attached, and embedded at the cursor position

Requirements for external drag-and-drop

- For dragging files from your computer or file system onto your browser, your browser must support the drag-and-drop functionality of [HTML5](#). Browsers such as Firefox 3.5, Safari 4 and Internet Explorer 9 offer limited HTML5 functionality and don't support drag-and-drop.

Note about supported web browsers: Please ensure that you are using one of the web browsers supported by Confluence. If you are using an unsupported browser or browser version, some features may not work correctly. You can find the list of supported web browsers and browser versions on this page: [Supported Platforms](#).

- Some older Confluence themes do not support Confluence's drag-and-drop feature.
 - **Supported themes:** Confluence Default theme, [Documentation theme](#).
 - **Themes that are not supported:** Left Navigation theme, Clickr theme. You cannot drag and drop attachments into spaces that use these themes.

Disabling drag-and-drop for external files

- If you wish to disable the drag-and-drop feature, you can disable the entire **Confluence Drag and Drop Plugin**. See [Disabling and Enabling Add-ons](#).

- You can also disable the drop zone that appears on the 'Attachments' view or the image dialog box, by disabling the **View Attachments Drop Zone** or **Image Dialog Drop Zone** modules of the above plugin. This will remove these drop zones while retaining Confluence's drag-and-drop functionality.

Attaching Files to a Page

An attachment is any file that is included with your page. Examples of attachments are screenshots, photographs, other images, Word documents, presentations, PDF documents, videos and sound files. Attachments are useful when you want to share information that exists in another file format. Read more in [Working with Attachments](#).

When you attach a file to a page, Confluence makes a copy of the file and stores it on the Confluence server. Page attachments in Confluence are managed using the 'Attachments' view of the page.

To attach a file, you need the 'Create Attachments' permission. See [Space Permissions](#).

When a page you are viewing contains attachments, a small paperclip icon  appears next to the page byline, under the page name. Clicking the paperclip will take you to the 'Attachments' view, where you will see the full list of attachments.

On this page:

- [Attaching files](#)
- [Attachment versions](#)
- [Notes](#)

Related pages:

- [Working with Attachments](#)
- [Configuring Attachment Size](#)
- [Displaying Images](#)
- [Attachment Versions](#)
- [Deleting an Attachment](#)
- [Confluence User's Guide](#)

Attaching files

This page describes the following ways of attaching files to a Confluence page:

- Drag and drop files on to a Confluence page.
- Browse to, and upload files from, your computer or network.

To attach a file to a page using **drag-and-drop**:

1. View the page to which you want to attach files.
2. Drag one or more files from your computer onto the page. The 'Attach File(s)' message box appears, indicating the upload status of the files being attached to your page.

You can drag and drop more than one file at a time onto a page. You cannot drag a folder of files onto a page.

▼ [Expand this section to see other ways to drag-and-drop a file on to a page...](#)

You can also drag and drop files:

- directly onto the 'Attachments' view for the page.
- directly onto the editor view of the page.
- onto any tab of the 'Insert Link' or 'Insert Image' dialogs, which are available from the **Insert** menu while editing.

To attach a file to a page from the computer's (or network's) file system:

1. Choose **Tools > Attachments**.
2. Choose **Browse** and navigate to the file.
3. Select the file and click **Open**.
4. Add a descriptive comment for the file (optional).
5. Choose **Attach more files** if required.
6. Choose **Attach**.

You can attach than one file at a time. You cannot attach a folder of files.

▼ [Expand this section to see other ways to upload a file to a page...](#)

You can also browse for, and upload, a file from:

- the 'Attachments' tab of the 'Insert Link' dialog. (While editing the page, choose **Insert > Link**.)
- the 'Attached Images' tab of the 'Insert Image' dialog. (While editing the page, choose **Insert > Image**.)

Attachment versions

If you upload a file with the same name as an existing attachment, Confluence will rename the old file and keep it as a previous version. Read more about [Attachment Versions](#) and [Viewing Attachment Details](#).

Notes

- **Reusing attachments:** If you want to display the same file on more than one page, the best way is to put the attachment on a page (say, page A) and then use the [Include Page Macro](#) to include page A into page B, page C, and all the pages where you want the diagram, presentation, or other file. Alternatively, you can [display an image that is attached to another page](#).
- **Updating the original file:** Any changes you make to the source file do not affect the copy that was uploaded to Confluence. To update the Confluence copy, you need to upload the new version of the file.

Attachment Versions

An attachment is any file that is included with your page. Examples of attachments are screenshots, photographs, other images, Word documents, presentations, PDF documents, videos and sound files. Attachments are useful when you want to share information that exists in another file format.

When [viewing a list of attachments](#), you can add a **new version of an existing attachment** by uploading an attachment with the same file name, as displayed on the attachment view. Existing files will be kept with the name '**Version x**', where the value of 'x' increments with each upload of an attachment with the same file name.

To see all versions of an attachment: Choose the arrow next to an attachment name.

Related pages:

- [Attaching Files to a Page](#)
- [Deleting an Attachment](#)
- [Moving an Attachment](#)
- [Viewing Attachment Details](#)
- [Working with Attachments](#)
- [Confluence User's Guide](#)

Screenshot: Attachment versions

Attachments									
Name	Size	Creator	Creation Date	Labels		Comment			
	5 kB	Rach Admin	Feb 15, 2013 15:33	penguin	chocolate	Updated colours			
Version 2 (current)	5 kB	Rach Admin	Feb 15, 2013 15:33			Updated colours			
Version 1	5 kB	Josh User	Feb 14, 2013 10:58						
	22 kB	Josh User	Feb 15, 2013 14:51	useful	logo				
	2 kB	Josh User	Feb 15, 2013 14:51	logo	confluence				

Notes

- You cannot revert to a previous version of an attachment. See feature request [CONF-1943](#).
- Confluence does not track the history of attachments in the same way as it does for pages. See feature request [CONF-13943](#).
- By default, attachments and their versions are stored in the `<confluence_home>/attachments` directory. (See [Attachment Storage Configuration](#). *Not applicable to Confluence OnDemand.*)
- There is no limit to the number of attachments or attachment versions, provided that there is enough disk space.

Deleting an Attachment

An attachment is any file that is included with your page. Examples of attachments are screenshots, photographs, other images, Word documents, presentations, PDF documents, videos and sound files. Attachments are useful when you want to share information that exists in another file format.

By default, when you remove an attachment, this will delete all versions of the attachment. To do that, you need the 'Remove Attachments' permission. See [Space permissions](#).

If you want to delete a specific version of an attachment, you need to be a [space administrator](#).

Related pages:

- [Working with Attachments](#)
- [Deleting an Image](#)
- [Displaying Images](#)
- [Confluence User's Guide](#)

To delete all versions of an attachment:

- Go to the page that contains the attachment.
- Choose **Tools** > **Attachments**. A list of the page's attachments will appear.
- Choose **Remove** next to the attachment you want to delete.
- Choose **Remove** to confirm your action.

To delete a specific version of an attachment:

- Go to the page that contains the attachment.
- Choose **Tools** > **Attachments**. A list of the page's attachments will appear.
- Choose the arrow on the left next to the attachment you want to manage. A list of attachment versions will appear.
- Choose **Remove** next to the version you want to delete.
- Choose **Remove** to confirm your action.

Screenshot: Attachments and attachment versions

Attachments									
Name	Size	Creator	Creation Date	Labels		Comment			
 penguin.png	5 kB	Rach Admin	Feb 15, 2013 15:33	penguin	chocolate	Updated colours			
Version 2 (current)	5 kB	Rach Admin	Feb 15, 2013 15:33			Updated colours			
Version 1	5 kB	Josh User	Feb 14, 2013 10:58						
 iBugs.gif	22 kB	Josh User	Feb 15, 2013 14:51	useful	logo				
 sitelogo.png	2 kB	Josh User	Feb 15, 2013 14:51	logo	confluence				

Displaying a List of Attachments

An attachment is any file that is included with your page. Examples of attachments are screenshots, photographs, other images, Word documents, presentations, PDF documents, videos and sound files. Attachments are useful when you want to share information that exists in another file format.

You can display a list of attachments on your page – these may be the files that are attached to the page or to any page in the space. Use the **Attachments** macro to show a list of the attachments on the current page. Use the **Space Attachments** macro to show a list of the attachments in the current space. Both these macros generate a table of attachments which is clickable.

Using the macros

To add the Attachments or Space Attachments macro to a page:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type `{` and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

On this page:

- [Using the macros](#)
- [Parameters of the Attachments macro](#)
- [Viewing files and changing file properties from the Attachments macro](#)
- [Parameters of the Space Attachments macro](#)
- [Code examples](#)

Related pages:

- [Attaching Files to a Page](#)
- [Working with Attachments](#)
- [Working with Macros](#)
- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)
- [Confluence User's Guide](#)

Parameters of the Attachments macro

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description

Filename Patterns	all	A comma-separated list of regular expressions, used to filter the attachments by file name. Note that the parameter values must be regular expressions. For example: • To match a file suffix of 'jpg', use <code>.*jpg</code> (not <code>*.jpg</code>). • To match file names ending in 'jpg' or 'png', use <code>.*jpg,.*png</code> Here is a tutorial on regular expressions.
Attachment Labels	(none)	A list of labels, used to filter the attachments to display. If you wish to enter more than one label, separate the labels with commas. Confluence will show only attachments that have all the labels specified. (The match is an AND, not an OR.) For information on labelling the attachments, see Adding Labels.
Include Old Attachment Versions	false	A value of <code>true</code> will include previous attachment versions in the list.
Sort By	date	The sort order for attachments. Note that people viewing the page can change the sort order by clicking the column headings. Valid values are: • date – sorts by reverse chronological order (newest first) • size – sorts largest to smallest • name – sorts alphabetically
Sort Order	ascending	Used in combination with the Sort By parameter, to sort the attachments in ascending or descending order.
Allow Upload	true	If selected, the list of attachments will include options allowing users to browse for, and attach, new files.

Page Title	(none)	Used to display attachments from another page. If you do not enter a page title, the macro will display the files attached to the current page.

Viewing files and changing file properties from the Attachments macro

The list of files displayed by the Attachments macro includes options for viewing the files and other actions, provided the user has the relevant permissions.

- If you have specified the 'Allow Upload' parameter, users will be able to [upload attachments](#) directly from the list.
- Users can remove attachments. Note that they can only remove the entire attachment, including all versions of the attachment. To remove a specific version of an attachment, they must go to the 'Attachments' view. See [Deleting an Attachment](#).
- Users can [edit attachment properties](#) and [labels](#). If an attachment is an Office or PDF file, they will see the appropriate options for [Office Connector](#) files.

Screenshot: The Attachments macro

Sample Page

3 Added by Rach Admin, last edited by Rach Admin on Feb 15, 2013 (view change)

Two penguins find themselves together on an ice floe, drifting helplessly into warmer waters. The penguins are very fond of each other. Suddenly **cra-a-a-ck** the ice flow splits in half, right between the penguins. As they drift apart, one penguin sadly waves a flipper and calls out "Chocolate milk!"

Name	Size	Creator	Creation Date	Labels	Comment
> penguin.png	5 kB	Rach Admin	16 minutes ago	penguin chocolate	Updated colours
lBugs.gif	22 kB	Josh User	about an hour ago	useful logo	Properties Remove
sitelogo.png	2 kB	Josh User	about an hour ago	logo confluence	

Parameters of the Space Attachments macro

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Space	(none)	Selects the Confluence space to display all attachments for. If no space is specified, the current space will be used.
Attachment Labels	(none)	Filters the attachments to display, based on a list of labels. If you wish to enter more than one label, separate the labels with commas. For information on labelling the attachments, see Adding Labels .

Show Filter Controls	true	Determines whether or not the filter panel is shown. The filter panel allows you to filter the list of attachments by file type (extension).

Screenshot: The Space Attachments macro

Sample Page
 @ 3 Added by Rach Admin, last edited by Rach Admin on Feb 15, 2013 (view change)

Attachments in this space - displayed via the space attachments macro.

Filter By File Extension: Filter By Label:

Name	Size	Creator	Creation Date	Last Modification Date	Labels	Attached To
penguin.png	5 kB	Rach Admin	20 minutes ago	20 minutes ago	penguin chocolate	Sample Page
iBugs.gif	22 kB	Josh User	about an hour ago	about an hour ago	useful logo	Sample Page
sitelogo.png	2 kB	Josh User	about an hour ago	about an hour ago	logo confluence	Sample Page
DefaultSpaceLogo_AngryNerds.png	10 kB	Rach Admin	Feb 13, 2013	Feb 13, 2013	No labels	Fancy Page

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Downloading Attachments

An attachment is any file that is included with your page. Examples of attachments are screenshots, photographs, other images, Word documents, presentations, PDF documents, videos and sound files. Attachments are useful when you want to share information that exists in another file format.

To download a single attachment from a page:

1. View the page.
2. Choose **Tools > Attachments**.
3. Right-click the link on the attachment name, and select **Save Link As**, **Save Target As** or a similar option provided by your browser. This will open a 'Save' dialog.
4. Select the location into which you want to download the file and choose **Save**.

Related pages:

- [Attaching Files to a Page](#)
- [Working with Attachments](#)
- [Confluence User's Guide](#)

To download all the attachments from a page:

1. View the page.
2. Choose **Tools > Attachments**.
3. Choose the **Download All** button at the end of the page to download a zipped file of all the page's attachments.

Notes

- There is no permission that controls the downloading of attachments. See an article in our knowledge base about [disabling the download of attachments](#).
- Confluence does not supply an option to download all attachments from a space. See the closed feature request: [CONF-5669 - Authenticate](#) to see issue details

Editing Attachment Properties

An attachment is any file that is included with your page. Examples of attachments are screenshots, photographs, other images, Word documents, presentations, PDF documents, videos and sound files. Attachments are useful when you want to share information that exists in another file format.

To edit an attachment's properties, you need the 'Create Attachments' permission. See [Space Permissions](#).

To edit the properties of an attachment:

1. View the page that contains the attachment.
2. Choose **Tools** > **Attachments**.
3. Choose **Properties** next to the attachment. The 'Properties' screen will appear.
4. Make your changes:
 - **File Name** — Rename or modify the name of the attachment.
 - **New Comment** — Update the existing comment or enter a new comment.
 - **New Content Type** — Change the content type of the attachment by entering a valid [MIME type](#).
 - **Page** — [Move the attachment](#) to another page.
5. Choose **Save**.

Related pages:

- [Attaching Files to a Page](#)
- [Moving an Attachment](#)
- [Viewing Attachment Details](#)
- [Working with Attachments](#)
- [Confluence User's Guide](#)

Screenshot: Editing an attachment's properties

Pages / ... / Sample Page / Attachments

Properties: penguin.png

Added on Feb 15, 2013 15:33 by [Rach Admin](#), last edited on Feb 15, 2013 15:33

File Name

Labels

New Comment

New Content Type

Page

Specify the page you want to move the attachment to.

Embedding Multimedia Content

Using multimedia files you can display movies, animations and videos, and embed audio files on your Confluence page.

There are several methods for [attaching files to a page](#). Once you have attached the multimedia file to a Confluence page, you then edit the page to set where the multimedia content should appear.

In the example below, we display a Flash file that is attached to this page.

Confluence supports the following multimedia formats:

- Adobe Flash (.swf)
- Apple QuickTime (.mov)
- Windows Media (.wma, .wmv)
- Real Media (.rm, .ram)
- MP3 and MP4 files (.mp3, .mp4)
- MPEG files (.mpeg, .mpg)
- AVI files (.avi) *You may need to enable an avi decoder within your browser.*

On this page:

- [Displaying a multimedia file attached to the page](#)
- [Multimedia macro parameters](#)
- [Notes](#)
- [Code examples](#)
- [Related topics](#)



Quick guide to displaying multimedia content on a page

Choose one of these methods:

- **Add the macro yourself:** Attach the multimedia file to the page in the usual way. Add the Multimedia macro using the macro browser.
- **Autocomplete:** Attach the multimedia file to the page in the usual way. Type '!' in the editor and choose the multimedia file from the list that appears.
- **Drag and drop:** Drop the video or other file into the editor. Confluence will attach the file and insert the Multimedia macro for you.
- **Adjust parameters if necessary:** Click on the Multimedia macro placeholder to set options for the macro, such as adjusting the width or height of the display, or setting autoplay on.

Displaying a multimedia file attached to the page

Once you have attached a multimedia file to a page, there are different methods for choosing where on the page the multimedia content should appear:

Inserting the Multimedia macro yourself

You can add the Multimedia macro to the page yourself using the Macro Browser. This allows you to display a multimedia file that is attached to either the current page or to another page in the Confluence site.

To insert the Multimedia macro on the page at the current cursor position:

1. In the Confluence editor, choose **Insert > Other Macros**.
2. Find and select the required macro.

Speeding up macro entry with autocomplete: Type { and the beginning of the macro name, to see a list of suggested macros. Details are in [Using Autocomplete](#).

To edit an existing macro: Click the macro placeholder and choose **Edit**. A macro dialog window will open, where you can edit the parameters of the macro.

Using autocomplete

Once a multimedia file is attached to the page, you can use [autocomplete](#), while editing the page, to choose where the multimedia content should appear.

To position an attached multimedia file on the page using autocomplete:

1. While editing the page, position the cursor where you want to place the multimedia content.
2. Trigger the autocomplete function by typing '!'.
3. Choose the multimedia file from the list that appears.
4. If necessary, click on the Multimedia macro placeholder and choose **Edit** to set various [options](#) such as the width, height or autoplay.

Using drag-and-drop

Depending on the browser you are using, you can attach and position a multimedia file in one step using drag-and-drop.

To attach and position multimedia content using drag-and-drop:

1. While you are editing a page, simply [drag-and-drop](#) the multimedia file on to the page. Confluence will attach the file to the page and insert the Multimedia macro at the current cursor position for you.
2. If necessary, click on the Multimedia macro placeholder and choose **Edit** to set various [options](#) such as the width, height or autoplay.

Multimedia macro parameters

Parameters are options that you can set to control the content or format of the macro output.

Parameter	Default	Description
Page Name	Current page	Name of the page to which the multimedia file is attached. If you are using the Macro Browser, just start typing the name of the page and then select it from the dropdown list that appears. The page can be in the same space or another space.
Attachment	None	File name of the multimedia file.
Width	If not specified, the browser will determine the width based on the file type.	Width of the movie window to be displayed on the page. By default, this value is specified in pixels. You can also choose to specify a percentage of the window's width, or any other value accepted by HTML.
Height	If not specified, the browser will determine the height based on the file type.	Height of the movie window to be displayed on the page. By default, this value is specified in pixels. You can also choose to specify a percentage of the window's height, or any other value accepted by HTML.

Autoplay	False	If this option is checked (that is, if the parameter is set to 'true') then the video or audio file will start playing as soon as the page is loaded. If this option is not checked (set to 'false') then the file will not play until the user clicks the icon or image on the page. See the note about autoplay below .

Notes

- **The multimedia file must be attached to a Confluence page.** For security reasons, files located on remote servers are not permitted. See the [Widget Connector](#) for displaying live content from external sites.
- **You will need the relevant multimedia plugin for your browser.** Your browser (Firefox, Internet Explorer, Safari and others) needs a plugin to play the video or audio file on a Confluence page. For example, to play a Flash movie you need the Flash plugin. Many plugins are shipped with the major browsers by default. If a user does not have the required plugin installed and enabled in their browser, they will not be able to view the multimedia files on the page.
- **Autoplay may not always work as expected.** You can set autoplay on, so that your video or audio file should start playing as soon as the page is loaded into the browser. (See [parameters](#).) However, this setting may not always work as expected. Confluence will send an instruction to the browser plugin that plays the multimedia file. Different browsers and different media plugins behave in different ways, and not all of them respect such instructions.
- **Use the Office Connector to display Office documents.** Take a look at the [Office Connector](#) for embedding Word documents, presentations and other Office documents onto your Confluence page.
- If you get the error, 'Unable to embed content of type application/octet-stream', this means the [MIME type](#) is not recognised.
- **Advanced users can try styling via CSS.** By default, each embedded object is wrapped in a div tag. If you wish to style the div and its contents, override the embeddedObject CSS class. Specifying an ID as a property also allows you to style different embedded objects differently. CSS class names in the format embeddedObject - ID are used.

Code examples

See:

- [Confluence Wiki Markup for Macros](#)
- [Confluence Storage Format for Macros](#)

Related topics

[Working with Macros](#)

[Widget Connector Macro](#)

[Working with the Office Connector](#)

[Working with Attachments](#)

Take me back to [Confluence User's Guide](#)

Embedding PowerPoint Presentations in a Page

Below are some ideas on how your wiki page can include information from a Microsoft PowerPoint presentation.

Option 1 — Office Connector for Confluence

The Office Connector provides the most straightforward way to display PowerPoint slides.

To attach and display a PowerPoint presentation in Confluence:

1. Attach the presentation to a Confluence page:
 - View the Confluence page where you want to display your presentation.
 - Open the 'Tools' menu and select 'Attachments'.
 - Browse for your PowerPoint presentation and upload it to the Confluence page.
You will find detailed instructions in [Attaching Files to a Page](#).
2. Now you can display the document embedded into the Confluence page, using the View File macro. Refer to the detailed instructions for the [View File macro](#).

On this page:

- [Option 1 — Office Connector for Confluence](#)
- [Option 2 — Gallery or Slide Show of JPEG or PNG Images](#)
- [Option 3 — Convert PowerPoint to HTML and display using the HTML Include macro](#) (*Not applicable to Confluence OnDemand.*)

Related pages:

- [Working with the Office Connector](#)
- [Working with Attachments](#)
- [Confluence User's Guide](#)

Option 2 — Gallery or Slide Show of JPEG or PNG Images

1. Convert your PowerPoint pages into JPEG or PNG images, using 'save as' from PowerPoint (slide1.jpg, slide2.jpg...).
2. Upload the image files as attachments to your Confluence page. To upload in bulk, consider using a [Web DAV client](#).
3. Use the [Gallery macro](#) to display the images as a slide show in Confluence.

Option 3 — Convert PowerPoint to HTML and display using the HTML Include macro (*Not applicable to Confluence OnDemand.*)

You can convert the PowerPoint file to web page format and embed the page inside your Confluence document.



If you accept page edits or comments from users that you do not know and trust, you should not attempt this process, due to a risk of malicious user attacks via the HTML Includemacro.

1. Review the risks associated with enabling the HTML Include macro [here](#).
2. If you decide to proceed, follow [the instructions](#) to enable embedded HTML pages using the macro.
3. Select an PowerPoint converter. There are at least two applications that can convert PPT to HTML:
 - [Producer for PowerPoint](#).
 - If you do not have the PowerPoint application on your machine, you can use the [Internet Assistant for Powerpoint](#) instead.
4. Download and install your chosen converter.
5. Follow the converter documentation to perform the HTML conversion. An Internet Assistant conversion guide can be found [here](#). The conversion process will create a small collection of HTML pages. Each slide will have its own page, plus an index page with buttons to let you switch between slide pages.
6. If you wish, you can test the HTML presentation now by loading the index page in your browser.

7. Place the HTML files into their own directory, named uniquely by the title of your presentation.
8. Find a suitable location to host these files within your web server. Confluence hosts all files within the <my-install-directory>/confluence/ directory, so a good example location for Confluence distribution users is to go to <my-install-directory>/confluence/pages/ and create a subdirectory called powerpoint.
9. Move the HTML directory into the PowerPoint folder, e.g. <my-install-directory>/confluence/pages/powerpoint/<my-presentation-name> containing index.html, slide01.html... or similar.
10. Edit or create the page where you wish to embed the PowerPoint presentation. Add the HTML Include macro pointing to the index page of your slides. Remember that URLs are case sensitive.
11. Save the page. The index page to your slides should now appear.

Moving an Attachment

You can move an attachment from its current location to any page within the site.

To move an attachment, you need the following permissions (see [Space Permissions](#)):

- 'Add Page' permission on the page where the attachment currently exists.
- 'Add Attachment' permission on the space into which you are moving the attachment.

To move an attachment:

1. Go to the page that contains the attachment.
2. Choose **Tools > Attachments**.
3. Choose **Properties** next to the attachment.
4. Type the name of the page where you want to move the attachment into the **Page** field.
5. Choose **Save**.

Related pages:

- [Moving a Page](#)
- [Working with Attachments](#)
- [Confluence User's Guide](#)

Viewing Attachment Details

An attachment is any file that is included with your page. Examples of attachments are screenshots, photographs, other images, Word documents, presentations, PDF documents, videos and sound files. Attachments are useful when you want to share information that exists in another file format.

You can view attachment details in the following places:

- The list of attachments in a space. This will show all files attached to all pages in the space. See below.
- The list of attachments for a specific page. See below.
- A list of attachments created by a macro and displayed on a page. See [Displaying a List of Attachments](#).

Viewing attachments in a space

To view the attachments associated with a space:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

- Choose **Content Tools > Attachments**
- You will see a list of all the attachments in the space, along with their details and the pages they are attached to.
To see only files of a particular type:
 - Type the last part of the file name in the **Filter By File Extension** box. For example, enter 'gif' to see only image files of the GIF format.
 - Choose **Filter**.
 - To see only files that have a particular label or labels:
 - Type the label or labels in the **Filter by Label** box. If you enter more than one label, separate the labels with commas or spaces. Confluence will show only attachments that have **all** the labels specified. (The match is an AND, not an OR.)
 - Choose **Filter**.

If your space uses the Documentation theme:

- Choose **Browse > Space Operations**.
- Choose **Attachments** from the left menu.

On this page:

- [Viewing attachments in a space](#)
- [Viewing attachments on a page](#)
- [Attachment details](#)

Related pages:

- [Working with Attachments](#)
- [Displaying a List of Attachments](#)
- [Confluence User's Guide](#)

Screenshot: List of attachments for a space

Templates	Orphaned Pages	Undefined Pages	Attachments	Trash	Export	Import	RSS Feeds
Filter By File Extension:		Filter By Label:		Filter			
Name	Size	Creator	Creation Date	Last Modification Date	Labels	Attached To	
confluence_spaceadmin_themes.png	27 kB	Rachel Robins	Feb 04, 2013 14:53	Feb 04, 2013 14:53	screenshot	Space Administration	
confluence_spaceadmin_import.png	15 kB	Rachel Robins	Feb 04, 2013 14:53	Feb 04, 2013 14:53	screenshot	Space Administration	
confluence_spaceadmin_colourscheme.png	67 kB	Rachel Robins	Feb 04, 2013 14:53	Feb 04, 2013 14:53	No labels	Space Administration	

Viewing attachments on a page

When a page you are viewing contains attachments, a small paperclip icon appears next to the page byline, under the page name. Clicking the paperclip will take you to the 'Attachments' view, where you will see the full list of attachments.

To view the attachments associated with a page:

- Go to the page.
- Choose **Tools > Attachments**. You will see a list of the attachments in the page along with their details.
- To see all versions of an attachment, choose the arrow on the left of the attachment name.

The list of attachments includes options for viewing the files, and other actions, provided the user has the relevant permissions. If you have specified the 'Allow Upload' parameter, users will be able to [upload attachments](#) directly from the list too. Users can also [remove attachments](#) or [edit attachment properties](#) and [labels](#). If an attachment is an Office or PDF file, you will see the appropriate options for [Office Connector](#) files.

Screenshot: List of attachments for a page

Attachments									
Name	Size	Creator	Creation Date	Labels		Comment			
 penguin.png	5 kB	Rach Admin	Feb 15, 2013 15:33	penguin	chocolate	Updated colours			
Version 2 (current)	5 kB	Rach Admin	Feb 15, 2013 15:33			Updated colours			
Version 1	5 kB	Josh User	Feb 14, 2013 10:58						
 iBugs.gif	22 kB	Josh User	Feb 15, 2013 14:51	useful	logo				
 sitelogo.png	2 kB	Josh User	Feb 15, 2013 14:51	logo	confluence				

Attachment details

Note that the page view shows a different subset of fields from the space view.

- **Name** is the name of the attached file.
- **Size** tells you how much space the attachment takes up. You can sort by size by clicking the column title.
- **Creator** is the person who attached the file. Clicking on the link takes you to the person's user profile.
- **Creation Date** is the date the file was attached. You can sort by date by clicking the column title.
- **Labels** are keywords, or tags, that you can enter to categorise the attachments. See how to [add labels](#).
- **Last Mod. Date** (in the space view) is the date the file was last modified.
- **Attached To** (in the space view) tells you which page contains the attachment.
- **Comment** (in the page view) is a short description of the attachment.
- The **Properties** link (in the page view) lets you edit the attachment details. See how to [edit attachment properties](#).
- The **Remove** link (in the page view) lets you delete the attachment, or a specific version of the attachment.
- The **Edit in Office** link (in the page view) appears next to Office files only, and lets you edit that attachment.
- The **Attach File** option lets you add another attachment or another version of an existing attachment. See how to [upload attachments](#).

Customising Confluence

You can customise or configure many aspects of Confluence:

- The [look and feel](#) of any Confluence space.
- [Personal aspects](#), including your personal profile and homepage.
- Setting up your [user profile](#).
- [User access](#), including permissions and page restrictions.
- Add-ons such as [gadgets](#) and [macros](#).
- Customisations for [specific uses](#) of Confluence.

Related pages:

- [Configuring Confluence](#)
- [Configuring Confluence Security](#)
- [Managing Add-ons and Macros](#) (*Not applicable to Confluence OnDemand.*)
- [Confluence User's Guide](#)

Personal Customisations

There are several ways that you can customise the way that Confluence works for you, including:

- Your [personal home page](#)
- Your [personal dashboard](#)
- Your [personal profile](#)
- Your [email notifications](#)
- Your [RSS Feed settings](#)

Related pages:

- [Customising Confluence](#)
- [Confluence User's Guide](#)

User Profile Overview

Each Confluence user has a user profile. In your own profile, you can access account management features and updated information about yourself. You can also view other users' profiles.

To find your user profile:

Choose **your profile picture** at top right of the screen, then choose **Profile**.
Or, choose the **Profile** link in the sidebar of your personal space.

To find someone else's user profile:

1. Open the user's hover profile popup:
 - Log in to Confluence, if you have not already done so.
Note: If a Confluence Administrator has granted the 'View User Profiles' permission to anonymous users, you can access people's hover profile popups without logging in. However, the hover profile features available to anonymous users are restricted.
 - Move your mouse pointer over a user's linked name or profile picture. The hover profile popup will appear.
2. Choose the user's linked name to open the user profile.

Alternatively, you can choose the **Profile** link in the sidebar of the user's personal space or go directly to this URL:

```
http://MY.CONFLUENCE.COM/users/viewuserprofile.action?username=USERNAME
```

Related pages:

- [Managing Changes and Notifications and Tasks](#)
- [Setting Up your Personal Space](#)
- [Confluence User's Guide](#)

Screenshot: User profile screen for the current user

The screenshot shows the Confluence user profile interface for a user named 'Josh User'. At the top, there is a header bar with a profile picture, the name 'Josh User', and an 'Edit profile' button. Below the header, there is a navigation bar with tabs: Profile, Network, Status Updates, Favourites, Watches, Drafts, and Settings. The 'Profile' tab is selected. The main content area is divided into three columns. The left column, titled 'Personal Space', contains links for PROFILE, Details, Picture, and Password. The middle column, titled 'About Me', contains a bio, an 'Activity' section with recent updates, and a 'Company' section. The right column, titled 'Personal', contains fields for Full Name, Email, Phone, IM, and Website.

Section	Field	Value
Personal	Full Name	Josh User
	Email	sample@email.com.au
	Phone	+55 987 654 321
	IM	
	Website	http://www.atlassian.com
Company	Position	Tech Writer
	Department	Confluence
	Location	Sydney

Profile

- View and [edit your personal details](#), such as your name and email address details and optionally, your photograph and other personal information. Note that as a security precaution, in order to change your email address, you will be required to re-enter your password.
- Upload a [profile picture](#) (optional).
- Change your [password](#).

Network

- View the recent activity of users that you are following via the [Network view](#).
- Follow other users from this view.

Status Updates

- View your history of [status updates](#).

Favourites

- View a list of your [favourite](#) spaces.

Watches

- View a list of the pages and spaces you are currently [watching](#).

Drafts

- Retrieve any pages you were in the process of editing. See [Working with Drafts](#).

Settings

- Edit your [General Settings](#) (homepage, language and timezone).
- Subscribe to [email notifications](#).
- View and revoke your [OAuth access tokens](#).

Notes

The 'Administer User' link is visible to Confluence administrators only. The administrator can click this link to go directly to the user management screen in the Administration Console.

Changing Password

To change your Confluence password:

1. Choose **your profile picture** at top right of the screen, then choose **Profile**.
2. On your **Profile** tab, click **Password** in the left-hand column.
3. Enter your current password and your new password in the form displayed.
4. Click **Submit**.

Related Topics

[Viewing User Profile](#)

[Editing Your User Profile](#)

[Choosing a Profile Picture](#)

[Setting Up your Personal Space](#)

[Updating Email Address](#)

[Email Address Privacy](#)

Take me back to the [Confluence User's Guide](#).

Editing User Settings

You can set various Confluence preferences that affect your personal session:

- General preferences such as home page, language and time zone, as described [below](#).
- Editor settings, as described [below](#).

- Email settings for subscriptions to email reports. See [Subscribing to Email Notifications of Updates to Confluence Content](#).
- OAuth access tokens that you have granted from your Confluence user account. See [Viewing and Revoking OAuth Access Tokens](#).

General User Preferences

To edit your general user settings:

1. Choose **your profile picture** at top right of the screen, then choose **Settings**.
2. Click **Edit** and update the settings:

Setting	Description
Site Homepage	Select the page that you would like to see whenever you log into Confluence.
Language	Select your language. See below .
Time zone	Select your time zone.
Use Keyboard Shortcuts	Enable keyboard shortcuts , other than for the editor.

3. Click **Submit**.

On this page:

- [General User Preferences](#)
- [More about Language](#)
- [Editor Preferences](#)

Related pages:

- [Editing Your User Profile](#)
- [Choosing a Profile Picture](#)
- [Setting Up your Personal Space](#)
- [Email Address Privacy](#)
- [Using Autocomplete](#)
- [Confluence User's Guide](#)

Screenshot: Editing your user profile settings

More about Language

Setting your language preference in your user profile is described in the section [above](#). This section gives more information about that setting and other settings that affect the language Confluence will use.

Individual users can choose the language that Confluence will use to display screen text and messages. Note that the list of supported languages depends on the language packs installed on your Confluence site.

The language used for your session will depend on the settings below, in the following order of priority from highest to lowest:

- The language preference defined in your user profile. Note that you need to be logged in for this setting to take effect.
- The language that you choose by clicking an option at the bottom of the Confluence login screen. Confluence stores this value in a cookie. When the cookie expires, the setting will expire too. *Not applicable to Confluence OnDemand.*
- The language set in your browser.
 - Note that your Confluence administrator can disable this option by setting a system property. *Not applicable to Confluence OnDemand.*
 - The browser sends a header with a prioritised list of languages. Confluence will use the first supported language in that list.
- The default language for your site, as defined by your Confluence site administrator.

Editor Preferences

You can set some options that determine the way the Confluence editor works. Note that these settings affect only you. Other people using Confluence can enable or disable the settings on their user profiles independently.

To change your editor preferences:

1. Choose **your profile picture** at top right of the screen, then choose **Settings**.
2. Click **Editor** under 'Your Settings' in the left-hand panel.
3. Click **Edit**.

Setting	Description

Disable Autocomplete	Select to disable autocomplete when you press one of the trigger characters.
Disable Autoformatting	Select to disable autoformatting when you type wiki markup in the editor. Click ? on the editor toolbar to learn more.

- Click **Submit**.

Screenshot: User settings for the editor

People
Rach Admin

Profile Network Status Updates Favourites Watches Drafts **Settings**

GADGETS
[View OAuth Access Tokens](#)

YOUR SETTINGS
[Password](#)
[Email](#)
[Editor](#)

Editor Settings

☐ **Disable Autocomplete**
Disable Autocomplete in the Editor, where it allows links to be inserted with the trigger [and images with the trigger !.

☐ **Disable Autoformatting**
Disable Autoformatting in the Editor, where it allows wiki-formatted text to be converted to its Rich Text equivalent (e.g. "h1. title" for a heading).

[Edit](#)

Editing Your User Profile

Your user profile contains basic information about you. If you do not have a [personal space](#), your user profile will be displayed when anyone clicks your name in the [People Directory](#).

To edit your user profile:

- Choose **your profile picture** at top right of the screen, then choose **Profile**.
Or, choose the **Profile** link in the sidebar of your personal space.
- Choose **Edit Profile**.
- Enter details about yourself in the form displayed.
- Click **Save**.

Related pages:

- [Viewing User Profile](#)
- [Choosing a Profile Picture](#)
- [Setting Up your Personal Space](#)
- [Email Address Privacy](#)
- [Confluence User's Guide](#).

Detail	Description
Full Name	Your name as you would like it to appear in your profile.
Email	Your email address which will be used to send you mail notifications.

Phone	Your phone number.
IM	Your Instant Messenger (IM) details.  To suit a variety of IM applications, this option accepts any string value. For example, you can enter IM details in the form of an email address, such as ' ' or a user ID, like '123456789'.
Website	Your website's URL.
About me	Information about yourself that other users can view (such as your professional information, hobbies, and other interests). You can use Confluence wiki markup in this field.
Position	The title of your position within your organisation.
Department	The name of your department within your organisation.
Location	Your location. This could be a town, city, region or country.

**Handy Hint**

Confluence administrators can configure Confluence to mask email addresses (e.g. 'example at atlassian dot com'), protecting your email address from search engine spiders and the like.

Email Address Privacy

Confluence can mask the email addresses of users to protect them from mail spammers.

This is done by a Confluence administrator and is configured through the [Administration Console](#). The [Confluence administrator](#) has three options for email address privacy:

- **Public:** email addresses are displayed publicly.
- **Masked:** email addresses are still displayed publicly, but masked in such a way to make it harder for spam-bots to harvest them.
- **Private:** only Confluence administrators can see the email addresses.

For more information on setting these options, which are configured using the Administration Console, refer to [User Email Visibility](#). *Not applicable to Confluence OnDemand.*

Related pages:

- [Editing Your User Profile](#)
- [Viewing User Profile](#)
- [User Email Visibility](#) (*Not applicable to Confluence OnDemand.*)
- [Confluence User's Guide](#)

Updating Email Address

The email address you specify in your profile settings is used for your mail [notifications](#) and is also displayed in your profile description.

To update your email address:

1. Choose **your profile picture** at top right of the screen, then choose **Profile**.
2. Click **Edit** in the 'Personal' section.
3. In the **Email** field, specify your new email address which will be used when sending you mail notifications.

4. Click **Save**.

Related Topics

[Changing Password](#)

[Editing Your User Profile](#)

Take me back to the [Confluence User's Guide](#).

Choosing a Profile Picture

Your profile picture is used as the icon for your [personal space](#), to represent you in the [People Directory](#), and to illustrate your [comments](#). It also appears in various other places next to your name, such as in the list of recent updates on the dashboard.

You can upload your own profile picture or use one of the images provided by Confluence. If you upload your own profile picture, you will have an opportunity to crop (trim) the picture.

To choose a profile picture:


1. Choose **your profile picture** at top right of the screen, then choose **Profile**.
2. Click **Picture** on the left.
3. Choose one of the following two options:
 - Upload a new picture: Click **Browse** to locate your picture, then click **Upload** to upload it from your computer or file server.
 - Or select one of the default icons provided.
4. Click **Set Profile Picture**.

On this page:

Related pages:

- [Deleting a Profile Picture](#)
- [Editing Your User Profile](#)
- [Setting Up your Personal Space](#)
- [Confluence User's Guide](#)

Screenshot: Choosing a profile picture




If you upload a profile picture that is larger than 48x48 pixels, the 'Edit My Profile Picture' screen will appear. You can select part of the picture or the entire picture, to be used as the final image for your profile. Note that the size

of the final image will always be scaled down to 48x48 pixels.

To edit your profile picture:

1. Click and drag the centre of the superimposed square to select the centre of the new image.
2. Click the corners of the square to resize the area for your new image.
3. Click **Save**.
4. The image from your selected area will be cropped, resized to 48x48 pixels and saved.

Screenshot: Trimming a profile picture



Deleting a Profile Picture

You can delete the profile picture images that you have uploaded to Confluence.


To delete a profile picture:

1. Choose **your profile picture** at top right of the screen, then choose **Profile**.
2. Click **Picture** on the left.
3. Locate and select the picture file you wish to delete, then click **Delete**.
i Note that you can only delete images that you have uploaded to Confluence. The standard icons cannot be deleted.
4. Click **Delete** to confirm the action. The picture is permanently removed from the server.

Related pages:

- [Choosing a Profile Picture](#)
- [Editing Your User Profile](#)
- [Setting Up your Personal Space](#)
- [Confluence User's Guide.](#)

Screenshot: Deleting a Profile Picture



Viewing User Profile

Each Confluence user has a user profile. In your own profile, you can access account management features and update information about yourself. You can also view other users' profiles, add them to your [network](#), and add their personal spaces to your list of [favourites](#).

To find your user profile:

Choose **your profile picture** at top right of the screen, then choose **Profile**.
Or, choose the **Profile** link in the sidebar of your personal space.

To find someone else's user profile:

1. Open the user's hover profile popup:
 - Log in to Confluence, if you have not already done so.
Note: If a Confluence Administrator has granted the 'View User Profiles' permission to anonymous users, you can access people's hover profile popups without logging in. However, the hover profile features available to anonymous users are restricted.
 - Move your mouse pointer over a user's linked name or profile picture. The hover profile popup will appear.
2. Choose the user's linked name to open the user profile.


Alternatively, you can choose the **Profile** link in the sidebar of the user's personal space or go directly to this URL:

```
http://MY.CONFLUENCE.COM/users/viewuserprofile.action?username=USERNAME
```

Related pages:

- [User Profile Overview](#)
- [Setting Up your Personal Space](#)
- [Confluence User's Guide](#)

Screenshot: User profile for the current user.



The screenshot shows a user profile for 'Josh User'. At the top, there's a header with a profile picture placeholder, the name 'Josh User', and an 'Edit profile' button. Below this is a navigation bar with tabs: Profile, Network, Status Updates, Favourites, Watches, Drafts, and Settings. The main content area is divided into three columns. The left column, titled 'Personal Space', contains links for PROFILE, Details, Picture, and Password. The middle column, titled 'About Me', contains a bio: 'Hi there, I'm Josh and unfortunately I am completely fictional. If I was a real live person I think I would quite like to be a tech writer.' Below this is an 'Activity' section with three items: 'Status update' (created about 5 hours ago), 'Josh User' (profile updated about 5 hours ago), and 'Josh User's Home' (created about 5 hours ago). The right column, titled 'Personal', contains fields for Full Name (Josh User), Email (sample@email.com.au), Phone (+55 987 654 321), IM, and Website (http://www.atlassian.com). Below this is a 'Company' section with fields for Position (Tech Writer), Department (Confluence), and Location (Sydney).

Updating your profile

You can update the following aspects of your profile from this view:

- **Information about yourself** – see [Editing Your User Profile](#).
- **Your Profile picture** – see [Choosing a Profile Picture](#).
- **Your login password** – see [Changing Password](#).

Viewing and Revoking OAuth Access Tokens

This page describes the purpose of OAuth access tokens which have been issued on behalf of your Confluence user account and provides instructions on how to revoke them.

On this page:

- [OAuth Access Tokens](#)
- [Viewing your OAuth Access Tokens](#)
 - [OAuth Access Token Details](#)
- [Revoking your OAuth Access Tokens](#)

OAuth Access Tokens

OAuth access tokens allow you to use a Confluence gadget on an external web application or website (also known as the 'consumer') and grant this gadget access to Confluence data which is restricted or privy to your Confluence user account.

OAuth access tokens will only appear in your user profile if the following conditions have been met:

1. Your Confluence Administrator has established an OAuth relationship between your Confluence site and the consumer.
Confluence Administrators should refer to [Configuring OAuth](#) for more information about establishing these OAuth relationships. *Not applicable to Confluence OnDemand.*
2. You have accessed a Confluence gadget on the consumer and have conducted the following tasks:
 - a. Logged in to your Confluence user account via the gadget and then,
 - b. Clicked the 'Approve Access' button to allow the gadget access to data that is privy to your Confluence user account.

i Confluence will then send the consumer an OAuth 'access token', which is specific to this gadget. You can view the details of this access token from your Confluence site's user account.

An OAuth access token acts as a type of 'key'. As long as the consumer is in possession of this access token, the Confluence gadget on the consumer will be able to access Confluence data that

is both publicly available and privy to your Confluence user account. As a Confluence user, you can revoke this access token at any time. Furthermore, all access tokens expire after seven days. Once the access token is revoked or has expired, the Confluence gadget will only have access to publicly available Confluence data.

Viewing your OAuth Access Tokens

To view all of your Confluence user account's OAuth access tokens:

1. Choose **your profile picture** at top right of the screen, then choose **Settings**.
 2. Click **View OAuth Access Tokens**. A view similar to [screenshot below](#) is displayed. Refer to [OAuth Access Token Details](#) below for information on interpreting this table.
-  If no access tokens have been set, then 'None specified' is shown.

Screenshot: Viewing your OAuth Access Tokens

Authorised Applications			
The following applications are using your account to access Confluence data:			
Consumer	Consumer Description	Issued on	Actions
Atlassian JIRA Special Projects	Atlassian JIRA at https://atlassian.com/jira	Jan 23, 2013 expires in 1,801 days	Revoke Access

OAuth Access Token Details

Your list of OAuth access tokens is presented in a tabular format, with each access token presented in separate rows and each property of these tokens presented in a separate columns:

Column Name	Description
Consumer	The name of the Confluence gadget that was added on the consumer.
Consumer Description	A description of this consumer application. This information would have been obtained from the consumer's own OAuth settings when an OAuth relationship was established between Confluence and that consumer.  If the consumer is another Atlassian application, this information is obtained from the Consumer Info tab's 'Description' field of the OAuth Administration settings. The application's administrator can customise this Consumer Info detail.
Issued On	The date on which the OAuth access token was issued to the consumer by Confluence. This would have occurred immediately after you approved this gadget access to your Confluence data (privy to your Confluence user account).
Expires On	The date when the OAuth access token expires. This is seven days after the 'Issued On' date. When this date is reached, the access token will be automatically removed from this list.

Actions	The functionality for revoking the access token .

Revoking your OAuth Access Tokens

To revoke one of your OAuth access tokens:

1. View your Confluence user account's OAuth access tokens ([described above](#)).
2. Locate the Confluence gadget whose OAuth access token you wish to revoke and click **Revoke OAuth Access Token** next to it.
The gadget's access token is revoked and the Confluence gadget on the consumer will only have access to publicly available Confluence data.

Choosing your Home Page

By default, all users are directed to the dashboard after logging in. However, you can choose to be redirected to the home page of any space on the Confluence site after logging in.

To set the home page:

1. Choose **your profile picture** at top right of the screen, then choose **Settings**.
2. Choose **Edit**.
3. Choose a page from the **Site Homepage** drop down. Only spaces for which you have 'view' access display. You will be directed to the home page of the selected space when you next log in.
4. Click **Submit**.

Related pages:

- [User Profile Overview](#)
- [Confluence User's Guide](#)

Screenshot: Profile Settings

The screenshot shows the 'Settings' tab of a Confluence user profile for 'Sophie Staunton'. The left sidebar contains links for 'GADGETS' (View OAuth Access Tokens) and 'YOUR SETTINGS' (Password, Email, Editor). The main content area is titled 'Settings' and includes the following options:

- Site Homepage:** A dropdown menu set to 'Site Default (Dashboard)'.
- Language:** A dropdown menu set to 'Automatically detect browser settings'. Below it is a link: 'Find more language packs on the [Atlassian Marketplace](#)...'.
- Time zone:** A dropdown menu set to 'Site Default ((GMT+1000) Sydney)'.
- Use Keyboard Shortcuts:** A checked checkbox. Below it is a note: 'Enable keyboard shortcuts (does not apply to editor shortcuts). Select "Keyboard Shortcuts" from the Browse menu to see available shortcuts.'

At the bottom of the settings area are 'Submit' and 'Cancel' buttons.

Customising your Personal Dashboard

You can customise the Confluence dashboard to provide access to the content on the site that is most relevant to you. The options described on this page will change your own personal dashboard, but will not affect the dashboard that other people see.

If you have System Administrator permissions, you can change the global dashboard, as seen by all Confluence

users. See [the administrator's guide to customising the dashboard](#). *Not applicable to Confluence OnDemand.*

Displaying your favourite spaces

Mark some spaces as [favourites](#). You can now choose the **Spaces** tab on the dashboard to see a list of your favourite spaces. You can also choose the **Favourite Spaces** tab at the top right of the dashboard to see recently updated content from just your favourite spaces.

Categorising your spaces

To help keep Confluence spaces organised, you can label spaces with different space categories. See [Using Labels to Categorise Spaces](#). Space categories are used to group related spaces.

For example, you might want to group spaces on your Confluence site by applying the following space categories to the relevant spaces:

- 'design' (for spaces relevant to a design team), and
- 'development' (for spaces relevant to a development team).

If a subset of these spaces is relevant to both teams, apply both the 'design' *and* 'development' categories to each of these spaces to make the spaces appear in both groups.

Once you have added space categories, you can choose the **Space Categories** tab at the top right of the dashboard and select a category from the drop-down menu to display only spaces belonging to that category.

On this page:

- [Displaying your favourite spaces](#)
- [Categorising your spaces](#)
- [Displaying your favourite pages](#)

Related pages:

- [Working with Confluence Labels](#)
- [Working with Favourites](#)
- [Configuring the Site Home Page](#)
- [Customising the Confluence Dashboard](#)
- [Confluence User's Guide](#)

Displaying your favourite pages

Mark some pages as [favourites](#). You can now choose the **Pages** tab on the dashboard to see a list of your favourite pages.

Screenshot: The dashboard, showing favourite pages and space categories

The screenshot shows the Confluence Dashboard. At the top, there's a 'Dashboard' header. Below it, a 'Welcome to Confluence' message states: 'Confluence is where your team collaborates and shares knowledge — create, share and discuss your files, ideas, minutes, specs, mockups, diagrams, and projects.' To the right of the welcome message are tabs: 'Popular', 'All Updates', 'Favourite Spaces', 'Network', and 'Space Categories'. Below the welcome message are tabs: 'Spaces', 'Pages', and 'Network'. On the left, under 'Favourite Pages', there's a list of four pages: 'Games as a communication medium', 'Ideas for Angry Nerds 2 - revenge of the...', 'Our new logo', and 'Step 1 - download the game', each with a star icon. On the right, there's a 'Select:' dropdown menu set to 'Development'. Below this, there's a user profile for 'Rach Admin' with a profile picture. Under Rach Admin's profile, there's a list of items: 'Logo2.jpg' (Attached Feb 15, 2013), 'atlassian_logo_detail.gif' (Attached Feb 15, 2013), 'Our new logo' (Updated Feb 15, 2013, with a '(view change)' link), and 'Overview' (Updated Feb 15, 2013, with a '(view change)' link). Below Rach Admin's profile is a user profile for 'Ewan User' with a profile picture. Under Ewan User's profile, there's a comment: 'Re: Step 1 - download the game Love this game!' (Commented Feb 15, 2013), followed by 'Step 2 - Play' (Updated Feb 15, 2013, with a '(view change)' link), and 'Why I loved Angry Nerds' (Created Feb 15, 2013).

Customising the Look and Feel of a Confluence Space

You can customise the 'look and feel' of a space on your Confluence site through options available in the **Space Administration** menu. By default, the look and feel of a space is based on site-wide settings configured from the [Administration Console](#).

You need to be a [space administrator](#) to change the look and feel of a space.

- [Applying a Theme to a Space](#)
- [Configuring a Sidebar](#)
- [Changing a Space's Logo](#)
- [Changing the Confluence Browser Icon, aka favicon](#)
- [Customising Space Layouts](#)
- [Editing a Space's Colour Scheme](#)
- [Styling Confluence with CSS](#)

Related pages:

- [Changing the Look and Feel of Confluence](#)
- [Working with Spaces](#)
- [Confluence User's Guide](#)

Applying a Theme to a Space

Themes allow you to personalise the 'look and feel' of Confluence. You can apply a theme to your entire Confluence site or to individual spaces. Choose a specific theme if you want to add new functionality or significantly alter the appearance of Confluence.

Confluence comes with a selection of themes. In addition, a [site administrator](#) can install new themes as plugins via the [Confluence Administration Console](#). Provided that the theme is installed into your Confluence site, any [space administrator](#) can apply a theme to a space.

By default when you create a new space, the space will have the Confluence default theme.

Related pages:

- [Applying a Theme to a Site](#)
- [Editing a Space's Colour Scheme](#)
- [Customising the Look and Feel of a Confluence Space](#)
- [Confluence User's Guide](#)

Want to customise Confluence or make it even more beautiful? Try a [Confluence theme from the Atlassian Marketplace](#).

**To apply a theme to a space:**

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Look and Feel > Themes**.
3. Select a theme option.
4. Choose **Confirm**.

Screenshot: Applying a theme

A screenshot of the 'Themes' configuration page in Confluence. The page has a top navigation bar with tabs: 'Themes' (selected), 'Colour Scheme', 'Layout', 'Stylesheet', 'PDF Layout', and 'PDF Stylesheet'. Below the tabs, the section 'Current Theme' is displayed, with a sub-header 'Global Look and Feel'. A description states: 'The globally configured look and feel. You can customise colour-schemes and layouts manually.' Below this, the 'Choose New Theme' section is shown, with a sub-header 'Documentation Theme' selected. A description for this theme states: 'This theme is well suited for structured content, such as documentation. It features a table of contents (page tree) on the left, making it easier to see the structure of a space and move from page to page. You can customise the left-hand panel, page header and page footer.' At the bottom left, there is a 'Confirm' button.

If your space is using the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Themes** from the space administration options
3. Select a theme option.
4. Choose **Confirm**.

Configuring the Documentation Theme

The Documentation theme is one of the themes bundled with Confluence.



Advance warning of plans to merge Documentation theme with the default theme

This is an advance notice that we plan to merge the functionality of the Confluence Documentation theme with the Confluence default theme. We do not yet have a specific date for this plan, and we are interested in your feedback. The new default theme, to be introduced in Confluence 5.0, includes a sidebar with contextual navigation. (For a preview, see the [Confluence 5.0-m9 release notes](#).) Our plan is to include all the features of the Documentation theme into the default theme, and then remove the Documentation theme from Confluence.

If you are interested in this change and would like to give us feedback, please add a **comment on this blog post**: [Advance warning of plans to merge Documentation theme with the default theme](#). We are especially interested to know which features of the Documentation theme you use and value the most.

The Documentation theme is designed for spaces containing technical documentation, but you may find it useful for other types of content too. It provides an inbuilt table of contents for your wiki space, a configurable header and footer, and text styles suited to documentation. (See features [below](#).)

Quick guide to applying and customising the Documentation theme:

- Go to **Space Admin** and choose **Themes**.
- Select **Documentation Theme** and choose **Confirm**.
- If you want to customise the theme, choose **Configure theme**.
 - Select or deselect the default page tree.
 - Select or deselect the space-restricted search.
 - Enter the text and wiki markup for your custom left-hand panel header and footer.
 - Choose **Save**.

The rest of this page gives more details of the above procedure.


On this page:

- [Applying the Documentation theme to your space](#)
- [Applying the Documentation theme to your site](#)
- [Customising the Documentation theme](#)
- [Features of the Documentation theme](#)
- [Hints and tips](#)
- [Notes](#)

Related pages:

- [Using the Documentation Theme](#)
- [Space Jump Macro](#)
- [Applying a Theme to a Space](#)
- [Applying a Theme to a Site](#)
- [Editing a Space's Colour Scheme](#)
- [Customising the Look and Feel of a Confluence Space](#)
- [Confluence User's Guide](#)

Screenshot: The Documentation theme showing the space sidebar replaced by a navigation sidebar.

**Applying the Documentation theme to your space**

You need [space administrator](#) permissions to apply a theme to a space.

Follow the steps below to apply the Documentation theme to your space. All pages in the space will start using the theme immediately.

To apply a theme to a space:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the `confluence-administrators` group).

2. Choose **Look and Feel > Themes**.
3. Select a theme option.
4. Choose **Confirm**.

Screenshot: Applying a theme

Themes Colour Scheme Layout Stylesheet PDF Layout PDF Stylesheet

Current Theme

The current theme controls the layout and colours of this space.

Global Look and Feel

The globally configured look and feel. You can customise colour-schemes and layouts manually.

Choose New Theme

To change the theme of this space, select one below.

☒ **Documentation Theme**

This theme is well suited for structured content, such as documentation. It features a table of contents (page tree) on the left, making it easier to see the structure of a space and move from page to page. You can customise the left-hand panel, page header and page footer.

Confirm

If your space is using the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the `confluence-administrators` group).
2. Choose **Themes** from the space administration options
3. Select a theme option.
4. Choose **Confirm**.

Applying the Documentation theme to your site

If you have [site administrator](#) permissions, you can apply the theme at site level. It will then be the default theme for all spaces in the site. See the administrator's guide to [applying a theme](#).

Customising the Documentation theme

The theme works well without any customisation. If necessary, you can restrict the search to just one space, change the content of the left-hand navigation panel and add your own header and footer.

To customise the Documentation theme:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the `confluence-administrators` group).

2. Choose **Themes** in the left-hand panel under the heading 'Look and Feel'.

3. If the space is not yet using the Documentation theme, apply the theme as described [above](#).
4. Choose **Configure theme** in the yellow area of the 'Current Theme' section at the top of the page. See screenshot [below](#). The 'Documentation Theme Configuration' screen appears. See screenshot [below](#).
5. Select or deselect the **Page Tree** check box. This determines whether your space will display the default search box and table of contents (page tree) in the left-hand panel.
6. Select or deselect the **Limit search results to the current space** check box.
 - If you select the check box:
 - The Confluence search will look for matches only in the current space by default. Users can override this restriction when entering their search term. See [Using the Documentation Theme](#).
 - The default page tree in the left-hand panel will not include a search box.
 - If you do not select the check box:
 - The Confluence search will look for matches in the entire Confluence site. This is the default behaviour for other themes too.
 - The default page tree in the left-hand panel will include a search box, which restricts search results to the current space.
7. Enter text, images, macros and other wiki markup into any or all of the three text boxes.
 -  You can use the [Include](#) or [Excerpt Include](#) to include re-usable content into your footer. See hint [below](#).
 - 'Navigation' – This text box contains content for the left-hand panel.
 - If the **Page Tree** check box is selected, the navigation panel contains the default search box and page tree. Any content you enter into the 'Navigation' text box will appear *above* the page tree and search box.
 - You can include your own content *underneath* the page tree as well as above. See hint [below](#). In summary: Deselect the **Page Tree** check box. Insert your own page tree using the [Pagetree macro](#), then add your own content under the macro.
 - 'Header' – This text box contains content for a page header that will appear above the page title on all pages in the space. See example screenshot [below](#).
 - 'Footer' – This text box contains content for a page footer that will appear after the comments and above the site footer, on all pages in the space. See example screenshot [below](#).
8. Choose **Save**.

Screenshot: The 'Configure theme' option

Current Theme

The current theme controls the layout and colours of this space.



Documentation Theme

This theme is well suited for structured content, such as documentation. It features a table of contents (page tree) on the left, making it easier to see the structure of a space and move from page to page. You can customise the left-hand panel, page header and page footer.

[Configure theme](#) - further customise this theme's options

Choose New Theme

To change the theme of this space, select one below.



☒ Global Look and Feel

The globally configured look and feel. You can customise colour-schemes and layouts manually.

 [Find more themes...](#)

Confirm

Screenshot: Customising the Documentation theme

Navigation

☐ Page Tree
Show the page tree in the sidebar.

☒ Limit search results to the current space
Limit search results returned by the top right search field to the current space.

Navigation

```
*[Latest Confluence
Documentation|Confluence
Documentation Home]*

{pagetree:root=Confluence
Documentation
Home|searchBox=false}

*[Downloads (PDF, HTML &
```

Add your own links and content to the sidebar using wiki markup.

Messages

Header

```
{section}
{column:width=1%}{column}
{column}{panel}
*{include:_MajorReleaseNumb
erConfluence|npanel=true}*
-- This documentation is
for *Confluence 5.0*
developer (EAP) releases
only. Not for you? *[See
```

Display a banner or text at the top of every page in this space by entering wiki markup here.

Footer

```
{include:_Documentation
Footer|npanel=true}
{include:ALLDOC:_Copyright
Notice|npanel=true}
```


Display a banner or text at the bottom of every page in this space by entering wiki markup here.

Customising the theme at site level

If you have [site administrator](#) permissions, you can apply and customise the theme at site level. The customisation options are the same as the space level options, as described above.

Features of the Documentation theme

Screenshot: A customised header, footer and left-hand panel



The above screenshot shows a wiki space with a customised left-hand panel, header and footer.

Here is a summary of the features that the Documentation theme provides:

- By default, the left-hand panel contains a search box and a table of contents (page tree) showing all the pages in your space. Specifically, it shows the pages that are children of the space's home page.
- The left-hand panel is fully customisable. You can choose to include or exclude the search box and page tree. You can enter your own text, images and wiki markup.
- People viewing the page can drag the thick bar between the left-hand panel and the content, to increase or decrease the width of the panel. They can also remove the panel altogether, by clicking the sidebar icon  at top right, next to the search box.
- The left-hand and right-hand panels scroll independently of each other.
- The page title is neatly above the page content, and not uncomfortably above the navigation panel as tends to happen when you insert the navigation panel yourself.
- Because the left-hand panel is part of the theme, it will be upgraded whenever Confluence is upgraded. There is no need to remove and then re-apply your customisations on each upgrade, as you would do if you added your own left-hand navigation bar.
- The theme also provides a customisable header and footer, which will appear at the top and bottom of every page.
- The text and heading styles are designed to enhance the content typically found in a documentation space.
- You can use the [Space Jump macro](#) to link from a page in one wiki space to a page with the same name in another space, without knowing the name of the page when you create the link.
- You can limit the Confluence search results to the current space. If you choose this option, the Confluence search will look for matches only in the current space by default. Users can override the restriction. See [Using the Documentation Theme](#).

Hints and tips

Below are some hints that you may find useful when using the Documentation theme. Where can I see a working example of the Documentation theme?

The Confluence documentation uses the Documentation theme. If you are reading this documentation online on [the Atlassian documentation wiki](#), you are seeing a working version of the Documentation theme.

Which pages will appear in the Documentation theme's table of contents?

The theme constructs the page tree in the left-hand panel from all pages that are child pages of the space's home page. Each space has a single page designated as the 'Home' page. You can specify the home page in the [space administration section](#).

Help, my pages do not appear in the Documentation theme table of contents

Cause 1: Your pages are not under the space's home page. The most probable reason why your pages do not appear in the page tree in the left-hand panel is this: The theme constructs that table of contents from all pages that are child pages of the space's home page. If your pages are above the home page in the page tree, they will not appear in the left-hand panel.

There are two ways to fix the problem:

- You can change the designated space home page in the [space administration section](#).
- Or you can drag and drop all your pages to make them children of the current home page. You can drag and drop pages in the 'Pages' section of the space 'Browse' screen. See [Moving a Page](#).

Cause 2: Problem with upgrade from Confluence 3.1, with Documentation theme as plugin, to Confluence 3.2 or later with Documentation theme bundled. If your existing Confluence installation already has the Documentation theme plugin installed, you may find that after upgrading to Confluence 3.2 the left-hand navigation bar is empty in the spaces that use the theme. The fix is to enable all modules of the Documentation theme plugin. See the [knowledge base article](#).

Help, my left-hand panel has disappeared

If your entire left-hand panel has disappeared when using the Documentation theme, this is probably because you have clicked the sidebar icon  at top right, next to the search box. Click the icon again to restore the panel.

Can I change the default width of the left-hand navigation panel?

The Confluence user interface does not offer a way to change the default width of the left-hand navigation panel supplied by the Documentation theme. Users can change the width by dragging the middle bar, but the default width is not configurable. This post on Atlassian Answers gives a way to do it with CSS: [Documentation Theme - Default Width \(in px\) of left panel](#).

Hiding pages from the left-hand table of contents

You can 'hide' pages by putting them at the same level as or higher than the space home page.

Each space has a single page designated as the 'Home' page. You can specify the home page in the [space administration section](#).

The theme constructs the page tree in the left-hand panel from all pages that are child pages of the space's home page.

If your documentation pages are at the same level as the space home page, they will not appear in the left-hand navigation bar. So you can 'hide' pages by putting them at the same level as or higher than the space home

page. The pages will show up in the search results and people can see the content if they open the page, but the pages will not appear in the left-hand panel.

More detail: The theme uses the [Pagetree macro](#) to produce the table of contents. When entering the Pagetree macro, you can choose the top page in the page tree. The Documentation theme chooses the space home page as the top page.

Using reusable content in your header, footer or left-hand panel

You can use any text or wiki markup in your theme header, footer or left-hand panel. One useful hint is to use the [Include](#) or [Excerpt Include](#) to include re-usable content into your footer.

The screenshot [above](#) shows the theme customisation options, with examples of the macros used to include content from other pages. And the example screenshot [also above](#) shows the resulting header, footer and left-hand panel.

Adding content below the page tree in your left-hand panel

If you want to include your own content underneath the page tree, you can deselect the 'Page Tree' check box, add your own page tree using the [Pagetree macro](#) in the 'Navigation' text box, and then add your own content under the macro.

The screenshot [above](#) shows the theme customisation options, with the default page tree deselected and a custom page tree inserted, along with additional content in the left-hand panel. The example screenshot [also above](#) shows the resulting left-hand panel.

Adding underlines to your links

By default, the Documentation theme does not underline hyperlinks. If you prefer to have your links underlined, you can edit the CSS stylesheet for your space and add the following CSS code:

```
.wiki-content a:link, .wiki-content a:visited, .wiki-content a:active {
  text-decoration: underline;
}
```

To edit a space's CSS style sheets:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Look and Feel > Stylesheet**.
3. Choose **Edit**.
4. Paste your custom CSS into the text field.
5. Save your changes. The new CSS will be visible on all content pages in the space.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Click **Stylesheet** in the left-hand panel under the heading 'Look and Feel'.
3. Choose **Edit**.
4. Paste your custom CSS into the text field.

5. Save your changes. The new CSS will be visible on all content pages in the space.

Notes:

- You need [system administrator](#) permissions to edit the CSS for a space or for the site.
- This function is turned off by default. To turn it on, go to **Confluence Admin > Security Configuration** and choose **Custom Stylesheets for Spaces**.

Jumping to the same page in another space

The {spacejump} macro is provided along with the Documentation theme. You can use space jumping to link from a page in one wiki space to a page with the same name in another space, without knowing the name of the page when you create the link. When a reader is viewing a page and chooses the link provided by the macro, they will go to a page with the same name, but in the space specified in the macro. See [more about the Space Jump macro](#).

Hiding the left-hand panel completely

It's not possible to remove the left-hand panel entirely, using the user interface supplied by the theme. There is an improvement request here: [CONF-25923 - Authenticate to see issue details](#) If you like, you can comment on and/or vote for that request. In the meantime, [Atlassian Answers](#) is a good place to ask the question and see if other people can help you with custom code to remove the panel.

Notes

- The Confluence default theme supplies a **sidebar**, which is different to the left-hand panel in the Documentation theme. For information about the sidebar, see [Finding Content](#) and [Configuring a Sidebar](#).
- The Documentation theme supplies a **Browse** menu in the Confluence header, which gives access to the space administration and advanced options.

Configuring a Sidebar

This guide describes the sidebar on the left of every page in spaces that use the default Confluence theme. For spaces using the Documentation theme, see [Configuring the Documentation Theme](#).

Hint for space administrators: Add links to the sidebar, pointing to pages and other locations that are important for your team or project. This is a great way of encouraging collaboration and improving productivity.

You need space administrator permissions to configure the sidebar. See [Space Permissions](#). Any changes you make to a space's sidebar will affect all Confluence users viewing the space.

To configure a space's sidebar:

1. Open the sidebar configuration panel, as follows:
 - Make sure the space uses the default Confluence theme. See [Applying a Theme to a Space](#).
 - Go to a page in the space and choose **Configure sidebar** in the sidebar. (Expand the sidebar if necessary, to see the 'Configure sidebar' option.)
Note: The 'Configure sidebar' option will only appear if you have space administration permissions.
2. Change the space name and/or space logo:
 - Choose the edit icon  next to the space name.
 - Type in a space **Name**.
 - Browse to find an image for the space **Logo**, and crop the image to the required size.
 - Choose **Save**.
3. Configure the **Pages** and **Blog** links:
 - Choose the icons to **hide** or **show** the 'Pages' or 'Blog' link. For example, you may want your space to be used primarily as a blog (hide the 'Pages' link) or you may not need a blog in your space (hide the 'Blog' link).
 - Drag the links to a different sequence within the section. Note that you cannot move a link from one section to another.
 - Note that add-ons may add other links in this section of the sidebar. For example, the Team

Calendars add-on may put a link in this location.


4. Configure the **shortcut links**:

- Choose **Add link** to add a shortcut link to the sidebar. This can be a link to an important page for your team, or to an external site, for example.
- Choose the icon to **remove** a shortcut link.
- Drag the links to a different sequence within the section. Note that you cannot move a link from one section to another.

Related pages:

- [Finding Content](#)
- [Administering a Space](#)
- [Confluence User's Guide](#)

Diagram: Configuring a space's sidebar



Notes

If you choose to hide the Pages and Blogs links in the sidebar your users may not be able to access some functionality such as **Watch this space** and **Watch this blog**.

Changing a Space's Logo

In Confluence, you can replace the default logo for a space with an image of your choice. The instructions below apply to site spaces. For your personal space, your [profile picture](#) is used as the space icon.

You need to be a [space administrator](#) to replace a space's logo.

To change a space's logo, in spaces using the default theme:

1. Open the sidebar configuration panel, as follows:
 - Make sure the space uses the default Confluence theme. See [Applying a Theme to a Space](#).
 - Go to a page in the space and choose **Configure sidebar** in the sidebar. (Expand the sidebar if necessary, to see the 'Configure sidebar' option.)

Note: The 'Configure sidebar' option will only appear if you have space administration permissions.
2. Choose the edit icon next to the space name.
3. Choose **Choose File**.
4. Browse to find and upload an image.
5. Adjust the size of the highlighted circle on the image, to crop the image to the required size.
6. Choose **Save**.

To change a space's logo, in spaces using the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.


Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Change Space Logo** in the left-hand panel.
3. Use the browse option to locate the new logo and choose **Upload**.

Related pages:

- [Configuring a Sidebar](#)
- [Customising the Look and Feel of a Confluence Space](#)
- [Confluence User's Guide](#)

Screenshot: Changing a space logo in the default theme

**Notes**

- **Dimensions of image when using the Documentation theme:** A space logo in the Documentation theme looks best if the height and width of the image are of the same or similar length. In other words, the area occupied by the image, including white space, should be square rather than rectangular.
- Space logos in the default theme are circular.

Changing the Confluence Browser Icon, aka favicon

The Confluence logo  is displayed in the user's browser to identify the Confluence browser tab. To use a custom image for your Confluence site:

1. Obtain or create an image in ICO file format. To maximise browser compatibility, it should be 32x32 pixels in size, 71x71 DPI (dots per inch) and have an 8 bit colour depth.
2. Inside the root of your Confluence installation directory, find the `confluence` subdirectory.
3. Back up the file `favicon.ico`.
4. Replace the `favicon.ico` file with your custom ICO image.
5. Restart your application server.

 *The information on this page **does not apply** to Confluence OnDemand.*

Users may need to clear their browser cache before they will see the new image. This can be done by pressing `ctrl+refresh` in the browser when a page in Confluence is open.

i **Converting a PNG to an icon**

To create an ICO out of a PNG image, you can use the freeware tool [png2ico](#) or the the online tool at <http://converticon.com/>.

Related Topics

[Customising the Look and Feel of a Confluence Space](#)

Customising Space Layouts

You can modify Confluence's look and feel by editing the 'decorator' (layout) files. This page tells you how to customise the layout files for a space

Confluence system administrators can also customise the layout of their entire Confluence site as a whole. For more information, please refer to [Customising Site and Space Layouts](#). Site layout customisations modify the default layout of all spaces in the Confluence site. *Not applicable to Confluence OnDemand.*

Any space layout customisations will override the equivalent site customisations.

A note about permissions: To perform these customisations, you will require [space administrator](#) permissions for that space. For security reasons, you must also have Confluence [system administrator](#) permissions to modify any **space** layout throughout your Confluence site.

! If you modify the look and feel of Confluence by following these instructions, you will need to update your customisations when upgrading Confluence. The more dramatic the customisations are, the harder it will be to reapply your changes when upgrading. Please take this into account before proceeding with any customisations. For more information on updating your customisations, please refer to [Upgrading Customised Site and Space Layouts](#).

Related pages:

- [Customising the Look and Feel of a Confluence Space](#)
- [Applying a Theme to a Space](#)

[Confluence User's Guide](#).

Confluence is built on top of the Open Source SiteMesh library, a web-page layout system that provides a consistent look and feel across a site. SiteMesh works through 'decorators' that define a page's layout and structure.

To edit the layout of Confluence, you will need to modify these decorator files. A decorator file is a .vmd file and is written in a very simple programming language called **Velocity**. Learn [more about Velocity](#). Once you become familiar with Velocity, you can edit the decorator files to personalise the appearance of Confluence.

The decorator files in Confluence are grouped into the following categories:

- **Site layouts:** These are used to define the controls that surround each page in the site. For example, if you want to make changes to the header and the footer, you will need to modify these layouts.
- **Content layouts:** These control the appearance of content such as pages and blog posts. They do not change the way the pages themselves are displayed, but they allow you to alter the way the surrounding comments or attachments are shown.
- **Export layouts:** These control the appearance of spaces and pages when they are exported to HTML. If you are using Confluence to generate a static website, for example, you will need to modify these layouts.

Learn more about using [decorators](#).

To edit a decorator file:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Look and Feel > Layout** (**Layout** is displayed only if you are a Confluence system administrator.)
3. You will see a list of the layouts for the space.
 - Click **View Default** to view the vmd file.
 - Click **Create Custom** to edit the default vmd file. This will open up the vmd file in edit mode. Make changes and click **Update**.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.

Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Layout** in the left-hand panel (**Layout** is displayed only if you are a Confluence system administrator.)
3. You will see a list of the layouts for the space.
 - Click **View Default** to view the vmd file.
 - Click **Create Custom** to edit the default vmd file. This will open up the vmd file in edit mode. Make changes and click **Update**.

Screenshot : Edit Layouts Example

Decorator	Operations
Space Export Layout When you export a space to HTML, this layout is used to create the index page.	< default > Create custom View Default
Page Export Layout When you perform an export, each page is converted to HTML using this layout.	< default > Create custom View Default

Click the thumbnail to see an example of a vmd file:



Editing a Space's Colour Scheme

Confluence allows you to customise the colour scheme of a space. By default, a space's colour scheme is based on [global settings](#) configured from the [Administration Console](#).

You need to be a [space administrator](#) to edit a space's colour scheme.

Related pages:

- [Customising the Look and Feel of a Confluence Space](#)
- [Confluence User's Guide](#)

To change the colour scheme for a space:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Look and Feel > Colour Scheme**
3. Choose **Select** next to a scheme listed under **Custom Colour Scheme** (if not already selected).
4. Choose **Edit**.
5. Enter standard HTML/CSS2 colour codes, or use the colour-picker  to choose a new colour from the palette provided. Any changes you make will immediately be reflected in this space.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Colour Scheme** under the heading **Look and Feel**.
3. Follow the steps above to select a custom colour scheme and edit the colours.

The colour scheme allows you to edit the colours of UI elements including the top bar, tabs and backgrounds.

Some UI elements below are for specific themes, and colour changes may not take effect for other themes.

- **Top Bar** - the top navigation bar background
- **Top Bar Text** - the text on the top navigation bar
- **Header Button Background** - buttons on the top navigation bar (e.g. Create button)
- **Header Button Text** - the text on buttons on the top navigation bar
- **Top Bar Menu Selected Background** - background colour of top navigation bar menu items when selected (e.g. spaces)
- **Top Bar Menu Selected Text** - text colour of top navigation bar menu items when selected
- **Top Bar Menu Item Text** - text on top navigation bar drop down menus (e.g. help or cog)
- **Menu Item Selected Background** - highlight colour on top navigation bar drop down menu items
- **Menu Item Selected Text** - text colour on highlighted top navigation bar drop down menu items
- **Page Menu Selected Background** - the background colour of the drop down page menu when selected
- **Page Menu Item Text** - the text of the menu items in the drop down page menu
- **Heading Text** - all heading tags throughout the space
- **Space Name Text** - the text of the current space name located above the page title
- **Links** - all links throughout the space
- **Borders and Dividers** - table borders and dividing lines
- **Tab Navigation Background** - the background colour of the tab navigation
- **Tab Navigation Text** - the text of the tab navigation when highlighted
- **Tab Navigation Background Highlight** - the background colour of the tab navigation when highlighted
- **Tab Navigation Text Highlight** - the text of the tab navigation elements when highlighted

Screenshot: Editing the colour scheme

Custom Colour Scheme

A custom colour scheme which can be edited.



Edit

The following colours can be customised for this colour scheme.

Top Bar		#205081	
Top Bar Text		#FFFFFF	
Header Button Background		#3B7FC4	
Header Button Text		#FFFFFF	
Top Bar Menu Selected Background		#3B73AF	
Top Bar Menu Selected Text		#FFFFFF	
Top Bar Menu Item Text		#333333	
Menu Item Selected Background		#3B73AF	
Menu Item Selected Text		#FFFFFF	
Page Menu Selected Background		#3B73AF	
Page Menu Item Text		#333333	
Heading Text		#333333	
Space Name Text		#999999	
Links		#3B73AF	
Borders and Dividers		#CCCCCC	
Tab Navigation Background		#3B73AF	
Tab Navigation Text		#FFFFFF	
Tab Navigation Background Highlight		#205081	
Tab Navigation Text Highlight		#FFFFFF	

Reset

Save

Cancel



Handy Hint

If you mess things up, just choose **Reset** then try again.

Styling Confluence with CSS

This page explains the facility for changing the look and feel of Confluence with CSS.

Introduction

Cascading Style Sheets (CSS) are an industry-standard way of styling a web page. The content of a page is

rendered with HTML, and its look and feel is determined by CSS files. You can upload a CSS text file, or simply type in a stylesheet, and apply it to a space or even a whole Confluence site.

Notes:

- You need [system administrator](#) permissions to edit the CSS for a space or for the site.
- This function is turned off by default. To turn it on, go to **Confluence Admin > Security Configuration** and choose **Custom Stylesheets for Spaces**.

Creating CSS styles that work seamlessly across different browsers is a delicate task for basic web sites, and reasonably challenging when customising web applications like Confluence. It is important to test each change that you make and ensure it works as expected in all areas of Confluence – for example, on the Confluence dashboard as well as on regular pages.

In order to get you started, we have compiled this introduction, a [basic styling tutorial](#).

On this page:

- [Introduction](#)
- [Considerations for Using Custom CSS](#)
- [Getting Started](#)
- [CSS Resources](#)

Related pages:

- [Basic Styling Tutorial](#)
- [Styling Fonts in Confluence](#)
- [Confluence User's Guide](#)

 *The information on this page **does not apply** to Confluence OnDemand.*

Considerations for Using Custom CSS

CSS Knowledge is Required

If you are not familiar with CSS, see the links in the [CSS Resources section](#) below. You should spend some time to become confident with Cascading Style Sheets before you start editing your Confluence style sheets.

Security

Custom CSS can be used to inject scripts into a page, opening the risk of cross-site scripting (XSS) attacks. With this feature enabled, space administrators could upload styles that steal other users' login credentials, trick their browsers into performing actions on the wiki without their knowledge, or even obtain global administration privileges. As such, this feature is disabled by default. Confluence administrators should only enable custom CSS if they are comfortable with the risks listed in this paragraph.

Scaling

Each page needs to scale. Depending on the resolution of the user's screen, the content should render intelligently. Your designs need to degrade gracefully. Try resizing each page that exists in Confluence. There are quite a few pages in the browse-space-section, like drafts, labels, page hierarchy, and so on. Your style has to work everywhere, not just in the first page you happen to be looking at.

Features Cannot Be Disabled

It is easy to turn off certain links, headers, or even menu items by simply setting their style to 'hidden'. This can help you to roll out Confluence to users that may not be very Wiki-savvy yet. The simpler the UI, the easier it may be for them to use. However, please remember that removing the link to a part of the application does not mean that the functionality is not available. Every user can still change their style from within their browsers, or access the URL directly. Don't rely on CSS to disable parts of Confluence.

Features Should Not Be Disabled

Users familiar with Confluence will expect to find the same controls that they are accustomed to. Removing buttons or controls from the interface is not advised as it may frustrate your users and cause them to circumvent your design by using direct URL access, as mentioned above.

Confluence Version Compatibility

Be aware of any plans to upgrade your Confluence instance. Future versions of Confluence may not be compatible with your custom CSS — this may cause your CSS to break, requiring maintenance when Confluence is upgraded. Ask your Confluence administrator for more information.

Test on Different Web Browsers

As a rule you should test your modifications on different web browsers. Internet Explorer, Firefox, Opera and Safari (on Mac OS X) are some of the more popular browsers.

Note about supported web browsers: Please ensure that you are using one of the web browsers supported by Confluence. If you are using an unsupported browser or browser version, some features may not work correctly. You can find the list of supported web browsers and browser versions on this page: [Supported Platforms](#).

CSS Customisation is Not Supported

As creating custom CSS has potentially limitless possibilities, Atlassian will not support issues that are caused by or related to CSS customisation.

Getting Started

Editing the CSS

To edit a space's CSS style sheets:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Look and Feel > Stylesheet**.
3. Choose **Edit**.
4. Paste your custom CSS into the text field.
5. Save your changes. The new CSS will be visible on all content pages in the space.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Click **Stylesheet** in the left-hand panel under the heading 'Look and Feel'.
3. Choose **Edit**.
4. Paste your custom CSS into the text field.
5. Save your changes. The new CSS will be visible on all content pages in the space.

To edit your global CSS stylesheet:

1. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
2. Choose **Stylesheet**.
3. Choose **Edit**.

4. Paste your custom CSS into the text field.
5. Choose **Save**.

Note:

- The new CSS will be visible across all spaces, provided they do not define their own custom stylesheet and are not using a theme. This CSS will also overwrite all styles defined in custom global themes.
- You may be able to add CSS to your site by choosing **Custom HTML** in the administration section, and adding your CSS definitions to the HEAD or BODY of the page. You should only use this option if you cannot achieve the desired results via the global stylesheet.

Follow the Tutorial

Follow the examples in the [Basic Styling Tutorial](#) to get started.

CSS Resources

- [W3C CSS Standards](#)
- [W3schools CSS Introduction](#)
- [Mozilla Developer Network](#)
- [W3resource.com](#)

Basic Styling Tutorial

This page contains instructions on how to get started with custom CSS styling in Confluence.

CSS Editing Quick-Start**To edit a space's CSS style sheets:**

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Look and Feel > Stylesheet**.
3. Choose **Edit**.
4. Paste your custom CSS into the text field.
5. Save your changes. The new CSS will be visible on all content pages in the space.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Click **Stylesheet** in the left-hand panel under the heading 'Look and Feel'.
3. Choose **Edit**.
4. Paste your custom CSS into the text field.
5. Save your changes. The new CSS will be visible on all content pages in the space.

On this page:

- [CSS Editing Quick-Start](#)
- [Tutorial: Changing the Header Background](#)
- [CSS Editing Tips](#)
- [Notes](#)

Related pages:

- [Styling Confluence with CSS](#)
- [Confluence User's Guide](#)

 *The information on this page **does not apply** to Confluence OnDemand.*

Tutorial: Changing the Header Background

The header is the menu area at the top of a default Confluence page where the **Breadcrumb Links**, **Browse menu**, **User** menu and the **Quick Search** box reside. In this example, we are going to change the background of the header to include a custom graphic.

1. Create a custom graphic. For this example, we created a custom header graphic of 1046 x 61 pixels.
2. Upload the custom graphic to a page in the space that you are customising.
3. Note the page ID of the page where you uploaded the new graphic. (in this example, the page ID was '**658833839**').
4. Compose your custom CSS for the header. The example below loads the new graphic (called '**header.png**') from a specific page (denoted by page ID '**658833839**') in the same space.

```
#header {  
  
    background-image:url('../download/attachments/658833839/header.png'  
    );  
        background-repeat: no-repeat;  
    }
```

5. Log in as the Space Administrator.
6. Open the Space Admin page.
7. Click **Stylesheet**.
8. Click **Edit** to change the code in the text field.
9. Paste your custom CSS into the text field.
10. Click **Save** and then reload the page (you may have to shift-reload). The background of the header will change.
11. The custom header will be visible on all content pages in the space. To revert your change, simply delete the custom code from the 'Stylesheet' page and click **Save**.

CSS Editing Tips**Begin With a Space Stylesheet**

A space stylesheet is a good starting point for CSS customisation, as it already includes all of the elements that can be changed. When you work on the space stylesheet it styles all content pages in the space. Build and test it at space-level, before considering applying the new stylesheet to your entire site. Once you are satisfied with your space design, test it thoroughly until you are confident that it has no problems. Then, you can look into advanced customisation of the Confluence CSS such as adjusting the Search page, the Dashboard and other integral pages.

Use the Right Tools

As the Confluence CSS is reasonably sophisticated, web development applications will help you to understand how the page styles have been created. In particular, you will need to view the existing source for the pages you're starting to work on. If you don't already have some, tools such as the following free applications will allow you to do this.

1. Firebug

Firebug, a plugin for the Firefox web browser, allows you to take a look at the style of each element on your page. This is very useful to see what styles are currently applied, for example styles applied to the header only.

2. Web Developer

The Web Developer plugin for Firefox allows you to edit CSS inline and create new page designs.

3. CSS Edit

CSS Edit is a stand-alone CSS editor for Macintosh that extracts all existing styles from a given page and allows you to overwrite these.

Edit Simple Elements First

Begin by editing simple elements and checking that they work. By making changes, then checking that each one worked, you can easily isolate any CSS code that is causing problems. Be aware that some page elements are more suited to customisation than others. For example, adding a gradient to the toolbar is less likely to 'break' the page than changing the page width. Editing reasonably static elements such as background graphics will render more predictably than designs which attempt to completely change the user interface or the Javascript-powered drop-down menus (which we don't recommend editing).

Notes

Notes:

- You need [system administrator](#) permissions to edit the CSS for a space or for the site.
- This function is turned off by default. To turn it on, go to **Confluence Admin > Security Configuration** and choose **Custom Stylesheets for Spaces**.

Styling Fonts in Confluence

Confluence provides the ability to adjust its visual style via Cascading Style Sheets (CSS). This tutorial shows you to change the fonts and font sizes of a Confluence page, using a few lines of CSS.

Screenshot 1: Default font in a Confluence page



Screenshot 2: Custom font in a Confluence page



Home

Added by [Matt Ryall \(Atlassian\)](#), last edited by [Matt Ryall \(Atlassian\)](#) on Oct 31, 2008 ([view change](#)) [show comment](#)

My name is Matt Ryall. I'm a developer on the Confluence team, and I started at Atlassian in January 2006.

I'm very interested in web development, specifically accessible and semantic site design. Wikis are actually one of the most interesting areas of web development, I believe, because they're a totally new form of content. Blogs came from the idea of personal journals, most static websites look like marketing brochures, but there's nothing comparable to a wiki in the physical world. On a wiki you can create an array of linked and searchable content, then anyone can improve on the words you've written, collaborating on whatever you want.

Below are some of the pages on this wiki where I've made a significant contribution:

- [Character Encodings in Confluence](#) (and the other [Confluence Internals](#) documents)
- [Running Confluence behind Apache](#)
- [Understanding User Management in Confluence](#)

Below is the code for the custom font. Copy and paste it into the Space Stylesheet form within the Space Administration section.

Related pages:

- [Basic Styling Tutorial](#)
- [Confluence User's Guide](#)

 The information on this page *does not apply* to Confluence OnDemand.

Changing the fonts

In order to customise the fonts in Confluence, you first need to set the body font to the font you want. Secondly, you may want to adjust the font size because different fonts have different relative sizes.

The relevant CSS is shown below. It changes Confluence's font from the default of Helvetica/Arial – *sans serif* to Times/Times New Roman – *serif*. To adjust for the fact that Times is a bit smaller than Helvetica, we increase the font size to 14 pixels. The many styles that 'wiki-content' in their definition are necessary to change the font size for all the tags in the wiki content.

```
body {
    font-family: Times, "Times New Roman", serif;
    font-size: 14px;
}
.wiki-content,
.wiki-content p,
.wiki-content table,
.wiki-content tr,
.wiki-content td,
.wiki-content th,
.wiki-content ol,
.wiki-content ul,
.wiki-content li {
    font-size: 14px;
}
```

Notes

Notes:

- You need [system administrator](#) permissions to edit the CSS for a space or for the site.
- This function is turned off by default. To turn it on, go to **Confluence Admin > Security Configuration** and choose **Custom Stylesheets for Spaces**.

Requesting Add-ons

The [Atlassian Marketplace](#) website offers hundreds of add-ons that the administrator of your Atlassian application can install to enhance and extend Confluence. If the add-on request feature is enabled for your Confluence instance, you can submit requests for add-ons from the Marketplace to your Confluence administrator.


The 'Atlassian Marketplace for Confluence' page provides an integrated view of the Atlassian Marketplace from within your Confluence instance. The page offers the same features as the Marketplace website, such as searching and category filtering, but tailors the browsing experience to Confluence.

This in-product view of the Marketplace gives day-to-day users of the Atlassian applications, not just administrators, an easy way to discover the add-ons that can help them work. When you find an add-on of interest, you can submit a request with just a few clicks.

Submitting an add-on request

To browse for add-ons in the Atlassian Marketplace, follow these steps:

1. Choose **your profile picture** at top right of the screen, then choose **Atlassian Marketplace**.
2. In the Atlassian Marketplace page, use the search box to find add-ons or use the category menus to browse or filter by add-ons by type, popularity, price or other criteria. You can see what your fellow users have requested by choosing the **Most Requested** filter.
3. When you find an add-on that interests you, click **Request** to generate a request for your administrator.
4. Optionally, type a personal message to your administrators in the text box. This message is visible to administrators in the details view for the add-on.



5. When ready, click **Submit Request**.
6. Click **Close** to dismiss the 'Success!' message dialog box.

At this point, a notification appears in the interface your administrators use to administer add-ons. Also your request message will appear in the add-on details view, visible from the administrator's 'Find New Add-ons' page. From there, your administrator can purchase the add-on, try it out or dismiss requests.

Updating an add-on request

After submitting the request, you can update your message at any time. Click the **Update Request** button next to the listing in the Atlassian Marketplace page to modify the message to your administrator.

The administrator is not notified of the update. However, your updated message will appear as you have modified it in the details view for the add-on immediately.

Giving People Access to Content

Confluence gives you the choice to make the site as open or as closed as you wish. Here are some points to consider:

- As a tool for communication and collaboration, Confluence is at its best when all your users can participate fully.
- So it is advisable not to restrict users unless you have a good reason for doing so.
- Confluence keeps a history of all changes to pages and other content. So it is easy to see who has changed what, and to reverse any edits if required.

Levels of permission

There are three levels of permissions in Confluence.

Global permissions

Global permissions are site-wide permissions, and are assigned by administrators. Confluence allows two levels of administrator permissions:

- **System Administrator** - Users with this permission can perform all the Confluence administrative functions.
- **Confluence Administrator** - Users with this permission can perform most of the Confluence administrative functions, but excluding those functions which could compromise the security of the Confluence system.

Users with 'System Administrator' or 'Confluence Administrator' permission can assign permissions to other users. For full details, please refer to the [overview of global permissions](#) in the *Administrator's Guide*.

Space permissions

The permission to create a new space or to administer one is granted by a **Confluence Administrator** from the global **Administration Console**.

Every space has its **own independent set of permissions**. These permissions determine the access settings for different users of the space. In order to assign these permissions to other users, a user must be a **space administrator** i.e. must have the 'Admin' permission for that space.

See [Users and Groups](#) to learn how these permissions are assigned.

Note: If you misconfigure a space so that nobody has access to administer it any more, someone in the 'confluence-administrators' group will need to fix the permissions for you.

Page restrictions

You can set **page-level restrictions**, if you have the 'Restrict Pages' permission within the space concerned.

Page restrictions allow you to control who can view or edit individual pages. To set page restrictions, edit the page and use the page restriction options below the text-entry box.

On this page:

- [Levels of permission](#)
 - [Global permissions](#)
 - [Space permissions](#)
 - [Page restrictions](#)
- [More information](#)
 - [How do space permissions and page restrictions work together?](#)
 - [How do space permissions and page restrictions affect links?](#)

Related pages:

- [Users and Groups](#)
- [Global Permissions Overview](#)
- [Space Permissions Overview](#)
- [Page Restrictions](#)
- [Configuring Confluence Security](#)
- [Confluence Security Overview and Advisories](#) (*Not applicable to Confluence OnDemand.*)
- [Confluence User's Guide](#)

More information

How do space permissions and page restrictions work together?

Example: In the HR (Human Resources) space, everyone in the organisation has the 'View' **space permission**, but only the HR team has the 'Pages --> Create' **space permission** (i.e. the ability to create and edit pages in the space). A member of the HR team starts to create a new page called 'Annual Leave Policy'. Because the page is not yet finished, she sets the 'Viewing' **page restriction** so that only the HR team can view the page. When the page is finished, she will remove the 'Viewing' restriction so that everyone in the company can see the page.

How do space permissions and page restrictions affect links?

Space permissions and page restrictions affect how [links between pages](#) are displayed to a visitor:

- if the link points to a page in a space to which the visitor does not have 'View' space permission, the link will not be rendered at all.
- if the visitor has 'View' space permission, but page restrictions prohibit her from viewing the page, the link will be rendered but an 'Access Denied' message will be displayed when she clicks the link.
- if the visitor has 'View' space permission, and is not restricted from viewing the page, the link will display and behave as normal.

[Links to attachments](#) are also affected: If the visitor does not have permission to view the page to which the attachment is attached, the link will not be rendered.

Page Restrictions

Page restrictions allow you to control who can view or edit individual pages. You set the page restrictions using the Page Restrictions dialog, either directly by choosing **Tools > Restrictions**, or when editing a page.


For instructions on using the Page Restrictions dialog, refer to [Setting a Page's Restrictions](#).

When a page you are viewing has restrictions applied, a small padlock icon  appears next to the page byline. Clicking the padlock will open the Page Restrictions dialog, where full details on the page restrictions are displayed.

On this page:

- [The Confluence Permissions and Page Restrictions Hierarchy](#)
- [Requirements for Setting Restrictions](#)
- [Page Security Rules](#)
- [Inherited Restrictions and Child Pages](#)
- [Example of Child Page Restrictions](#)
- [How to Open Part of a Space](#)
- [Related Topics](#)

Screenshot: The Confluence Page Restrictions dialog




The screenshot shows the 'Page Restrictions' dialog box in Confluence. At the top, there are two radio buttons: 'Restrict viewing of this page' (selected) and 'Restrict editing of this page'. Below these, there is a 'To:' label followed by three buttons: 'Me' (with a user icon), 'Person...' (with a person icon), and 'Group...' (with a group icon). To the right of these buttons is a text input field labeled 'Enter user or group name' and a 'Restrict' button. At the bottom, there are two lines of text: 'No view restrictions are defined for this page' (with an eye icon) and 'No edit restrictions are defined for this page' (with a pencil icon).

The Confluence Permissions and Page Restrictions Hierarchy

Permissions and page restrictions in Confluence work within a hierarchical manner. For example, users who can access and modify global permissions (for instance, Confluence Administrators) can define which users can access and modify space level permissions (that is, space administrators). Space administrators can then define which users have access to create and modify pages. These users in turn can then apply viewing and editing restrictions to a page. By inheritance, these restrictions will also be applied to any child or descendant pages which are then added to that page.

See the diagram below for an illustration.

Diagram: Confluence Restrictions Hierarchy



Requirements for Setting Restrictions

In order to set or modify page restrictions, you need to have both:

- 'Restrict Pages' permission in the space to which the page belongs (since page restrictions operate within the bounds of [space permissions](#)).
- Permission to edit the page itself. That is, if a user is prevented from editing a page through page restrictions, they are also prevented from changing the restrictions themselves.

Page Security Rules

Users can only view page or space content for which they (or a group they are in) have 'View' permission. Pages that a user does not have 'View' access to are referred to as 'inaccessible' pages. Visit [Inaccessible Page](#) to see how Confluence deals with pages a user cannot view:

- Anonymous users are directed to the login page.
- Logged-in users are shown a permissions error page.

It is not possible to conceal the existence of pages, though you can restrict 'View' access to page content.

i Users will still be able to find the page if they know its URL. But they will not be able to view the content if they don't have the correct permissions.

Inherited Restrictions and Child Pages

If a page has its 'View' restriction set, that restriction will be inherited by all its children (and their children, and so on). If a 'View' restriction is added to a page that has already inherited page restrictions from its parent, users must satisfy both restrictions in order to see the page.

'Edit' restrictions are not inherited from the parent page, only from the space. In a space, the 'Add Pages' permission governs both the creation and the editing of pages. See [Space Permissions Overview](#).

Example of Child Page Restrictions

Consider the page 'Documents', with a child page 'Executive', which itself has a child page 'Payroll'. To begin with, anyone who can view the space to which these pages belong can see all three pages.

For security reasons, 'View' restrictions are set on the 'Executive' page, restricting it to the 'mycompany-management group'. At this point, anyone can still see the 'Documents' page, but you must be in the 'mycompany-management group' in order to view either 'Executive' or 'Payroll'.

Since 'Payroll' information is considered particularly private, the 'Payroll' page then has its page restrictions set to only allow members of the 'mycompany-financial' group to view it. At this point, anyone can see the 'Documents' page, only members of 'mycompany-management' can see 'Executive', and only users who are members of both the 'mycompany-management' and 'mycompany-financial' groups can view 'Payroll'.

How to Open Part of a Space



If designing a large site implementation with this strategy, consult [Page Restrictions Performance Considerations](#).

Often there are cases for which a section of a space should be opened to a group or set of users (for this example, we'll call them group B), but the rest of the space should not be visible to your main users (for this example, we'll call them group A). In this case:

1. Add 'view' permission for both groups A and B in [space permissions](#).
2. [Move the page](#) to be opened to the root of the space. When browsing the pages in the space, your normal space home page and this page should both be at the root level.
3. Add a page restriction to allow Group A and B to see this page.
4. Add a page restriction to your main landing page for Group A, thereby excluding this set of pages from Group B.

You can repeat this with any page hierarchy.



Administrators

- Space administrators are responsible for the management of a space and its contents. They therefore have the ability to remove all restrictions from a page (as described in [Viewing Restricted Pages](#)). This means that space administrators can view and edit all content in the space.
- Users who are members of the 'confluence-administrators' group ('super-users') cannot immediately see pages from which [they are excluded](#) by page restrictions. Also, to be able to edit the page, you will need to remove the restriction from it first – go to **Space Administration > Restricted Pages**.

**You cannot exclude yourself**

As creator or editor of a page, you cannot use page restrictions to deny yourself access to the page. Confluence will automatically add your username into the list of users/groups allowed to view/edit the page. If you remove your username, Confluence will put it back again.

Related Topics

[View a Page's Restrictions](#)

[Set a Page's Restrictions](#)

[View All Restricted Pages](#)

[Page Restrictions Performance Considerations](#)

[Working with Pages](#)

Take me back to the [Confluence User's Guide](#).

Inaccessible Page

Please do not change the page restrictions on this page.

This page is intentionally restricted to viewing by the 'documentation' group only. We use it for demonstration purposes, to show what happens if someone tries to view a restricted page. For example, '[Page Restrictions](#)' links to this page.

Setting a Page's Restrictions

[Page restrictions](#) control who may view or edit a specific page, within the bounds of the [space permissions](#):

- View restrictions make the page invisible to everyone except the chosen users and groups.
- Edit restrictions prevent everyone except the chosen users and groups from editing the page.

You can restrict the page to as many users and groups as you like.



In order to set or modify page restrictions, you need to have the 'Restrict Pages' permission in the space to which the page belongs, as well as permission to edit the page itself.

Setting Page Restrictions**To set restrictions on a page:**

1. Choose **Tools > Restrictions**. The Page Restrictions dialog opens. You can also click the padlock icon  in the page's byline (if available), or click either **Unrestricted** or **Restricted** when editing the page.
2. Select the restriction option required.
3. Choose the users and groups who you want to be able to view or edit the page:
 - To choose just yourself, click **Me**.
 - To choose a particular user or group, type the user's username (or their full name), or the group name, into the **Enter ... name** box, and click **Restrict**. You can enter multiple user and group names, when separated by commas.
 - To search for a user or group (if you are unsure of the name), click **Person...** or **Group...** (You can read more about [searching for users](#).)
4. Click **Save**.

Screenshot: The Confluence Page Restrictions dialog

Page Restrictions

☒ Restrict viewing of this page
 ☐ Restrict editing of this page

To:

Me
 Person...
 Group...

Restrict

No view restrictions are defined for this page
 No edit restrictions are defined for this page

Removing Page Restrictions

To remove restrictions on a page:

1. Choose **Tools > Restrictions**. The Page Restrictions dialog opens. You can also click the padlock icon in the page's byline (if available), or click either **Unrestricted** or **Restricted** when editing the page.
2. Click **Remove restriction** next to the appropriate users or groups.
3. Click **Save**.

You can both set and remove restrictions for different users or groups when using the Page Restrictions dialog.

Notes

When a page you are viewing has restrictions applied, a small padlock icon appears next to the page byline. Clicking the padlock will open the Page Restrictions dialog, where full details on the page restrictions are displayed.

View and edit restrictions apply to all users including space administrators. *However*, space administrators can remove *any* restriction on a page. See [Viewing Restricted Pages](#).

Related Topics

[Space Permissions Overview](#)

[Viewing a Page's Restrictions](#)

[Viewing Restricted Pages](#)

[Working with Pages](#)

Take me back to the [Confluence User's Guide](#).

Viewing a Page's Restrictions

Viewing page restrictions in View mode

When a page you are viewing has restrictions applied, a small padlock icon appears next to the page byline. Clicking the padlock will open the Page Restrictions dialog, where full details on the page restrictions are displayed. See [Setting a Page's Restrictions](#) for instructions on how to change these.

Viewing page restrictions in Edit mode

You can view a page's restrictions when editing the page. You can only edit the page if you have permissions to do so.

To view the restrictions that apply to a page:

- When editing the page, click **Restrictions**. See [Setting a Page's Restrictions](#) for instructions on how to change these.

Related Topics[Setting a Page's Restrictions](#)[Viewing Restricted Pages](#)[Working with Pages](#)

Take me back to the [Confluence User's Guide](#).

Viewing Restricted Pages

Restricted pages are pages that have viewing or editing restrictions applied to them through [page-level restrictions](#).

You need to be a [space administrator](#) to view the list of restricted pages in a space.

To view restricted pages:

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Permissions > Restricted Pages**.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.

Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. Choose **Restricted Pages** in the space administration options.

A list of all restricted pages in the space displays.

Related pages:

- [Setting a Page's Restrictions](#)
- [Working with Pages](#)
- [Space Permissions Overview](#)
- [Confluence User's Guide](#)

Screenshot: Restricted pages in a space

Permissions Restricted Pages					
This report shows all the pages where access is restricted to specific groups or users by page level permissions.					
Title (Space)	Type	Permitted User/Group	Creator	Created	Operations
 Induction plan - Sophie User (Stars)	Edit	leah	Leah Admin	Feb 18, 2013	
 Induction plan - Ewan User (Stars)	Edit	leah	Leah Admin	Feb 18, 2013	
 Draft status report (Stars)	View	admin	Rach Admin	Feb 18, 2013	
	View	sophie	Rach Admin	Feb 18, 2013	

Site Administrators and their Permissions

All site administrative functions are performed from the Administration Console. You need 'System Administrator' or 'Confluence Administrator' permissions to access the Administration Console.

The Confluence permission scheme allows the following levels of site administrator permissions, with the most powerful at the top of the list:

- **Super user** – A 'super user' belongs to the confluence-administrators group, has full administrative access to Confluence, and can see all the content.
- **System Administrator** – A person with 'System Administrator' permission has full administrative access to Confluence.
- **Confluence Administrator** – A person with 'Confluence Administrator' permission has access to most of the Confluence administrative functions.

 Some functionality described on this page *is restricted* in Confluence OnDemand.

Please refer to the [overview of global permissions](#) for full details.

Related Topics

- [Users and Groups](#)
- [Confluence User's Guide](#)

Contacting Confluence Administrators

If you receive an error message from Confluence, the error page may offer you a link to click in order to contact the administrators of the Confluence site.

When you click the link to contact the Confluence administrators, you will see an administrator contact page with the title '**Contact Site Administrators**'. By default, the administrator contact page looks like the screenshot below.

Screenshot: The administrator contact screen

Contact Site Administrators

Please enter information about your request for the site administrators. If you are reporting an error please be sure you include information on what you were doing and the time the problem occurred.

To

From

Subject*

Request Details*

Related pages:

- [Configuring the Administrator Contact Page](#)

The screen may look different

In certain configurations of Confluence, you will not be able to use the form shown in the screenshot above. Instead, you will see a message telling you about one of the following conditions:

- If your Confluence administrator has not configured a mail server for Confluence, this means that Confluence will not be able to send an email message to the administrators.
- If none of the Confluence administrators has an email address, Confluence will not be able to send an email message to them.
- If there are no Confluence administrators defined to Confluence, Confluence will not be able to send an email message to them.
- The Confluence administrator can disable the form and specify a different message to be displayed on the above screen instead of the default message and form. See the [administrator's guide](#).

Notes

You can also access this contact form using the following URL.

```
yoursite.com/wiki/contactadministrators.action
```

Space Administrators and their Permissions

A space administrator is a user with the '**Space Admin**' permission for a space. This permission itself is assigned from the Space Administration screens by a space administrator.

Who is a space administrator?

The person who creates a space is automatically the administrator of that space. That person can then [assign other space administrators](#) as required.

i Confluence administrators are not necessarily space administrators.

- A user who has the 'Administer Confluence' permission is not automatically a space administrator for a particular space. In order for them to be a space administrator, they must belong to a group which has space administration rights on the space, or their username must be specifically granted space administration rights on the space.
- Users who are members of the 'confluence-administrators' group do automatically have space administration permissions for all spaces.

Refer to the [Administrator's Guide](#) for more details about Confluence administrator permissions.

What can a space administrator do?

A space administrator has permission to do anything in the space regardless of any other setting. Space administrators are responsible for the management of a space and its contents. Note that page permissions affect space administrators differently from other users.

Space administrators can:

- view all content in the space. If there are page permissions that restrict the viewing of a page to a single user, or to a group to which the space administrator doesn't belong, a space administrator can still view the page by removing the restriction.
- edit all content on any page in the space.
- remove restrictions from any page in the space (using the Space Administration interface).
- manage the watchers for any page in the space (but not watchers of the space).
- grant themselves any other space permissions (e.g. permission to set restrictions on a particular page).

All space administration functions, with the exception of managing watchers, are performed from the 'Space Admin' tab (choose **Browse** > **Space Admin**). You need to be a space administrator to access the Space Administration screens.

Related Topics

[Space Permissions Overview](#)

Take me back to [Confluence User's Guide](#)

Space Permissions Overview

Every space has its own independent set of permissions. Space permissions can only be granted by a [space administrator](#).

Permissions can be assigned to any [group](#), to any individual user in the **Confluence-User** group, and to users in the **Anonymous** group.

These are the permissions that can be assigned at the space level:

- **View:** user can view this space's content, including the space's details, and its pages and news items (blog posts)
- **Pages:**
 - Add – user may create and edit pages in this space.
 - Restrict – user may apply [page-level restrictions](#).

- Remove – user may remove pages in this space.
- **Blog:**
 - Add – user may add and edit blog posts in this space.
 - Remove – user may remove blog posts in this space.
- **Comments:**
 - Add – user may make comments in this space.
 - Remove – user may remove comments from this space.
- **Attachments:**
 - Add – user may add attachments in this space.
 - Remove – user may remove attachments from this space.
- **Mail:**
 - Remove – user may delete individual mail items.
- **Space:**
 - Export – user may export content from this space via the space-level export screens. Note that this permission does not affect the exporting of a single page's content. Anyone who has permission to view the page also has permission to export its content.
 - Admin – user has administrative permissions over this space.

Related pages:

- [Space Administrators and their Permissions](#)
- [Users and Groups](#)
- [Assigning Space Permissions](#)
- [Page Restrictions](#)
- [Confluence User's Guide](#)

Notes

- **Warning:** If you deny all administrative access to a space by mistake, so that nobody has access to administer the space any more, you will need to ask someone in the [confluence-administrators](#) group to fix the permissions for you.
- The Confluence CLI tool is useful for bulk operations, including adjustments to space permissions. You can download it from the [Atlassian Marketplace](#). The [documentation for the Confluence CLI](#) includes information about the AddPermissions action.

Assigning Space Permissions

You can assign space permissions to groups or to individual users. You need to be a [space administrator](#) to assign space permissions. In addition, [Confluence administrators](#) can set the default permissions that will be applied to new spaces as described [below](#).

To access the permissions for a space:

1. Go to the 'Space Permissions' view:
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the [confluence-administrators](#) group).

- The 'Space Permissions' page appears.

2. Choose **Edit Permissions**.

If your space is using the Documentation theme:

1. Go to the 'Space Permissions' page:
 - Choose **Browse > Space Admin** at the top of the screen.

Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

- Choose **Permissions** from the space administration options.

2. Choose **Edit Permissions**.

The 'Edit Space Permissions' page is divided into the following sections:

- Groups – a list of groups which already have permissions to access the site.
- Individual Users – a list of users who already have permissions to access the site.
- Anonymous Access – the space permissions granted to all anonymous users of the site.

On this page:

- [Assigning space permissions to groups](#)
- [Assigning space permissions to users](#)
- [Assigning space permissions to anonymous users](#)
- [Setting default space permissions](#)
- [Notes](#)

Related pages:

- [Space Permissions Overview](#)
- [Users and Groups](#)
- [Confluence User's Guide](#)

Screenshot : Space permissions

View Space Permissions

Overview
Permissions
Content Tools
Look and Feel

Permissions
Restricted Pages

Groups

These are the permissions currently assigned to groups for this space.

	All	Pages				Blog		Comments		Attachments		Mail	Space	
	View	Add	Restrict	Remove	Add	Remove	Add	Remove	Add	Remove	Remove	Export	Admin	
confluence-administrators	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	
confluence-users	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	

Edit Permissions

Individual Users

These are the permissions currently assigned to individual users for this space.

	All	Pages				Blog		Comments		Attachments		Mail	Space	
	View	Add	Restrict	Remove	Add	Remove	Add	Remove	Add	Remove	Remove	Export	Admin	
Connie Admin (connie)	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	

Edit Permissions

Anonymous Access

When a user is using Confluence while not logged in, they are using it anonymously.
For example: Enabling anonymous 'commenting' permission, allows non-logged-in users to make comments in this space.

	All	Pages				Blog		Comments		Attachments		Mail	Space	
	View	Add	Restrict	Remove	Add	Remove	Add	Remove	Add	Remove	Remove	Export	Admin	
Anonymous	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	

Edit Permissions

Assigning space permissions to groups

- To assign a permission, check the box next to the relevant group.
- To deny a permission, uncheck the relevant box.
- To add a new group to the list, type the group name into the text box in the 'Groups' section and choose **Add**. The group will appear in the list of groups. You can then assign the permissions.
- To search for a group:
 - Choose the  icon.
 - The **Group Search** window opens. Enter all or part of the group name. You can use an asterisk '*' as a wild card.
 - Check the boxes to select the required group(s).
 - Choose **Select Groups**. The group name(s) will appear in the text box in the 'Groups' section.
 - Choose **Add**.
- To bulk assign or revoke group member permissions, choose either **Select All** or **Deselect All** from the **Actions** dropdown list.

Choose **Save All** to apply the changes.

Assigning space permissions to users

- To assign a permission, check the box next to the relevant user.
- To deny a permission, uncheck the relevant box.
- To add a new user to the list, type the username into the text box in the 'Individual Users' section and

choose **Add**. The user will appear in the list of users, with 'View' permission assigned. You can then add more permissions if necessary.

- To search for a user:
 - Choose the  icon.
 - The **User Search** window opens. You can read more about [searching for users](#).
 - Check the boxes to select the required user(s).
 - Choose **Select User(s)**. The username(s) will appear in the text box in the 'Individual Users' section.
 - Choose **Add**.
- To bulk assign or revoke individual user permissions, choose either **Select All** or **Deselect All** from the **Actions** dropdown list.

Choose **Save All** to apply the changes.

Assigning space permissions to anonymous users

- To assign a permission, check the box for the required permission.
- To deny a permission, uncheck the relevant box.
- To bulk assign or revoke anonymous user permissions, choose either **Select All** or **Deselect All** from the **Actions** dropdown list.

Choose **Save All** to apply the changes.

Note: You cannot grant space administration rights or page restriction rights to anonymous users.

Setting default space permissions

If you are a [Confluence Administrator](#), you can set the default permissions that will be applied to new spaces. The default permissions are configurable for groups only, not for individual users or anonymous users.

To set the default space permissions:

1. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
2. Choose **Space Permissions** under Security in the sidebar.
3. Choose **Edit Permissions**.

Screenshot: Default space permissions

Space Permissions

Default Space Permissions

These are the default permissions that will be assigned to groups when someone adds a new space. The 'confluence-administrators' group always has all permissions for all spaces, and any permissions set for it here will be ignored.

	All	Pages			Blog		Comments		Attachments		Mail	Space	
	View	Add	Restrict	Remove	Add	Remove	Add	Remove	Add	Remove	Remove	Export	Admin
confluence-users	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒	☒

[Edit Permissions](#)

Individual Spaces

These are the current wiki spaces.

Name	Key	Operations
Demonstration Space	ds	Manage Permissions
Documentation	DOC	Manage Permissions

Notes

Assigning permissions in bulk. There is no way to change a number of space permissions at once, via the Confluence user interface. Instead, take a look at the [Confluence Command Line Interface](#). Here is a link to the [CLI documentation](#). For an introduction to the CLI, see this blog post: [Confluence CLI for bulk actions like deleting or publishing pages](#).

Users and Groups

A 'user' is the account for an individual who accesses Confluence.

New users are created by a [Confluence administrator](#) via the [Administration Console](#). See [Searching For and Administering Users](#) for more information.

A Confluence administrator can also group users together into user groups for more convenient administration. This means that any permissions you assign at the site, space and page levels can be assigned to a whole group. A user in one of these groups will automatically be granted all permissions granted to the group.

There are two special groups in Confluence:

- **Confluence-Administrators** - This is a 'super-group' and a user from this group has permission to do anything in the site regardless of any other setting.
- **Confluence-Users** - This is the default group into which all new users are assigned. Permissions you assign to this group will be assigned to all newly signed-up users of Confluence.

Anonymous Users

Confluence treats all users who do not log in when they access Confluence as being 'Anonymous'. Administrators can assign permissions to this group separately.

Overlapping group and user permissions

When a user is assigned more than one permission, the most powerful permission will prevail.

Further explanation:

- A user may be assigned a permission specifically to their username. They may also be assigned a permission by belonging to a group, or even several groups.
- The user will then be able to perform all functions assigned to them.
- So if a user is allowed to do something over and above what the group can do, the user will be able to do it. And if the group is allowed to do something over and above the specific permissions granted to the user, the user will still be able to do it.

Related Topics

[Space Permissions Overview](#)

[Assigning Space Permissions](#)

[Page Permissions](#)

[Managing Confluence Users](#)

[Confluence User's Guide](#)


Searching for Users

This page describes how to use the 'User Search' window, which appears when you click **Choose Users** or a user search  icon on a Confluence page.

Accessing the User Search

To access the 'User Search' window:

1. Choose the user search icon when you are performing one of the following actions:
 - When [assigning space permissions](#), choose the **user search** icon in the users section.
 - When [adding members to a group](#), choose the **user search** icon.



2. The simple 'User Search' window will appear, as shown below.

On this page:

- [Accessing the User Search](#)
- [Using the Simple User Search](#)
- [Searching for Users in One or More Groups](#)
- [Selecting One or More Users](#)
- [Notes](#)


Related pages:

- [Searching Confluence](#)
- [Setting a Page's Restrictions](#)
- [Assigning Space Permissions](#)
- [Adding or Removing Users in Groups](#)
- [Confluence User's Guide](#)

Using the Simple User Search**To search via the simple user search:**

1. Select the **User** tab on the 'User Search' screen. (See [above](#) for instructions on accessing the screen.)
2. Enter information about the user in the User Details field, such as all or part of a username, full name or email address.
3. Choose **Search**.
4. Confluence will return a list of matching users. See [below](#) for instructions on selecting one or more users.

Screenshot: Simple user search



Searching for Users in One or More Groups

You can also list the users who appear in a particular group or in a set of groups.

To search for users in a particular group:

1. Select the **Membership** tab on the 'User Search' screen. (See [above](#) for instructions on accessing the screen.)
2. Enter all or part of a group name into the **Group Membership** field.
3. Choose **Search**.
4. Confluence will return a list of users belonging to any groups which match your search term.
 In the example screenshot below, we entered a group name of 'dev'. The search results show all users belonging to the group 'developers' and all users belonging to the group 'developers-mates'.
5. Now you can select one or more users, as described [below](#).

Screenshot: Searching for users in a group

User Search

User

Membership

Group Membership

Enter a group to list all its members

Search

Listing members of **developers, developers-mates**

Check All		User	Full name	Email
☐		ewan	Ewan User	sample@email.com.au
☐		josh	Josh User	sample@email.com.au
☐		leah	Leah Admin	sample@email.com.au

Select User(s)

Selecting One or More Users

After searching for users and receiving a list of names from Confluence, as described above, you can now select the user(s) you need.

To select one or more users:

1. Click the box next to the username(s) to select or deselect one or more users.
You can click **Check All** to select or deselect all users.
2. Click **Select User(s)**.
3. The 'User Search' window will close and the selected users will appear on the screen which you were using before you accessed the user search.

Notes

- **Case sensitivity:** The search is not case sensitive. You can enter either upper- or lower-case text, and it will make no difference to the search results.
- **Wild cards:** The search allows the asterisk as a wild card, but you do not need to use it. The search

results will be the same whether you use a wild card or not. The wildcard functionality remains available for compatibility with older versions of Confluence.

- **Multiple user directories:** You may define multiple user directories in Confluence, so that Confluence looks in more than one place for its users and groups. For example, you may use the default Confluence **internal directory** and also connect to an **LDAP** directory server. In such cases, you can define the **directory order** to determine where Confluence looks first when processing users and groups.

Here is a summary of how the directory order affects the processing:

- The order of the directories is the order in which they will be searched for users and groups.
- Changes to users and groups will be made only in the first directory where the application has permission to make changes.

See [Managing Multiple Directories](#). (Not applicable to Confluence OnDemand.)

- **Crowd and the user search:** If you are using Atlassian's [Crowd](#) for user management, you will need [Crowd 1.5.1 or later](#) to use the 'Simple' option in the user search. If your version of Crowd does not support the simple user search, you will see only the 'Advanced' search form.

Using Confluence on a Mobile Device

When you view a Confluence page on a mobile device, such as an iPhone or an iPad, Confluence will display an optimised version of the page. Confluence chooses the mobile or desktop interface based on your device. See [Supported Platforms](#) for details of supported mobile devices.


On your phone or other supported mobile device, you can:

- View the Confluence dashboard, pages, blog posts, and user profiles.
- Add a comment to a page or blog post.
- Like a page, blog post or comment.
- Manage your personal tasks and notifications.

You cannot add or edit pages or blog posts, or edit existing comments, using the mobile interface.

The dashboard – the first thing you see

Screenshot: *The dashboard in Confluence mobile*



Choose a tab to see:


- Popular content – what people like in your wiki.
- Recent blogs – the latest blog posts.
- Network – updates by people in your network.

Tap the links to view the full content of a page, blog post or comment.

Searching for content and people

Tap the menu icon  to open the menu panel on the left of the page. Then type text or a person's name in the **Search** box. The mobile interface offers the quick navigation search, which returns matches on page title only. (See [Searching Confluence](#).) To use the full search, switch to desktop mode.

Screenshot: The menu panel in Confluence mobile




Viewing pages, blog posts and comments

Tap a link on the dashboard or on any other page. Confluence will display the linked page, blog post or comment.

You can:

- View the content, tap a link to move to another page, and interact with the page using the standard functionality supported by mobile browsers.
- Like or unlike a page, blog post or comment.
- Add a comment. Confluence mobile supports plain-text comments only.


Screenshot: A page with a 'Like' button and a comment box



Viewing people's profiles

Search for a person's name, then view that person's user profile. Tap the options to phone, SMS or email a colleague directly from your mobile device.


Screenshot: A user profile on Confluence mobile



Following up on notifications

You can view and respond to your notifications on your phone or other mobile device. Tap the menu icon  to open the menu panel on the left of the page. Choose **Notifications**, and tap a notification to see its details. You can reply, watch or like via the inline actions. Tap **Open** to open the page or blog post in a new page. For full details, see [Managing Notifications in Confluence](#).


Screenshot: Notifications in Confluence mobile



Managing tasks

You can view and manage your tasks on your phone or other mobile device too. Tap the menu icon  to open the menu panel on the left of the page. Choose **Tasks**, and tap the plus sign  to add a new task. Tap a task to see its details. You can add notes, complete a task, and tap a link to open the related page. For full details, see [Managing Tasks in Confluence](#).

Screenshot: Tasks in Confluence mobile



More things you may need to know

See [Notes about Confluence Mobile](#).

Related pages

- [Dashboard](#)
- [Managing Notifications in Confluence](#)
- [Managing Tasks in Confluence](#)
- [Confluence User's Guide](#)

Notes about Confluence Mobile

When you view a Confluence page on a mobile device, such as an iPhone or an iPad, Confluence will display an optimised version of the page. Confluence chooses the mobile or desktop interface based on your device. See [Supported Platforms](#) for details of supported mobile devices.

For a summary of mobile features, see [Using Confluence on a Mobile Device](#). Below are additional notes that you will find useful.

On this page:

- [Some macros may not work](#)
- [You can swap from mobile to standard Confluence and back again](#)
- [Administrators can disable Confluence mobile on your site](#)
- [Confluence mobile is a web interface, not a native app](#)
- [Request for Android support](#)
- [Related pages](#)

Some macros may not work

Confluence macros are not yet fully supported in Confluence mobile. If you view a page that contains an unsupported macro, you will see a message inviting you to click through to the desktop version of the page.


Screenshot: Macro not rendered in Confluence mobile



You can swap from mobile to standard Confluence and back again


You can swap from the mobile view to the standard view of a page at any time. Choose the menu icon  then choose **Switch to desktop version**.

Screenshot: The menu panel in Confluence mobile



You can also swap from the desktop view to the mobile view, if you are on a mobile device. Choose the option **Switch to Confluence Mobile** at the top of the window.

Screenshot: Option to switch to Confluence mobile



Administrators can disable Confluence mobile on your site

The mobile functionality is provided by a plugin called the 'Confluence Mobile Plugin'. To remove the functionality from your site, you can disable the plugin.

Confluence mobile is a web interface, not a native app

Atlassian does not supply a native mobile application that you can download and install onto your mobile device. Confluence mobile is a web-based user interface that the Confluence server displays when it detects a mobile client.

Request for Android support

You can watch this ticket to be informed when support for Android devices is added:

 [CONF-25529](#) - [Authenticate](#) to see issue details

Related pages

- [Using Confluence on a Mobile Device](#)
- [Dashboard](#)
- [Confluence User's Guide](#)

Advanced and Special Uses of Confluence

This section describes the more advanced features of Confluence, and gives guidelines on some specific uses of the wiki.

Confluence markup formats

The syntax and usage of Confluence wiki markup and the Confluence XHTML-based storage format – see [Working with Confluence Markup](#).

Gadgets

How to add gadgets to a wiki page, or use Confluence gadgets on other sites – see [Working with Confluence Gadgets](#).

Using Confluence for technical documentation

A technical communicator's guide to using Confluence – see [Developing Technical Documentation on Confluence Wiki](#).

Setting up a knowledge base

A support engineer's guide to using Confluence as a knowledge base – see [Developing a Knowledge Base on Confluence Wiki](#).

Setting up an intranet

A quick guide to setting up an intranet wiki – see [Developing an Intranet on Confluence Wiki](#).

Related pages:

- [Confluence User's Guide](#)
- [Confluence Administrator's Guide](#)

Working with Confluence Markup

This section describes two types of markup found in Confluence:

- **Confluence storage format.** Confluence stores the content of pages and blog posts in an XHTML-based format. Advanced users can view the storage format of a page and even edit it, provided their Confluence site is configured to allow that. See [Confluence Storage Format](#) for a description of the core elements of the storage format. For details of the elements used to define a macro, see [Confluence Storage Format for Macros](#).
- **Wiki markup.** Confluence allows data entry via a shorthand code called wiki markup. Some parts of the Confluence administration interface also accept wiki markup for defining content. For a description of the wiki markup syntax, see [Confluence Wiki Markup](#). For details of the wiki markup used to define Confluence macros, see [Confluence Wiki Markup for Macros](#).

Related pages:

- [Working with Macros](#)
- [Managing Add-ons and Macros](#) (*Not applicable to Confluence OnDemand.*)
- [Confluence User's Guide](#)

A request from the Atlassian technical writers about comments and feedback: When adding comments to this page, please restrict your comments to constructive feedback on the documentation itself: Things we've missed in the documentation, and things that will be useful to other readers. If you have other feedback about the editor, wiki markup, the XML storage format, and Confluence 4 in general, please add your comments in the section titled [Confluence 4 Editor - Customer Feedback](#), and its child pages. Our reason for this request: When a page attracts a large number of comments, it makes it difficult for everyone to read the page, and to add or respond to comments about the documentation. Thanks. 😊

Confluence Storage Format

This page describes the XHTML-based format that Confluence uses to store the content of pages, page templates, blog posts and comments. This information is intended for advanced users who need to interpret and edit the underlying markup of a Confluence page.

We refer to the Confluence storage format as 'XHTML-based'. To be correct, we should call it XML, because the Confluence storage format does not comply with the XHTML definition. In particular, Confluence includes custom elements for macros and more. We're using the term 'XHTML-based' to indicate that there is a large

proportion of HTML in the storage format.

Notes:

- You can view the Confluence storage format for a given page by choosing **Tools > View Storage Format**. This option is only available if one of the following is true:
 - You are a Confluence administrator.
 - Your Confluence site has the [Confluence Source Editor](#) plugin installed and you have permission to use the source editor.
- If you would like to edit the storage format for a page, your Confluence system administrator will need to install the [Confluence Source Editor](#) plugin.
- Clarification of terminology: If you choose **Tools > View Source**, you will see the format used within the editor panel, not the storage format of the page.
- A request from the Atlassian technical writers about comments and feedback:** When adding comments to this page, please restrict your comments to constructive feedback on the documentation itself: Things we've missed in the documentation, and things that will be useful to other readers. If you have other feedback about the editor, wiki markup, the XML storage format, and Confluence 4 in general, please add your comments in the section titled [Confluence 4 Editor - Customer Feedback](#), and its child pages. Our reason for this request: When a page attracts a large number of comments, it makes it difficult for everyone to read the page, and to add or respond to comments about the documentation. Thanks. 😊

On this page:

- [Macros](#)
- [Headings](#)
- [Text effects](#)
- [Text breaks](#)
- [Lists](#)
- [Links](#)
- [Images](#)
- [Tables](#)
- [Page layouts](#)
- [Emoticons](#)
- [Resource identifiers](#)
- [Template variables](#)

Related pages:

- [Confluence Storage Format for Macros](#)
- [Feedback on Confluence Storage Format](#) (*Not applicable to Confluence OnDemand.*)
- [Working with Confluence Markup](#)

Macros

See [Confluence Storage Format for Macros](#).

Headings

Format type	In Confluence 3.5 and earlier	In Confluence 4.0 and later	What you will get	
Heading 1	h1. Heading 1	<pre><h1>Heading 1</h1></pre>	Heading 1	Underlined in the Documentation Theme

Heading 2	h2. Heading 2	<code><h2>Heading 2</h2></code>	Heading 2	Underlined in the Documentation Theme
Heading 3	h3. Heading 3	<code><h3>Heading 3</h3></code>	Heading 3	
Headings 4 to 6 are also available and follow the same pattern				

Text effects

Format type	In Confluence 3.5 and earlier	In Confluence 4.0 and later	What you will get	
strong/bold	<code>*strong*</code>	<code>strong text</code>	strong	<code></code> will also work but get converted to <code></code> upon saving
emphasis	<code>_emphasis_</code>	<code>Italics Text</code>	<i>emphasis</i>	<code><i></code> will also work but get converted to <code></code> upon saving

strikethrough	-strikethrough-	<pre>strikethrough</pre>	~~strikethrough~~	<s> and <del> will also work
underline	+underline+	<pre><u>underline</u></pre>	<u>underline</u>	
superscript	^superscript^	<pre><sup>superscript</sup></pre>	^{superscript}	
subscript	~subscript~	<pre><sub>subscript</sub></pre>	_{subscript}	
monospace	{{monospaced}}	<pre><code>monospaced</code></pre>	monospaced	

preformatted	n/a	<pre><pre>pre formatted text </pre></pre>	preformatted text	
block quotes	bq. block quote or {quote} block quote {quote}	<pre><blockquote> <p>block quote</p> </blockquote></pre>	<i>block quote</i>	
text colour	{color:red} red text{color}	<pre>red text</pre>	red text	
small	n/a	<pre><small>small text</small></pre>	small text	

big	n/a	<pre><big>big text</big></pre>	big text	
center-align	n/a	<pre><p style="text-align: center;">centered text</p></pre>	centered text	
right-align	n/a	<pre><p style="text-align: right;">right aligned text</p></pre>	right aligned text	

Text breaks

Format type	In Confluence 3.5 and earlier	In Confluence 4.0 and later	What you will get
New paragraph	Paragraph 1 (empty line) Paragraph 2	<pre><p>Paragraph 1</p><p>Paragraph 2</p></pre>	Paragraph 1 Paragraph 2

Line break	Line 1 \\ Line 2	Line 1
 Line 2 Note: Created in the editor using Shift + Return/Enter	Line 1 Line 2
Horizontal rule	----	<hr />	
— symbol	---	&mdash;	—
– symbol	--	&ndash;	–

Lists

Format type	In Confluence 3.5 and earlier	In Confluence 4.0 and later	What you will get
Unordered list – round bullets	* Round bullet list item	round bullet list item	Round bullet list item
Unordered list – square bullets	- Square bullet list item	square bullet list item	Square bullet list item
Ordered list (numbered list)	# Ordered list item	numbered list item	Ordered list item

Links

Format type	In Confluence 3.5 and earlier	In Confluence 4.0 and later	What you will get
Link to another Confluence page	[Link to another Confluence page Page Title]	<pre><ac:link> <ri:page ri:content-t itle="Page Title" /> <ac:plain-te xt-link-body > <![CDATA[Li nk to another Confluence Page]]> </ac:plain-t ext-link-bod y> </ac:link></pre>	Link to another Confluence page
Link to an attachment	[Link to an attachment^atlassian_logo.gif]	<pre><ac:link> <ri:attachme nt ri:filename= "atlassian_l ogo.gif" /> <ac:plain-te xt-link-body > <![CDATA[Li nk to a Confluence Attachment]] > </ac:plain-t ext-link-bod y> </ac:link></pre>	Link to an attachment
Link to an external site	[Atlassian http://www.atlassian.com/]	<pre>Atla ssian</pre>	Atlassian

Anchor link (same page)	[Anchor Link #anchor]	<pre> <ac:link ac:anchor="a nchor"> <ac:plain-te xt-link-body > <![CDATA[Anc hor Link]]> </ac:plain-t ext-link-bod y> </ac:link> </pre>	Anchor Link
Anchor link (another page)	[Anchor Link pagetitle#anchor]	<pre> <ac:link ac:anchor="a nchor"> <ri:page ri:content-t itle="pageti tle"/> <ac:plain-te xt-link-body > <![CDATA[Anc hor Link]]> </ac:plain-t ext-link-bod y> </ac:link> </pre>	Anchor Link

Link with an embedded image for the body	[!google.png! pagetitle#anchor]	<pre> <ac:link ac:anchor="Anchor Link"> <ac:link-body> <ac:image>< ri:url ri:value="http://confluence.atlassian.com/images/logo/confluence_48_trans.png" /></ac:image> </ac:link-body> </ac:link> </pre>  For rich content like <i>images</i>, you need to use ac:link-body to wrap the contents.	

A note about link bodies

All links received from the editor will be stored as plain text by default, unless they are detected to contain the limited set of mark up that we allow in link bodies. Here are some examples of markup we support in link bodies.

An example of different link bodies

```

<ac:link>
  <!-- Any resource identifier -->
  <ri:page ri:content-title="Home" ri:space-key="SANDBOX" />
  <ac:link-body>Some <strong>Rich</strong> Text</ac:link-body>
</ac:link>
<ac:link>
  <ri:page ri:content-title="Plugin developer tutorial stuff"
ri:space-key="TECHWRITING" />
  <ac:plain-text-link-body><![CDATA[A plain <text> link
body]]></ac:plain-text-link-body>
</ac:link>
<ac:link>
  <ri:page ri:content-title="Plugin developer tutorial stuff"
ri:space-key="TECHWRITING" />
  <!-- A link body isn't necessary. Auto-generated from the resource identifier for
display. -->
</ac:link>

```

The markup tags permitted within the `<ac:link-body>` are `<b>`, `<strong>`, `<em>`, `<i>`, `<code>`, `<tt>`, `<sub>`, `<sup>`, `<br>` and `<span>`.

Images

Format type	In Confluence 3.5 and earlier	In Confluence 4.0 and later	What you will get
Attached image	<code>!atlassian_logo.gif!</code>	<pre><ac:image> <ri:attachment ri:filename="atlassian_logo.gif" /> </ac:image></pre>	
External image	<code>!http://confluence.atlassian.com/images/logo/confluence_48_trans.png!</code>	<pre><ac:image> <ri:url ri:value="http://confluence.atlassian.com/images/logo/confluence_48_trans.png" /> </ac:image></pre>	

Supported image attributes (some of these attributes mirror the equivalent HTML 4 IMG element):

Name	Description
<code>ac:align</code>	image alignment
<code>ac:border</code>	Set to "true" to set a border
<code>ac:class</code>	css class attribute.
<code>ac:title</code>	image tool tip.
<code>ac:style</code>	css style
<code>ac:thumbnail</code>	Set to "true" to designate this image as a thumbnail.
<code>ac:alt</code>	alt text

ac:height	image height
ac:width	image width
ac:vspace	the white space on the top and bottom of an image
ac:hspace	the white space on the left and right of an image

Tables

Format type	In Confluence 3.5 and earlier	In Confluence 4.0 and later	What you will get					
Two column, two row (top header row)	<pre> Table Heading Cell 1 Table Heading Cell 2 Normal Cell 1 Normal Cell 2 </pre>	<pre><table> <tbody> <tr> <th>Tab le Heading Cell 1</th> <th>Tab le Heading Cell 2</th> </tr> <tr> <td>Nor mal Cell 1</td> <td>Nor mal Cell 2</td> </tr> </tbody> </table></pre>	<table><tr><th>Table Headi ng Cell 1</th><th>Table Headi ng Cell 2</th></tr><tr><td>Normal Cell 1</td><td>Normal Cell 2</td></tr></table>	Table Headi ng Cell 1	Table Headi ng Cell 2	Normal Cell 1	Normal Cell 2	
Table Headi ng Cell 1	Table Headi ng Cell 2							
Normal Cell 1	Normal Cell 2							

Two column, three rows, 2nd and third with merged cells in first row	N/A	<pre><table> <tbody> <tr> <th>Tab le Heading Cell 1</th> <th>Tab le Heading Cell 2</th> </tr> <tr> <td rowspan ="2">Me rged Cell</td> <td>Nor mal Cell 1</td> </tr> <tr> <td colspan ="1">No rma l Cell 2</td> </tr> </tbody> > </table> ></pre>	<table><tr><th>Table Head ing Cell 1</th><th>Table Head ing Cell 2</th></tr><tr><td rowspan="2">Merge d Cell</td><td>Normal Cell 1</td></tr><tr><td>Normal Cell 2</td></tr></table>	Table Head ing Cell 1	Table Head ing Cell 2	Merge d Cell	Normal Cell 1	Normal Cell 2
Table Head ing Cell 1	Table Head ing Cell 2							
Merge d Cell	Normal Cell 1							
	Normal Cell 2							

Page layouts

Confluence supports [page layouts](#) directly, as an alternative to macro-based layouts such as those using the [section and column](#) macros. This section documents the storage format XML created when these layouts are used in a page.

Notes:

- Page layouts were introduced in Confluence 4.2, and are not available in earlier versions of Confluence.
- The word {content} in the layouts below indicates where further XHTML or Confluence storage format block content would be entered, such as <p> or <table> tags.

Layout Type	In Confluence 4.2 and later



Two columns

```
<div class="contentLayout"
data-atlassian-layout="{&quot;name&
quot;:&quot;pagelayout-two-simple&q
uot;,&quot;columns&quot;:[&quot;&qu
ot;,&quot;&quot;]}">
  <div class="columnLayout
twoColumns">
    <div class="cell ">
      <div class="innerCell">
        {content}
      </div>
    </div>
    <div class="cell ">
      <div class="innerCell">
        {content}
      </div>
    </div>
  </div>
</div>
```



Left sidebar

```
<div class="contentLayout"
data-atlassian-layout="{&quot;name&
quot;:&quot;pagelayout-two-simple-l
eft&quot;,&quot;columns&quot;:[&quo
t;,&quot;large&quot;]}">
  <div class="columnLayout
twoColumns">
    <div class="cell aside">
      <div class="innerCell">
        {content}
      </div>
    </div>
    <div class="cell large">
      <div class="innerCell">
        {content}
      </div>
    </div>
  </div>
</div>
```



Right sidebar

```
<div class="contentLayout"
data-atlassian-layout="{&quot;name&
quot;:&quot;pagelayout-two-simple-r
ight&quot;,&quot;columns&quot;:[&qu
ot;large&quot;,&quot;aside&quot;]}"
>
  <div class="columnLayout
twoColumns">
    <div class="cell large">
      <div class="innerCell">
        {content}
      </div>
    </div>
    <div class="cell aside">
      <div class="innerCell">
        {content}
      </div>
    </div>
  </div>
</div>
```



Three columns

```
<div class="contentLayout"
data-atlassian-layout="{&quot;name&
quot;:&quot;pagelayout-three-simple
&quot;,&quot;columns&quot;:[&quot;&
quot;,&quot;&quot;,&quot;&quot;]}"
>
  <div class="columnLayout
threeColumns">
    <div class="cell ">
      <div class="innerCell">
        {content}
      </div>
    </div>
    <div class="cell ">
      <div class="innerCell">
        {content}
      </div>
    </div>
    <div class="cell">
      <div class="innerCell">
        {content}
      </div>
    </div>
  </div>
</div>
```



Two columns with header and footer

```
<div class="contentLayout"
data-atlassian-layout="{&quot;name&
quot;:&quot;pagelayout-two&quot;,&q
uot;columns&quot;:[&quot;&quot;,&qu
ot;&quot;],&quot;header&quot;:true,
&quot;footer&quot;:true}">
  <div class="header">
    <div class="innerCell">
      {content}
    </div>
  </div>
  <div class="columnLayout
twoColumns">
    <div class="cell ">
      <div class="innerCell">
        {content}
      </div>
    </div>
    <div class="cell ">
      <div class="innerCell">
        {content}
      </div>
    </div>
  </div>
  <div class="footer">
    <div class="innerCell">
      {content}
    </div>
  </div>
</div>
```



Left sidebar with header and footer

```
<div class="contentLayout"
data-atlassian-layout="{&quot;name&
quot;:&quot;pagelayout-two-left&quo
t;,&quot;columns&quot;:[&quot;aside
&quot;,&quot;large&quot;],&quot;hea
der&quot;:true,&quot;footer&quot;:t
rue}">
  <div class="header">
    <div class="innerCell">
      {content}
    </div>
  </div>
  <div class="columnLayout
twoColumns">
    <div class="cell aside">
      <div class="innerCell">
        {content}
      </div>
    </div>
    <div class="cell large">
      <div class="innerCell">
        {content}
      </div>
    </div>
  </div>
  <div class="footer">
    <div class="innerCell">
      {content}
    </div>
  </div>
</div>
```



Right sidebar with header and footer

```
<div class="contentLayout"
data-atlassian-layout="{&quot;name&
quot;:&quot;pagelayout-two-right&qu
ot;,&quot;columns&quot;:[&quot;larg
e&quot;,&quot;aside&quot;],&quot;he
ader&quot;:true,&quot;footer&quot;:
true}">
  <div class="header">
    <div class="innerCell">
      {content}
    </div>
  </div>
  <div class="columnLayout
twoColumns">
    <div class="cell large">
      <div class="innerCell">
        {content}
      </div>
    </div>
    <div class="cell aside">
      <div class="innerCell">
        {content}
      </div>
    </div>
  </div>
  <div class="footer">
    <div class="innerCell">
      {content}
    </div>
  </div>
</div>
```



Three columns with header and footer

```

<div class="contentLayout"
data-atlassian-layout="{&quot;name&
quot;:&quot;pagelayout-three&quot;;,
&quot;columns&quot;:[&quot;&quot;;,&
quot;&quot;;,&quot;&quot;],&quot;hea
der&quot;:true,&quot;footer&quot;:t
rue}">
  <div class="header">
    <div class="innerCell">
      {content}
    </div>
  </div>
  <div class="columnLayout
threeColumns">
    <div class="cell ">
      <div class="innerCell">
        {content}
      </div>
    </div>
    <div class="cell ">
      <div class="innerCell">
        {content}
      </div>
    </div>
    <div class="cell">
      <div class="innerCell">
        {content}
      </div>
    </div>
  </div>
  <div class="footer">
    <div class="innerCell">
      {content}
    </div>
  </div>
</div>

```



Left and right sidebar with header and footer

```
<div class="contentLayout"
data-atlassian-layout="{&quot;name&
quot;:&quot;pagelayout-three-sideba
rs&quot;,&quot;columns&quot;:[&quot;
;sidebars&quot;,&quot;large&quot;,&
quot;sidebars&quot;],&quot;header&
uot;:true,&quot;footer&quot;:true}"
>
  <div class="header">
    <div class="innerCell">
      {content}
    </div>
  </div>
  <div class="columnLayout
threeColumns">
    <div class="cell sidebars">
      <div class="innerCell">
        {content}
      </div>
    </div>
    <div class="cell large">
      <div class="innerCell">
        {content}
      </div>
    </div>
    <div class="cell sidebars">
      <div class="innerCell">
        {content}
      </div>
    </div>
  </div>
  <div class="footer">
    <div class="innerCell">
      {content}
    </div>
  </div>
</div>
```

Emoticons

Format type	In Confluence 3.5 and earlier	In Confluence 4.0 and later	What you will get
Emoticons	:)	<pre><ac:emoticon ac:name="smi le" /></pre>	
	:(	<pre><ac:emoticon ac:name="sad " /></pre>	

	:P	<code><ac:emoticon ac:name="che eky" /></code>	
	:D	<code><ac:emoticon ac:name="lau gh" /></code>	
	:)	<code><ac:emoticon ac:name="win k" /></code>	
	(y)	<code><ac:emoticon ac:name="thu mbs-up" /></code>	
	(n)	<code><ac:emoticon ac:name="thu mbs-down" /></code>	
	(i)	<code><ac:emoticon ac:name="inf ormation" /></code>	
	(/)	<code><ac:emoticon ac:name="tic k" /></code>	
	(x)	<code><ac:emoticon ac:name="cro ss" /></code>	
	(!)	<code><ac:emoticon ac:name="war ning" /></code>	

Resource identifiers

Resource identifiers are used to describe "links" or "references" to resources in the storage format. Examples of resources include pages, blog posts, comments, shortcuts, images and so forth.

Resource	Resource identifier format
Page	<pre><ri:page ri:space-key="F00" ri:content-title="Test Page"/></pre> Notes: • <code>ri:space-key</code>: (optional) denotes the space key. This can be omitted to create a relative reference. • <code>ri:content-title</code>: (required) denotes the title of the page.
Blog Post	<pre><ri:blog-post ri:space-key="F00" ri:content-title="First Post" ri:posting-day="2012/01/30" /></pre> Notes: • <code>ri:space-key</code>: (optional) denotes the space key. This can be omitted to create a relative reference. • <code>ri:content-title</code>: (required) denotes the title of the page. • <code>ri:posting-day</code>: (required) denotes the posting day. The format is YYYY/MM/DD.

Attachment	<pre data-bbox="853 163 1409 331"><ri:attachment ri:filename> ... resource identifier for the container of the attachment ... </ri:attachment></pre> Notes: • <code>ri:filename</code>: (required) denotes the name of the attachment. • the body of the <code>ri:attachment</code> element should be a resource identifier denoting the container of the attachment. This can be omitted to create a relative attachment reference (similar to <code>[foo.png]</code> in wiki markup). Examples: Relative Attachment Reference <pre data-bbox="874 864 1252 925"><ri:attachment ri:filename="happy.gif" /></pre> Absolute Attachment Reference <pre data-bbox="874 1095 1311 1245"><ri:attachment ri:filename="happy.gif"> <ri:page ri:space-key="TST" ri:content-title="Test Page"/> </ri:attachment></pre>
URL	<pre data-bbox="853 1357 1409 1496"><ri:url ri:value="http://example.org/sample.gif"/></pre> Notes: • <code>ri:value</code>: (required) denotes the actual URL value.

Shortcut	<pre><ri:shortcut ri:key="jira" ri:parameter="ABC-123"></pre> Notes: • <code>ri:key</code>: (required) represents the key of the Confluence shortcut. • <code>ri:parameter</code>: (required) represents the parameter to pass into the Confluence shortcut. • The example above is equivalent to <code>[ABC-123@jira]</code> in wiki markup.
User	<pre><ri:user ri:username="fred"/></pre> Notes: • <code>ri:username</code>: (required) denotes the name of the user.
Space	<pre><ri:space ri:space-key="TST"/></pre> Notes: • <code>ri:space-key</code>: (required) denotes the key of the space.
Content Entity	<pre><ri:content-entity ri:content-id="123"/></pre> Notes: • <code>ri:content-id</code>: (required) denotes the id of the content.

Template variables

This screenshot shows a simple template:

Dashboard › Chocolate › Browse Space › Edit Template

Sarah template

Paragraph **B** *I* U A ^A   

This is Sarah's template

A single-line text variable: **\$MyText**

A multi-line text variable: **\$MyMulti**

A selection list: **\$MyList**

End of page.

The template contains the following variables:

Variable name	Type	Values
\$MyText	Single-line text	
\$MyMulti	Multi-line text	Size: 5 x 100
\$MyList	List	List items: Apples, Pears, Peaches

The XML export produces the following code for the template:

```
<at:declarations>
  <at:string at:name="MyText" />
  <at:textarea at:columns="100" at:name="MyMulti" at:rows="5" />
  <at:list at:name="MyList">
    <at:option at:value="Apples" />
    <at:option at:value="Pears" />
    <at:option at:value="Peaches" />
  </at:list>
</at:declarations>

<p>This is Sarah's template</p>
<p>A single-line text variable:&nbsp;<at:var at:name="MyText" /></p>
<p>A multi-line text variable:&nbsp;<at:var at:name="MyMulti" /></p>
<p>A selection list:&nbsp;<at:var at:name="MyList" /></p>
<p>End of page.</p>
```

Confluence Storage Format for Macros



Work in progress

We are adding the details for each macro in turn. They are not all here yet. See

 **CONF-24972** - [Authenticate](#) to see issue details .

This page is an extension of the page about the [Confluence storage format](#). This page describes the XML used to define specific Confluence macros – those that are shipped with Confluence. For each macro, we define the macro name, parameter names, and accepted parameter values.

This information is intended for advanced users who need to interpret and edit the underlying markup for a Confluence page.

Anchor macro

Allows you to link to a specific part of a page.

Macro name: anchor

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
default-parameter (Unnamed in wiki markup)	Yes	(None)	The name of the anchor.

Example:

```
<ac:macro ac:name="anchor">
  <ac:default-parameter>here</ac:default-parameter>
</ac:macro>
```

On this page:

- [Anchor macro](#)
- [Attachments macro](#)
- [Blog Posts macro](#)
- [Change-History macro](#)
- [Chart macro](#)
- [Cheese macro](#)
- [Children Display macro](#)
- [Code Block macro](#)
- [Column macro](#)
- [Content by Label macro](#)
- [Content by User macro](#)
- [Content Report Table macro](#)
- [Contributors macro](#)
- [Contributors Summary macro](#)
- [Create Space Button macro](#)
- [Excerpt Include macro](#)
- [Excerpt macro](#)
- [Expand macro](#)
- [Favourite Pages macro](#)
- [Gadget macro](#)
- [Gallery macro](#)
- [Global Reports macro](#)
- [HTML Include macro](#)
- [HTML macro](#)
- [IM Presence macro](#)
- [Include Page macro](#)
- [Info macro](#)
- [JIRA Issues macro](#)
- [JUnit Report macro](#)
- [Labels List macro](#)
- [Livesearch macro](#)
- [Loremipsum macro](#)
- [Multimedia macro](#)
- [Page Properties macro](#)
- [Page Properties Report macro](#)
- [Section macro](#)
- [Table of Contents macro](#)
- [Macro format notes](#)
 - [Macro bodies](#)
 - [Plain text bodies](#)
- [Other notes](#)

Related pages:

- [Confluence Storage Format](#)
- [Working with Confluence Markup](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Attachments macro

Displays a list of attachments on a given page.

Macro name: attachments

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
old	No	false	Available values: • false - Displays only the latest version of each attachment. • true – Displays all versions of each attachment, including the old versions.
patterns	No	(None)	A comma-separated list of regular expressions, used to filter the attachments by file name. Note that the parameter values must be regular expressions. For example: • To match a file suffix of 'jpg', use <code>*.jpg</code> (not <code>*.jpg</code>). • To match file names ending in 'jpg' or 'png', use <code>*.jpg,*.png</code> Here is a tutorial on regular expressions .
sortBy	No	date	Available values: • date • size • name
page	No	The page on which the macro exists.	Page name, used to display attachments from another page.

sortOrder	No	The default sort order is determined by the sortBy type: • Reverse chronological for 'date'. • Largest to smallest for 'size'. • Alphabetical for 'name'.	Available values: • ascending • descending
labels	No	(None)	A comma-separated list of labels. Confluence will show only attachments that have all the labels specified. (The match is an AND, not an OR.)
upload	No	false	Determines whether the list of attachments will include options allowing users to browse for, and attach, new files.

Example:

```
<ac:macro ac:name="attachments">
  <ac:parameter ac:name="old">false</ac:parameter>
  <ac:parameter ac:name="patterns">.*png, .*jpg</ac:parameter>
  <ac:parameter ac:name="sortBy">name</ac:parameter>
  <ac:parameter ac:name="page">My page about chocolate</ac:parameter>
  <ac:parameter ac:name="sortOrder">descending</ac:parameter>
  <ac:parameter ac:name="labels">chocolate,cookies</ac:parameter>
  <ac:parameter ac:name="upload">>false</ac:parameter>
</ac:macro>
```

Blog Posts macro

Lists the most recent news items in the space.

Macro name: blog-posts

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values

content	No	entire	Available values: • <code>entire</code> – Display the whole content of each blog post. • <code>excerpts</code> – Display a short extract from each blog post. If the post contains an Excerpt macro, the Blog Posts macro will display the content defined in the Excerpt macro. If the post does not contain an Excerpt macro, the Blog Posts macro will display the first few sentences of the post. • <code>titles</code> – Display a list of blog posts, showing titles only.
spaces	No	@self	One or more space keys, separated by a comma or a space.

- To exclude content in a specific space, put a minus sign (-) immediately in front of that space key. For example: If you specify a space key of -BADSPACE you will get only content which is not in the BADSPACE.
- To indicate that the results **must** come from a specific space, put a plus sign (+) immediately in front of that space key. For example: If you specify a space key of +GOODSPACE you will get only content in GOODSPACE. (Note that this is not particularly useful, because each content item belongs to one space only. If you put a plus sign next to one space key and list other space keys too, the other space keys will be ignored.)

Special values:

- @self — The current space.
- @personal — All [personal](#) spaces.
- @global — All [site](#) spaces.
- @favorite — The spaces you have marked as [favourite](#).
- @favourite — The same as @favorite above.
- @all — All spaces in your Confluence site.
- * — The same as @all above.

			When specifying a personal space, remember to use the tilde (~) sign in front of the username, such as ~jbl oggs or ~jbloggs@example.com.
author	No	(None)	One or more usernames, separated by commas.
time	No	(None)	Available values: • m — Minutes • h — Hours • d — Days • w — Weeks For example, • time=12h – Display blog posts created in the last twelve hours. • time=7d – Display blog posts created in the last seven days.
reverse	No	false	A value of true changes the sort order.
sort	No	creation	Available values: • title — Sort alphabetically by title. • creation — Sort by the date on which the content was added. • modified — Sort by the date on which the content was last updated.
max	No	15	The maximum number of results to be displayed.

label	No	(None)	One or more label values, separated by a comma or a space. - To exclude content which matches a given label, put a minus sign (-) immediately in front of that label value. For example: If you specify a label value of -badpage you will get only content which is not labelled with 'badpage'. - To indicate that the results must match a given label value, put a plus sign (+) immediately in front of that label value. For example: If you specify a label value of +superpage, +goodpage you will get only content which has at least two labels, being 'superpage' and 'goodpage'.

Example:

```
<ac:macro ac:name="blog-posts">
  <ac:parameter ac:name="content">titles</ac:parameter>
  <ac:parameter ac:name="spaces">@self,ds</ac:parameter>
  <ac:parameter ac:name="author">jsmith</ac:parameter>
  <ac:parameter ac:name="time">4w</ac:parameter>
  <ac:parameter ac:name="reverse">>true</ac:parameter>
  <ac:parameter ac:name="sort">creation</ac:parameter>
  <ac:parameter ac:name="max">10</ac:parameter>
  <ac:parameter ac:name="label">chocolate,cookies</ac:parameter>
</ac:macro>
```

Change-History macro

Displays a history of updates made to a page.

Macro name: change-history

Macro body: None.

Parameters: None

Example:

```
<ac:macro ac:name="change-history"/>
```

Chart macro

Displays a chart based on tabular data.

Macro name: chart

Macro body: Accepts rich text, consisting of tables that hold the chart's data.

This macro recognises a large number of parameters, listed here by type for convenience.

Chart type parameters

These parameters determine the type of chart to display and how the chart looks.

Parameter	Required	Default	Description
type	No	pie	The type of chart to display. XY charts have numerical x- and y-axes. The x values may optionally be time-based. See the <code>timeSeries</code> parameter. Available values: <i>Standard charts</i> - pie, bar, line, area <i>XY plots</i> – xyArea, xyBar, xyLine, xyStep, xyStepArea, scatter, timeSeries <i>Other charts</i> – gantt (beta)
orientation	No	vertical	The display orientation. Applies to area, bar and line charts. Available values: <code>vertical</code> – y-axis is vertical <code>horizontal</code> – x-axis is vertical

3D	No	false	Show in three dimensions. Applies to area, bar and line charts.
stacked	No	false	Stacked values. Applies to area and bar charts.
showShapes	No	true	Applies to line charts. Shapes are shown at each data point.
opacity	No	75 percent for 3D charts 50 percent for non-stacked area charts 100 percent for all other charts	A percentage value between 0 (transparent) and 100 (opaque) that determines how opaque the foreground areas and bars are.

Chart display parameters

Parameter	Required	Default	Description
width	No	300	The width of the chart in pixels.
height	No	300	The height of the chart in pixels.
dataDisplay	No	false	Determines whether to display the body of the macro, consisting of the data table. By default, the chart data table is not displayed. Available values: - false – the data is not displayed. - true or after – the data is displayed after the chart. - before – the data is displayed before the chart.
imageFormat	No	png	The image format to be used for the chart. Available values: - png - jpg

Chart title and label parameters

Parameter	Required	Default	Description
title	No	(None)	The title of the chart.
subTitle	No	(None)	A subtitle for the chart.
xLabel	No	(None)	The label for the x-axis (domain).
yLabel	No	(None)	The label for the y-axis (range).
legend	No	false	Determines whether to show a legend (key) for the chart.

Chart data parameters

The data for the chart is taken from tables found in the macro body. The parameters below control how this data is interpreted. By default, numeric and date values are interpreted according to the Confluence global default language (locale) formats. If conversion fails, other languages defined in Confluence will be tried. You can specify additional conversion options using the parameters below.

Parameter	Required	Default	Description
tables	No	All first level tables	You can supply a comma-separated list of table IDs and/or table numbers (starting at 1) contained within the body of the macro that will be used as the data for the chart. If data tables are embedded in other tables, then table selection will be required. This occurs when more complex formatting is done (for example using section and column macros).

columns	No	All columns	You can supply a comma-separated list of column labels and/or column titles and/or column numbers for tables used for chart data. This applies to all tables processed. Columns are enumerated starting at 1. Column label is the text for the column in the header row. Column title is the HTML title attribute for the column in the header row.
dataOrientation	No	horizontal	The content orientation. By default, the data tables will be interpreted as columns (horizontally) representing domain and x values. Available values: • <code>vertical</code> – data table columns will be interpreted as series. • <code>horizontal</code> – data tables rows will be interpreted as series.
timeSeries	No	false	If 'true', the x values in an XY plot will be treated as time series data and so will be converted according date formats.
dateFormat	No	Confluence language defined date formats	For time series data, the date format allows for additional customisation of the conversion of data to date values. If a <code>dateFormat</code> is specified, it will be the first format used to interpret date values. Specify a format that matches the time series data. See simple date format.

timePeriod	No	day	The time period for time series data. Defines the granularity of how the data is interpreted. Available values: milli second, second, minute, hour, day, week, month, quarter, year
language	No	(None)	Use in combination with the country parameter to form a locale. These additional number and date formats will be used for data conversion before the default languages. Available values are the two-character ISO 639-1 alpha-2 codes.
country	No	(None)	Use in combination with the language parameter to form a locale. Valid values are the two-character ISO 3166 codes.
forgive	No	true	Determines whether the macro will forgive (allow) some data formatting errors. Available values: • <code>true</code> — the macro tries to convert numeric and date values that do not totally match any of the default or user-specified formats. • <code>false</code> — the macro enforces strict data formatting. If there are data format errors, the chart will not be produced.

Chart colour parameters

Colours are specified using hexadecimal notation or HTML colour names.

Parameter	Required	Default	Description
bgColor	No	White	Background colour of the chart.
borderColor	No	No border	Colour of the border around the chart.
colors	No		A comma-separated list of colours used to customise the colours of categories, sections, and series.

Chart axis parameters

Depending on the chart type, the range and domain axis may be customised. These values are automatically generated based on the data but can be overridden by specifying one or more more of these parameters.

Parameter	Required	Default	Description
rangeAxisLowerBound	No	(None)	Minimum value for the range axis.
rangeAxisUpperBound	No	(None)	Maximum value for the range axis.
rangeAxisTickUnit	No	(None)	Range axis units between axis tick marks.
rangeAxisLabelAngle	No	(None)	Angle for the range axis label in degrees.
domainAxisLowerBound	No	(None)	Only applies to XY plots. Domain axis lower bound. For a date axis, this value must be expressed in the date format specified by the dateFormat parameter.
domainAxisUpperBound	No	(None)	Only applies to XY plots. Domain axis upper bound. For a date axis, this value must be expressed in the date format specified by the dateFormat parameter.

domainAxisTickUnit	No	(None)	Only applies to XY plots. Domain axis units between axis tick marks. For a date axis, this value represents a count of the units specified in the timePeriod parameter. The timePeriod unit can be overridden by specifying a trailing character: y (years), M (months), d (days), h (hours), m (minutes), s (seconds), u (milliseconds).
domainAxisLabelAngle	No	(None)	Only applies to XY plots. The angle for the domain axis label, in degrees.
categoryLabelPosition	No	(None)	Placement of the axis label text for categories. Available values: • up45 — 45 degrees going upward • up90 — 90 degrees going upward • down45 — 45 degrees going downward • down90 — 90 degrees going downward
dateTickMarkPosition	No	start	Placement of the date tick mark. Available values: • start — tick mark is at the start of the date period. • middle — tick mark is in the middle of the date period. • end — tick mark is at the end of the date period.

Pie chart Parameters

Parameter	Required	Default	Description

pieSectionLabel	No	Show only the pie section key value	Format of pie section labels. The format uses a string with special replacement variables: • %0% is replaced by the pie section key. • %1% is replaced by the pie section numeric value. • %2% is replaced by the pie section percent value. Example 1: To display something like 'Independent = 20': %0% = %1% Example 2: To display something like 'Independent (20%)': %0% (%2%)
pieSectionExplode	No	No exploded sections	A comma-separated list of pie keys that are to be shown exploded. Note: requires jFreeChart version 1.0.3 or higher.

Chart attachment parameters

These are advanced options that can be used for chart versioning, to enable automation and to improve performance. Use these options carefully! Normally, the chart image is regenerated each time the page is displayed. These options allow for the generated image to be saved as an attachment and have subsequent access to re-use the attachment. This can be useful especially when combined with the Cache plugin to improve performance. Depending on the options chosen, chart images can be versioned for historical purposes.

Parameter	Required	Default	Description

attachment	No	(None)	The name and location where the chart image will be saved as an attachment. The user must be authorised to add attachments to the page specified. Available syntax for this parameter: • ^attachmentName.png — the chart is saved as an attachment to the current page. • page name^attachmentName.png — the chart is saved as an attachment to the page name provided. • spacekey:page name^attachmentName.png — the chart is saved as an attachment to the page name provided in the space indicated.

attachmentVersion	No	new	Defines the the versioning mechanism for saved charts. Available values: • new — creates new version of the attachment. • replace — replaces all previous versions of the chart. To replace an existing attachment, the user must be authorised to remove attachments for the page specified. • keep — only saves a new attachment if an existing export of the same name does not exist. An existing attachment will not be changed or updated.
attachmentComment	No	(None)	Comment used for a saved chart attachment.
thumbnail	No	false	If true, the chart image attachment will be shown as a thumbnail (small, expandable) image.

Example:

Below is a simple example of a pie chart. See more examples in [Storage Format Examples for Chart Macro](#).

```
<ac:macro ac:name="chart">
  <ac:parameter ac:name="title">Fish Sold</ac:parameter>
  <ac:parameter ac:name="type">pie</ac:parameter>
  <ac:rich-text-body>
    <table>
      <tbody>
        <tr>
          <th>
            <p>Fish Type</p>
          </th>
          <th>
            <p>2004</p>
          </th>
          <th>
            <p>2005</p>
          </th>
        </tr>
        <tr>
          <th>
            <p>Herring</p>
          </th>
          <td>
            <p>9,500</p>
          </td>
          <td>
            <p>8,300</p>
          </td>
        </tr>
        <tr>
          <th>
            <p>Salmon</p>
          </th>
          <td>
            <p>2,900</p>
          </td>
          <td>
            <p>4,200</p>
          </td>
        </tr>
        <tr>
          <th>
            <p>Tuna</p>
          </th>
          <td>
            <p>1,500</p>
          </td>
          <td>
            <p>1,500</p>
          </td>
        </tr>
      </tbody>
    </table>
  </ac:rich-text-body>
</ac:macro>
```

Cheese macro

Displays the words "I like cheese!"

Macro name: cheese

Macro body: None.

Parameters: None

Example:

```
<ac:macro ac:name="cheese"/>
```

Children Display macro

Displays the children and descendants of the current page.

Macro name: children

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
reverse	No	false	Reverses the sort order in the list of child pages. Use this parameter in conjunction with the sort parameter described below. A value of true will change the sort order from ascending to descending.
sort	No	Manual if the pages have been manually reordered, otherwise alphabeticalby page title	Determines the sort order of the list of child pages. Available values: - creation – Sort by the date on which the page was created. - title – Sort alphabetically by page name. - modified – Sort by the date on which the page was last updated.
style	No	Bullet list	A heading style to be applied to the list of child pages. Available values: h1 (heading level 1) through to h6 (heading level 6).

page	No	The page that contains the macro	The name of the parent page. The macro will display the children of the specified page. To specify a page in a different space, use a space key followed by a colon. For example: MYSPACE:My page If the value of this parameter is a forward slash (/) the macro will list the pages at the root of the current space. In other words, the pages without parents.
excerpt	No	false	If true, Confluence will display any excerpts that are defined on the child pages. The excerpts must be defined via an Excerpt macro.
first	No	(None)	The maximum number of child pages to be displayed (at the top level). For example, if the value of this parameter is 99, the macro will display the first 99 pages at the top level. It will also display their children, as determined by the depth and all parameters
depth	No	(None)	The number of levels of child pages to display. For example, if the value is 2, the macro will display 2 levels of child pages.
all	No	false	If true, Confluence will display all levels of child pages. This setting will override the depth setting.

Example:

```
<p>
  <ac:macro ac:name="children">
    <ac:parameter ac:name="reverse">true</ac:parameter>
    <ac:parameter ac:name="sort">creation</ac:parameter>
    <ac:parameter ac:name="style">h4</ac:parameter>
    <ac:parameter ac:name="page">Home</ac:parameter>
    <ac:parameter ac:name="excerpt">true</ac:parameter>
    <ac:parameter ac:name="first">99</ac:parameter>
    <ac:parameter ac:name="depth">2</ac:parameter>
    <ac:parameter ac:name="all">true</ac:parameter>
  </ac:macro>
</p>
```

Code Block macro

Displays code in your document with the appropriate syntax highlighting.

Macro name: code

Macro body: Accepts plain text.

Parameter name	Required	Default	Parameter description and accepted values
title	No	(None)	Adds a title to the code macro box.
theme	No	Confluence	Specifies the colour scheme used for displaying your code. Many of these themes are based on the default colour schemes of popular integrated development environments (IDEs). The default theme is Confluence (also known as Default), which is typically black and coloured text on a blank background. Available themes: • Django • Emacs • FadeToGrey • Midnight • RDark • Eclipse • Confluence (same as default)

linenumbers	No	false	If true, a line number will be shown to the left of each line of code. Numbering is incremented by 1. If false, no line numbers are shown.
language	No	java	Specifies the language (or environment) for syntax highlighting. • (none) — that is, no syntax highlighting • actionscript3 • bash • csharp — that is, C# • coldfusion • cpp — that is, C++ • css • delphi • diff • erlang • groovy • java • javafx • javascript • perl • php • powershell • python • ruby • scala • sql • vb — that is, Visual Basic • html/xml
firstline	No	1	When linenumbers is true, this value defines the number of the first line of code.

collapse	No	false	If true, the code macro's content will be collapsed upon visiting or refreshing the Confluence page. Clicking the 'expand source' link allows you to view the content. If false, the code macro's content is always displayed in full.

Example:

The following example shows all parameters and a body:

```
<ac:macro ac:name="code">
  <ac:parameter ac:name="title">This is my title</ac:parameter>
  <ac:parameter ac:name="theme">FadeToGrey</ac:parameter>
  <ac:parameter ac:name="linenumbers">true</ac:parameter>
  <ac:parameter ac:name="language">html/xml</ac:parameter>
  <ac:parameter ac:name="firstline">0001</ac:parameter>
  <ac:parameter ac:name="collapse">true</ac:parameter>
  <ac:plain-text-body><![CDATA[<b>This is my code</b>]]></ac:plain-text-body>
</ac:macro>
```

Below are three examples of the Code Block macro with various optional parameters used.

Description	Markup	What you will get
Code block macro with a body and no optional parameters	<pre><ac:macro ac:name="code"> <ac:plain-text-body ><![CDATA[this is my code]]></ac:plain-te xt-body> </ac:macro></pre>	this is my code
Code block macro with a body and the optional <i>language</i> parameter defined	<pre><ac:macro ac:name="code"> <ac:parameter ac:name="language">h tml/xml</ac:parame ter> <ac:plain-text-body ><![CDATA[this is my code]]></ac:plain-te xt-body> </ac:macro></pre>	this is my code

Code block macro with a body and optional *title*, *line numbers* and *language* parameters defined

```
<ac:macro
ac:name="code">
  <ac:parameter
ac:name="title">This
is my
title</ac:parameter>
  <ac:parameter
ac:name="linenumbers"
">true</ac:parameter
>
  <ac:parameter
ac:name="language">h
tml/xml</ac:parame
ter>
  <ac:plain-text-body
><![CDATA[this is my
code]]></ac:plain-te
xt-body></ac:macro>
```

This is my title

this is my code

Column macro

Used with the Section macro to define columns on a page. See [Working with page layouts and columns and sections](#).

Macro name: column

Macro body: Accepts rich text.

Parameter name	Required	Default	Parameter description and accepted values
width	No	100% of the page width, divided equally by the number of columns in the section.	The width of the column. Can be specified either in pixels (for example, 400 px) or as a percentage of the available page width (for example, 50%).

Example:

```
<ac:macro ac:name="column">
  <ac:parameter ac:name="width">100px</ac:parameter>
  <ac:rich-text-body>
    <p>This is the content of <strong>column 1</strong>.</p>
  </ac:rich-text-body>
</ac:macro>
```

Content by Label macro

Displays a list of content associated with specific labels.

Macro name: contentbylabel

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
spaces	No	@all	Filters the results by space. The macro will display only the pages and other content types which belong to the space(s) you specify here. You can specify one or more space keys, separated by a comma or a space. • To exclude content in a specific space, put a minus sign (-) immediately in front of that space key. For example: If you specify a space key of -BADSPACE you will get only content which is not in the BADSPACE. • To indicate that the results must come from a specific space, put a plus sign (+) immediately in front of that space key. For example: If you specify a space key of +GOODSPACE you will get only content in GOODSPACE. (Note that this is not particularly useful, because each content item belongs to one space only. If you put a plus sign next to one space key and list other space keys too, the other space keys will be ignored.) Special values:

			• <code>@self</code> — The current space. • <code>@personal</code> — All personal spaces. • <code>@global</code> — All site spaces. • <code>@favorite</code> — The spaces you have marked as favourite. • <code>@favourite</code> — The same as <code>@favorite</code> above. • <code>@all</code> — All spaces in your Confluence site. • <code>*</code> — The same as <code>@all</code> above. When specifying a personal space, remember to use the tilde (~) sign in front of the username, such as <code>~jbloggs</code> or <code>~jbloggs@example.com</code>.
<code>author</code>	No	(None)	Filters the results by author. The macro will display only the pages and other content types which are written or updated by the author(s) you specify here. You can specify one or more authors, separated by a comma. For example: <code>jsmith,jbrown</code>
<code>title</code>	No	(None)	Adds a heading to the list.
<code>showLabels</code>	No	<code>true</code>	Determines whether to display the matching labels in the list of results.

reverse	No	false	Use this parameter in conjunction with the sort parameter. Set reverse=true to change the sort from ascending to descending. This parameter is ignored if the sort parameter is not specified.
sort	No	modified	Determines how the results are sorted. To change the sort order from ascending to descending, use the reverse parameter described above. If this parameter is not specified, the sort order defaults to descending order based on the last modification date. Values: • title — Sort alphabetically by title. • creation — Sort by the date on which the content was added. • modified — Sort by the date on which the content was last updated.
max	No	15	Determines the maximum number of results to be displayed. Note that the results are sorted first, and then the maximum parameter is applied.

excerpt	No	false	If this parameter is set to <code>true</code>, the macro displays an excerpt from each page listed in the results. Note that you must define the excerpts on each of those pages, by adding the Excerpt macro to each page. If a particular page does not have an excerpt defined, then the Content by Label macro will not attempt to show an excerpt for that page. The Content by Label macro will show only the first few lines of the excerpt for each page.

labels	Yes	(None)	Use this parameter to filter the results by label. The macro will display only the pages and other content types which are tagged with the label(s) you specify here. See also the operator parameter. You can specify one or more label values, separated by a comma or a space. • To exclude content which matches a given label, put a minus sign (-) immediately in front of that label value. For example: If you specify a label value of -badpage you will get only content which is not labelled with 'badpage'. • To indicate that the results must match a given label value, put a plus sign (+) immediately in front of that label value. For example: If you specify a label value of +superpage, +goodpage you will get only content which has at least two labels, being 'superpage' and 'goodpage'.
showSpace	No	true	Determines whether to display the spaces in the list of results.

type	No	All	Filters the results by content type. The macro will display only the content of the type you specify here. You can specify one or more types, separated by a comma or a space. To exclude content of a given content type, put a minus sign (-) immediately in front of that content type. For example: If you specify a content type of -blogpost you will get pages and all other content except for blog posts. Available values: • page — pages. • blogpost or news — blog posts, also known as news items. • attachment — attachments.

operator	No	OR	The operator to apply to the supplied lists of labels. By default, a page with any of the non-prefixed labels (that is, labels without a plus (+) or minus (-) sign immediately preceding it) will be listed. If you specify a value of AND, only pages with all of the supplied non-prefixed labels will be listed. Note that this parameter only modifies the behaviour of the 'Label(s)' parameter and only affects label values without a plus (+) or minus (-) sign prefix. To avoid confusion or unexpected results, we recommend that you do not use the operator parameter in conjunction with any label values prefixed with '+' or '-' signs.

Example:

```
<ac:macro ac:name="contentbylabel">
  <ac:parameter ac:name="spaces">@personal,@self</ac:parameter>
  <ac:parameter ac:name="author">admin,smaddox</ac:parameter>
  <ac:parameter ac:name="title">My labelled pages</ac:parameter>
  <ac:parameter ac:name="showLabels">>false</ac:parameter>
  <ac:parameter ac:name="reverse">>true</ac:parameter>
  <ac:parameter ac:name="sort">creation</ac:parameter>
  <ac:parameter ac:name="max">10</ac:parameter>
  <ac:parameter ac:name="excerpt">>true</ac:parameter>
  <ac:parameter ac:name="labels">chocolate, cake</ac:parameter>
  <ac:parameter ac:name="showSpace">>false</ac:parameter>
  <ac:parameter ac:name="type">page</ac:parameter>
  <ac:parameter ac:name="operator">AND</ac:parameter>
</ac:macro>
```

Content by User macro

Displays a list of the content items that have been created by a specified Confluence user.

Macro name: content-by-user

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
default-parameter (Unnamed in wiki markup)	Yes	(None)	The Confluence username for the person whose content you wish to display

Example:

```
<ac:macro ac:name="content-by-user">
  <ac:default-parameter>jsmith</ac:default-parameter>
</ac:macro>
```

Content Report Table macro

Displays a set of pages and blog posts in tabular format, based on the labels specified in the macro parameters.

Macro name: content-report-table

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
spaces	No	(None)	This parameter is required. Specify one or more labels, separated by a comma. The macro will display only the content tagged with the label(s) specified here.
labels	Yes	(None)	Specify one or more space keys, separated by a comma or a space. The macro will display only the content which belongs to the space(s) specified here. When specifying a personal space, remember to use the tilde (~) sign in front of the username, such as ~jbloggs or ~jbloggs@example.com.

Example:

```
<ac:macro ac:name="content-report-table">
  <ac:parameter ac:name="spaces">DOC</ac:parameter>
  <ac:parameter ac:name="labels">LDAP</ac:parameter>
  <ac:parameter ac:name="analytics-key">meeting-notes</ac:parameter>
</ac:macro>
```

Contributors macro

Displays a list of Confluence users who have made a contribution of some type to a page.

Macro name: contributors

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
limit	No	(None)	Limits the number of contributors displayed in the list.
spaces	No	Current space	Specifies the space key of the Confluence space to search. Space keys are case sensitive. Special values: • @global — All site spaces. • @personal — All personal spaces. • @all — All spaces in the Confluence site. You can specify one or more space keys or special values, separated by commas. If no <code>page</code> and <code>labels</code> are specified, all pages from the specified set of spaces are included.
reverse	No	false	Reverses the order of contributors in the list. Must be used in conjunction with the <code>order</code> parameter.

scope	No	The specified page only	Specifies additional pages to include when generating the list of contributors. Available values: • children – only the child pages of the specified page. • descendants – all descendants of the specified page.
labels	No	(None)	Limits the list of contributors to those who created the specified labels on a page. You can specify one or more labels, separated by commas.
showPages	No	false	If the value is true, the macro will display a list of the pages used to generate the list of contributors.
noneFoundMessage	No	"No contributors found for:" (and a summary of selected parameter values)	Any message given here will override the default message that is displayed when no contributors are found.
showCount	No	false	Determines whether the macro will show the number of times each person made a contribution.
contentType	No	Both pages and blog posts	Restricts the content type that the macro will use when generating the list of contributors. Available values: • pages – pages • blogposts – blog posts.

include	No	authors	Filters by either the type of contribution made to a page (and optionally its descendant pages), or the watches on the page. Contribution types are: • <code>authors</code> - includes people who created or have edited the page(s) • <code>comments</code> - includes people who have added comments to the page(s) • <code>labels</code> - includes people who have added labels to the page(s) • <code>watches</code> - includes people who are watching the page(s). You can specify one or more contribution types, separated by commas.
mode	No	inline	Determines how the list of contributors is formatted: • <code>inline</code> — a comma-separated list • <code>list</code> — a bullet list.
showAnonymous	No	false	Determines whether to include those who contributed anonymously to a page.

order	No	count	Specifies the criteria used to sort contributors. Sort criteria are: - count – sorts the names based on the total number of contributions to the page(s) - name – sorts the names into alphabetical order - update – sorts the names by the date of their last contribution to the page(s).
page	No	The current page	Specifies the page to use when generating the list of contributors. If page and spaces are left blank, the current page is assumed.
showLastTime	No	false	Determines whether to show the last time each person made a contribution.
publishDate	No	(None)	Specifies the publication date for a blog post. The date format required is: YYYY/MM/DD.

Example:

This example specifies a content type of blog posts:

```
<ac:macro ac:name="contributors">
  <ac:parameter ac:name="limit">10</ac:parameter>
  <ac:parameter ac:name="spaces">ds,@personal</ac:parameter>
  <ac:parameter ac:name="reverse">true</ac:parameter>
  <ac:parameter ac:name="labels">chocolate, cake</ac:parameter>
  <ac:parameter ac:name="showPages">true</ac:parameter>
  <ac:parameter ac:name="noneFoundMessage">Oh dear, no contributors
found</ac:parameter>
  <ac:parameter ac:name="showCount">true</ac:parameter>
  <ac:parameter ac:name="contentType">blogposts</ac:parameter>
  <ac:parameter ac:name="include">authors, comments, labels, watches</ac:parameter>
  <ac:parameter ac:name="mode">list</ac:parameter>
  <ac:parameter ac:name="showAnonymous">true</ac:parameter>
  <ac:parameter ac:name="order">update</ac:parameter>
  <ac:parameter ac:name="showLastTime">true</ac:parameter>
  <ac:parameter ac:name="publishDate">2012/06/30</ac:parameter>
</ac:macro>
```

This example specifies a content type of pages:

```
<ac:macro ac:name="contributors">
  <ac:parameter ac:name="limit">10</ac:parameter>
  <ac:parameter ac:name="spaces">ds,@personal</ac:parameter>
  <ac:parameter ac:name="reverse">true</ac:parameter>
  <ac:parameter ac:name="scope">descendants</ac:parameter>
  <ac:parameter ac:name="labels">chocolate, cake</ac:parameter>
  <ac:parameter ac:name="showPages">true</ac:parameter>
  <ac:parameter ac:name="noneFoundMessage">Oh dear, no contributors
found</ac:parameter>
  <ac:parameter ac:name="showCount">true</ac:parameter>
  <ac:parameter ac:name="contentType">pages</ac:parameter>
  <ac:parameter ac:name="include">authors, comments, labels, watches</ac:parameter>
  <ac:parameter ac:name="mode">list</ac:parameter>
  <ac:parameter ac:name="showAnonymous">true</ac:parameter>
  <ac:parameter ac:name="order">update</ac:parameter>
  <ac:parameter ac:name="page">ds:Advanced Topics</ac:parameter>
  <ac:parameter ac:name="showLastTime">true</ac:parameter>
</ac:macro>
```

Contributors Summary macro

Displays a table of contribution-based statistics for a set of pages.

Macro name: contributors-summary

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
limit	No	(None)	Limits the number of contributors or pages displayed in the table.

spaces	No	Current space	Specifies the space key of the Confluence space to search. Space keys are case sensitive. Special values: • @global — All site spaces. • @personal — All personal spaces. • @all — All spaces in the Confluence site. You can specify one or more space keys or special values, separated by commas. If no page and labels are specified, all pages from the specified set of spaces are included.
reverse	No	false	Reverses the order of items in the table. Must be used in conjunction with the order parameter.
showAnonymous	No	false	Determines whether to include those who contributed anonymously to a page.
scope	No	The specified page only	Specifies additional pages to include when generating the list of contributors. Available values: • children – only the child pages of the specified page. • descendants – all descendants of the specified page.

order	No	edits	Sets the criterion used for sorting items in the table. Available values: • <code>edits</code> – sorts items in the table based on the total number of edits made, either by a contributor or to a page. • <code>name</code> – sorts items in the table in alphabetical order, either by contributor or page name. • <code>editTime</code> – sorts items in the table based on when the contributor last edited a page (or a specified set of pages) or when the page was last edited. • <code>update</code> – sorts items in the table based on when the contributor last made any contribution to a page (or a specified set of pages) or when the page last had any contribution made to it.
page	No	The current page	A page title. Specifies the page to use when generating the list of contributors. If <code>page</code> and <code>spaces</code> are left blank, the current page is assumed.
labels	No	(None)	Limits contribution-based statistics to the specified labels only. You can specify one or more labels, separated by commas.
columns	No	edits, comments, labels	

Determines the columns that should appear in the table. The statistics or type of information presented depends on the `groupby` parameter.

Available values:

- `edits` – the number of times each contributor has edited the page(s) or the number of edits made to each page.
- `edited` – a list of the pages edited by each contributor or a list of contributors who have edited each page.
- `comments` – the number of times each contributor has added comments to the page(s) or the number of comments on each page.
- `commented` – a list of pages to which each contributor has added comments or a list of contributors who have commented on each page.
- `labels` – the number of times each contributor has added labels to the page(s) or the number of labels on each page.
- `labeled` – a list of pages to which each contributor has added labels or a list of contributors who have added a label to each page.
- `labelList` – a list of labels either added by each contributor or on each page.

			• watches – the number of pages being watched by each contributor/person or the number of contributors/people watching each page. • watching – a list of pages being watched by each contributor/person or a list of contributors/people watching each page. • lastupdate – the last time each contributor made an update or when each page was last updated. Valid updates can include edits, comments or label modifications to a page. You can specify one or more columns, separated by commas.
groupby	No	contributors	Specifies the basis for grouping contribution-based statistics: • contributors – group by the people who have contributed. • pages – group by the pages used to find the contributors.
contentType	No	Both pages and blog posts	Restricts the content type that the macro will use when generating the list of contributors. Available values: • pages – pages • blogposts – blog posts.

showZeroCounts	No	false	Determines whether contributors or pages are included for which the calculated statistic is zero.
publishDate	No	(None)	Specifies the publication date for a blog post. The date format required is: YYYY/MM/DD.

Example:

This example specifies a content type of blog posts:

```
<ac:macro ac:name="contributors-summary">
  <ac:parameter ac:name="limit">10</ac:parameter>
  <ac:parameter ac:name="spaces">ds,@personal</ac:parameter>
  <ac:parameter ac:name="reverse">true</ac:parameter>
  <ac:parameter ac:name="showAnonymous">true</ac:parameter>
  <ac:parameter ac:name="order">update</ac:parameter>
  <ac:parameter ac:name="labels">chocolate,cake</ac:parameter>
  <ac:parameter ac:name="columns">edits,comments,labels,lastupdate</ac:parameter>
  <ac:parameter ac:name="groupby">pages</ac:parameter>
  <ac:parameter ac:name="contentType">blogposts</ac:parameter>
  <ac:parameter ac:name="showZeroCounts">true</ac:parameter>
  <ac:parameter ac:name="publishDate">2012/06/07</ac:parameter>
</ac:macro>
```

This example specifies a content type of pages:

```
<ac:macro ac:name="contributors-summary">
  <ac:parameter ac:name="limit">10</ac:parameter>
  <ac:parameter ac:name="spaces">ds,@personal</ac:parameter>
  <ac:parameter ac:name="reverse">true</ac:parameter>
  <ac:parameter ac:name="showAnonymous">true</ac:parameter>
  <ac:parameter ac:name="scope">descendants</ac:parameter>
  <ac:parameter ac:name="order">update</ac:parameter>
  <ac:parameter ac:name="page">ds:Advanced Topics</ac:parameter>
  <ac:parameter ac:name="labels">chocolate,cake</ac:parameter>
  <ac:parameter ac:name="columns">edits,comments,labels,lastupdate</ac:parameter>
  <ac:parameter ac:name="groupby">pages</ac:parameter>
  <ac:parameter ac:name="contentType">pages</ac:parameter>
  <ac:parameter ac:name="showZeroCounts">true</ac:parameter>
</ac:macro>
```

Create Space Button macro

Displays a create space button linked to the create space page.

Macro name: create-space-button

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
size	No	large	Determines the size of the 'create space' icon displayed. Available values: • large • small
width	No	Natural size of icon (1:1 pixel ratio)	The width of the icon to be displayed, specified in pixels. Confluence will stretch or shrink the width of the icon to the number of pixels specified. Note: This parameter is not available via the macro browser.
height	No	Natural size of icon (1:1 pixel ratio)	The height of the icon to be displayed, specified in pixels. Confluence will stretch or shrink the height of the icon to the number of pixels specified. Note: This parameter is not available via the macro browser.

Example:

```
<ac:macro ac:name="create-space-button">
  <ac:parameter ac:name="size">small</ac:parameter>
</ac:macro>
```

Excerpt Include macro

Allows you to display an excerpt from another page within the current page.

Macro name: excerpt-include

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values

default-parameter (Unnamed in wiki markup)	Yes	(None.)	The name of the page that contains the excerpt to be displayed. To include an excerpt from a page in another space, type the space key followed by a colon (:) and the page name, like this: SPACEKEY:My page name Note: The ability to include excerpts from other spaces is available only in Confluence 4.3.2 and later. In earlier versions of Confluence, the Excerpt Include macro does not work across spaces. Use the Include Page macro instead.
nopanel	No	False	Determines whether Confluence will display a panel around the excerpted content. The panel includes the title of the page containing the excerpt, and the border of the panel. By default, the panel and title are shown.

Example:

```
<ac:macro ac:name="excerpt-include">
  <ac:parameter ac:name="nopanel">true</ac:parameter>
  <ac:default-parameter>My page name</ac:default-parameter>
</ac:macro>
```

Excerpt macro

Define a part of a page as the page's 'excerpt' which can then be displayed in another page.

Macro name: excerpt

Macro body: Accepts rich text.

Parameter name	Required	Default	Parameter description and accepted values
hidden	No	False	Determines whether the content of the Excerpt macro body is displayed on the page that contains the Excerpt macro. Note that this option affects only the page that contains the Excerpt macro. It does not affect any pages where the content is reused.
atlassian-macro-output-type	No	BLOCK	Determines whether the content of the Excerpt macro body is displayed on a new line or inline. Available values: • BLOCK – Displays the content of the macro on a new line . • INLINE – Displays the the content of the macro as part of the same paragraph as the text preceding and following it. Note that this option affects only the page that contains the Excerpt macro. It does not affect any pages where the content is reused.

Example:

```
<ac:macro ac:name="excerpt">
  <ac:parameter ac:name="hidden">true</ac:parameter>
  <ac:parameter ac:name="atlassian-macro-output-type">BLOCK</ac:parameter>
  <ac:rich-text-body>
    <p>This is the <strong>text</strong> I want to reuse in other pages. This text
is inside an Excerpt macro.</p>
  </ac:rich-text-body>
</ac:macro>
```

Expand macro

Displays an expandable/collapsible section of text.

Macro name: expand

Macro body: Accepts rich text.

Parameter name	Required	Default	Parameter description and accepted values
default-parameter (Unnamed in wiki markup)	No	Click here to expand...	Text that will be displayed on the line that people can click to expand the hidden text.

Example:

```
<ac:macro ac:name="expand">
<ac:default-parameter>This is my message</ac:default-parameter>
<ac:rich-text-body>
  <p>This text is <em>hidden</em> until you expand it.</p>
</ac:rich-text-body>
</ac:macro>
```

Favourite Pages macro

Displays a list of your favourite pages.

Macro name: favpages

Macro body: None.

Parameters: None.

Example:

```
<ac:macro ac:name="favpages"/>
```

Gadget macro

Allows you to add Confluence gadgets to pages or blog posts.

Macro name: gadget

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values

width	No	450 pixels	The width of the gadget, using one of the following conventions: • Width in pixels, using px or plain numbers. For example, 500px or 500 • A percentage of the page width, using %. For example, 50% • Automatic resizing of the gadget to fit 100% of the page width: auto
border	No	true	Determines whether Confluence will draw a border around the gadget.
url	Yes	(none.)	This is the location of the gadget specification (XML file).
preferences	No	(Gadget-dependent.)	Specific property settings that are particular to each gadget.

A note about editing a gadget's properties (preferences) in markup: It is possible to edit the values of these properties directly in the wiki markup or storage format. However, this will allow the entry of invalid values. If a gadget property supports a certain set of values, the macro browser will restrict the user to selecting only valid values for that property. For that reason, we recommend that you use the macro browser to edit a gadget's properties.

Example:

This example shows the Confluence Page gadget:

```
<ac:macro ac:name="gadget">
  <ac:parameter ac:name="width">500</ac:parameter>
  <ac:parameter ac:name="border">false</ac:parameter>
  <ac:parameter
ac:name="url">rest/gadgets/1.0/g/com.atlassian.confluence.plugins.gadgets:confluenc
e-page-gadget/gadgets/confluence-page-gadget.xml</ac:parameter>
  <ac:parameter
ac:name="preferences">spaceName=Documentation&spaceKey=DOC&quickfind-space=
Documentation&pageId=753666&pageName=Documentation%20Home&quickfind-pag
e=Documentation%20Home&isEditable=true&isConfigured=true&refresh=15&
;showLink=false</ac:parameter>
</ac:macro>
```

This example shows the Confluence News gadget:

```
<ac:macro ac:name="gadget">
  <ac:parameter
ac:name="url">rest/gadgets/1.0/g/com.atlassian.confluence.plugins.gadgets:confluence-news-gadget/gadgets/confluence-news-gadget.xml</ac:parameter>
  <ac:parameter ac:name="preferences"/>
</ac:macro>
```

Gallery macro

Forms a thumbnail gallery of all images attached to a page.

Macro name: gallery

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
title	No	(None)	Specify a title to be displayed above your gallery of pictures.
reverse	No	Not specified. Sort order is ascending.	Used in combination with the sort parameter, to change the sort order from ascending to descending. Available values: • true – Sort order is descending. • false – Sort order is ascending.
sort	No	None. The sort order is unspecified and therefore unpredictable.	Specify an attribute to sort the images by. Sort order is ascending, unless you specify the reverse parameter. Available values: • name – file name. • comment – comment linked to the attached file. • date – date/time last modified. • size – size of the attached file.

page	No	If no page is specified, the gallery macro displays the images attached to the page on which the macro is used.	Specify the title of the page which contains the images you want displayed. You can specify more than one page name, separated by commas. To specify a page in a different space, use the following syntax: SPACEKEY : Page title.
includeLabel	No	None. The images are not filtered by label.	The gallery will include only those pictures that have the specified label. If you wish to enter more than one label, separate the labels with commas. Confluence will show only images that have all the labels specified. (The match is an AND, not an OR.) For information on labelling the attachments, see Adding Labels .
excludeLabel	No	No exclusions. The gallery will include all the pictures on the page.	The gallery will ignore any pictures that have the specified label. You can specify more than one label, separated by commas. For information on labelling the attachments, see Adding Labels .
columns	No	4	Specify the number of columns for the table that forms the gallery.

exclude	No	No exclusions. Include all the pictures on the page.	Specify images by file name. The gallery will ignore any images specified. You can specify more than one image, separated by commas. Note: The file name and file type for this parameter are case sensitive. For example, 'my picture.PNG' will not be recognised as 'my picture.png'.
include	No	Include all the pictures on the page.	If you specifically include one or more pictures, the gallery will show only those pictures. You can specify more than one picture, separated by commas. Note: The file name and file type for this parameter are case-sensitive. For example, 'my picture.PNG' will not be recognised as 'my picture.png'.

Example:

```
<ac:macro ac:name="gallery">
  <ac:parameter ac:name="title">My holiday pictures</ac:parameter>
  <ac:parameter ac:name="reverse">true</ac:parameter>
  <ac:parameter ac:name="sort">size</ac:parameter>
  <ac:parameter ac:name="page">My page1, ds:Welcome to Confluence</ac:parameter>
  <ac:parameter ac:name="excludeLabel">badlabel1, badlabel2</ac:parameter>
  <ac:parameter ac:name="columns">3</ac:parameter>
  <ac:parameter ac:name="exclude">badpicture.png</ac:parameter>
</ac:macro>
```

Global Reports macro

Displays a list of links to global reports within a table.

Macro name: global-reports

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values

width	No	99%	Specify the width of the table in which the links are displayed, as a percentage of the window width.

Example:

```
<ac:macro ac:name="global-reports">
  <ac:parameter ac:name="width">50%</ac:parameter>
</ac:macro>
```

HTML Include macro

Includes the content of an external HTML file into a Confluence page.

Macro name: html-include

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
url	Yes	(None)	Specify a URL of the content to be included into your Confluence page.

Example:

```
<ac:macro ac:name="html-include">
  <ac:parameter ac:name="url">http://www.example.com</ac:parameter>
</ac:macro>
```

HTML macro

Renders your specified HTML code within the current page.

Macro name: html

Macro body: Text, consisting of HTML code.

Parameters: None.

Example:

```
<ac:macro ac:name="html">
  <ac:plain-text-body><![CDATA[<a href="http://www.atlassian.com">Click here</a> to
see the <b>Atlassian</b> website.]]></ac:plain-text-body>
</ac:macro>
```

IM Presence macro

Displays graphically when a contact is online.

Macro name: im

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
showid	No	true	Determines whether the macro shows or hides the user ID of the contact. Available values: • true – User ID is shown on the page. • false – User ID is not shown on the page.
service	Yes	Not specified.	The web service that Confluence should query. Available values: • aim – AOL Instant Messenger • gtalk – Google Talk • icq – ICQ • jabber – Jabber • msn – MSN Instant Messenger • sametime – IBM Lotus Sametime • skype – Skype • skypeme – Skype • wildfire – Openfire Server • yahoo – Yahoo! Messenger
default-parameter (Unnamed in wiki markup)	Yes	Not specified.	User ID. Identifies the IM contact by their ID, account name or screen name.

Example:

```
<ac:macro ac:name="im">
  <ac:parameter ac:name="showid">false</ac:parameter>
  <ac:parameter ac:name="service">skype</ac:parameter>
  <ac:default-parameter>MySkypeName</ac:default-parameter>
</ac:macro>
```

Include Page macro

Inserts the contents of the specified page into the current one.

Macro name: include

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
default-parameter (Unnamed in wiki markup)	Yes	(None.)	The name of the page whose content should be included on the current page To include content from a page in another space, type the space key followed by a colon (:) and the page name, like this: SPACEKEY:My page name To include a blog post, specify the date as well as the title of the blog post. For example: /2010/12/01/My blog post. You can include pages from personal spaces using ~username as the space key, where 'username' is the person's username. For example, ~jsmith:My page name.

Example:

```
<ac:macro ac:name="include">  
  <ac:default-parameter>DOC:My chocolate page</ac:default-parameter>  
</ac:macro>
```

Info macro

Displays a block of text in a blue highlight box.

Macro name: info

Macro body: Accepts rich text.

Parameter name	Required	Default	Parameter description and accepted values
icon	No	true	Determines whether to display the  icon in the title bar of the information box.
title	No	(None)	The title of the information box. If specified, the title text will be displayed in bold next to the icon.

Example:

The following example shows all parameters and a body:

```
<ac:macro ac:name="info">
<ac:parameter ac:name="icon">false</ac:parameter>
<ac:parameter ac:name="title">This is my title</ac:parameter>
<ac:rich-text-body>
  <p>
    <span>This is </span>
    <em>important</em>
    <span> information.</span>
  </p>
</ac:rich-text-body>
</ac:macro>
```

Below are some examples of the Info macro with various optional parameters used.

Description	Markup	What you will get
Info macro with a body defined and no optional parameters	<pre><ac:macro ac:name="info"> <ac:rich-text-body> <p>This is important information.</p></ac:rich-text-body></ac:macro></pre>	 This is <i>important</i> information.

Info macro with with a body and an optional <i>Title</i> parameter defined	<pre><ac:macro ac:name="info"> <ac:parameter ac:name="title">This is my title</ac:parameter> <ac:rich-text-body> <p>This is important information.</p></ac: rich-text-body> </ac:macro></pre>	 This is my title This is <i>important</i> information.
Info macro with a body and optional <i>Title</i> and <i>Icon</i> parameters defined	<pre><ac:macro ac:name="info"> <ac:parameter ac:name="icon">false </ac:parameter> <ac:parameter ac:name="title">This is my title</ac:parameter> <ac:rich-text-body> <p> This is important information. </p> </ac:rich-text-body> </ac:macro></pre>	This is my title This is <i>important</i> information.

JIRA Issues macro

Displays a list of JIRA issues in a page.

Macro name: jiraissues

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values

anonymous	No	false	If this parameter is set to 'true', JIRA will return only the issues which allow unrestricted viewing i.e. the issues which are visible to anonymous viewers, as determined by JIRA's viewing restrictions. If this parameter is omitted or set to 'false', then the results depend on how your administrator has configured the communication between JIRA and Confluence. By default, Confluence will show only the JIRA issues which the user is authorised to view. See more details below .
baseurl	No	The value of the 'url' parameter	If you specify a 'baseurl', then the link in the header, pointing to your JIRA site, will use this base URL instead of the value of the 'url' parameter. This is useful when Confluence connects to JIRA with a different URL from the one used by other users.
columns	No	By default, the following columns are shown: • type • key • summary • assignee • reporter • priority • status • resolution • created • updated • due	A list of JIRA column names, separated by semi-colons (;). Example columns are: key, summary, type, created, fixversion, updated, due, assignee, reporter, priority, status and resolution. You can include any columns recognised by your JIRA site, including custom columns. See the JIRA documentation for a list of names.

count	No	false	If this parameter is set to 'true', the issue list will show the number of issues in JIRA. The count will be linked to your JIRA site.
cache	No	on	The macro maintains a cache of the issues which result from the JIRA query. If the 'cache' parameter is set to 'off', the relevant part of the cache is cleared each time the macro is reloaded. (The value 'false' also works and has the same effect as 'off'.)
height	No	480	The height in pixels of the table displaying the JIRA issues. Note that this height specification is ignored in the following situations: • If you set the 'renderMode' parameter (see below) to 'static'. • When the JIRA issues are displayed in a PDF or Word document, in an email message or in an RSS feed.

renderMode	No	In formats not mentioned below, the default is 'dynamic'. The default is 'static' when the JIRA issues are displayed in a PDF or Word document, in an email message or in an RSS feed.	By default, the JIRA Issues macro offers a dynamic display with the following features: • Click the column headers to sort the output. • Drag and drop the columns into a different order. • Temporarily remove a column from the display. • View a page of issues at a time, for faster response times. Set the 'renderMode' parameter to 'static' if you want to disable the dynamic display features.
title	No	JIRA Issues	You can customise the title text at the top of the JIRA issues table with this parameter. For instance, setting the title to 'Bugs-to-fix' will replace the default 'JIRA Issues' text. This can help provide more context to the list of issues displayed.

url	Yes	none	The URL of the XML view of your selected issues in JIRA Issue Navigator. Note: If the URL in the 'url' parameter does not contain a tempMax argument, then the value of tempMax will default to 500. If your JIRA server is version 3.12 or earlier, this means that the JIRA Issues macro will return a maximum of 500 issues. If your JIRA server is version 3.13 or later, a value of 500 means that the JIRA Issues macro will return a maximum of 500 issues per page.
width	No	100%	The width of the table displaying the JIRA issues. Can be indicated either as a percentage (%) or in pixels (px).

Example:

```
<ac:macro ac:name="jiraissues">
  <ac:parameter ac:name="anonymous">true</ac:parameter>
  <ac:parameter ac:name="columns">type;key;summary</ac:parameter>
  <ac:parameter
ac:name="url">http://jira.atlassian.com/sr/jira.issueviews:searchrequest-xml/temp/Se
archRequest.xml?jqlQuery=project+%3D+CONF+AND+%28summary+%7E+jiraissues+OR+descrip
tion+%7E+jiraissues+OR+comment+%7E+jiraissues%29&tempMax=10</ac:parameter>
</ac:macro>
```

JUnit Report macro

Display a summary of JUnit test results.

Macro name: junitreport

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values

directory	Must include either the directory or the url parameter	(None)	URL of a directory containing your test result files. This must be a directory name and not the XML file itself. Overrides the url parameter if you use both. Note: When using a local drive, you must use a directory name and not the XML file itself.
reportdetail	No	all	Level of detail required in the report. Available values: • all • fixture • summary • failuresonly
url	Must include either the directory or the url parameter	(None)	URL of a particular test result XML file. This parameter is overridden by the directory parameter if you use both. For Confluence installations that require authentication, you can specify login credentials as part of this parameter, in the form of URL parameters: • os_username — The username of a Confluence user with permission to access the JUnit test results. • os_password — The password of the Confluence user specified in the os_username parameter.

debug	No	false	If the value of this parameter is true, the report will show the content of failures, as well as the error messages.

Example:

```
<ac:macro ac:name="junitreport">
  <ac:parameter ac:name="reportdetail">summary</ac:parameter>
  <ac:parameter
ac:name="directory">http://confluence.com/download/attachments/123/</ac:parameter>
  <ac:parameter ac:name="debug">true</ac:parameter>
  <ac:parameter
ac:name="url">http://confluence.com/download/attachments/123/file.xml</ac:parameter
>
</ac:macro>
```

Labels List macro

Displays a hyperlinked alphabetical index of all labels within the current space.

Macro name: listlabels

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
spaceKey	No	Current space	The key of the space whose labels you want to display.

Example:

```
<ac:macro ac:name="listlabels">
  <ac:parameter ac:name="spaceKey">DOC</ac:parameter>
</ac:macro>
```

Livesearch macro

Add a dynamic search box to a wiki page.

Macro name: livesearch

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values

id	No	(None)	Uniquely identifies the Livesearch macro when there are more than one Livesearch macros in a page.
spaceKey	No	All spaces	Specify a space key to limit the search to the given space.

Example:

```
<ac:macro ac:name="livesearch">
  <ac:parameter ac:name="id">mysearch1</ac:parameter>
  <ac:parameter ac:name="spaceKey">DOC</ac:parameter>
</ac:macro>
```

Loremipsum macro

Display a few paragraphs of pseudo-Latin text.

Macro name: loremipsum

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
default-parameter (No name in wiki markup)	No	3	Number of paragraphs. Determines the amount of pseudo-Latin (space-filler) text to display. The macro will display a maximum number of 30 paragraphs.

Example:

```
<ac:macro ac:name="loremipsum">
  <ac:default-parameter>2</ac:default-parameter>
</ac:macro>
```

Multimedia macro

Displays videos, animations and more, sourced from a file attached to a Confluence page and displayed on your page.

Macro name: multimedia

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
page	No	Current page	Name of the page to which the multimedia file is attached.
space	No	Current space	Space key of the page that has the multimedia file attached.
name	Yes	None	File name of the multimedia file, which is attached to a Confluence page.
width	No	If not specified, the browser will determine the width based on the file type.	Width of the movie window to be displayed on the page. By default, this value is specified in pixels. You can also choose to specify a percentage of the window's width, or any other value accepted by HTML.
height	No	If not specified, the browser will determine the height based on the file type.	Height of the movie window to be displayed on the page. By default, this value is specified in pixels. You can also choose to specify a percentage of the window's height, or any other value accepted by HTML.
autostart	No	false	If the parameter is set to <code>true</code> then the video or audio file will start playing as soon as the page is loaded. If this option is set to <code>false</code> then the file will not play until the user clicks the icon or image on the page.

Example:

```
<ac:macro ac:name="multimedia">
  <ac:parameter ac:name="page">Macros</ac:parameter>
  <ac:parameter ac:name="name">ninjas.swf</ac:parameter>
  <ac:parameter ac:name="space">DOC</ac:parameter>
  <ac:parameter ac:name="autostart">true</ac:parameter>
</ac:macro>
```

Page Properties macro

The page Metadata Details Macro could not be found.

The page `_MetadataDetailsMacroMarkup` could not be found.

Example:

```
<ac:macro ac:name="details">
  <ac:parameter ac:name="hidden">true</ac:parameter>
  <ac:parameter ac:name="label">status</ac:parameter>
  <ac:rich-text-body>
    <table>
      <tbody>
        <tr>
          <td style="text-align: left;">Project Status</td>
          <td style="text-align: left;">Complete</td>
        </tr>
        <tr>
          <td colspan="1" style="text-align: left;">Team</td>
          <td colspan="1" style="text-align: left;">Green Parrots</td>
        </tr>
        <tr>
          <td colspan="1" style="text-align: left;">Deadline</td>
          <td colspan="1" style="text-align: left;">2012-09</td>
        </tr>
      </tbody>
    </table>
  </ac:rich-text-body>
</ac:macro>
```

Page Properties Report macro

The page Details Summary Macro could not be found.

The page `_DetailsSummaryMacroMarkup` could not be found.

Example:

```
<ac:macro ac:name="detailssummary">
  <ac:parameter ac:name="label">status</ac:parameter>
</ac:macro>
```

Section macro

Used with the Column macro to define columns on a page. See [Working with page layouts and columns and sections](#).

Macro name: section

Macro body: Rich text, consisting of one or more Column macros.

Parameter name	Required	Default	Parameter description and accepted values
border	No	False	If the value is <code>true</code> , the columns in this section will have a dashed border.

Example:

```
<ac:macro ac:name="section">
  <ac:parameter ac:name="border">true</ac:parameter>
  <ac:rich-text-body>
    <ac:macro ac:name="column">
      <ac:parameter ac:name="width">100px</ac:parameter>
      <ac:rich-text-body>
        <p>This is the content of <strong>column 1</strong>.</p>
      </ac:rich-text-body>
    </ac:macro>
    <ac:macro ac:name="column">
      <ac:rich-text-body>
        <p>This is the content of <strong>column 2</strong>.</p>
      </ac:rich-text-body>
    </ac:macro>
  </ac:rich-text-body>
</ac:macro>
```

Table of Contents macro

Displays a table of contents from your page headings.

Macro name: toc

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
printable	No	true	If you set this parameter to <code>false</code> , the table of contents will not be visible when you print the page.

style	No	none	The style of bullet point for each list item. You can use any valid CSS style. For example: • none – No list style is displayed. • circle – The list style is a circle. • disc – The list style is a filled circle. This is the typical bullet list, and is the one we are using in this example list. • square – The list style is a square. • decimal – The list is numbered (1, 2, 3, 4, 5). • lower-alpha – The list style is lower case, alphabetised (a, b, c, d, e). • lower-roman – The list style is lower-case roman numerals (i, ii, iii, iv, v, vi). • upper-roman – The list style is upper-case roman numerals (I, II, III, IV, V, VI).
maxLevel	No	7	Maximum heading level. Use this parameter to select the highest heading level to include. For example, a value of 2 will list h1 and h2 levels, but will not include h3 and below.

indent	No	(None)	This parameter applies to vertical lists only (type = list). Use this parameter to indent the list items according to CSS quantities. For example, a value of 10px will successively indent list heading groups by 10 pixels. Level 1 headings will be indented 10px, and level 2 headings by an additional 10px, and so on.
minLevel	No	1	Minimum heading level. The heading level at which the table of contents will start. For example, a value of 2 will list h2, h3, and h4 headings, but will not include h1 headings.
class	No	(None)	A CSS class name. If you have a custom style sheet, you can use this parameter to output the table of contents with the specified class attribute.
exclude	No	(None)	Specifies the headings to exclude by pattern matching. The value must be a regular expression. If this parameter is specified, the table of contents will include only the headings that match the regular expression. Example: <code>.*\.[1//2]</code> See Sun's Regex documentation for examples of constructing regular expression strings.

type	No	list	Defines the overall format of the table of contents. Available values: • <code>list</code> – displays the table of contents in a vertical list. • <code>flat</code> – displays a horizontal series of links. For example: [Heading 1] [Heading 2] [Heading 3].
outline	No	false	A value of <code>true</code> will apply outline numbering to the headings as displayed in the table of contents. For example: 1.1, 1.2, 1.3.

separator	No	brackets	This parameter applies to flat lists only (type = flat). Use this parameter to style the display of a flat list. Available values: • brackets – Each item is enclosed by square brackets: []. • braces – Each item is enclosed by braces: { }. • parens – Each item is enclosed by parentheses: (). • pipe – The items are separated by a pipe: • anything – The items are separated by the value you enter. You can enter any text as a separator, for example ***. If using a custom separator, be aware that text displays exactly as entered, with no additional white space to further separate the characters.
include	No	(None)	Specifies the headings to include by pattern matching. The value must be a regular expression. If this parameter is specified, the table of contents will ignore any headings that do not match the regular expression. Example: <code>.*\.[1/2]</code> See Sun's Regex documentation for examples of constructing regular expression strings.

Example:

This example shows a list-type table of contents.

```
<ac:macro ac:name="toc">
  <ac:parameter ac:name="printable">true</ac:parameter>
  <ac:parameter ac:name="style">square</ac:parameter>
  <ac:parameter ac:name="maxLevel">2</ac:parameter>
  <ac:parameter ac:name="indent">5px</ac:parameter>
  <ac:parameter ac:name="minLevel">2</ac:parameter>
  <ac:parameter ac:name="class">bigpink</ac:parameter>
  <ac:parameter ac:name="exclude">[1//2]</ac:parameter>
  <ac:parameter ac:name="type">list</ac:parameter>
  <ac:parameter ac:name="outline">true</ac:parameter>
  <ac:parameter ac:name="include">.*</ac:parameter>
</ac:macro>
```

This example shows a flat table of contents.

```
<ac:macro ac:name="toc">
  <ac:parameter ac:name="printable">true</ac:parameter>
  <ac:parameter ac:name="maxLevel">2</ac:parameter>
  <ac:parameter ac:name="minLevel">2</ac:parameter>
  <ac:parameter ac:name="class">bigpink</ac:parameter>
  <ac:parameter ac:name="exclude">[1//2]</ac:parameter>
  <ac:parameter ac:name="type">flat</ac:parameter>
  <ac:parameter ac:name="outline">true</ac:parameter>
  <ac:parameter ac:name="separator">pipe</ac:parameter>
  <ac:parameter ac:name="include">.*</ac:parameter>
</ac:macro>
```

Macro format notes**Macro bodies**

Some macros accept a body as well as parameters.

- The [Info macro](#) and [Expand macro](#) are examples of macros that accept a rich text body.
- The [Code Block macro](#) is a good example of a macro that accepts a plain text body.

Plain text bodies

The body of a plain text macro must be inside a CDATA block. So the following is not sufficient:

```
<ac:plain-text-body>text</ac:plain-text-body>
```

The correct usage is:

```
<ac:plain-text-body><![CDATA[text]]></ac:plain-text-body>
```

Other notes

- The 'Required' column indicates whether the parameter is required on data entry. If the parameter is not supplied, Confluence will insert default values as indicated in the 'Default' column.
- **A request from the Atlassian technical writers about comments and feedback:** When adding comments to this page, please restrict your comments to constructive feedback on the documentation itself: Things we've missed in the documentation, and things that will be useful to other readers. If you have other feedback about the editor, wiki markup, the XML storage format, and Confluence 4 in general, please add your comments in the section titled [Confluence 4 Editor - Customer Feedback](#), and its child pages. Our reason for this request: When a page attracts a large number of comments, it makes it difficult for everyone to read the page, and to add or respond to comments about the documentation. Thanks. 😊

Confluence Storage Format Examples for Chart Macro

This page is an extension of [Confluence Storage Format for Macros](#), which contains storage format examples for all Confluence macros. The [Chart macro](#) is a special case, because it offers so many options via parameters and chart types. This page offers additional examples for the Chart macro.

Pie chart

Here is a simple example of a pie chart.

Storage format


```

<ac:macro ac:name="chart">
  <ac:parameter ac:name="title">Fish Sold</ac:parameter>
  <ac:parameter ac:name="type">pie</ac:parameter>
  <ac:rich-text-body>
    <table>
      <tbody>
        <tr>
          <th>
            <p>Fish Type</p>
          </th>
          <th>
            <p>2004</p>
          </th>
          <th>
            <p>2005</p>
          </th>
        </tr>
        <tr>
          <th>
            <p>Herring</p>
          </th>
          <td>
            <p>9,500</p>
          </td>
          <td>
            <p>8,300</p>
          </td>
        </tr>
        <tr>
          <th>
            <p>Salmon</p>
          </th>
          <td>
            <p>2,900</p>
          </td>
          <td>
            <p>4,200</p>
          </td>
        </tr>
        <tr>
          <th>
            <p>Tuna</p>
          </th>
          <td>
            <p>1,500</p>
          </td>
          <td>
            <p>1,500</p>
          </td>
        </tr>
      </tbody>
    </table>
  </ac:rich-text-body>
</ac:macro>

```

Resulting chart

Fish Sold



■ 2004 (1,500 - 50%) ■ 2005 (1,500 - 50%)

Bar chart

Here is a simple example of a bar chart.


Storage format

```

<ac:macro ac:name="chart">
  <ac:parameter ac:name="title">Fish Sold</ac:parameter>
  <ac:parameter ac:name="type">bar</ac:parameter>
  <ac:rich-text-body>
    <table>
      <tbody>
        <tr>
          <th>
            <p>Fish Type</p>
          </th>
          <th>
            <p>2004</p>
          </th>
          <th>
            <p>2005</p>
          </th>
        </tr>
        <tr>
          <th>
            <p>Herring</p>
          </th>
          <td>
            <p>9,500</p>
          </td>
          <td>
            <p>8,300</p>
          </td>
        </tr>
        <tr>
          <th>
            <p>Salmon</p>
          </th>
          <td>
            <p>2,900</p>
          </td>
          <td>
            <p>4,200</p>
          </td>
        </tr>
        <tr>
          <th>
            <p>Tuna</p>
          </th>
          <td>
            <p>1,500</p>
          </td>
          <td>
            <p>1,500</p>
          </td>
        </tr>
      </tbody>
    </table>
  </ac:rich-text-body>
</ac:macro>

```

Resulting chart



Time series chart

Here is an example of a time series chart.

Storage format

```
<ac:macro ac:name="chart">
  <ac:parameter ac:name="timePeriod">Month</ac:parameter>
  <ac:parameter ac:name="dataOrientation">vertical</ac:parameter>
  <ac:parameter ac:name="rangeAxisLowerBound">0</ac:parameter>
  <ac:parameter ac:name="dateFormat">MM/yyyy</ac:parameter>
  <ac:parameter ac:name="type">timeSeries</ac:parameter>
  <ac:parameter ac:name="domainaxisrotateticklabel">true</ac:parameter>
  <ac:rich-text-body>
    <table>
      <tbody>
        <tr>
          <th>
            <p>Month</p>
          </th>
          <th>
            <p>Revenue</p>
          </th>
        </tr>
        <tr>
          <td>
            <p>1/2005</p>
          </td>
          <td>
            <p>31.8</p>
          </td>
        </tr>
        <tr>
          <td>
            <p>2/2005</p>
          </td>
          <td>
            <p>41.8</p>
          </td>
        </tr>
        <tr>
          <td>

```



<p>3/2005</p>	
</td>	
<td>	
<p>51.3</p>	
</td>	
</tr>	
<tr>	
<td>	
<p>4/2005</p>	
</td>	
<td>	
<p>33.8</p>	
</td>	
</tr>	
<tr>	
<td>	
<p>5/2005</p>	
</td>	
<td>	
<p>27.6</p>	
</td>	
</tr>	
<tr>	
<td>	
<p>6/2005</p>	
</td>	
<td>	
<p>49.8</p>	
</td>	
</tr>	
<tr>	
<td>	
<p>7/2005</p>	
</td>	
<td>	
<p>51.8</p>	
</td>	
</tr>	
<tr>	
<td>	
<p>8/2005</p>	
</td>	
<td>	
<p>77.3</p>	
</td>	
</tr>	
<tr>	
<td>	
<p>9/2005</p>	
</td>	
<td>	
<p>73.8</p>	
</td>	
</tr>	
<tr>	
<td>	
<p>10/2005</p>	
</td>	
<td>	
<p>97.6</p>	
</td>	
</tr>	
<tr>	

```
<td>
  <p>11/2005</p>
</td>
<td>
  <p>101.2</p>
</td>
</tr>
<tr>
  <td>
    <p>12/2005</p>
  </td>
  <td>
    <p>113.7</p>
  </td>
</tr>
</tbody>
</table>
<table>
  <tbody>
    <tr>
      <th>
        <p>Month</p>
      </th>
      <th>
        <p>Expenses</p>
      </th>
    </tr>
    <tr>
      <td>
        <p>1/2005</p>
      </td>
      <td>
        <p>41.1</p>
      </td>
    </tr>
    <tr>
      <td>
        <p>2/2005</p>
      </td>
      <td>
        <p>43.8</p>
      </td>
    </tr>
    <tr>
      <td>
        <p>3/2005</p>
      </td>
      <td>
        <p>45.3</p>
      </td>
    </tr>
    <tr>
      <td>
        <p>4/2005</p>
      </td>
      <td>
        <p>45.0</p>
      </td>
    </tr>
    <tr>
      <td>
        <p>5/2005</p>
      </td>
```

```
<td>
  <p>44.6</p>
</td>
</tr>
<tr>
  <td>
    <p>6/2005</p>
  </td>
  <td>
    <p>43.8</p>
  </td>
</tr>
<tr>
  <td>
    <p>7/2005</p>
  </td>
  <td>
    <p>51.8</p>
  </td>
</tr>
<tr>
  <td>
    <p>8/2005</p>
  </td>
  <td>
    <p>52.3</p>
  </td>
</tr>
<tr>
  <td>
    <p>9/2005</p>
  </td>
  <td>
    <p>53.8</p>
  </td>
</tr>
<tr>
  <td>
    <p>10/2005</p>
  </td>
  <td>
    <p>55.6</p>
  </td>
</tr>
<tr>
  <td>
    <p>11/2005</p>
  </td>
  <td>
    <p>61.2</p>
  </td>
</tr>
<tr>
  <td>
    <p>12/2005</p>
  </td>
  <td>
    <p>63.7</p>
  </td>
</tr>
</tbody>
```

```
</table>
</ac:rich-text-body>
</ac:macro>
```

Resulting chart




XY line chart

Here is an example of an XY line chart.

Storage format

```
<ac:macro ac:name="chart">
  <ac:parameter ac:name="type">xyline</ac:parameter>
  <ac:rich-text-body>
    <table>
      <tbody>
        <tr>
          <th>
            <p>&nbsp;</p>
          </th>
          <th>
            <p>12</p>
          </th>
          <th>
            <p>14</p>
          </th>
          <th>
            <p>23</p>
          </th>
        </tr>
        <tr>
          <td>
            <p>Revenue</p>
          </td>
          <td>
            <p>41.1</p>
          </td>
          <td>
            <p>31.8</p>
          </td>
          <td>
            <p>12.4</p>
          </td>
        </tr>
        <tr>
          <td>
            <p>Expense</p>
          </td>
          <td>
            <p>31.1</p>
          </td>
          <td>
            <p>41.8</p>
          </td>
          <td>
            <p>43.6</p>
          </td>
        </tr>
      </tbody>
    </table>
  </ac:rich-text-body>
</ac:macro>
```

Resulting chart



XY bar chart

Here is an example of an XY bar chart.


Storage format

```

<ac:macro ac:name="chart">
  <ac:parameter ac:name="opacity">60</ac:parameter>
  <ac:parameter ac:name="type">xybar</ac:parameter>
  <ac:rich-text-body>
    <table>
      <tbody>
        <tr>
          <th>
            <p>&nbsp;</p>
          </th>
          <th>
            <p>2005</p>
          </th>
          <th>
            <p>2006</p>
          </th>
          <th>
            <p>2007</p>
          </th>
        </tr>
        <tr>
          <td>
            <p>Revenue</p>
          </td>
          <td>
            <p>41.1</p>
          </td>
          <td>
            <p>31.8</p>
          </td>
          <td>
            <p>12.4</p>
          </td>
        </tr>
        <tr>
          <td>
            <p>Expense</p>
          </td>
          <td>
            <p>31.1</p>
          </td>
          <td>
            <p>41.8</p>
          </td>
          <td>
            <p>43.6</p>
          </td>
        </tr>
      </tbody>
    </table>
  </ac:rich-text-body>
</ac:macro>

```

Resulting chart

***XY area chart***

Here is an example of an XY area chart.


Storage format


```

<ac:macro ac:name="chart">
  <ac:parameter ac:name="type">xyarea</ac:parameter>
  <ac:rich-text-body>
    <table>
      <tbody>
        <tr>
          <th>
            <p>&nbsp;</p>
          </th>
          <th>
            <p>12</p>
          </th>
          <th>
            <p>14</p>
          </th>
          <th>
            <p>23</p>
          </th>
        </tr>
        <tr>
          <td>
            <p>Revenue</p>
          </td>
          <td>
            <p>41.1</p>
          </td>
          <td>
            <p>31.8</p>
          </td>
          <td>
            <p>12.4</p>
          </td>
        </tr>
        <tr>
          <td>
            <p>Expense</p>
          </td>
          <td>
            <p>31.1</p>
          </td>
          <td>
            <p>41.8</p>
          </td>
          <td>
            <p>43.6</p>
          </td>
        </tr>
      </tbody>
    </table>
  </ac:rich-text-body>
</ac:macro>

```

Resulting chart



Area chart

Here are two examples of area charts.

Storage format for area chart 1

```
<ac:macro ac:name="chart">
  <ac:parameter ac:name="height">300</ac:parameter>
  <ac:parameter ac:name="legend">true</ac:parameter>
  <ac:parameter ac:name="width">300</ac:parameter>
  <ac:parameter ac:name="opacity">50</ac:parameter>
  <ac:parameter ac:name="type">area</ac:parameter>
  <ac:parameter ac:name="dataDisplay">true</ac:parameter>
  <ac:rich-text-body>
    <table>
      <tbody>
        <tr>
          <th>
            <p>Satisfaction</p>
          </th>
          <th>
            <p>2002</p>
          </th>
          <th>
            <p>2003</p>
          </th>
          <th>
            <p>2004</p>
          </th>
        </tr>
        <tr>
          <td>
            <p>Very satisfied</p>
          </td>
          <td>
            <p>20</p>
          </td>
          <td>
            <p>23</p>
          </td>
          <td>
            <p>34</p>
          </td>
        </tr>
      </tbody>
    </table>
  </ac:rich-text-body>
</ac:macro>
```


```
</td>
</tr>
<tr>
  <td>
    <p>Satisfied</p>
  </td>
  <td>
    <p>40</p>
  </td>
  <td>
    <p>34</p>
  </td>
  <td>
    <p>23</p>
  </td>
</tr>
<tr>
  <td>
    <p>Disatisfied</p>
  </td>
  <td>
    <p>25</p>
  </td>
  <td>
    <p>26</p>
  </td>
  <td>
    <p>25</p>
  </td>
</tr>
<tr>
  <td>
    <p>Very dissatisfied</p>
  </td>
  <td>
    <p>15</p>
  </td>
  <td>
    <p>17</p>
  </td>
  <td>
    <p>18</p>
  </td>
</tr>
</tbody>
```

```

    </table>
  </ac:rich-text-body>
</ac:macro>

```

Resulting area chart 1



Satisfaction	2002	2003	2004
Very satisfied	20	23	34
Satisfied	40	34	23
Disatisfied	25	26	25
Very disatisfied	15	17	18

Storage format for area chart 2

```

<ac:macro ac:name="chart">
  <ac:parameter ac:name="stacked">true</ac:parameter>
  <ac:parameter ac:name="height">300</ac:parameter>
  <ac:parameter ac:name="legend">true</ac:parameter>
  <ac:parameter ac:name="width">300</ac:parameter>
  <ac:parameter ac:name="type">area</ac:parameter>
  <ac:parameter ac:name="dataDisplay">true</ac:parameter>
  <ac:rich-text-body>
    <table>
      <tbody>
        <tr>
          <th>
            <p>Satisfaction</p>
          </th>
          <th>
            <p>2002</p>
          </th>
          <th>
            <p>2003</p>
          </th>
          <th>
            <p>2004</p>
          </th>

```


```
</th>
</tr>
<tr>
  <td>
    <p>Very satisfied</p>
  </td>
  <td>
    <p>12</p>
  </td>
  <td>
    <p>23</p>
  </td>
  <td>
    <p>31</p>
  </td>
</tr>
<tr>
  <td>
    <p>Satisfied</p>
  </td>
  <td>
    <p>1</p>
  </td>
  <td>
    <p>34</p>
  </td>
  <td>
    <p>36</p>
  </td>
</tr>
<tr>
  <td>
    <p>Disatisfied</p>
  </td>
  <td>
    <p>4</p>
  </td>
  <td>
    <p>6</p>
  </td>
  <td>
    <p>22</p>
  </td>
</tr>
<tr>
  <td>
    <p>Very dissatisfied</p>
  </td>
  <td>
    <p>2</p>
  </td>
  <td>
    <p>7</p>
  </td>
  <td>
    <p>12</p>
  </td>
</tr>
</tbody>
```

```

</table>
</ac:rich-text-body>
</ac:macro>

```

Resulting area chart 2



Satisfaction	2002	2003	2004
Very satisfied	12	23	31
Satisfied	1	34	36
Disatisfied	4	6	22
Very disatisfied	2	7	12

Confluence Wiki Markup

This page describes the wiki markup used on some administration screens in Confluence. Another page describes the [wiki markup for macros](#).

Wiki markup is useful when you want to do one of the following:

- Configure the [Documentation theme](#).
- Type wiki markup directly into the editor. Confluence will convert it to the rich text editor format as you type.
- Create [links](#) using the **Advanced** tab of the Links Browser.
- Insert a block of wiki markup into the Confluence editor. (Choose **Insert > Wiki Markup**.)

Note: You cannot edit content in wiki markup. Confluence does not store page content in wiki markup. Although you can enter wiki markup into the editor, Confluence will convert it to the rich text editor format immediately. You will not be able to edit the wiki markup after initial entry.

A request from the Atlassian technical writers about comments and feedback: When adding comments to this page, please restrict your comments to constructive feedback on the documentation itself: Things we've missed in the documentation, and things that will be useful to other readers. If you have other feedback about the editor, wiki markup, the XML storage format, and Confluence 4 in general, please add your comments in the section titled [Confluence 4 Editor - Customer Feedback](#), and its child pages. Our reason for this request: When a page attracts a large number of comments, it makes it difficult for everyone to read the page, and to add or respond to comments about the documentation. Thanks. 😊

Can I type wiki markup into the editor?

Yes. You can type wiki markup directly into the editor, and Confluence will convert it as you type. (You cannot edit the wiki markup after conversion.) **See it in action in this video:**

Read this blog post for more examples: [12 Things You Didn't Know About the Confluence Editor](#).

On this page:

- [Can I type wiki markup into the editor?](#)
- [Headings](#)
- [Lists](#)
- [Tables](#)
- [Text Effects](#)
- [Text Breaks](#)
- [Links](#)
- [Images](#)
- [Page Layouts](#)
- [Useful Information](#)

Related pages:

- [Confluence Wiki Markup for Macros](#)
- [Confluence User's Guide](#)

Headings

To format a line as a heading, type "hn." at the start of your line, where n can be a number from 1 to 6.

What you need to type	What you will get
h1. Biggest heading	Biggest heading
h3. Big heading	<i>Big heading</i>
h5. Small heading	<i>Small heading</i>

Lists

Wiki markup allows you to create bulleted or numbered lists, and is flexible enough to allow a combination of the two list types.

i If you need to separate the text within lists using line breaks, make sure you do so using a double slash (//). Empty lines may disrupt the list.

Simple lists

Use the hyphen (-) to create simple lists.

Make sure there is a space between the hyphen and your text.

What you need to type	What you will get

```
- some
- bullet
- points
```

- some
- bullet
- points

Bulleted lists

Use the asterisk (*) to create bullets. For each subsequent level, add an extra asterisk. Make sure there is a space between the asterisk and your text.

What you need to type

```
* some
* bullet
** indented
** bullets
* points
```

What you will get

- some
- bullet
 - indented
 - bullets
- points

Numbered lists

Use the hash (#) to create numbered lists. Make sure there is a space between the hash and your text.

What you need to type

```
# a
# numbered
# list
```

What you will get

1. a
2. numbered
3. list

A second level of hashes will produce a sub-list, such as the **alphabetical** sub-list shown below.

What you need to type

```
# Here's a sentence.
## This is a sub-list point.
## And a second sub-list point.
# Here's another sentence.
```

What you will get

1. Here's a sentence.
 - a. This is a sub-list point.
 - b. And a second sub-list point.
2. Here's another sentence.

You can use a third level of hashes to produce a sub-sub-list.

What you need to type

What you will get


```
# Here's a sentence.
## This is a sub-list point.
### Third list level.
### Another point at the third
level.
## And a second sub-list point.
# Here's another sentence.
```

1. Here's a sentence.
 - a. This is a sub-list point.
 - i. Third list level.
 - ii. Another point at the third level.
 - b. And a second sub-list point.
2. Here's another sentence.

Note: In numbered lists as described above, the format of the 'number' displayed at each list level may be different, depending upon your browser and the style sheets installed on your Confluence instance. So in some cases, you may see letters (A, B, C, etc; or a, b, c, etc) or Roman numerals (i, ii, iii, etc) at different list levels.

Mixed lists

What you need to type	What you will get
<pre># Here #* is #* an # example #* of #* a # mixed # list</pre>	1. Here • is • an 2. example • of • a 3. mixed 4. list

Tables

You can create two types of tables.

Table Type 1

Allows you to create a simple table with an optional header row. You cannot set the width of the columns in this table.

Use double bars for a table heading row.

What you need to type:

```
||heading 1||heading 2||heading 3||
|cell A1|cell A2|cell A3|
|cell B1|cell B2|cell B3|
```

What you will get:

heading 1	heading 2	heading 3
cell A1	cell A2	cell A3
cell B1	cell B2	cell B3

You can also use a vertical header.

What you need to type:

```
||heading 1|col A1|col A2|col A3|
||heading 2|col B1|col B2|col B3|
```

What you will get:

heading 1	col A1	col A2	col A3
heading 2	col B1	col B2	col B3

Table Type 2

This method allows you to specify the width of the columns in the table.

What you need to type

```
{section:border=true}
{column:width=30%}
Text for this column goes here. This is the smaller column with a width of only
30%.
{column}
{column:width=70%}
Text for this column goes here. This is the larger column with a width of 70%.
{column}
{section}
```

What you will get

Text for this column goes here. This is the smaller column with a width of only 30%.

Text for this column goes here. This is the larger column with a width of 70%.

 For more details please see the [Column Macro](#) and the [Section Macro](#).

Advanced Formatting**Colour and Other Formatting**

To add colour and other formatting to your tables, you can use the [Panel Macro](#) within columns. More table-formatting options may be available if your Confluence administrator has installed additional [macros](#).

Here's an example of how to embed lists in a table:

What you need to type

```
||Heading 1||Heading 2||
|* Item 1
* Item 2
* Item 3|# Item 1
# Item 2
# Item 3|
```

What you will get

Heading 1	Heading 2
- Item 1 - Item 2 - Item 3	- Item 1 - Item 2 - Item 3

Text Effects

Use the markup shown in the examples below to format text.

What you need to type	What you will get
<code>*strong*</code>	strong
<code>*bold text*</code>	bold text
<code>_emphasis_</code>	<i>emphasis</i>
<code>_italics_</code>	<i>italics</i> <i>Hint: To italicise parts of a word, add braces (curly brackets) around the underscore. For example, Thing{ }x_ gives you this: Thingx</i>
<code>??citation??</code>	— <i>citation</i>
<code>-deleted-</code>	~~deleted~~
<code>+inserted+</code>	<ins>inserted</ins>
Text with ^{superscript}	Text with ^{superscript} <i>Hint: There are two ways to make superscripts work, when used directly after another word or character:</i> • Add a space before the superscript. For example, kg/m ^3^ gives you this: kg/m ³ • Add braces (curly brackets) around the superscript markup. For example, kg/m{^3^} gives you this: kg/m³
Text with~subscript~	Text with _{subscript}
<code>{{monospaced}}</code>	monospaced
bq. Here's how you make a paragraph appear as a block quotation.	<i>Here's how you make a paragraph appear as a block quotation.</i>
<code>{color:red}look ma, red text!{color}</code>	look ma, red text!

Text Breaks

Paragraph Break

In wiki markup, a paragraph is a continuous line of text ending in two carriage returns. This is equivalent to a continuous line of text followed by a blank line.

When rendered into HTML, the result is a line of text wrapped in a set of `<p></p>` tags.

Line Break

Confluence provides two options for forcing a line break within a paragraph of text:

- Implicitly, by entering a single carriage return at its end.
- Explicitly, by entering two consecutive backslashes: `\\`

When rendered into HTML, the result is a paragraph of text that is split into separate lines by `<br>` tags, wherever a forced line break appears.

 For most purposes, explicit line breaks are not required because a single carriage return is enough.

The examples below show how to use explicit line breaks.

What you need to type	What you will get
here is some text \\ divided \\ using line \\ \\ breaks\\	here is some text divided using line breaks
This is a short list: * Point 1 Text to go with point 1 * Point 2 \\ \\ Text to go with point 2 with a break	This is a short list: • Point 1 Text to go with point 1 • Point 2 Text to go with point 2 with a break

If you wish to use multiple consecutive line breaks, each should be separated by a space character. For example, use this for two consecutive line breaks:

`\\ \\`

Horizontal Rule

To create a horizontal line across the width of your page or content block, type four dashes (like this: `----`) at the beginning of a line, then press Enter or space.

Make sure that the dashes are on a separate line from the rest of the text.

What you need to type	What you will get

here is some text ---- divided by a horizontal rule	here is some text divided by a horizontal rule

Links

You can use wiki markup to add hyperlinks to your text.

What you need to type	What you will get
[#anchor]	A link to an anchor on the same page.
[Confluence Wiki Markup^attachment.ext]	A link to a file attached to the page.
[pagetitle]	A link to a page.
[pagetitle#anchor]	A link to an anchor on another page.
[pagetitle^attachment.ext]	A link to a file attached to another page.
[spacekey:pagetitle]	A link to a page in another space.
[spacekey:pagetitle#anchor]	A link to an anchor on a page in another space.
[spacekey:pagetitle^attachment.ext]	A link to a file attached to a page in another space.
[/2004/01/12/blogposttitle]	A link to a blog post.
[spacekey:/2004/01/12/blogposttitle]	A link to a blog post in another space.
[/2004/01/12]	A link to a whole day's blog posts.
[spacekey:/2004/01/12]	A link to a whole day's blog posts in another space.
[spacekey:]	A link to the space homepage (or the space summary page of the space).
[~username]	A link to the user profile page of a particular user.
[phrase@shortcut]	A shortcut link to the specified shortcut site. Shortcuts are configured by the site administrator.
[http://confluence.atlassian.com]	A link to an external resource.
[mailto:legendaryservice@atlassian.com]	A link to an email address.
[file://z:/file/on/network/share.txt]	A link to a file on your computer or on a network share that you have mapped to a drive. <i>This only works on Internet Explorer.</i>

Note that Confluence treats headings as anchors, so you can link to headings using this pattern: [spacekey:pagename#headingname], where headingname is case-sensitive and must be entered without spaces.

For each of these link forms:

- You can prepend a link alias, so that alternate text is displayed on the page. Example: [link alias|pagetitle#anchor]

- You can append a link tip, which appears as a tooltip. Example: [pagetitle#anchor|link tip]

Images

You can display images from attached files or remote sources.

What you need to type	What you will get
!http://www.host.com/image.gif!	An image from a remote source is displayed on the page. Uses a fully qualified URL.
!attached-image.gif!	An image file attached to the page is displayed.
!pageTitle^image.gif!	An image file attached to a different page is displayed.
!spaceKey:pageTitle^image.gif!	An image file attached to a page in a different space is displayed.
!/2010/05/23/My Blog Post^image.gif!	An image file attached to a blog post is displayed.
!image.jpg thumbnail!	The image is displayed as a thumbnail on the page (only works with images that are attached to the page). Users can click on the thumbnail to see the full-sized image. Thumbnails must be enabled by the site administrator for this to work.
!image.gif align=right, vspace=4!	For any image, you can specify attributes of the HTML image tag as a comma separated list of name=value pairs.

Available HTML image tags include:

Image tag	Details
align	Available values are 'left', 'right', 'bottom', 'center', 'top'.
border	Specifies the width of the border (in pixels).
bordercolor	Use with the 'border' tag. Specify colours by name or hex value.
hspace	Specifies the amount of whitespace to be inserted to the left and right of the image (in pixels).
vspace	Specifies the amount of whitespace to be inserted above and below the image (in pixels).
width	Specifies the width of the image (in pixels). This will override the natural width of the image.
height	Specifies the height of the image (in pixels). This will override the natural height of the image.
title	Specifies alternate text for the image, which is displayed when the pointer hovers over the image.

alt	Specifies alternate text for the image. This text is retrievable via search, and contributes to accessibility of the page for text-only viewing.

Page Layouts

There is no wiki markup representation for page layouts.

Useful Information

- A **space key** is a short, unique identifier for a space. For example, you might give your documentation space a key of "DOC". To find the key of an existing space, look at the Confluence URL for a page in the space. The standard Confluence URL has this format:

```
http://my.confluence.site.com/display/SPACEKEY/Page+Name
```

- If you would like to edit the XML source of a page, your Confluence system administrator will need to install the [Confluence Source Editor](#) plugin. See more about the [Confluence Storage Format](#).
- *Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#).*

Confluence Wiki Markup for Macros



Work in progress

We are adding the details for each macro in turn. They are not all here yet. See

CONF-24972 - [Authenticate](#) to see issue details . In the meantime, please refer to the [Confluence 3.5 macro documentation](#).

This page is an extension of [Confluence Wiki Markup](#). It describes the wiki markup used to define specific Confluence macros – the macros that are shipped with Confluence. For each macro, we define the macro name, parameter names, and accepted parameter values.

Wiki markup is useful when you want to do one of the following:

- Configure the [Documentation theme](#).
- Type wiki markup directly into the editor. Confluence will convert it to the rich text editor format as you type.
- Create [links](#) using the **Advanced** tab of the Links Browser.
- Insert a block of wiki markup into the Confluence editor. (Choose **Insert > Wiki Markup**.)

Note: You cannot edit content in wiki markup. Confluence does not store page content in wiki markup. Although you can enter wiki markup into the editor, Confluence will convert it to the rich text editor format immediately. You will not be able to edit the wiki markup after initial entry.

Anchor macro

Allows you to link to a specific part of a page.

Macro name: anchor

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
default-parameter (Unnamed in wiki markup)	Yes	(None)	The name of the anchor.

Example:

```
{anchor:here}
```


On this page:

- [Anchor macro](#)
- [Attachments macro](#)
- [Blog Posts macro](#)
- [Change-History macro](#)
- [Chart macro](#)
- [Cheese macro](#)
- [Children Display macro](#)
- [Code Block macro](#)
- [Column macro](#)
- [Content by Label macro](#)
- [Content by User macro](#)
- [Content Report Table macro](#)
- [Contributors macro](#)
- [Contributors Summary macro](#)
- [Create Space Button macro](#)
- [Excerpt Include macro](#)
- [Excerpt macro](#)
- [Expand macro](#)
- [Favourite Pages macro](#)
- [Gadget macro](#)
- [Gallery macro](#)
- [Global Reports macro](#)
- [HTML Include macro](#)
- [HTML macro](#)
- [IM Presence macro](#)
- [Include Page macro](#)
- [Info macro](#)
- [JIRA Issues macro](#)
- [JUnit Report macro](#)
- [Labels List macro](#)
- [Livesearch macro](#)
- [Loremipsum macro](#)
- [Multimedia macro](#)
- [Page Properties macro](#)
- [Page Properties Report macro](#)
- [Section macro](#)
- [Table of Contents macro](#)
- [Notes](#)

Related pages:

- [Confluence Wiki Markup](#)
- [Working with Confluence Markup](#)
- [Working with Macros](#)
- [Confluence User's Guide](#)

Attachments macro

Displays a list of attachments on a given page.

Macro name: attachments

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
old	No	false	Available values: • false - Displays only the latest version of each attachment. • true – Displays all versions of each attachment, including the old versions.
patterns	No	(None)	A comma-separated list of regular expressions, used to filter the attachments by file name. Note that the parameter values must be regular expressions. For example: • To match a file suffix of 'jpg', use <code>.*jpg</code> (not <code>*.jpg</code>). • To match file names ending in 'jpg' or 'png', use <code>.*jpg,.*png</code> Here is a tutorial on regular expressions.
sortBy	No	date	Available values: • date • size • name
page	No	The page on which the macro exists.	Page name, used to display attachments from another page.
sortOrder	No	The default sort order is determined by the sortBy type: • Reverse chronological for 'date'. • Largest to smallest for 'size'. • Alphabetical for 'name'.	Available values: • ascending • descending

labels	No	(None)	A comma-separated list of labels. Confluence will show only attachments that have all the labels specified. (The match is an AND, not an OR.)
upload	No	false	Determines whether the list of attachments will include options allowing users to browse for, and attach, new files.

Example:

```
{attachments:old=false|patterns=.*png,.*jpg|sortBy=name|page=My page about chocolate|sortorder=descending|labels=chocolate,cookies|upload=false}
```

Blog Posts macro

Lists the most recent news items in the space.

Macro name: blog-posts

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
content	No	entire	Available values: - entire – Display the whole content of each blog post. - excerpts – Display a short extract from each blog post. If the post contains an Excerpt macro, the Blog Posts macro will display the content defined in the Excerpt macro. If the post does not contain an Excerpt macro, the Blog Posts macro will display the first few sentences of the post. - titles – Display a list of blog posts, showing titles only.

spaces	No	@self	One or more space keys, separated by a comma or a space. • To exclude content in a specific space, put a minus sign (-) immediately in front of that space key. For example: If you specify a space key of -BADSPACE you will get only content which is not in the BADSPACE. • To indicate that the results must come from a specific space, put a plus sign (+) immediately in front of that space key. For example: If you specify a space key of +GOODSPACE you will get only content in GOODSPACE. (Note that this is not particularly useful, because each content item belongs to one space only. If you put a plus sign next to one space key and list other space keys too, the other space keys will be ignored.) Special values:

			• <code>@self</code> — The current space. • <code>@personal</code> — All personal spaces. • <code>@global</code> — All site spaces. • <code>@favorite</code> — The spaces you have marked as favourite. • <code>@favourite</code> — The same as <code>@favorite</code> above. • <code>@all</code> — All spaces in your Confluence site. • <code>*</code> — The same as <code>@all</code> above. When specifying a personal space, remember to use the tilde (~) sign in front of the username, such as <code>~jbloggs</code> or <code>~jbloggs@example.com</code>.
author	No	(None)	One or more usernames, separated by commas.
time	No	(None)	Available values: • <code>m</code> — Minutes • <code>h</code> — Hours • <code>d</code> — Days • <code>w</code> — Weeks For example, • <code>time=12h</code> – Display blog posts created in the last twelve hours. • <code>time=7d</code> – Display blog posts created in the last seven days.
reverse	No	false	A value of <code>true</code> changes the sort order.

sort	No	creation	Available values: • title — Sort alphabetically by title. • creation — Sort by the date on which the content was added. • modified — Sort by the date on which the content was last updated.
max	No	15	The maximum number of results to be displayed.
label	No	(None)	One or more label values, separated by a comma or a space. • To exclude content which matches a given label, put a minus sign (-) immediately in front of that label value. For example: If you specify a label value of -badpage you will get only content which is not labelled with 'badpage'. • To indicate that the results must match a given label value, put a plus sign (+) immediately in front of that label value. For example: If you specify a label value of +superpage, +goodpage you will get only content which has at least two labels, being 'superpage' and 'goodpage'.

Example:

```
{blog-posts:content=titles|spaces=@self,ds|author=jsmith|time=4w|reverse=true|sort=creation|max=10|label=chocolate,cookies}
```

Change-History macro

Displays a history of updates made to a page.

Macro name: change-history

Macro body: None.

Parameters: None

Example:

```
{change-history}
```

Chart macro

Displays a chart based on tabular data.

Macro name: chart

Macro body: Accepts rich text, consisting of tables that hold the chart's data.

This macro recognises a large number of parameters, listed here by type for convenience.

Chart type parameters

These parameters determine the type of chart to display and how the chart looks.

Parameter	Required	Default	Description
type	No	pie	The type of chart to display. XY charts have numerical x- and y-axes. The x values may optionally be time-based. See the <code>timeSeries</code> parameter. Available values: • <i>Standard charts</i> - pie, bar, line, area • <i>XY plots</i> – xyArea, xyBar, xyLine, xyStep, xyStepArea, scatter, timeSeries • <i>Other charts</i> – gantt (beta)

orientation	No	vertical	The display orientation. Applies to area, bar and line charts. Available values: • vertical – y-axis is vertical • horizontal – x-axis is vertical
3D	No	false	Show in three dimensions. Applies to area, bar and line charts.
stacked	No	false	Stacked values. Applies to area and bar charts.
showShapes	No	true	Applies to line charts. Shapes are shown at each data point.
opacity	No	• 75 percent for 3D charts • 50 percent for non-stacked area charts • 100 percent for all other charts	A percentage value between 0 (transparent) and 100 (opaque) that determines how opaque the foreground areas and bars are.

Chart display parameters

Parameter	Required	Default	Description
width	No	300	The width of the chart in pixels.
height	No	300	The height of the chart in pixels.

dataDisplay	No	false	Determines whether to display the body of the macro, consisting of the data table. By default, the chart data table is not displayed. Available values: • false – the data is not displayed. • true or after – the data is displayed after the chart. • before – the data is displayed before the chart.
imageFormat	No	png	The image format to be used for the chart. Available values: • png • jpg

Chart title and label parameters

Parameter	Required	Default	Description
title	No	(None)	The title of the chart.
subTitle	No	(None)	A subtitle for the chart.
xLabel	No	(None)	The label for the x-axis (domain).
yLabel	No	(None)	The label for the y-axis (range).
legend	No	false	Determines whether to show a legend (key) for the chart.

Chart data parameters

The data for the chart is taken from tables found in the macro body. The parameters below control how this data is interpreted. By default, numeric and date values are interpreted according to the Confluence global default language (locale) formats. If conversion fails, other languages defined in Confluence will be tried. You can specify additional conversion options using the parameters below.

Parameter	Required	Default	Description

tables	No	All first level tables	You can supply a comma-separated list of table IDs and/or table numbers (starting at 1) contained within the body of the macro that will be used as the data for the chart. If data tables are embedded in other tables, then table selection will be required. This occurs when more complex formatting is done (for example using section and column macros).
columns	No	All columns	You can supply a comma-separated list of column labels and/or column titles and/or column numbers for tables used for chart data. This applies to all tables processed. Columns are enumerated starting at 1. Column label is the text for the column in the header row. Column title is the HTML title attribute for the column in the header row.
dataOrientation	No	horizontal	The content orientation. By default, the data tables will be interpreted as columns (horizontally) representing domain and x values. Available values: • <code>vertical</code> – data table columns will be interpreted as series. • <code>horizontal</code> – data tables rows will be interpreted as series.

timeSeries	No	false	If 'true', the x values in an XY plot will be treated as time series data and so will be converted according date formats.
dateFormat	No	Confluence language defined date formats	For time series data, the date format allows for additional customisation of the conversion of data to date values. If a date Format is specified, it will be the first format used to interpret date values. Specify a format that matches the time series data. See simple date format .
timePeriod	No	day	The time period for time series data. Defines the granularity of how the data is interpreted. Available values: milli second, second, minute, hour, day, week, month, quarter, year
language	No	(None)	Use in combination with the country parameter to form a locale. These additional number and date formats will be used for data conversion before the default languages. Available values are the two-character ISO 639-1 alpha-2 codes .
country	No	(None)	Use in combination with the language parameter to form a locale. Valid values are the two-character ISO 3166 codes .

forgive	No	true	Determines whether the macro will forgive (allow) some data formatting errors. Available values: <code>true</code> — the macro tries to convert numeric and date values that do not totally match any of the default or user-specified formats. <code>false</code> — the macro enforces strict data formatting. If there are data format errors, the chart will not be produced.

Chart colour parameters

Colours are specified using hexadecimal notation or HTML colour names.

Parameter	Required	Default	Description
<code>bgColor</code>	No	White	Background colour of the chart.
<code>borderColor</code>	No	No border	Colour of the border around the chart.
<code>colors</code>	No		A comma-separated list of colours used to customise the colours of categories, sections, and series.

Chart axis parameters

Depending on the chart type, the range and domain axis may be customised. These values are automatically generated based on the data but can be overridden by specifying one or more more of these parameters.

Parameter	Required	Default	Description
<code>rangeAxisLowerBound</code>	No	(None)	Minimum value for the range axis.
<code>rangeAxisUpperBound</code>	No	(None)	Maximum value for the range axis.
<code>rangeAxisTickUnit</code>	No	(None)	Range axis units between axis tick marks.

rangeAxisLabelAngle	No	(None)	Angle for the range axis label in degrees.
domainAxisLowerBound	No	(None)	Only applies to XY plots. Domain axis lower bound. For a date axis, this value must be expressed in the date format specified by the dateFormat parameter.
domainAxisUpperBound	No	(None)	Only applies to XY plots. Domain axis upper bound. For a date axis, this value must be expressed in the date format specified by the dateFormat parameter.
domainAxisTickUnit	No	(None)	Only applies to XY plots. Domain axis units between axis tick marks. For a date axis, this value represents a count of the units specified in the timePeriod parameter. The timePeriod unit can be overridden by specifying a trailing character: y (years), M (months), d (days), h (hours), m (minutes), s (seconds), u (milliseconds).
domainAxisLabelAngle	No	(None)	Only applies to XY plots. The angle for the domain axis label, in degrees.
categoryLabelPosition	No	(None)	Placement of the axis label text for categories. Available values: • up45 — 45 degrees going upward • up90 — 90 degrees going upward • down45 — 45 degrees going downward • down90 — 90 degrees going downward

dateTickMarkPosition	No	start	Placement of the date tick mark. Available values: • start — tick mark is at the start of the date period. • middle — tick mark is in the middle of the date period. • end — tick mark is at the end of the date period.

Pie chart Parameters

Parameter	Required	Default	Description
pieSectionLabel	No	Show only the pie section key value	Format of pie section labels. The format uses a string with special replacement variables: • %0% is replaced by the pie section key. • %1% is replaced by the pie section numeric value. • %2% is replaced by the pie section percent value. Example 1: To display something like 'Independent = 20': <pre>%0% = %1%</pre> Example 2: To display something like 'Independent (20%)': <pre>%0% (%2%)</pre>

pieSectionExplode	No	No exploded sections	A comma-separated list of pie keys that are to be shown exploded. Note: requires jFreeChart version 1.0.3 or higher.

Chart attachment parameters

These are advanced options that can be used for chart versioning, to enable automation and to improve performance. Use these options carefully! Normally, the chart image is regenerated each time the page is displayed. These options allow for the generated image to be saved as an attachment and have subsequent access to re-use the attachment. This can be useful especially when combined with the Cache plugin to improve performance. Depending on the options chosen, chart images can be versioned for historical purposes.

Parameter	Required	Default	Description
attachment	No	(None)	The name and location where the chart image will be saved as an attachment. The user must be authorised to add attachments to the page specified. Available syntax for this parameter: • <code>^attachmentName.png</code> — the chart is saved as an attachment to the current page. • <code>page name^attachmentName.png</code> — the chart is saved as an attachment to the page name provided. • <code>spacekey:page name^attachmentName.png</code> — the chart is saved as an attachment to the page name provided in the space indicated.

attachmentVersion	No	new	Defines the the versioning mechanism for saved charts. Available values: • new — creates new version of the attachment. • replace — replaces all previous versions of the chart. To replace an existing attachment, the user must be authorised to remove attachments for the page specified. • keep — only saves a new attachment if an existing export of the same name does not exist. An existing attachment will not be changed or updated.
attachmentComment	No	(None)	Comment used for a saved chart attachment.
thumbnail	No	false	If true, the chart image attachment will be shown as a thumbnail (small, expandable) image.

Example:

Below is a simple example of a pie chart. See more examples in [Wiki Markup Examples for Chart Macro](#).

```
{chart:type=pie|title=Fish Sold}
|| Fish Type || 2004 || 2005 ||
|| Herring | 9,500 | 8,300 |
|| Salmon | 2,900 | 4,200 |
|| Tuna | 1,500 | 1,500 |
{chart}
```

Cheese macro

Displays the words "I like cheese!"

Macro name: cheese

Macro body: None.

Parameters: None

Example:

```
{cheese}
```

Children Display macro

Displays the children and descendants of the current page.

Macro name: children

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
reverse	No	false	Reverses the sort order in the list of child pages. Use this parameter in conjunction with the sort parameter described below. A value of true will change the sort order from ascending to descending.
sort	No	Manual if the pages have been manually reordered, otherwise alphabeticalby page title	Determines the sort order of the list of child pages. Available values: - creation – Sort by the date on which the page was created. - title – Sort alphabetically by page name. - modified – Sort by the date on which the page was last updated.
style	No	Bullet list	A heading style to be applied to the list of child pages. Available values: h1 (heading level 1) through to h6 (heading level 6).

page	No	The page that contains the macro	The name of the parent page. The macro will display the children of the specified page. To specify a page in a different space, use a space key followed by a colon. For example: MYSPACE:My page If the value of this parameter is a forward slash (/) the macro will list the pages at the root of the current space. In other words, the pages without parents.
excerpt	No	false	If true, Confluence will display any excerpts that are defined on the child pages. The excerpts must be defined via an Excerpt macro.
first	No	(None)	The maximum number of child pages to be displayed (at the top level). For example, if the value of this parameter is 99, the macro will display the first 99 pages at the top level. It will also display their children, as determined by the depth and all parameters
depth	No	(None)	The number of levels of child pages to display. For example, if the value is 2, the macro will display 2 levels of child pages.
all	No	false	If true, Confluence will display all levels of child pages. This setting will override the depth setting.

Example:

```
{children:reverse=true|sort=creation|style=h4|page=Home|excerpt=true|first=99|depth=2|all=true}
```

Code Block macro

Displays code in your document with the appropriate syntax highlighting.

Macro name: code

Macro body: Accepts plain text.

Parameter name	Required	Default	Parameter description and accepted values
title	No	(None)	Adds a title to the code macro box.
theme	No	Confluence	Specifies the colour scheme used for displaying your code. Many of these themes are based on the default colour schemes of popular integrated development environments (IDEs). The default theme is Confluence (also known as Default), which is typically black and coloured text on a blank background. Available themes: • Django • Emacs • FadeToGrey • Midnight • RDark • Eclipse • Confluence (same as default)
linenumbers	No	false	If true, a line number will be shown to the left of each line of code. Numbering is incremented by 1. If false, no line numbers are shown.

language	No	java	Specifies the language (or environment) for syntax highlighting. • (none) — that is, no syntax highlighting • actionscript3 • bash • csharp — that is, C# • coldfusion • cpp — that is, C++ • css • delphi • diff • erlang • groovy • java • javafx • javascript • perl • php • powershell • python • ruby • scala • sql • vb — that is, Visual Basic • html/xml
firstline	No	1	When <code>linenumbers</code> is <code>true</code>, this value defines the number of the first line of code.
collapse	No	false	If <code>true</code>, the code macro's content will be collapsed upon visiting or refreshing the Confluence page. Clicking the 'expand source' link allows you to view the content. If <code>false</code>, the code macro's content is always displayed in full.

Example:

```
{code:title=This is my  
title|theme=FadeToGrey|linenumbers=true|language=html/xml|firstline=0001|collapse=t  
rue}  
This is my code  
{code}
```

Column macro

Used with the Section macro to define columns on a page. See [Working with page layouts and columns and sections](#).

Macro name: column

Macro body: Accepts rich text.

Parameter name	Required	Default	Parameter description and accepted values
width	No	100% of the page width, divided equally by the number of columns in the section.	The width of the column. Can be specified either in pixels (for example, 400 px) or as a percentage of the available page width (for example, 50%).

Example:

```
{column:width=100px}  
This is the content of *column 1*.  
{column}
```

Content by Label macro

Displays a list of content associated with specific labels.

Macro name: contentbylabel

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
spaces	No	@all	

Filters the results by space. The macro will display only the pages and other content types which belong to the space(s) you specify here.

You can specify one or more space keys, separated by a comma or a space.

- To exclude content in a specific space, put a minus sign (-) immediately in front of that space key. For example: If you specify a space key of -BADSPACE you will get only content which is not in the BADSPACE.
- To indicate that the results **must** come from a specific space, put a plus sign (+) immediately in front of that space key. For example: If you specify a space key of +GOODSPACE you will get only content in GOODSPACE. (Note that this is not particularly useful, because each content item belongs to one space only. If you put a plus sign next to one space key and list other space keys too, the other space keys will be ignored.)

Special values:

			• <code>@self</code> — The current space. • <code>@personal</code> — All personal spaces. • <code>@global</code> — All site spaces. • <code>@favorite</code> — The spaces you have marked as favourite. • <code>@favourite</code> — The same as <code>@favorite</code> above. • <code>@all</code> — All spaces in your Confluence site. • <code>*</code> — The same as <code>@all</code> above. When specifying a personal space, remember to use the tilde (~) sign in front of the username, such as <code>~jbl</code> <code>oggs</code> or <code>~jbloggs@example.com</code>.
<code>author</code>	No	(None)	Filters the results by author. The macro will display only the pages and other content types which are written or updated by the author(s) you specify here. You can specify one or more authors, separated by a comma. For example: <code>jsmith,jbrown</code>
<code>title</code>	No	(None)	Adds a heading to the list.
<code>showLabels</code>	No	<code>true</code>	Determines whether to display the matching labels in the list of results.

reverse	No	false	Use this parameter in conjunction with the sort parameter. Set reverse=true to change the sort from ascending to descending. This parameter is ignored if the sort parameter is not specified.
sort	No	modified	Determines how the results are sorted. To change the sort order from ascending to descending, use the reverse parameter described above. If this parameter is not specified, the sort order defaults to descending order based on the last modification date. Values: • title — Sort alphabetically by title. • creation — Sort by the date on which the content was added. • modified — Sort by the date on which the content was last updated.
max	No	15	Determines the maximum number of results to be displayed. Note that the results are sorted first, and then the maximum parameter is applied.

excerpt	No	false	If this parameter is set to <code>true</code>, the macro displays an excerpt from each page listed in the results. Note that you must define the excerpts on each of those pages, by adding the Excerpt macro to each page. If a particular page does not have an excerpt defined, then the Content by Label macro will not attempt to show an excerpt for that page. The Content by Label macro will show only the first few lines of the excerpt for each page.

labels	Yes	(None)	Use this parameter to filter the results by label. The macro will display only the pages and other content types which are tagged with the label(s) you specify here. See also the operator parameter. You can specify one or more label values, separated by a comma or a space. • To exclude content which matches a given label, put a minus sign (-) immediately in front of that label value. For example: If you specify a label value of -badpage you will get only content which is not labelled with 'badpage'. • To indicate that the results must match a given label value, put a plus sign (+) immediately in front of that label value. For example: If you specify a label value of +superpage, +goodpage you will get only content which has at least two labels, being 'superpage' and 'goodpage'.
showSpace	No	true	Determines whether to display the spaces in the list of results.

type	No	All	Filters the results by content type. The macro will display only the content of the type you specify here. You can specify one or more types, separated by a comma or a space. To exclude content of a given content type, put a minus sign (-) immediately in front of that content type. For example: If you specify a content type of -blogpost you will get pages and all other content except for blog posts. Available values: • page — pages. • blogpost or news — blog posts, also known as news items. • attachment — attachments.

operator	No	OR	The operator to apply to the supplied lists of labels. By default, a page with any of the non-prefixed labels (that is, labels without a plus (+) or minus (-) sign immediately preceding it) will be listed. If you specify a value of AND, only pages with all of the supplied non-prefixed labels will be listed. Note that this parameter only modifies the behaviour of the 'Label(s)' parameter and only affects label values without a plus (+) or minus (-) sign prefix. To avoid confusion or unexpected results, we recommend that you do not use the operator parameter in conjunction with any label values prefixed with '+' or '-' signs.

Example:

```
{contentbylabel:spaces=@personal,@self|author=admin,smaddox|title=My labelled
pages|showLabels=false|reverse=true|sort=creation|max=10|excerpt=true|labels=chocol
ate,cake|showSpace=false|type=page|operator=AND}
```

Content by User macro

Displays a list of the content items that have been created by a specified Confluence user.

Macro name: content-by-user

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
default-parameter (Unnamed in wiki markup)	Yes	(None)	The Confluence username for the person whose content you wish to display

Example:

```
{content-by-user:jsmith}
```

Content Report Table macro

Wiki markup is not available for this macro. You cannot add this macro via wiki markup.

Contributors macro

Displays a list of Confluence users who have made a contribution of some type to a page.

Macro name: contributors

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
limit	No	(None)	Limits the number of contributors displayed in the list.
spaces	No	Current space	Specifies the space key of the Confluence space to search. Space keys are case sensitive. Special values: • @global — All site spaces. • @personal — All personal spaces. • @all — All spaces in the Confluence site. You can specify one or more space keys or special values, separated by commas. If no <code>page</code> and <code>labels</code> are specified, all pages from the specified set of spaces are included.
reverse	No	false	Reverses the order of contributors in the list. Must be used in conjunction with the <code>order</code> parameter.

scope	No	The specified page only	Specifies additional pages to include when generating the list of contributors. Available values: • children – only the child pages of the specified page. • descendants – all descendants of the specified page.
labels	No	(None)	Limits the list of contributors to those who created the specified labels on a page. You can specify one or more labels, separated by commas.
showPages	No	false	If the value is true, the macro will display a list of the pages used to generate the list of contributors.
noneFoundMessage	No	"No contributors found for:" (and a summary of selected parameter values)	Any message given here will override the default message that is displayed when no contributors are found.
showCount	No	false	Determines whether the macro will show the number of times each person made a contribution.
contentType	No	Both pages and blog posts	Restricts the content type that the macro will use when generating the list of contributors. Available values: • pages – pages • blogposts – blog posts.

include	No	authors	Filters by either the type of contribution made to a page (and optionally its descendant pages), or the watches on the page. Contribution types are: • <code>authors</code> - includes people who created or have edited the page(s) • <code>comments</code> - includes people who have added comments to the page(s) • <code>labels</code> - includes people who have added labels to the page(s) • <code>watches</code> - includes people who are watching the page(s). You can specify one or more contribution types, separated by commas.
mode	No	inline	Determines how the list of contributors is formatted: • <code>inline</code> — a comma-separated list • <code>list</code> — a bullet list.
showAnonymous	No	false	Determines whether to include those who contributed anonymously to a page.

order	No	count	Specifies the criteria used to sort contributors. Sort criteria are: - count – sorts the names based on the total number of contributions to the page(s) - name – sorts the names into alphabetical order - update – sorts the names by the date of their last contribution to the page(s).
page	No	The current page	Specifies the page to use when generating the list of contributors. If page and spaces are left blank, the current page is assumed.
showLastTime	No	false	Determines whether to show the last time each person made a contribution.
publishDate	No	(None)	Specifies the publication date for a blog post. The date format required is: YYYY/MM/DD.

Example:

This example specifies a content type of blog posts:

```
{contributors:limit=10|spaces=ds,@personal|reverse=true|labels=chocolate, cake|showPages=true|noneFoundMessage=0h dear, no contributors found|showCount=true|contentType=blogposts|include=authors, comments, labels, watches|mode=list|showAnonymous=true|order=update|showLastTime=true|publishDate=2012/06/30}
```

This example specifies a content type of pages:

```
{contributors:limit=10|spaces=ds,@personal|reverse=true|scope=descendants|labels=chocolate, cake|showPages=true|noneFoundMessage=0h dear, no contributors found|showCount=true|contentType=pages|include=authors, comments, labels, watches|mode=list|showAnonymous=true|order=update|page=ds:Advanced Topics|showLastTime=true}
```


Contributors Summary macro

Displays a table of contribution-based statistics for a set of pages.

Macro name: contributors-summary

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
limit	No	(None)	Limits the number of contributors or pages displayed in the table.
spaces	No	Current space	Specifies the space key of the Confluence space to search. Space keys are case sensitive. Special values: • @global — All site spaces. • @personal — All personal spaces. • @all — All spaces in the Confluence site. You can specify one or more space keys or special values, separated by commas. If no page and labels are specified, all pages from the specified set of spaces are included.
reverse	No	false	Reverses the order of items in the table. Must be used in conjunction with the order parameter.
showAnonymous	No	false	Determines whether to include those who contributed anonymously to a page.

scope	No	The specified page only	Specifies additional pages to include when generating the list of contributors. Available values: • <code>children</code> – only the child pages of the specified page. • <code>descendants</code> – all descendants of the specified page.
order	No	edits	Sets the criterion used for sorting items in the table. Available values: • <code>edits</code> – sorts items in the table based on the total number of edits made, either by a contributor or to a page. • <code>name</code> – sorts items in the table in alphabetical order, either by contributor or page name. • <code>editTime</code> – sorts items in the table based on when the contributor last edited a page (or a specified set of pages) or when the page was last edited. • <code>update</code> – sorts items in the table based on when the contributor last made any contribution to a page (or a specified set of pages) or when the page last had any contribution made to it.

page	No	The current page	A page title. Specifies the page to use when generating the list of contributors. If page and spaces are left blank, the current page is assumed.
labels	No	(None)	Limits contribution-based statistics to the specified labels only. You can specify one or more labels, separated by commas.
columns	No	edits, comments, labels	Determines the columns that should appear in the table. The statistics or type of information presented depends on the groupby parameter. Available values: • edits – the number of times each contributor has edited the page(s) or the number of edits made to each page. • edited – a list of the pages edited by each contributor or a list of contributors who have edited each page. • comments – the number of times each contributor has added comments to the page(s) or the number of comments on each page. • commented – a list of pages to which each contributor has added comments or a list of contributors who have commented on each page.

- `labels` – the number of times each contributor has added labels to the page(s) or the number of labels on each page.
- `labeled` – a list of pages to which each contributor has added labels or a list of contributors who have added a label to each page.
- `labelList` – a list of labels either added by each contributor or on each page.
- `watches` – the number of pages being watched by each contributor/person or the number of contributors/people watching each page.
- `watching` – a list of pages being watched by each contributor/person or a list of contributors/people watching each page.
- `lastupdate` – the last time each contributor made an update or when each page was last updated. Valid updates can include edits, comments or label modifications to a page.

You can specify one or more columns, separated by commas.

groupby	No	contributors	Specifies the basis for grouping contribution-based statistics: • contributors – group by the people who have contributed. • pages – group by the pages used to find the contributors.
contentType	No	Both pages and blog posts	Restricts the content type that the macro will use when generating the list of contributors. Available values: • pages – pages • blogposts – blog posts.
showZeroCounts	No	false	Determines whether contributors or pages are included for which the calculated statistic is zero.
publishDate	No	(None)	Specifies the publication date for a blog post. The date format required is: YYYY/MM/DD.

Example:

This example specifies a content type of blog posts:

```
{contributors-summary:limit=10|spaces=ds,@personal|reverse=true|showAnonymous=true|order=update|labels=chocolate,cake|columns=edits,comments,labels,lastupdate|groupBy=pages|contentType=blogposts|showZeroCounts=true|publishDate=2012/06/07}
```

This example specifies a content type of pages:

```
{contributors-summary:limit=10|spaces=ds,@personal|reverse=true|showAnonymous=true|scope=descendants|order=update|page=ds:Advanced Topics|labels=chocolate,cake|columns=edits,comments,labels,lastupdate|groupBy=pages|contentType=pages|showZeroCounts=true}
```

Create Space Button macro

Displays a create space button linked to the create space page.

Macro name: create-space-button

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
size	No	large	Determines the size of the 'create space' icon displayed. Available values: • large • small
width	No	Natural size of icon (1:1 pixel ratio)	The width of the icon to be displayed, specified in pixels. Confluence will stretch or shrink the width of the icon to the number of pixels specified. Note: This parameter is not available via the macro browser.
height	No	Natural size of icon (1:1 pixel ratio)	The height of the icon to be displayed, specified in pixels. Confluence will stretch or shrink the height of the icon to the number of pixels specified. Note: This parameter is not available via the macro browser.

Example:

```
{create-space-button:size=small}  
{create-space-button:height=50px|width=50px}
```

Excerpt Include macro

Allows you to display an excerpt from another page within the current page.

Macro name: excerpt-include

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values

default-parameter (Unnamed in wiki markup)	Yes	(None.)	The name of the page that contains the excerpt to be displayed. To include an excerpt from a page in another space, type the space key followed by a colon (:) and the page name, like this: SPACEKEY:My page name Note: The ability to include excerpts from other spaces is available only in Confluence 4.3.2 and later. In earlier versions of Confluence, the Excerpt Include macro does not work across spaces. Use the Include Page macro instead.
nopanel	No	False	Determines whether Confluence will display a panel around the excerpted content. The panel includes the title of the page containing the excerpt, and the border of the panel. By default, the panel and title are shown.

Example:

```
{excerpt-include:My page name|nopanel=true}
```

Excerpt macro

Define a part of a page as the page's 'excerpt' which can then be displayed in another page.

Macro name: excerpt

Macro body: Accepts rich text.

Parameter name	Required	Default	Parameter description and accepted values

hidden	No	False	Determines whether the content of the Excerpt macro body is displayed on the page that contains the Excerpt macro. Note that this option affects only the page that contains the Excerpt macro. It does not affect any pages where the content is reused.
atlassian-macro-output-type	No	BLOCK	Determines whether the content of the Excerpt macro body is displayed on a new line or inline. Available values: • BLOCK – Displays the content of the macro on a new line . • INLINE – Displays the the content of the macro as part of the same paragraph as the text preceding and following it. Note that this option affects only the page that contains the Excerpt macro. It does not affect any pages where the content is reused.

Example:

```
{excerpt:hidden=true|atlassian-macro-output-type=BLOCK}
This is the *text* I want to reuse in other pages. This text is inside an Excerpt macro.
{excerpt}
```

Expand macro

Displays an expandable/collapsible section of text.

Macro name: expand

Macro body: Accepts rich text.

Parameter name	Required	Default	Parameter description and accepted values

default-parameter (Unnamed in wiki markup)	No	Click here to expand...	Text that will be displayed on the line that people can click to expand the hidden text.

Example:

```
{expand:This is my message}
This text is _hidden_ until you expand it.
{expand}
```

Favourite Pages macro

Displays a list of your favourite pages.

Macro name: favpages

Macro body: None.

Parameters: None.

Example:

```
{favpages}
```

Gadget macro

Allows you to add Confluence gadgets to pages or blog posts.

Macro name: gadget

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
width	No	450 pixels	The width of the gadget, using one of the following conventions: - Width in pixels, using px or plain numbers. For example, 500px or 500 - A percentage of the page width, using %. For example, 50% - Automatic resizing of the gadget to fit 100% of the page width: auto

border	No	true	Determines whether Confluence will draw a border around the gadget.
url	Yes	(none.)	This is the location of the gadget specification (XML file).
preferences	No	(Gadget-dependent.)	Specific property settings that are particular to each gadget.

A note about editing a gadget's properties (preferences) in markup: It is possible to edit the values of these properties directly in the wiki markup or storage format. However, this will allow the entry of invalid values. If a gadget property supports a certain set of values, the macro browser will restrict the user to selecting only valid values for that property. For that reason, we recommend that you use the macro browser to edit a gadget's properties.

Example:

This example shows the Confluence Page gadget:

```
{gadget:width=500|border=false|url=rest/gadgets/1.0/g/com.atlassian.confluence.plugins.gadgets:confluence-page-gadget/gadgets/confluence-page-gadget.xml}
spaceName=Documentation&spaceKey=DOC&quickfind-space=Documentation&pageId=753666&pageName=Documentation%20Home&quickfind-page=Documentation%20Home&isEditable=true&isConfigured=true&refresh=15&showLink=false
{gadget}
```

This example shows the Confluence News gadget:

```
{gadget:url=rest/gadgets/1.0/g/com.atlassian.confluence.plugins.gadgets:confluence-news-gadget/gadgets/confluence-news-gadget.xml}
{gadget}
```

Gallery macro

Forms a thumbnail gallery of all images attached to a page.

Macro name: gallery

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
title	No	(None)	Specify a title to be displayed above your gallery of pictures.

reverse	No	Not specified. Sort order is ascending.	Used in combination with the <code>sort</code> parameter, to change the sort order from ascending to descending. Available values: <code>true</code> – Sort order is descending. <code>false</code> – Sort order is ascending.
sort	No	None. The sort order is unspecified and therefore unpredictable.	Specify an attribute to sort the images by. Sort order is ascending, unless you specify the <code>reverse</code> parameter. Available values: <code>name</code> – file name. <code>comment</code> – comment linked to the attached file. <code>date</code> – date/time last modified. <code>size</code> – size of the attached file.
page	No	If no page is specified, the gallery macro displays the images attached to the page on which the macro is used.	Specify the title of the page which contains the images you want displayed. You can specify more than one page name, separated by commas. To specify a page in a different space, use the following syntax: <code>SPACEKEY:Page title</code>.

<code>includeLabel</code>	No	None. The images are not filtered by label.	The gallery will include only those pictures that have the specified label. If you wish to enter more than one label, separate the labels with commas. Confluence will show only images that have all the labels specified. (The match is an AND, not an OR.) For information on labelling the attachments, see Adding Labels .
<code>excludeLabel</code>	No	No exclusions. The gallery will include all the pictures on the page.	The gallery will ignore any pictures that have the specified label. You can specify more than one label, separated by commas. For information on labelling the attachments, see Adding Labels .
<code>columns</code>	No	4	Specify the number of columns for the table that forms the gallery.
<code>exclude</code>	No	No exclusions. Include all the pictures on the page.	Specify images by file name. The gallery will ignore any images specified. You can specify more than one image, separated by commas. Note: The file name and file type for this parameter are case sensitive. For example, 'my picture.PNG' will not be recognised as 'my picture.png'.

include	No	Include all the pictures on the page.	If you specifically include one or more pictures, the gallery will show only those pictures. You can specify more than one picture, separated by commas. Note: The file name and file type for this parameter are case-sensitive. For example, 'my picture.PNG' will not be recognised as 'my picture.png'.

Example:

```
{gallery:title=My holiday pictures|reverse=true|sort=size|page=My page1, ds:Welcome to Confluence|excludeLabel=badlabel1, badlabel2|columns=3|exclude=badpicture.png}
```

Global Reports macro

Displays a list of links to global reports within a table.

Macro name: global-reports

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
width	No	99%	Specify the width of the table in which the links are displayed, as a percentage of the window width.

Example:

```
{global-reports:width=50%}
```

HTML Include macro

Includes the content of an external HTML file into a Confluence page.

Macro name: html-include

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
url	Yes	(None)	Specify a URL of the content to be included into your Confluence page.

Example:

```
{html-include:url=http://www.example.com}
```

HTML macro

Renders your specified HTML code within the current page.

Macro name: html

Macro body: Text, consisting of HTML code.

Parameters: None.

Example:

```
{html}<a href="http://www.atlassian.com">Click here</a> to see the <b>Atlassian</b> website.{html}
```

IM Presence macro

Displays graphically when a contact is online.

Macro name: im

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
showid	No	true	Determines whether the macro shows or hides the user ID of the contact. Available values: • true – User ID is shown on the page. • false – User ID is not shown on the page.

service	Yes	Not specified.	The web service that Confluence should query. Available values: • aim – AOL Instant Messenger • gtalk – Google Talk • icq – ICQ • jabber – Jabber • msn – MSN Instant Messenger • sametime – IBM Lotus Sametime • skype – Skype • skypeme – Skype • wildfire – Openfire Server • yahoo – Yahoo! Messenger
default-parameter (Unnamed in wiki markup)	Yes	Not specified.	User ID. Identifies the IM contact by their ID, account name or screen name.

Example:

```
{im:MySkypeName|service=skype|showid=false}
```

Include Page macro

Inserts the contents of the specified page into the current one.

Macro name: include

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values

default-parameter (Unnamed in wiki markup)	Yes	(None.)	The name of the page whose content should be included on the current page To include content from a page in another space, type the space key followed by a colon (:) and the page name, like this: SPACEKEY:My page name To include a blog post, specify the date as well as the title of the blog post. For example: /2010/12/01/My blog post. You can include pages from personal spaces using ~username as the space key, where 'username' is the person's username. For example, ~jsmith:My page name.

Example:

```
{include:DOC:My chocolate page}
```

Info macro

Displays a block of text in a blue highlight box.

Macro name: info

Macro body: Accepts rich text.

Parameter name	Required	Default	Parameter description and accepted values
icon	No	true	Determines whether to display the  icon in the title bar of the information box.

title	No	(None)	The title of the information box. If specified, the title text will be displayed in bold next to the icon.

Example:

```
{info:title=This is my title|icon=false}
This is _important_ information.
{info}
```

JIRA Issues macro

Displays a list of JIRA issues in a page.

Macro name: jiraissues

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
anonymous	No	false	If this parameter is set to 'true', JIRA will return only the issues which allow unrestricted viewing i.e. the issues which are visible to anonymous viewers, as determined by JIRA's viewing restrictions. If this parameter is omitted or set to 'false', then the results depend on how your administrator has configured the communication between JIRA and Confluence. By default, Confluence will show only the JIRA issues which the user is authorised to view. See more details below .

baseurl	No	The value of the 'url' parameter	If you specify a 'baseurl', then the link in the header, pointing to your JIRA site, will use this base URL instead of the value of the 'url' parameter. This is useful when Confluence connects to JIRA with a different URL from the one used by other users.
columns	No	By default, the following columns are shown: • type • key • summary • assignee • reporter • priority • status • resolution • created • updated • due	A list of JIRA column names, separated by semi-colons (;). Example columns are: key, summary, type, created, fixversion, updated, due, assignee, reporter, priority, status and resolution. You can include any columns recognised by your JIRA site, including custom columns. See the JIRA documentation for a list of names.
count	No	false	If this parameter is set to 'true', the issue list will show the number of issues in JIRA. The count will be linked to your JIRA site.
cache	No	on	The macro maintains a cache of the issues which result from the JIRA query. If the 'cache' parameter is set to 'off', the relevant part of the cache is cleared each time the macro is reloaded. (The value 'false' also works and has the same effect as 'off'.)

height	No	480	The height in pixels of the table displaying the JIRA issues. Note that this height specification is ignored in the following situations: • If you set the 'renderMode' parameter (see below) to 'static'. • When the JIRA issues are displayed in a PDF or Word document, in an email message or in an RSS feed.
renderMode	No	In formats not mentioned below, the default is 'dynamic'. The default is 'static' when the JIRA issues are displayed in a PDF or Word document, in an email message or in an RSS feed.	By default, the JIRA Issues macro offers a dynamic display with the following features: • Click the column headers to sort the output. • Drag and drop the columns into a different order. • Temporarily remove a column from the display. • View a page of issues at a time, for faster response times. Set the 'renderMode' parameter to 'static' if you want to disable the dynamic display features.
title	No	JIRA Issues	You can customise the title text at the top of the JIRA issues table with this parameter. For instance, setting the title to 'Bugs-to-fix' will replace the default 'JIRA Issues' text. This can help provide more context to the list of issues displayed.

url	Yes	none	The URL of the XML view of your selected issues in JIRA Issue Navigator. Note: If the URL in the 'url' parameter does not contain a tempMax argument, then the value of tempMax will default to 500. If your JIRA server is version 3.12 or earlier, this means that the JIRA Issues macro will return a maximum of 500 issues. If your JIRA server is version 3.13 or later, a value of 500 means that the JIRA Issues macro will return a maximum of 500 issues per page.
width	No	100%	The width of the table displaying the JIRA issues. Can be indicated either as a percentage (%) or in pixels (px).

Example:

```
{jiraissues:anonymous=true|url=http://jira.atlassian.com/sr/jira.issueviews:searchrequest-xml/temp/SearchRequest.xml?jqlQuery=project+%3D+CONF+AND+%28summary+%7E+jiraissues+OR+description+%7E+jiraissues+OR+comment+%7E+jiraissues%29&tempMax=10|columns=type;key;summary}
```

JUnit Report macro

Display a summary of JUnit test results.

Macro name: junitreport

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values

directory	Must include either the directory or the url parameter	(None)	URL of a directory containing your test result files. This must be a directory name and not the XML file itself. Overrides the url parameter if you use both. Note: When using a local drive, you must use a directory name and not the XML file itself.
reportdetail	No	all	Level of detail required in the report. Available values: • all • fixture • summary • failuresonly
url	Must include either the directory or the url parameter	(None)	URL of a particular test result XML file. This parameter is overridden by the directory parameter if you use both. For Confluence installations that require authentication, you can specify login credentials as part of this parameter, in the form of URL parameters: • os_username — The username of a Confluence user with permission to access the JUnit test results. • os_password — The password of the Confluence user specified in the os_username parameter.

debug	No	false	If the value of this parameter is <code>true</code> , the report will show the content of failures, as well as the error messages.

Example:

Loading JUnit reports from a local drive:

```
{junitreport:directory=file:///C:/TEMP/}
```

Loading JUnit reports from a network drive:

```
{junitreport:url=http://*host*/*path*}
```

Loading JUnit reports from a Confluence site:

```
{junitreport:url=http://yourConfluenceInstance.com/download/attachments/<pageid>/file.xml}
```

Loading JUnit reports from a Confluence site that requires authentication:

If your Confluence site is not accessible by anonymous users, specify login credentials with the `os_username` and `os_password` URL parameters (as part of the macro's `url` parameter). In this case, we are specifying a username of 'admin' and a password of 'secret'.

```
{junitreport:url=http://yourConfluenceInstance.com/download/attachments/<pageid>/file.xml?os_username=admin&os_password=secret}
```

Labels List macro

Displays a hyperlinked alphabetical index of all labels within the current space.

Macro name: `listlabels`

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
spaceKey	No	Current space	The key of the space whose labels you want to display.

Example:

```
{listlabels:spaceKey=DOC}
```

Livesearch macro

Add a dynamic search box to a wiki page.

Macro name: livesearch

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
id	No	(None)	Uniquely identifies the Livesearch macro when there are more than one Livesearch macros in a page.
spaceKey	No	All spaces	Specify a space key to limit the search to the given space.

Example:

```
{livesearch:spaceKey=DOC|id=mysearch1}
```

Loremipsum macro

Display a few paragraphs of pseudo-Latin text.

Macro name: loremipsum

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
default-parameter (No name in wiki markup)	No	3	Number of paragraphs. Determines the amount of pseudo-Latin (space-filler) text to display. The macro will display a maximum number of 30 paragraphs.

Example:

```
{loremipsum:2}
```

Multimedia macro

Displays videos, animations and more, sourced from a file attached to a Confluence page and displayed on your page.

Macro name: multimedia

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
page	No	Current page	Name of the page to which the multimedia file is attached.
space	No	Current space	Space key of the page that has the multimedia file attached.
name	Yes	None	File name of the multimedia file, which is attached to a Confluence page.
width	No	If not specified, the browser will determine the width based on the file type.	Width of the movie window to be displayed on the page. By default, this value is specified in pixels. You can also choose to specify a percentage of the window's width, or any other value accepted by HTML.
height	No	If not specified, the browser will determine the height based on the file type.	Height of the movie window to be displayed on the page. By default, this value is specified in pixels. You can also choose to specify a percentage of the window's height, or any other value accepted by HTML.

autostart	No	false	If the parameter is set to <code>true</code> then the video or audio file will start playing as soon as the page is loaded. If this option is set to <code>false</code> then the file will not play until the user clicks the icon or image on the page.

Example:

```
{multimedia:space=DOC|page=My macros|name=ninjas.swf|autostart=true}
```

Page Properties macro

Allows you to embed metadata into a page and then display that data in tabular form using the [Page Properties Report macro](#). Previously known as the Metadata Details macro.

Macro name: details

Macro body: Accepts rich text.

Parameter name	Required	Default	Parameter description and accepted values
hidden	No	false	Determines whether the data in the Page Properties macro will be displayed on the current page. This setting does not affect the display of the detail in the Page Properties Report macro.
label	No	(None)	The label used to identify the metadata on this page. Confluence will add this label to the page.

Example:

```
{details:hidden=true|label=status}  
Project Status: Complete  
Team: Green Parrots  
Deadline: 2012-09  
{details}
```

Page Properties Report macro

Presents a tabulated summary of selected metadata, which has been embedded on pages using the [Page Properties macro](#). Previously known as the Details Summary macro.

Macro name: detailssummary

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
label	No	(None)	Identifies the metadata to be included in the Page Properties Report. The report will show data from the Page Properties macros on the pages in the current space that have this label on the page.

Example:

```
{detailssummary:label=status}
```

Section macro

Used with the Column macro to define columns on a page. See [Working with page layouts and columns and sections](#).

Macro name: section

Macro body: Rich text, consisting of one or more Column macros.

Parameter name	Required	Default	Parameter description and accepted values
border	No	False	If the value is <code>true</code> , the columns in this section will have a dashed border.

Example:

```
{section:border=true}
{column:width=100px}
This is the content of *column 1*.
{column}
{column}
This is the content of *column 2*.
{column}
{section}
```

Table of Contents macro

Displays a table of contents from your page headings.

Macro name: toc

Macro body: None.

Parameter name	Required	Default	Parameter description and accepted values
printable	No	true	If you set this parameter to false, the table of contents will not be visible when you print the page.
style	No	none	The style of bullet point for each list item. You can use any valid CSS style. For example: • none – No list style is displayed. • circle – The list style is a circle. • disc – The list style is a filled circle. This is the typical bullet list, and is the one we are using in this example list. • square – The list style is a square. • decimal – The list is numbered (1, 2, 3, 4, 5). • lower-alpha – The list style is lower case, alphabetised (a, b, c, d, e). • lower-roman – The list style is lower-case roman numerals (i, ii, iii, iv, v, vi). • upper-roman – The list style is upper-case roman numerals (I, II, III, IV, V, VI).

<code>maxLevel</code>	No	7	Maximum heading level. Use this parameter to select the highest heading level to include. For example, a value of 2 will list h1 and h2 levels, but will not include h3 and below.
<code>indent</code>	No	(None)	This parameter applies to vertical lists only (type = list). Use this parameter to indent the list items according to CSS quantities. For example, a value of 10px will successively indent list heading groups by 10 pixels. Level 1 headings will be indented 10px, and level 2 headings by an additional 10px, and so on.
<code>minLevel</code>	No	1	Minimum heading level. The heading level at which the table of contents will start. For example, a value of 2 will list h2, h3, and h4 headings, but will not include h1 headings.
<code>class</code>	No	(None)	A CSS class name. If you have a custom style sheet, you can use this parameter to output the table of contents with the specified class attribute.

excl ude	No	(None)	Specifies the headings to exclude by pattern matching. The value must be a regular expression. If this parameter is specified, the table of contents will include only the headings that match the regular expression. Example: <code>. * \. [1//2]</code> See Sun's Regex documentation for examples of constructing regular expression strings.
type	No	list	Defines the overall format of the table of contents. Available values: • <code>list</code> – displays the table of contents in a vertical list. • <code>flat</code> – displays a horizontal series of links. For example: <code>[Heading 1] [Heading 2] [Heading 3]</code>.
outline	No	false	A value of <code>true</code> will apply outline numbering to the headings as displayed in the table of contents. For example: <code>1.1, 1.2, 1.3</code>.

separator	No	brackets	This parameter applies to flat lists only (type = flat). Use this parameter to style the display of a flat list. Available values: • brackets – Each item is enclosed by square brackets: []. • braces – Each item is enclosed by braces: { }. • parens – Each item is enclosed by parentheses: (). • pipe – The items are separated by a pipe: • anything – The items are separated by the value you enter. You can enter any text as a separator, for example ***. If using a custom separator, be aware that text displays exactly as entered, with no additional white space to further separate the characters.
include	No	(None)	Specifies the headings to include by pattern matching. The value must be a regular expression. If this parameter is specified, the table of contents will ignore any headings that do not match the regular expression. Example: <code>.*\[1//2]</code> See Sun's Regex documentation for examples of constructing regular expression strings.

Example:

This example shows a list-type table of contents.

```
{toc:printable=true|style=square|maxLevel=2|indent=5px|minLevel=2|class=bigpink|exclude=[1//2]|type=list|outline=true|include=.*}
```

This example shows a flat table of contents.

```
{toc:printable=true|maxLevel=2|minLevel=2|class=bigpink|exclude=[1//2]|type=flat|outline=true|separator=pipe|include=.*}
```

Notes

- The 'Required' column indicates whether the parameter is required on data entry. If the parameter is not supplied, Confluence will insert default values as indicated in the 'Default' column.
- Wiki markup is not case sensitive. For example, you can specify a parameter name of sortBy or sortby.
- For a few macros in wiki markup, the default parameter may be unnamed. The examples on this page show the macros concerned. In such cases, the unnamed parameter is always the first parameter specified.
- **A request from the Atlassian technical writers about comments and feedback:** We would like to distinguish between the documentation of the current solution (this page) and any discussion of the solution and possible changes to Confluence wiki markup and/or the XHTML-based storage format. If you have a suggestion for, or correction of, this documentation, please add your suggestion to this page. If you have feedback on the Confluence markup, storage format and related functionality, please add your suggestion to the page titled [Confluence 4 Editor - Customer Feedback](#). Thanks. 😊

Wiki Markup Examples for Chart Macro

This page is an extension of [Confluence Wiki Markup for Macros](#), which contains wiki markup examples for all Confluence macros. The [Chart macro](#) is a special case, because it offers so many options via parameters and chart types. This page offers additional examples for the Chart macro.

Pie chart


Here is a simple example of a pie chart.

Wiki markup

```
{chart:type=pie|title=Fish Sold}
|| Fish Type || 2004 || 2005 ||
|| Herring | 9,500 | 8,300 |
|| Salmon | 2,900 | 4,200 |
|| Tuna | 1,500 | 1,500 |
{chart}
```

Resulting chart

Fish Sold



■ 2004 (1,500 - 50%) ■ 2005 (1,500 - 50%)


Bar chart

Here is a simple example of a bar chart.

Wiki markup

```
{chart:type=bar|title=Fish Sold}
|| Fish Type || 2004 || 2005 ||
|| Herring | 9,500 | 8,300 |
|| Salmon | 2,900 | 4,200 |
|| Tuna | 1,500 | 1,500 |
{chart}
```

Resulting chart



Time series chart


Here is an example of a time series chart.

Wiki markup


```
{chart:type=timeSeries|dateFormat=MM/yyyy|timePeriod=Month|
dataOrientation=vertical|rangeAxisLowerBound=0|domainaxisrotateticklabel=true}
|| Month || Revenue ||
| 1/2005 | 31.8 |
| 2/2005 | 41.8 |
| 3/2005 | 51.3 |
| 4/2005 | 33.8 |
| 5/2005 | 27.6 |
| 6/2005 | 49.8 |
| 7/2005 | 51.8 |
| 8/2005 | 77.3 |
| 9/2005 | 73.8 |
| 10/2005 | 97.6 |
| 11/2005 | 101.2 |
| 12/2005 | 113.7 |

|| Month || Expenses ||
| 1/2005 | 41.1 |
| 2/2005 | 43.8 |
| 3/2005 | 45.3 |
| 4/2005 | 45.0 |
| 5/2005 | 44.6 |
| 6/2005 | 43.8 |
| 7/2005 | 51.8 |
| 8/2005 | 52.3 |
| 9/2005 | 53.8 |
| 10/2005 | 55.6 |
| 11/2005 | 61.2 |
| 12/2005 | 63.7 |
{chart}
```

Resulting chart


**XY line chart**

Here is an example of an XY line chart.

Wiki markup

```
{chart:type=xyline}
|| || 12 || 14 || 23 ||
| Revenue | 41.1 | 31.8 | 12.4 |
| Expense | 31.1 | 41.8 | 43.6 |
{chart}
```

Resulting chart


**XY bar chart**

Here is an example of an XY bar chart.

Wiki markup

```
{chart:type=xybar|opacity=60}
|| || 2005 || 2006 || 2007 ||
| Revenue | 41.1 | 31.8 | 12.4 |
| Expense | 31.1 | 41.8 | 43.6 |
{chart}
```

Resulting chart




XY area chart

Here is an example of an XY area chart.

Wiki markup

```
{chart:type=xyarea}
|| || 12 || 14 || 23 ||
| Revenue | 41.1 | 31.8 | 12.4 |
| Expense | 31.1 | 41.8 | 43.6 |
{chart}
```

Resulting chart




Area chart

Here are two examples of area charts.

Wiki markup for area chart 1

```
{chart:type=area|dataDisplay=true|legend=true|width=300|height=300|opacity=50}
|| Satisfaction || 2002 || 2003 || 2004 ||
| Very satisfied | 20 | 23 | 34 |
| Satisfied      | 40 | 34 | 23 |
| Dissatisfied   | 25 | 26 | 25 |
| Very dissatisfied | 15 | 17 | 18 |
{chart}
```

Resulting area chart 1




Satisfaction	2002	2003	2004
Very satisfied	20	23	34
Satisfied	40	34	23
Dissatisfied	25	26	25
Very dissatisfied	15	17	18

Wiki markup for area chart 2

```
{chart:type=area|dataDisplay=true|legend=true|width=300|height=300|stacked=true}
|| Satisfaction || 2002 || 2003 || 2004 ||
| Very satisfied | 12 | 23 | 31 |
| Satisfied      | 1 | 34 | 36 |
| Dissatisfied   | 4 | 6 | 22 |
| Very dissatisfied | 2 | 7 | 12 |
{chart}
```

Resulting area chart 2



Satisfaction	2002	2003	2004
Very satisfied	12	23	31
Satisfied	1	34	36
Disatisfied	4	6	22
Very disatisfied	2	7	12

Working with Confluence Gadgets

This section introduces the concept of gadgets in Confluence and provides an outline on how to use gadgets in Confluence and other web applications.

Introduction to Gadgets in Confluence

A gadget is a small object (i.e. a piece of functionality) offering dynamic content that can be placed into the page of:

- An Atlassian application's website, such as a Confluence page or blog post or a JIRA 4.0+ dashboard.
- A third-party application's website, such as [iGoogle](#) or [Gmail](#). (But see the limitations on using [Confluence gadgets in other applications](#).)

Gadgets allow interactions between Confluence and other compatible websites. Confluence interacts with gadgets that support the [OpenSocial](#) specification.

For more information about Atlassian gadgets, please refer to the [introduction to Atlassian gadgets](#) and the [big list of Atlassian gadgets](#).

Using Gadgets in Confluence

You can place any gadget that complies with the OpenSocial specification from an external source, such as [iGoogle](#) or other Atlassian applications such as [JIRA 4.0+](#), onto a Confluence page or blog post. To add a gadget to a page, use the Confluence macro browser to add a [Gadget macro](#).

See the page on [adding JIRA gadgets to a Confluence page](#).

On this page:

- [Introduction to Gadgets in Confluence](#)
- [Using Gadgets in Confluence](#)
- [Adding Confluence Gadgets in Other Applications](#)
 - [Adding a Confluence Gadget to JIRA](#)
 - [Adding a Confluence Gadget to Non-Atlassian Web Applications](#)
 - [Confluence Gadgets](#)

Related pages:

- [Gadget Macro](#)
- [Configuring Confluence Gadgets for Use in Other Applications](#)
- [Adding a Confluence Gadget to a JIRA Dashboard](#)
- [Confluence Gadgets](#)
- [Configuring OAuth \(Not applicable to Confluence OnDemand.\)](#)
- [All Atlassian gadgets](#)
- [External Gadgets](#)

Adding Confluence Gadgets in Other Applications

You can add a Confluence gadget to a JIRA dashboard or another Confluence site. In principle, you can also put a Confluence gadget on any other OpenSocial-compliant website such as iGoogle or [Gmail](#). See the limitations on using [Confluence gadgets in other applications](#).

Adding a Confluence Gadget to JIRA

See [Adding a Confluence Gadget to a JIRA Dashboard](#).

Adding a Confluence Gadget to Non-Atlassian Web Applications

For instructions on how to add Confluence gadgets in another compatible non-Atlassian web application or container, refer to [Configuring Confluence Gadgets for Use in Other Applications](#).

Confluence Gadgets

The [Confluence Gadgets](#) topic explains the purpose of the 'Confluence Gadgets' window and provides information about the gadgets which are bundled with Confluence.

Adding a Confluence Gadget to a JIRA Dashboard

JIRA 4.0 is the first major Atlassian application that can incorporate OpenSocial-compliant gadgets, such as Confluence gadgets onto its dashboard. This page explains how to add a Confluence gadget to the dashboard of a JIRA 4.0+ installation.

To add a Confluence gadget to a JIRA dashboard, complete the steps below.

Note:

- You need system administrator privileges in JIRA, to add a gadget to the list of available gadgets.
- In **Atlassian OnDemand** products, it is not possible for administrators to add gadgets to the directory. If you would like to add an Atlassian gadget to a directory, please contact Atlassian Support.

Creating an Application Link between Confluence and JIRA (Not applicable to Confluence OnDemand.)

If your Confluence gadgets need to access user-restricted Confluence data, then your Confluence administrator must first establish an [Application Link](#) between your Confluence site and the JIRA site. For more information about configuring an Application Link between Confluence and other web applications, refer to [Configuring OAuth Authentication for an Application Link. \(Not applicable to Confluence OnDemand.\)](#)

If you only need to access anonymously accessible Confluence data, then you can skip the section about adding an Application Link, and go directly to [Finding a Confluence Gadget's URL](#), below.

On this page:

- [Creating an Application Link between Confluence and JIRA \(Not applicable to Confluence OnDemand.\)](#)
- [Finding a Confluence Gadget's URL](#)
- [Adding a Confluence gadget to JIRA's gadget directory \(Not applicable to Confluence OnDemand.\)](#)
- [Adding a Confluence gadget to the JIRA dashboard](#)

Related pages:

- [All Atlassian gadgets](#)
- [Working with Confluence Gadgets](#)
- [Confluence User's Guide](#)

 *Some functionality described on this page is restricted in Confluence OnDemand.*

Finding a Confluence Gadget's URL


A gadget's URL points to the gadget's XML specification file. These URLs look something like this:

```
http://example.com/my-gadget-location/my-gadget.xml
```

To find a Confluence gadget's URL:


1. Choose the help icon  at top right of the screen, then choose **Available Gadgets**.
2. Find the gadget you want.
3. Copy the **Gadget URL** link to your clipboard.

Screenshot: Finding a gadget's URL



Adding a Confluence gadget to JIRA's gadget directory (Not applicable to Confluence OnDemand.)**To add a Confluence gadget to the gadget directory in JIRA:**

1. Go to the dashboard by clicking **Dashboard** at the top left of the screen.
2. The dashboard will appear. Click **Add Gadget**.
3. The 'Add Gadget' screen appears, showing the list of gadgets in your directory. See [screenshot 1](#) below. Click **Add Gadget to Directory**.
Note: You will only see this button if you have system administrator permissions in JIRA.
4. The 'Add Gadget to Directory' screen appears. See [screenshot 2](#) below. Paste the gadget URL (which you copied to your clipboard [above](#)) into the text box.
5. Click **Add Gadget**.
6. The gadget appears in your gadget directory. (It will be highlighted for a short time, so that you can see it easily.)

Screenshot 1: Gadget directory with 'Add Gadget to Directory' button

Screenshot 2: Adding a gadget to the directory

Add Gadget to Directory

Type or paste the gadget's URL below.

ation-gadget-spec-provider/application-gadget.xml

Add Gadget

By adding a gadget to the directory, you are making the gadget available for people to use on their dashboards.

Only add gadgets that you trust! Gadgets can allow unwanted or malicious code onto your web page.

You can add gadgets from Atlassian applications such as Confluence, JIRA and others. You can also add gadgets from other websites such as iGoogle. Many public gadgets will work on an Atlassian dashboard. Some gadgets may rely on specific iGoogle features that will not work properly on Atlassian dashboards. In that case, you can simply remove the gadget from the directory.

A gadgets URL looks something like this: <http://example.com/my-gadget-location/my-gadget.xml>

Find [more gadgets](#) to add. | You can create your own gadgets! [Learn how.](#)

Back

Finished

Adding a Confluence gadget to the JIRA dashboard

In the procedure below, 'your Atlassian dashboard' and 'your Atlassian application' refers to the JIRA dashboard and application, respectively.

You can add a gadget from the directory of gadgets that are available to your Atlassian application.

To add a gadget to your Atlassian dashboard,

1. Go to the dashboard by clicking the '**Dashboard**' link or the '**Home**' link at the top left of the screen.
2. The dashboard will appear, looking something like [screenshot 1](#) below. Click '**Add Gadget**'.
3. The '**Add Gadget**' screen will display a list of available gadgets in your gadget directory, as shown in [screenshot 2](#) below. Find the gadget you want, using one or more of the following tools:
 - Use the scroll bar on the right to move up and down the list of gadgets.
 - Select a category in the left-hand panel to display only gadgets in that category.
 - Start typing a key word for your gadget in the '**Search**' textbox. The list of gadgets will change as you type, showing only gadgets that match your search term.
4. When you have found the gadget you want, click the '**Add it Now**' button to add the gadget to your dashboard.

Screenshot 1: An Atlassian dashboard

The screenshot shows a Confluence page with a header bar containing '+ Add Gadget', 'Edit Layout', and 'Tools'. The page contains three gadgets:

- Spider**: A gadget with a red header bar, a small spider icon, and a large empty box.
- Remember The Milk**: A gadget with a grey header bar, the 'remember the milk' logo, and a login form with fields for 'Username:', 'Password:', and a 'Remember me' checkbox. It also has a 'Login' button and a link to 'Signup now for a free account'.
- JIRA Issues**: A gadget with a blue header bar, titled 'Apache Struts JIRA'. It lists several JIRA issues with links to their details, such as '[TILES-287] Separate 2.1.x examples from 2.0.x ones.' and '[TILES-280] Move inheritance resolution from UriDefinitionsFactory to a resolving LocaleUriDefinitionDao'.

Screenshot 2: Adding a gadget from the gadget directory

The screenshot shows the 'Add Gadget' dialog box. It has a search bar at the top with the text 'at'. On the left is a list of categories: All, Admin, Bamboo, Charts, Clover, Confluence, Crowd, Crucible, External Content, Fisheye, JIRA, and Other. The main area displays three gadgets:

- Atlassian Gadgets Reference Implementation**: Includes a 'Gadget URL' and 'By Atlassian'.
- Date & Time**: Includes a 'Gadget URL', 'By James L.', and a description: 'Add a clock to your page. Click edit to change it to the color of your choice.'
- Directory Gadget**: Includes a 'Gadget URL', 'By Atlassian', and a description: 'Directory Gadget description'.

Each gadget has an 'Add it now' button. At the bottom of the dialog are two buttons: 'Add Gadget to Directory' and 'Finished'.

Note:

- You need administrator privileges to add a gadget to the list of available gadgets. If you have permission to add gadgets to and remove gadgets from the directory itself, you will see the '**Add Gadget to Directory**' and '**Remove**' buttons on the 'Add Gadget' screen, as shown in the screenshot about. Please refer to the [Gadgets and Dashboards Administration Guide](#).
- In **Atlassian OnDemand** products, it is not possible for administrators to add gadgets to the directory. If you would like to add an Atlassian gadget to a directory, please contact Atlassian Support.

Configuring Confluence Gadgets for Use in Other Applications

This page tells you how to add a Confluence gadget to another (external) application. The instructions and examples given in this topic focus on adding and using Confluence Gadgets in other web applications.



Atlassian support does not cover gadgets on external sites like iGoogle and Gmail

In principle, you should be able to add Atlassian gadgets to iGoogle, Gmail and other external sites that support OpenSocial gadgets. However, these external integrations are experimental at this stage and we have encountered problems with them. Please do have fun playing around with them, but be aware that Atlassian does not support the use of Atlassian gadgets on iGoogle, Gmail or other external web sites. See the detailed section on [gadget limitations](#).

Gadgets that display information from Atlassian applications, such as [Confluence](#), should be able to run on [iGoogle](#), [Gmail](#) and other web applications that provide [OpenSocial containers](#). Below are specific instructions for iGoogle and Gmail. You can experiment by adding a Confluence gadget to other web sites and applications, such as a [Ning](#) community like [The Content Wrangler](#).

On this page:

- [Overview of Adding a Confluence Gadget to Another Web Application](#)
- [Finding a Confluence Gadget's URL](#)
- [Adding an Atlassian Gadget to iGoogle](#)
- [Adding an Atlassian Gadget to Gmail](#)
- [Limitations and Support](#)
- [Related Topics](#)

Overview of Adding a Confluence Gadget to Another Web Application

The exact procedure for adding a Confluence gadget depends on the application where you want to add the gadget. The basic steps are the same:

1. Find the Confluence gadget's URL, i.e. the URL for the gadget's XML specification file.
2. Ensure one of the following two mandatory (typically one-off) procedures have been conducted:
 - An OAuth relationship between Confluence (as the 'service provider') and the other web application (as the 'consumer') has been established. Refer to [Configuring OAuth](#) for more information about OAuth and instructions on establishing these relationships.
 - A Trusted Applications relationship between Confluence and JIRA has been established. Refer to [Configuring Trusted Applications](#) in the [JIRA documentation](#) for more information about establishing these relationships.
3. Follow the procedure provided by the external web application where you want to add the Confluence gadget.

Finding a Confluence Gadget's URL


A gadget's URL points to the gadget's XML specification file. These URLs look something like this:

```
http://example.com/my-gadget-location/my-gadget.xml
```

To find a Confluence gadget's URL:

1. Choose the help icon  at top right of the screen, then choose **Available Gadgets**.
2. Find the gadget you want.
3. Copy the **Gadget URL** link to your clipboard.

Screenshot: Finding a gadget's URL



Adding an Atlassian Gadget to iGoogle

You can customise your [iGoogle](#) home page by adding gadgets and moving them around on the page.

To add an Atlassian gadget to your iGoogle page:

1. First find the gadget's URL as described [above](#).
2. Go to [iGoogle](#) and log in if you have a username and password.
3. Click **Add stuff** near the top right of the iGoogle page.
4. The Google gadget directory will appear, showing a list of available gadgets. Click **Add feed or gadget** in the right-hand panel.



5. A text box will open, as shown above. Enter or paste the gadget's URL from your clipboard into the textbox and click **Add**.
6. Go back to your iGoogle home page. The gadget will appear on your iGoogle page.

Adding an Atlassian Gadget to Gmail

You can add gadgets to the left-hand panel of your [Gmail](#) page.


To add an Atlassian gadget to your Gmail page:

1. First find the gadget's URL as described [above](#).
2. Log in to [Gmail](#).
3. Click **Settings** near the top right of the Gmail page. The Gmail settings page will appear.
4. Click the **Labs** tab. The Gmail Labs page will appear. This is a laboratory area or testing ground where Google allows you to use experimental features in Gmail.
5. Scroll down to find the feature called 'Add any gadget by URL'.
6. Select the **Enable** option, as shown here:



7. Click **Save Changes**.
8. A new **Gadgets** tab will appear on your 'Settings' page. Click the **Gadgets** tab. The 'Gadgets' page will appear, as shown in the screenshot [below](#).
9. Enter or paste your gadget's URL into the **Add a gadget by its URL** box, then click **Add**.
10. The gadget will appear in the left-hand panel of your Gmail page, as shown in the screenshot [below](#).

Screenshot: Adding a gadget to Gmail



Limitations and Support



Atlassian support does not cover gadgets on external sites like iGoogle and Gmail

In principle, you should be able to add Atlassian gadgets to iGoogle, Gmail and other external sites that support OpenSocial gadgets. However, these external integrations are experimental at this stage and we have encountered problems with them. Please do have fun playing around with them, but be aware that Atlassian does not support the use of Atlassian gadgets on iGoogle, Gmail or other external web sites. See the detailed section on [gadget limitations](#).

Related Topics

[The big list of Atlassian gadgets](#)

Confluence Gadgets

This page describes the purpose of the 'Confluence Gadgets' dialog and how to access it, and provides information about the gadgets that are bundled with Confluence.

Gadgets:

- Interact with and provide access to data in your Confluence installation.
- Can be used externally such as on a JIRA dashboard, a page or blog post of another Confluence site, or any compatible page on a web site that accepts gadgets, such as iGoogle. (But see the limitations on using [Confluence gadgets in other applications](#).)

The gadgets dialog

The 'Confluence Gadgets' dialog displays a list of all the Confluence gadgets available in your Confluence installation. The Confluence gadgets bundled with Confluence are described [below](#). Any additional Confluence gadgets installed by your Confluence administrator (typically as Confluence plugins), will also appear in this list.

To access the Confluence Gadgets dialog: Choose the help icon  at top right of the screen, then choose Available Gadgets.

You can use a Confluence gadget within the same Confluence site, by adding it to a page or blog post using the [gadget macro](#).

You can also add Confluence gadgets to external applications. See [Adding a Confluence Gadget to a JIRA Dashboard](#) and [Configuring Confluence Gadgets for Use in Other Applications](#).


On this page:

- [The gadgets dialog](#)
- [Confluence gadgets](#)

Related pages:

- [Adding a Confluence Gadget to a JIRA Dashboard](#)
- [Configuring Confluence Gadgets for Use in Other Applications](#)
- [Gadget Macro](#)
- [The big list of Atlassian gadgets](#)
- [Confluence User's Guide](#)

Screenshot: The 'Confluence Gadgets' dialog



Confluence gadgets

This following table lists the gadgets which are bundled with Confluence. Click the name of the gadget for more information.

Name	Description
Confluence Page Gadget	The Confluence page gadget allows you to show content from a page on your Confluence site in a gadget. You can optionally configure the gadget to display links to view and/or edit the page on your Confluence site. The page gadget can also be displayed in canvas view, so that it takes up all of the space provided by your dashboard.
Activity Stream Gadget	The activity stream gadget is similar to the recently updated macro and shows a list of the most recently changed content within your Confluence site.
Confluence News Gadget	The Confluence news gadget is an example of a 'news feed' gadget that shows a list of recent Confluence Product Blogs and events at Atlassian .
Confluence Quicknav Gadget	The Confluence QuickNav gadget provides the Quick Navigation Aid functionality for searching the Confluence site. For more information on how to use this feature, refer to the Quick Navigation Aid section of Searching Confluence .

Activity Stream Gadget


The activity stream gadget is similar to the [recently updated macro](#) and shows a list of the most recently changed content within your Confluence site.

i For instructions on how to use Confluence gadgets in your applications, please see [Confluence Gadgets](#).

In addition to showing a list of most recently changed content, the activity stream gadget also provides the following features:

- The ability to add comments to pages and blog posts, by clicking the 'add comment' icon at the top-right of an added or edited page or blog post in the activity stream.
- The ability to reply to a comment by clicking the 'add comment' icon at the top-right of a comment in the activity stream.
- Activities are grouped by separate date.
- An RSS feed link to its content in the top-right corner of the gadget.

Screenshot: Adding a Comment in the Activity Stream Gadget



Activity Stream Gadget Properties

Properties are settings for Confluence gadgets that allow the user to control the content or presentation of data retrieved by the gadget. These are similar to a Confluence macro's parameters. The table below lists relevant properties for this gadget.

Property	Required?	Default	Description
Title	Yes	None	Adds a title to the top of the Activity Stream.
Projects	No	None specified (i.e. display content in all spaces)	Filters the content by space. This gadget will display only the pages etc. which belong to the space(s) you specify here.
Username	No	None specified (i.e. display content by all users)	Filters the results by user. The macro will display only the pages etc. which were last modified by the user(s) you specify here. You can specify one or more user, separated by a comma or a space.

Number of Entries	No	10	Specify the maximum number of results to be displayed. A maximum of 10 results will be displayed by default. The maximum value that this property can accept is 100.
Refresh Interval	No	Never/false	Specify the time interval between each 'refresh' action undertaken by the activity stream gadget. A refresh makes the activity stream gadget reflect any new activity that has been conducted on the Confluence site.

Confluence News Gadget

The Confluence news gadget is an example of a 'news feed' gadget that shows a list of recent [Confluence Product Blogs](#) and [events at Atlassian](#).

i For instructions on how to use Confluence gadgets in your applications, please see [Confluence Gadgets](#).

Clicking an item in the Confluence news gadget takes you directly to the selected blog post of the [Confluence Product Blogs](#) feed or event details on the [events at Atlassian](#) page.

Clicking **More news** takes you to the [Confluence Product Blogs](#) feed page and clicking **More events** takes you to the [events at Atlassian](#) page.

Screenshot: The News Gadget

The screenshot displays the 'News' gadget interface. It features a 'News' section with three bullet points: 'Confluence 5 Highlights: 4 Improvements to User and Content Manageme', 'Confluence 5 Highlights: Automagic Theming', and 'How-to: Building a Company Glossary with Confluence – Part Three'. Below these is a 'More news...' link. The 'Events' section follows, listing three events: 'INTRA.NET Reloaded' (Thu Apr 25, 2013 to Fri Apr 26, 2013), 'Facebook Conference' (Tue Mar 12, 2013 5am to 10:30am PDT), and 'Zertifizierungsschulungen zum JIRA Professional von SEIBERT MEDIA WI'. A 'More events...' link is also present. At the bottom, there is a blue banner for the 'ATLASSIAN USER GROUP' with the text 'Find an Atlassian User Group in your area »' and a small icon of a person with arms raised.

Confluence: News Gadget Properties

Properties are settings for Confluence gadgets that allow the user to control the content or presentation of data retrieved by the gadget. These are similar to a Confluence macro's parameters. The table below lists relevant properties for this gadget.

Property	Required?	Default	Description
Show News?	No	True	Shows a short list of the most recent Confluence Product Blogs .
Show Events?	No	True	Shows a short list of the most recent events at Atlassian .
Show Banners?	No	True	Shows any banner advertisements (if available).

Confluence Page Gadget

The Confluence page gadget allows you to show content from a page on your Confluence site in a gadget. You can optionally configure the gadget to display links to view and/or edit the page on your Confluence site. The page gadget can also be displayed in canvas view, so that it takes up all of the space provided by your dashboard.

 For instructions on how to use Confluence gadgets in your applications, please see [Confluence Gadgets](#).

Macros that work with the page gadget

Please note, not all macros work with the page gadget. Please refer to the [Working Macros](#) section below for more information.

On this page:

- [Confluence Page Gadget Properties](#)
- [Working Macros](#)

Related pages:

- [Confluence Gadgets](#)
- [Confluence User's Guide](#)

Screenshot: The Confluence page gadget displaying a sample page

Sample Page

View

Two penguins find themselves together on an ice floe, drifting helplessly into warmer waters. The penguins are very fond of each other. Suddenly **cra-a-a-a-ck** the ice flow splits in half, right between the penguins. As they drift apart, one penguin sadly waves a flipper and calls out "Chocolate milk!"

 ▼

Confluence Page Gadget Properties

Properties are settings for Confluence gadgets that allow the user to control the content or presentation of data retrieved by the gadget. These are similar to a Confluence macro's parameters. The table below lists relevant properties for this gadget.

Property	Required?	Default	Description
Space	No	None	Specify the space that your desired page is located in. Suggestions will display in a dropdown when you start typing. (Note, this property is only used to make searching for pages easier. It is not required.)
Page	Yes	None	Specify the page that you want to display in your gadget. Suggestions will display in a dropdown when you start typing.
Show View Link	No	Yes	Select whether to display a link to view the page on your Confluence site. Clicking the link will open the page in Confluence.
Show Edit Link	No	No	Select whether to display a link to edit the page on your Confluence site. Clicking the link will open the page for editing in Confluence.
Refresh Interval	No	Never/false	Specify the time interval between each 'refresh' action undertaken by the page gadget. A refresh makes the activity stream gadget reflect any new activity that has been conducted on the Confluence site.

Working Macros

The Confluence page gadget will only render a subset of the macros that are used in Confluence correctly. Refer to the table below for the list of macros that work and do not work with the page gadget and known limitations.



Some of the issues with macros in the page gadget can be worked around, if you are comfortable developing in Confluence. Please see [Troubleshooting Macros in the Page Gadget](#) for more information.

Key:
 Works with the page gadget

 * Partially works with the page gadget

 Does not work with the page gadget

Macro	Works with page gadget?	Limitations
Activity Stream		You cannot have another gadget embedded within the Confluence Page Gadget
Anchor (within a page)	 *	Opens in a new page
Attachments		N/A
Blog Posts		N/A
Chart		N/A
Children Display		N/A
Content By Label		N/A
Content By User		N/A
Excerpt		N/A
Gallery		N/A
Include Page		N/A
Info		N/A
Labels List		N/A
Livesearch		N/A
Note		N/A
Metadata		N/A
Metadata Summary		N/A
Pagetree Search		N/A
Pagetree		N/A
Panel		N/A
Quick Nav		You cannot have another gadget embedded within the Confluence Page Gadget
Recently Updated		N/A
RSS Feed		N/A
Section & Column		N/A
Spaces List		N/A


Table of Contents	 *	Works, however links will be opened in a new browser window when clicked.
Tasklist	 *	Tasks can be viewed but not added/edited.
View File (PDF or PPT)	 *	Works, but you may need to refresh the gadget the first time (see CONF-19932).
Widget Connector	 *	Only works for some content: • Works: blip.tv, Episodic, Flickr, Google Calendar, presentations on Google Docs, MySpace Video, Scribd, Skitch.com, SlideRocket, SlideShare, Viddler, Vimeo, YouTube, Dailymotion, Metacafe, FriendFeed, Yahoo Video, Wufoo HTML Form Builder • Does not work: FriendFeed, Google Gadgets, Google Video (consumer service discontinued), Twitter, Widgetbox, DabbleDB, BackType

Confluence Quicknav Gadget

The Confluence QuickNav gadget provides the [Quick Navigation Aid](#) functionality for searching the Confluence site. For more information on how to use this feature, refer to the [Quick Navigation Aid](#) section of [Searching Confluence](#).

 For instructions on how to use Confluence gadgets in your applications, please see [Confluence Gadgets](#).

Screenshot: Using the QuickNav Gadget



Confluence QuickNav Gadget Properties

This gadget has no properties and cannot be customised.

Adding JIRA Gadgets to a Confluence Page

This is a summary of the steps required to add a JIRA gadget to a Confluence page:

- If your JIRA site does not allow anonymous access, your JIRA administrator will need to configure JIRA to trust Confluence via Application Links. See the [JIRA administrator's guide](#). (Not applicable to Confluence OnDemand.)
- Your Confluence administrator will need to add the JIRA gadget URL to the list of authorised external gadgets in Confluence. See the [Confluence administrator's guide](#). (Not applicable to Confluence OnDemand.)
- Now you can add the gadget to a wiki page in Confluence using the Macro Browser. See the Confluence user's guide to the [Gadget macro](#).

Note that the Confluence Gadget macro is a specific type of macro which is used to display a gadget in a Confluence page - so once you have configured external gadgets in the Confluence Administration Console, they will appear in the Macro Browser.

Related Topics

[All Atlassian gadgets](#)

[External Gadgets](#)

Developing Technical Documentation on Confluence Wiki

Welcome! This is a guide to using Confluence wiki for technical documentation. You will find this guide useful if you want to write a technical manual such as a user's guide, administrator's guide, installation guide, and so on.

- [Creating your Technical Documentation Space](#)
- [Using Templates in Technical Documentation](#)
- [Re-using Content in Technical Documentation](#)
- [Managing the Life Cycle of your Technical Documentation](#)
- [Providing PDF Versions of your Technical Documentation](#)
- [Exporting and Printing Technical Documentation](#)
- [Essential Confluence Features for Technical Documentation](#)
- [Confluence Add-ons for Technical Documentation](#)

- [Further Reading about Developing Technical Documentation on Confluence](#)

RELATED TOPICS

[Confluence User's Guide](#)

[Confluence Administrator's Guide](#)

Creating your Technical Documentation Space

This guide is for people who want to develop and publish technical documentation on Confluence wiki. You will find it useful if you want to write a technical manual such as a user's guide, administrator's guide, installation guide, and so on. This page is a quick-start guide to creating a wiki space for technical documentation.



Quick guide to creating a technical documentation space

- Add a space and select the Documentation theme.
- Set the space permissions.
- Change the title and content of the space home page.
- Customise the Documentation theme.
- Create an inclusions library to manage your re-usable content.
- Create the table of contents for your manual or manuals, by adding top-level pages for all the usual sections (user's guide, administrator's guide, and so on).
- Customise your PDF layout and stylesheet, if required.
- *Hint:* Now that you have a good skeleton for a documentation space, save the space as a template space.

The rest of this page gives more details of the above procedure.

On this page:

- [Step 1. Add your Space](#)
- [Step 2. Set the Space Permissions](#)
 - [A Bit More about Permissions](#)
- [Step 3. Customise the Title and Content of the Home Page](#)
- [Step 4. Customise the Documentation Theme](#)
 - [Example of a Customised Footer](#)
- [Step 5. Create an Inclusions Library](#)
 - [Examples of Inclusions Libraries](#)
- [Step 6. Create the Table of Contents](#)
- [Step 7. \(Optional\) Customise the PDF Layout and Stylesheet](#)
- [Step 8. Save your New Space as a Template Space](#)

Step 1. Add your Space

Below is a quick guide to adding a space. See [Creating a Space](#) for a full description.

1. Go to the Confluence dashboard and choose **Add Space**.
Hint: If you cannot see **Add Space**, this means that you do not have permission to add spaces. Please contact your Confluence administrator.
2. In the 'Create Space' screen, enter a **space name** and a short, unique **space key**.
3. Leave the **permission** settings as default, or choose to allow only yourself to view or contribute content to this space. You can change these settings later and with more flexible options.
4. Choose **OK**.
5. Your new space appears. Choose **Space Tools** in the sidebar.
6. Choose **Look and Feel > Themes** and select the **Documentation** theme.
7. Choose **OK**

The home page of your new space will appear, with the Documentation theme. Because you created the space, you are the space administrator. Now you can do some basic configuration, as described in the sections below. From this point on, instructions will refer to navigating in the Documentation theme, which is slightly different to the default theme.

Step 2. Set the Space Permissions

Define the space permissions to determine who can do what in your new space.

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose '**Permissions**'.
3. Choose '**Edit Permissions**'.
4. Set the permissions to suit your needs then choose '**Save All**'.
 - You can add **groups** and/or individual **users** to the list, then select the permissions for each group or user.
 - You can also set the permissions for **anonymous** users – these are people who have not logged in to the wiki. Anonymous access is available only if enabled for the entire Confluence site.
 - Note that you can change these permissions at any time. You may want to restrict the permissions to specific groups now, and later open the space to more people.

A Bit More about Permissions

Confluence has a robust and granular permissions scheme that you can use to determine who can view, comment on and even update the documentation. There are three levels of permissions in Confluence:

- Global permissions apply across the entire site.
- Space permissions apply to a space.
- Page restrictions allow you to restrict the editing and/or viewing of a specific page. Below we discuss a way of using these in the draft, review and publishing workflow.

Space permissions in Confluence are simple yet granular enough to be useful for technical documentation. You can:

- Use the permission levels to control who can create pages in the space, delete pages, create comments, delete comments, administer the space, and so on.
- Grant a permission level to one or more users, and/or to one or more groups, and/or to anonymous users.

Terminology:

- '**Anonymous**' means people who have not logged in to the wiki.
- The '**confluence-users**' group is the default group into which all new users are assigned. Everyone who can log in to Confluence is a member of this group.

For example, you might allow your team full edit and administration rights while others can only add comments. Or you might grant the general public access to your documentation, while only staff members can update it.

Groups

These are the permissions currently assigned to groups for this space.

	All	Pages			Blog		Comments		Attachments		Mail	Space	
	View	Add	Restrict	Remove	Add	Remove	Add	Remove	Add	Remove	Remove	Export	Admin
confluence-users	✓	✗	✗	✗	✗	✗	✓	✗	✗	✗	✗	✓	✗
my-team	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓

Edit Permissions

Individual Users

These are the permissions currently assigned to individual users for this space.

	All	Pages			Blog		Comments		Attachments		Mail	Space	
	View	Add	Restrict	Remove	Add	Remove	Add	Remove	Add	Remove	Remove	Export	Admin
Rach Admin (admin)	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓

Edit Permissions

Anonymous Access

When a user is using Confluence while not logged in, they are using it anonymously.

For example: Enabling anonymous 'commenting' permission, allows non-logged-in users to make comments in this space.

	All	Pages			Blog		Comments		Attachments		Mail	Space	
	View	Add	Restrict	Remove	Add	Remove	Add	Remove	Add	Remove	Remove	Export	Admin
Anonymous	✗	✗	✗	✗	✗	✗	✗	✗	✗	✗	✗	✗	✗

Edit Permissions


For detailed information, see the documentation on:

- [Global permissions](#)
- [Space permissions](#)
- [Page restrictions](#)
- [Users and groups](#)

Step 3. Customise the Title and Content of the Home Page

When you created your space, Confluence created a home page with default content and a default title, 'Home'. You will want to change the title and content.

1. Go to your space home page.
2. By default, the page title is 'X Home', where 'X' is the name you gave the space.
3. Choose **Edit**.
4. The page opens in the editor. Change the title to suit your needs.



5. Update the content to suit your needs.
Hint: If you do not know what to add yet, just add a short description. You can refine the content of the page later. Take a look at an [example of a home page](#).
6. Choose **Save**.

Step 4. Customise the Documentation Theme

When you added the space you chose the Documentation theme, which provides a left-hand navigation bar and a good look and feel for technical documentation. If necessary, you can configure the Documentation theme to add your own page header and footer or to customise the default left-hand navigation bar. These customisations affect the online look and feel of your documentation. See [Configuring the Documentation Theme](#) for the full description.

1. Choose **Browse > Space Admin** (if you have not yet applied the Documentation theme choose **Space Tools > Look and Feel > Themes**)
2. Choose **Themes** in the left menu.
3. If the space is not yet using the Documentation theme, apply the theme now.
4. Choose **Configure theme**

Current Theme

The current theme controls the layout and colours of this space.



Documentation Theme

This theme is well suited for structured content, such as documentation. It features a table of contents (page tree) on the left, making it easier to see the structure of a space and move from page to page. You can customise the left-hand panel, page header and page footer.

[Configure theme](#) - further customise this theme's options

5. The 'Documentation Theme Configuration' screen appears. Customise the left-hand navigation bar, header and footer to suit your needs. Details are in the [documentation](#). Here are some hints:
 - The **Page Tree** check box determines whether your space will display the default search box and table of contents (page tree) in the left-hand panel.
 - The **Limit search results to the current space** check box determines whether Confluence will search only the current space or the whole Confluence site. This setting affects the default search. Viewers can override it each time they do a search.
 - Enter text, images, macros and other wiki markup into any or all of the three text boxes for the left-hand navigation bar, header and footer. You can use the [Include macro](#) and the [Excerpt Include macro](#) to include re-usable content.
 - Any content you add to the navigation panel will appear **above** the default page tree.
 - If you like, you can remove the default page tree (by unticking the box) and add your own, customised version of the [Pagetree](#) macro instead.
6. Choose **Save**.

Example of a Customised Footer

Take a look at the footer of a page in the [Crowd documentation space](#).

Get Support
 Log a request with our support team.

Report a Bug
 Raise an issue for our developers.

Visit the Forums
 See answers from the community.

Add to our Docs
 Blog and update our documentation.

Except where otherwise noted, content in this space is licensed under a [Creative Commons Attribution 2.5 Australia License](#).

Powered by Atlassian Confluence 3.4.1, the Enterprise Wiki | [Report a bug](#) | [Atlassian News](#)

To produce the above footer, we have the following content in the footer panel in the Documentation theme configuration screen:

Footer	<pre>{include:_Documentation Footer nopanel=true} {include:ALLDOC:_Copyright Notice nopanel=true}</pre>

Here it is in text form:

```
{include:_Documentation Footer|npanel=true}
{include:ALLDOC:_Copyright Notice|npanel=true}
```

The above content consists of two [Include macros](#).


- The first macro includes a page called [_Documentation Footer](#). This page contains the big blue buttons and hyperlinked text.
- The second macro includes a page from a different space, the ALLDOC space, called [_Copyright Notice](#). This page includes our standard copyright notice, used in all our documentation spaces.

Step 5. Create an Inclusions Library

Using Confluence, you can dynamically include content from one page into another page. You can include a whole page into another one, using the [Include macro](#). You can also define an 'excerpt' on a page, and then include that excerpted text into another page using the [Excerpt Include macro](#).

To organise your re-usable content, we recommend that you create a set of pages called an 'inclusions library'.

1. Choose **Create** and create a new page in your space.
2. Enter a suitable title. We use '[_InclusionsLibrary](#)'. The unusual format of the title helps to let people know this page is special.
3. Enter some content and **save** the page. We enter text explaining the purpose of the inclusions library and how to re-use the content. You can copy our text by clicking through to one of the example pages listed below.
4. Choose **Browse > Pages** and drag your new page *above* the space homepage.
5. Go to your new inclusions page and choose **Create** to add child pages containing your re-usable content. See the examples of our own inclusions libraries listed in the [examples](#) below.



Some notes about inclusions libraries:

- The inclusions library is not a specific feature of Confluence. The pages in the inclusions library are just like any other Confluence page.
- The pages are located at the root of the wiki space, not under the home page. This means that they will not appear in the table of contents on the left and they will not be picked up by the search in the left-hand navigation bar either.
- The pages will be picked up by other searches, because they are just normal wiki pages.
- We have decided to start the page name with an underscore. For example, '[_My Page Name](#)'. This indicates that the page is slightly unusual, and will help prevent people from changing the page name or updating the content without realising that the content is re-used in various pages.

Examples of Inclusions Libraries

Here are some examples in our documentation:

- [Crowd inclusions library](#)
- [Confluence inclusions library](#)

Step 6. Create the Table of Contents

Create the table of contents for your documentation, by adding the top-level pages for all the usual sections:

- User's guide
- Administrator's guide
- Installation guide
- Configuration guide
- Release notes
- FAQ
- Whatever else you need

1. Go to your space home page.
2. Choose '**Create**' to add a page as a child of the homepage.
3. Enter the page title, '**User's Guide**'.
4. Enter the content of the page.
Hint: If you do not know what to add yet, just add a short description then refine the content of the page later. If you like, you can add the [Children macro](#). That will act as a table of contents on the page once you have added child pages.
5. Choose '**Save**'.

Now do the same for all the sections of your technical document.

Step 7. (Optional) Customise the PDF Layout and Stylesheet

If you are planning to provide PDF versions of your documentation, you may want to customise the PDF layout and styles for your space. You can skip this step for now and do it later, if you prefer. The instructions are in a separate section of this guide, dedicated to PDF. See [Providing PDF Versions of your Technical Documentation](#).

Step 8. Save your New Space as a Template Space

This is a useful suggestion. Once you have set up your first documentation space and are more-or-less happy with it, use the [Copy Space plugin](#) (see notes [below](#)) to copy the space while it still has very little content. From this point on, you can copy it each time you want to create a new documentation space.

1. Choose **Browse > Space Admin**
2. Choose **Copy Space** in the left menu
Hint: If you cannot see the 'Copy Space' option, this means that the plugin is not installed on your Confluence site. Refer to the documentation on [installing plugins](#). (Not applicable to Confluence OnDemand.)
3. The '**Copy Space**' screen will appear. Enter the details as prompted, to copy your space to another new space.

Copy Space

You are about to copy this space. Please fill in the new key and space name you wish to use.

Name:

Key:

Use existing authors and dates: ☒

Copy comments: ☒

Copy attachments: ☒

Copy personal labels: ☐

4. Choose '**Save**'.

You now have a template space. From this point on, you can use the Copy Space plugin to copy the template space each time you want to create a new documentation space.

Notes:

- The Copy Space plugin is not covered by Atlassian support. However, the Atlassian technical writers use it for all our documentation. If you like, you can vote for an comment on the request for Atlassian support to cover this plugin: [CONF-14198](#).
- Your site administrator will need to install the Copy Space plugin into Confluence. Refer to the documentation on [installing plugins](#). *Not applicable to Confluence OnDemand.*

Next Steps

You now have the basic structure and configuration for your technical documentation space. You have also created a handy template to use next time you need a space. What next? Take a look at [Using Templates in Technical Documentation](#).

Using Templates in Technical Documentation

This page is part of the guide to [developing technical documentation on Confluence Wiki](#). We have already shown you how to [create your technical documentation space](#). Now we offer an introduction to the templates that Confluence provides.



Quick guide to templates in Confluence

- A template is a page with predefined content that can be used as a prototype when creating other pages.
- Templates are available across the Confluence site (global templates) or per space (space templates).
- Both 'global templates' and 'space templates', as described on this page, define the content of a page. They do not define the content of an entire space.
- You can import predefined templates, including those shipped with Confluence and additional templates from the [Atlassian Plugin Exchange](#).
- To create a template for an entire space, see our guide to [creating your documentation space](#).

On this page:

- [Deciding Where to Put Your Templates](#)
- [Creating a Global Template](#)
- [Creating a Space Template](#)
- [Importing Templates](#)
- [Using a Template to Create a Page](#)

Deciding Where to Put Your Templates

In Confluence, there are two places to store your page templates:

- **Space templates:** These page templates are available in a specific space only. People who have [space administrator](#) permission can define templates via the space administration screen.
- **Global templates:** These page templates are available in every space on the site. People who have [Confluence Administrator permission](#) can define the global templates via the Confluence Administration Console.

Decide whether your template is useful across more than one space.

- If yes, create a global template. You will need Confluence administrator permissions.
- If no, create a space template.
 - You will need space administrator permissions for the relevant space(s).
 - You may have already saved your documentation space as a template, as described in our guide to [creating your documentation space](#). In that case, it may be useful to save your template page in your template space. When you later copy the space, the template pages will be copied too.

Creating a Global Template

1. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
2. Choose **Global Templates** in the left-hand panel.
3. Choose **Add New Global Template**.

See [Administering Site Templates](#) for more information.

Creating a Space Template

1. Go to the space and choose **Space tools > Content Tools** on the sidebar.
2. Choose **Templates > Add New Space Template**.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Templates** from the space administration options.
3. Choose **Add New Space Template**.

See [Adding a Template](#) for more information.

Importing Templates

Confluence ships with a number of templates, including the 'Charts', 'Document List' and 'Meeting Notes' templates. These templates are not available for use by default. However, if you have the appropriate [permissions](#) to access the Administration Console, you can import any of these templates to be used globally or within a specific space. In addition, you can find more template bundles on the [Atlassian Plugin Exchange](#).

1. Log in to Confluence as an administrator.
2. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
3. Choose **Import Templates**. The 'Import Templates' screen will appear, listing the template packages deployed to your Confluence instance and the templates included in each package.
4. Select the templates you want to import.
Note: You can view a preview of the template by clicking the template name.
5. Choose the destination to **Import To**. If you want the templates to be available to your documentation space only, select the name of the space, otherwise select 'Global Templates' to make the templates available to all spaces.
6. Choose **Import** to import the selected templates.

Using a Template to Create a Page

When people create a page on your Confluence site, they can choose to base their new page on a template.

Go to the page that will be the parent of your new page, and choose **Create**.

All available templates for that space will display, select a template then choose **Next**.

Next Steps

You now have a good idea of how Confluence templates work. What next? Take a look at [Re-using Content in Technical Documentation](#).

Re-using Content in Technical Documentation

This page is part of the guide to [developing technical documentation on Confluence Wiki](#). In the page about [creating your technical documentation space](#), we showed you how to set up an 'inclusions library' to contain content that you can re-use on more than one page. Now we offer further guidelines on re-using content in your documentation space.

Your documentation may be about using a software application, or it may be a technical manual for your product range. On this page, we use the term 'widget' to describe the things that you are documenting, such as the screen, form, document, product or object.



Quick guide to re-using content

- Create an 'inclusions library' to manage your re-usable content. See our guide to [creating your technical documentation space](#).

- Use the `excerpt` macro to define a re-usable section ('excerpt') on a page, or just decide to re-use the entire content of the page.
- Use the `excerpt - include` macro to include the excerpt from one page onto another page.
- Use the `include` macro to include the entire content of a page onto another page.
- Consider installing the Multi Excerpt plugin if you need to define multiple excerpts per page.

The rest of this page gives an overview and more details of the above procedures.

On this page:

- [Reasons for Re-Using Content](#)
- [Defining an Inclusions Library](#)
- [Working with Excerpts and Inclusions](#)
 - [Using the Include Page Macro](#)
 - [Using the Excerpt Include Macro](#)
 - [Using the Multi Excerpt Plugin \(*Not applicable to Confluence OnDemand.*\)](#)
- [An Example of Content Re-Use: A Glossary](#)
 - [Creating a One-Page Glossary](#)
 - [Creating a Glossary with Child Pages](#)
 - [Referring to Glossary Terms](#)
- [Further Reading](#)

Reasons for Re-Using Content

A golden rule for technical documentation is to write the content only once but allow that content to be used in many places and in many forms.

For example, you may have the following types of content:

- A technical manual that describes each widget in detail.
- Tips and tricks on how to get the most out of the widget.
- A step-by-step user guide for first-time users on how to use the most common widgets.
- A training manual with exercises or videos that people can follow in their own time.
- A one-page cheat sheet for users to stick up on their workstation.
- Text for a sales brochure that is sent out to a print house for production.

Each of these types of content will share common information, such as a glossary entry, a technical or marketing description of the widget, or a step-by-step guide on how to use the widget.

Some initial planning of your technical documentation will allow you to re-use any or all of the content you write, so there is only ever one place to update the content, and those changes flow through to all of your other documentation.

Defining an Inclusions Library

We recommend that you create an 'inclusions library' to manage your re-usable content. If you have not already done this when creating your documentation space, see our guide to [creating your technical documentation space](#).

Working with Excerpts and Inclusions

Excerpts and inclusions (sometimes called 'includes') are very useful for re-using content:

- Use the `Excerpt` macro (`excerpt`) to define a re-usable section ('excerpt') on a page.
- Use the `Excerpt Include` macro (`excerpt - include`) to include the excerpt on another page.
- Use the `Include Page` macro (`include`) to include the entire content of a page onto another page.

A simple example of an inclusion is a note or warning that is used in many places in your documentation. Here is

an example:

**Example note -- "Draft in progress"**

This document is still in draft status. Please treat the content with caution.

Tip: Keep your re-usable pages short and sweet. Do not worry if you find that you need hundreds of pages to hold your inclusions. It helps to keep things separate and organised.

Using the Include Page Macro

In this example, we use the Include Page macro to create a note that you can re-use on your documentation pages. The Include Page macro will include the entire content of one page into another page. (See the '**Excerpt**' macro below for including parts of a page.)

1. Create a page in your inclusions library called **_Draft Note**.
2. Add the content of the page. In this example, we use the Note macro with some text in the title and body:

```
{note:title=Draft in progress}This document is still in draft status.  
Please treat the content with caution.{note}
```

3. Use the Include Page macro to include that note in any page in your documentation. For example:

```
{include:_Draft Note|npanel=true}
```

See the documentation on the [Include Page macro](#) for more details.

Using the Excerpt Include Macro

An excerpt is a section of a page that you can include into another page.

1. Use the excerptmacro to define any content in your page that you want to be able to use elsewhere. This content can be as short as a word or as long as the entire page. For example, let's assume we have a page called 'My Short Poem':

```
I really love this poem:  
{excerpt}  
Mary had a little lamb  
Its fleece was white as snow  
{excerpt}  
And I'm going to use it all over the place.
```

2. Use the Excerpt Include macro to include the excerpt into another page. For example:

```
{excerpt-include:My Short Poem|npanel=true}
```

You can only define one excerpt on a page. See the documentation on the [Excerpt Include macro](#) for more details.

To have multiple excerpts on a page, see the '**Multi Excerpt plugin**' below.

Using the Multi Excerpt Plugin (Not applicable to Confluence OnDemand.)

The Multi Excerpt plugin provides additional macros that enable you to have multiple excerpts on a page. A good example of where you would find this useful is in the glossary page discussed below. If you want to include a single glossary entry or a subset of the glossary entries in another page, then the named excerpts allowed by the Multi Excerpt plugin are very useful.

Notes:

- The [Multi Excerpt plugin](#) is a commercial plugin and is not free.
- Your Confluence administrator will need to download and install the plugin into your Confluence site before you can use the macros described below. Refer to the documentation on [installing plugins](#).
- *Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#). Please refer to the [Multi Excerpt plugin page](#) for support details.*

1. Use the following code on the base page containing the content you want to use elsewhere:

```
{multi-excerpt:name=ExcerptName1}
Excerpt text 1
{multi-excerpt}
Any other text
{multi-excerpt:name=ExcerptName2}
Excerpt text 2
{multi-excerpt}
```

2. Use the following code on the page where you want to include the named excerpt:

```
{multi-excerpt-include:pageTitle=PageName|name=ExcerptName1|nopanel=true}
```

3. You can also include excerpts from other spaces using the following syntax:

```
{multi-excerpt-include:spaceKey:pageName|name=excerptName|nopanel=true}
```

See the [Multi Excerpt plugin page](#) for more details.

An Example of Content Re-Use: A Glossary

A glossary is something that most technical documentation will require. There are a few ways to set up glossaries in Confluence. These are the most popular:

- All glossary entries on one page.
- Each glossary entry on separate child pages with a main page showing excerpts of the glossary.

Once you have defined the glossary entry, you can refer to it from the main pages of your technical documentation.

Creating a One-Page Glossary

This style of glossary is useful if the glossary entries tend to be short and there are not too many of them.

1. Create a page named **Glossary**.
2. Add an alphabetical index at the top of the page and a heading for each letter of the alphabet:

```
[A|#A] | [B|#B] | [C|#C] ...
{anchor:A}
h2. A
{anchor:B}
h2. B
{anchor:C}
h2. C ...
```

3. Enter each glossary entry under the relevant alphabetical heading. Each glossary entry (term) should include:
 - An anchor tag, so that you can link to it from other pages.
 - The term itself.
 - A definition of the term.
 - A link to the page in your technical documentation that explains the term in greater detail, where relevant.

```
{anchor:MyGlossaryTerm}
h4. MyGlossaryTerm
This is the definition of MyGlossaryTerm. See [Page Name] for
more information.
```

4. Optionally, include a horizontal line between the terms. This depends on how long each entry is. If your glossary tends to have short entries, it may look too cluttered with horizontal lines.

```
---
```

See the glossary in the [Confluence documentation](#) for an example of this style of glossary (without the alphabetical index).

Creating a Glossary with Child Pages

This style of glossary is useful if the glossary entries tend to be quite long or have additional information over and above the definition of the term.

1. Create a page named **Glossary**.
2. Create a child page for each glossary entry (term). Each child page should contain:
 - The term as the title of the page.
 - The definition of the term in the body of the page.
 - Excerpt tags (excerpt) tags surrounding the definition.
 - Any additional information after the excerpt tags.

```
{excerpt}
This is the definition of MyGlossaryTerm
{excerpt}
More information to describe MyGlossaryTerm
```

3. On the '**Glossary**' page, use the childrenmacro to show the excerpts from each child page in a list, with the page name displayed in 'h4' style.

```
{children:excerpt=true|style=h4}
```

See the glossary in the [Crowd documentation](#) for an example of this style of glossary.

Referring to Glossary Terms

In the main pages of your technical documentation, create a link to the glossary page for each glossary term.

```
_ [MyGlossary Term|Glossary#MyGlossaryTerm] _
```

Note that this is a standard page link with an anchor. We have formatted the link as italics, because it helps to have the glossary links looking different to other page links. Readers can just skip over the glossary link if they are already familiar with the term.

Further Reading

- A blog post about content re-use: [Technical Writing in a Wiki - Content Re-use and Structure](#) (November 2010).

Next Steps

You now have a good idea of how to re-use content in a Confluence documentation space. What next? Take a look at [Managing the Life Cycle of your Technical Documentation](#).

Managing the Life Cycle of your Technical Documentation

This page is part of the guide to [developing technical documentation on Confluence Wiki](#). We have already shown you how to [create your technical documentation space](#), including how to set permissions for your space. Now we offer a quick-start guide to managing the life cycle of your technical documentation in Confluence. The life cycle includes drafting, reviewing and publishing a document, as well as managing documentation that is release-specific.



Quick guide to managing the technical documentation life cycle

- Create draft pages with restricted permissions, to hide them until they are ready for publication.
- Set the permissions to allow reviewers to comment on and/or update the pages.
- When ready, publish the page by removing the permission restrictions.

- Monitor updates to your draft and published pages by watching your space and/or subscribing to RSS feeds.
- Use spaces as a mechanism for matching your documentation version to product releases: one space per major release number.
- Consider installing plugins for extended workflow and publication management.

The rest of this page gives more details of the above procedures.

On this page:

- [Using the Built-In Confluence Functionality to Manage Workflow and Release Cycle](#)
 - [Drafting, Reviewing and Publishing a Page](#)
 - [Keeping Track of Documentation Updates](#)
 - [Viewing the History of a Page](#)
 - [Receiving Email Notification of Updates](#)
 - [Monitoring Updates via RSS Feeds](#)
 - [Release Management](#)
 - [Space Keys](#)
 - [The Release Management Process](#)
 - [Other Scenarios using the Built-In Confluence Functionality](#)
- [Using Add-Ons for Extended Workflow, Publication and Concurrent Version Management \(Not applicable to Confluence OnDemand.\)](#)
- [Notes](#)

Using the Built-In Confluence Functionality to Manage Workflow and Release Cycle

This section describes how to use the built-in Confluence functionality to manage your workflow (draft, review, publish) and to align your documentation version control to the product release cycle.

In this scenario we also assume that you want a *live* space that always has the same space key and always contains the *latest* version of your documentation. This scenario suits the requirements of an organisation that wants their technical documentation to be 'live'. Various groups of people can refine the content as and when required. People can also subscribe to the space, knowing that they will always get the latest version of the documentation and comments.

This is the way we manage our documentation at Atlassian. The content of the wiki is dynamic, continuously updated, commented on, subscribed to and watched by thousands of people all over the world.

Drafting, Reviewing and Publishing a Page

The workflow is simple.

1. Create a page with [restricted permissions](#). For example, you might restrict viewing to a group of people such as your team. On a public wiki, you might restrict viewing to staff members, so that the general public cannot see the page.
2. Write the page content.
3. Ask other people to review the page. They can add comments to the page or simply edit the page content directly.
4. Publish the page when ready, by doing the following:
 - Delete the comments on the page.
 - Remove the permission restrictions on the page. The page has now been published. The space permissions and site permissions now determine who can see and/or update the page.

The screenshot below shows a page under review. Notice the lock icon at top left, indicating that restricted permissions apply to this page.

Documentation / ... / Sample Page

Introducing workflow

Added by Rach Admin, last edited by Josh User on Feb 18, 2013 (view change)

Comment: Added note about plugin support ← **Comment made about an update made**

Confluence does not have any built-in workflow.

It does have the features and plugin points to let you design a workflow to suit your needs .

Interesting plugging already created include:

- Approvals Workflow plugin
- Content Publishing plugin

⚠ Atlassian does not officially support these plugins. Please refer to the [guidelines](#) on Atlassian plugin support. ← **Page updated by a reviewer**

Like Be the first to like this No labels

1 Comment

Ewan User ← **Comment from a reviewer**

I think we should mention that not all plugins are supported.

Reply • Edit • Delete • Like • 2 minutes ago

Keeping Track of Documentation Updates

On a wiki, it is quite usual for a number of different people to update a single page. Technical writers need to know what happens to our documents, both during review and after publication.

Viewing the History of a Page

Confluence creates a new version of the page every time someone edits the page. The page history shows all the versions, with date, author, and any comments made on the update.

Go to the page and choose **Tools > Page History**.

Compare selected versions			
Version	Date	Changed By	Operations
☐ CURRENT (v. 6)	Jul 02, 2010 15:46	Andrew Lui: Migrated to Confluence 4.0	
☐ v. 5	Jul 02, 2010 15:46	Andrew Lui: (Migrated to Confluence 4.0)	Restore this version · Remove
☐ v. 4	Jul 02, 2010 15:46	Andrew Lui	Restore this version · Remove
☐ v. 3	Mar 06, 2010 14:41	Sarah Maddox ♥	Restore this version · Remove
☐ v. 2	Sep 29, 2008 12:23	Sarah Maddox ♥	Restore this version · Remove
☐ v. 1	May 06, 2008 14:33	Sarah Maddox ♥	Restore this version · Remove

On the page history view, you can:

- View the content of a specific version of the page.
- Revert to (restore) a specific version.
- Select any two versions and ask for a comparison, to see what has changed between those two versions.

See [Page History and Page Comparison Views](#) for detailed information.

It is all very well to go to a specific page and see what has happened to it, but how do you know when to go and look at the page? You need a notification of any changes made to your documentation space.

In Confluence, you can monitor updates to your documentation via email notifications and via RSS feeds.

Receiving Email Notification of Updates

You can 'watch' a page or an entire space. Whenever anyone updates the page or space, you will receive an email notification.

To watch a page:

Choose **'Tools' > 'Watch'**.

To watch a space:

1. Choose **'Browse' > 'Space Operations'**.
2. Choose **'Watch this space'** in the left-hand menu.

See [Subscribing to Email Notifications of Updates to Confluence Content](#) for details of the various notifications Confluence will send, and how to configure your notification settings.

Monitoring Updates via RSS Feeds

RSS feeds provide another way to keep track of updates. The simplest way to build an RSS feed is to use Confluence's feed builder, accessible from the dashboard. This will give you a URL that you can ping to get the latest updates.

Below we describe how to set up a useful feed for your technical documentation space. Remember that you can adjust the settings to suit your own needs.

1. Choose **Help ? > Feed Builder**. The RSS feed builder form appears.
2. Check the boxes to select all the content types. (Even if you are not expecting comments, blog posts or mail in your documentation space, it does no harm to receive notifications if they do arrive.):
 - **Pages** and the **comments** and **attachments** on pages.
 - **Blog posts** and their **comments** and **attachments**.
 - **Mail**.
3. Select your documentation **space** from the list. Press Ctrl and click to select multiple spaces.
4. Click the **Create RSS Feed** button to create your feed.
5. This will take you to a new screen. Drag or copy the link into your RSS reader. The feed URL is linked to the words **Drag or copy this link to your RSS reader**.

Now that you have set up your RSS feed, you need to decide how to read it. There are various options to choose from. For example:

- Use an RSS reader, such as the [Sage add-on for Firefox](#).
- Use an email client, such as [Thunderbird](#).

See [Subscribing to RSS Feeds within Confluence](#) for details.

Release Management

Let's assume that your product goes through a regular release cycle, and that you need to retain separate documentation for each major version of the product.

At Atlassian, we use spaces as our version-control mechanism.

- **Archive spaces**. At each release, we create a new archive space to house the *previous* version of the documentation.
- **The live space**. The documentation for the *latest* version of the product resides in the live space. The live space always retains the same space key and is always available for viewing and updating.

Space Keys

The live space has just the product name as its space key. For example, for the Crowd product the space key is 'CROWD'. (See the [Crowd documentation space](#).)

For the archived versions, we use a combination of the product name plus version number as the space key. For example, we use 'CROWD020' for the Crowd 2.0 documentation, 'CROWD016' for the Crowd 1.6 documentation, and so on.

The Release Management Process

Here is an overview of the process we follow at Atlassian.

1. **Leading up to release date.** Work with hidden draft pages in the live space. A 'hidden draft' is simply a page that has [restricted permissions](#) applied:
 - For each new feature, create a new page with restricted permissions.
 - If you need to update existing pages, create a hidden copy of the existing page and apply the updates to the copy.
 - Follow the usual draft and review procedure for each page.
2. **A few days before release date.** Use the [Copy Space plugin](#) to copy the live space to a new space. This creates a snapshot of the current documentation, and will act as an archive for the current release which is soon to become the previous release. (We described the use of the Copy Space plugin in the earlier section of this guide: [Creating your Technical Documentation Space](#).)
3. **On release date.** Publish the updated documentation for the new version of the product:
 - Rebrand the live documentation space to reflect the new release number. In other words, change the space name and any other descriptions that include the product release number.
 - Unhide all the new pages, by removing the permission restrictions on each hidden page.
 - Copy the content of the updated pages to the proper pages, then delete the copies.
 - Export the newly updated space to PDF, HTML and XML, for those customers who prefer offline versions of the documentation.

Note that the above process is applicable to major releases of the product. For minor bug-fix releases, we simply update the documentation in the live space. We do not create archive spaces for every minor release.

The example below shows an extract from the dashboard of our documentation wiki, listing the spaces for different versions of the Crowd documentation. (Crowd is one of our products.) Each space holds the documentation for a specific major release of Crowd.

Screenshot: Archive Bamboo spaces and Bamboo Latest for the current version of the documentation.

Bamboo			Filter
Space	Description	Categories	
 Bamboo 4.0	Documentation for Bamboo 4.0	bamboo documentation	☆
 Bamboo 4.1	Documentation for Bamboo 4.1	bamboo documentation	☆
 Bamboo 4.2	Documentation for Bamboo 4.2	bamboo documentation	☆
 Bamboo 4.3	Documentation for Bamboo 4.3	bamboo documentation	☆
 Bamboo Latest	Documentation for the latest version of Bamboo (4.4)	bamboo documentation	☆

Other Scenarios using the Built-In Confluence Functionality

It is easy to design other ways of managing your documentation spaces using the built-in Confluence functionality. For example, the simplest scenario is to publish a new space for every new release of your product, using the same [Copy Space plugin](#) as described above.

Using Add-Ons for Extended Workflow, Publication and Concurrent Version Management (*Not applicable to Confluence OnDemand.*)

For advanced workflow features, consider installing the [Ad Hoc Workflows](#) add-on onto your Confluence site.

For advanced publication and concurrent version management consider using the [Scroll Versions add-on](#). Scroll Versions enables you to set up and manage concurrent versions of your documentation in a single space. Multiple versions of software, different product variants, and even multiple languages of documentation can be managed. Changes to pages are scheduled for a specified version and then published all at once.

1. Install the [Scroll Versions add-on from the Marketplace](#) or from the Confluence [Universal Plugin Manager](#).
2. Create a space for your documentation or activate Scroll Versions on your existing documentation.
3. Add the version numbers that you want to work with via the version management screen.
4. When a version is ready to publish go to '**Browse**' > '**Scroll Versions**' > '**Manage Versions**' and publish your documentation within the same space or to another space.

See the [documentation of Scroll Versions](#) for further information.

Similarly, consider using the [Content Publishing](#) add-on to publish content from a master space to a published space. In this scenario, you will create a *master* space that contains your drafts in progress and new releases. The master space is visible only to the authors and reviewers. You will periodically publish the master space to a *published* space. This suits the requirements of an organisation that needs a 'published' or 'official' set of documentation, published only when a new version of the product is released. There is no requirement for continual updating of the documentation.

1. Install the Content Publishing plugin.
2. Create a space for your master content.
3. Create a space for your published content.
4. When the content in the master space is ready to publish, go to the '**Advanced**' tab in the '**Space Admin**' section of the master space (if you are using the Documentation theme).
5. Choose '**Publish Space**' to configure the settings and then publish your space. See the plugin documentation to choose the options best for your needs.
6. Choose '**Publish**'.

 **Automatic publishing.** The Content Publishing plugin can work together with the Ad Hoc Workflows plugin to publish pages automatically when the page reaches a specified state in the workflow.

Notes

- **Installing plugins.** If you decide to use additional plugins, your site administrator will need to install the plugins into your Confluence site. Refer to the documentation on [Installing Add-ons](#). (*Not applicable to Confluence OnDemand.*)
- **Plugin support.** *Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#).*

Next Steps

Now you know about managing your workflow and documentation release process on Confluence. What next? Take a look at [Providing PDF Versions of your Technical Documentation](#).

Providing PDF Versions of your Technical Documentation

This page is part of the guide on [Developing Technical Documentation on Confluence Wiki](#).

Confluence is a platform for publishing online documentation. It also provides an export to PDF feature for producing PDF versions of your documentation, allowing you to print it, or to provide a copy to customers who are unable to access the online version. This guide describes how to export your technical documentation to PDF using Confluence's built-in PDF export, and introduces a third-party plugin that provides additional PDF layout and style functionality.



Quick guide to PDF exports

- Customise the PDF layout (title page, header and footer) and style, for use each time you export your documentation.
- Export a single page to PDF.
- Export a selection of pages or an entire space to PDF.
- Consider installing a third-party plugin for advanced PDF export functionality.

The rest of this page gives more details of the above procedures.

On this page:

- Customising the PDF Layout and Style
 - Editing the PDF Layout
 - Setting a global PDF layout
 - Setting the PDF layout at space level
 - Editing the PDF Stylesheet
 - Setting a global PDF Stylesheet
 - Setting a space PDF stylesheet
 - Examples of PDF Customisation
 - Adding a Title Page
 - Adding Headers and Footers
 - Adding Page Numbering to a Header or Footer
- Exporting to PDF
 - Exporting a Single Page to PDF
 - Exporting a Selection of Pages or a Space to PDF
- Using the Scroll PDF Exporter Plugin to Export to PDF (*Not applicable to Confluence OnDemand.*)
- Notes

Customising the PDF Layout and Style

If you plan to create PDF versions of your documentation, you may want to customise the PDF layout and styles for your space. These customisations will be applied every time you export documentation to PDF.

Under **PDF layout** you can add HTML to customise the PDF title page, and page headers and footers. Under **PDF stylesheet**, you can adjust the appearance of the PDF pages.

Editing the PDF Layout

Setting a global PDF layout

1. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
2. Choose **PDF Layout**. You can enter HTML and CSS that will be rendered on the PDF title page, as well as page headers and footers.

Setting the PDF layout at space level

1. Go to the space and choose **Space tools > Look and Feel** on the sidebar. You'll need [Space Admin permissions](#) to do this.
2. Choose **PDF Layout**.
3. Choose **Edit**.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **PDF Layout** in space administration options.
3. Choose **Edit**.

You can customise the HTML that is generated for the following areas when the space is exported to PDF:

- **PDF Space Export Title Page** – title page.
- **PDF Space Export Header** – page headers.
- **PDF Space Export Footer** – page footers.

Enter your customisations into each text box as required. The PDF layout section accepts HTML code. You can include inline CSS in the HTML too.

Editing the PDF Stylesheet

Setting a global PDF Stylesheet

1. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
2. Choose **Look and Feel > PDF Stylesheet**. The following screen allows you to enter and save CSS code that will render content on each page.

Setting a space PDF stylesheet

1. Go to the space and choose **Space tools > Look and Feel** on the sidebar. You'll need [Space Admin permissions](#) to do this.
2. Choose **PDF Stylesheet**.
3. Choose **Edit**.
4. Enter your customisations.

If your space uses the Documentation theme:

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **PDF Stylesheet** in the space administration options.
3. Choose **Edit**.
4. Enter your customisations.

The PDF Export Stylesheet field accepts Cascading Style Sheets (CSS) rules. The 'PDF Export Stylesheet' page shows the current (e.g. customised) contents of your PDF stylesheet.

Examples of PDF Customisation

Below are typical customisations you may want to make for your technical documentation. For more examples, see [Customising Exports to PDF](#).

Adding a Title Page

You can create a title or cover page to your PDF document using HTML. Use the **PDF Space Export Title Page** section of the PDF layout to do this.

Adding a New Title Page

The following example uses HTML with an inline CSS rule to generate a title page.

```
<div class="fsTitlePage"
style="margin-left:auto;margin-top:75mm;margin-right:auto;page-break-after:always">

</div>
```

Including Content Above Table of Contents in Default Title Page

The following example includes content above the automatically-generated table of contents that appears on the default title page, so that your title page includes your own content plus the table of contents.

```
<div class="fsTitlePage"
style="margin-left:auto;margin-top:75mm;margin-right:auto;">

</div>
```

Adding an Image to your Title Page

In the examples above, the title page includes an image called 'titlepage.png', centred in the middle of the page. The image is attached to a Confluence page and is referenced via its relative URL (that is, we use only the last part of the URL, excluding the Confluence site's base URL).

Follow these instructions to include an image on your title page:

1. Attach the image to a Confluence page.
2. View the list of attachments on that page.
3. Right-click the image and copy its location.
4. Paste the link into the appropriate `src=""` attribute within your PDF stylesheet, as shown above.
5. Remove the first part of the URL before `/download/` . . .

Adding Headers and Footers

You can add headers and footers to your PDF pages using HTML. Use the 'PDF Space Export Header' and 'PDF Space Export Footer' sections of the PDF layout to do this. For simple headers and footers, plain text is enough. The following example adds a simple copyright notice.

```
Copyright © 2010, Atlassian Pty Ltd.
```

Adding Page Numbering to a Header or Footer

To add page numbering, you need to combine customised HTML in the PDF Layout with customised CSS in the PDF Stylesheet.

1. PDF Layout HTML: In the Footer section (or the Header section), use an empty span element with a unique ID, for example `pageNum`, to act as a place holder for the page number.

HTML - PDF Layout: Footer Section

```
<span id="pageNum"/>
```

2. PDF Stylesheet CSS: Create the following CSS selector rule for the empty span:

CSS - PDF Stylesheet

```
#pageNum:before
{
content: counter(page);
}
```

Analysing the above CSS selector rule in more detail:

- The `#pageNum` rule selects the HTML element with the specified ID of "pageNum", which is the span ele

ment we created for the header or footer.

- The `:before` part of the selector is a pseudo class that allows the insertion of content before the span element is processed.
- The `counter(page)` is a function that returns the current page number as its content.
- The `content` property tells the CSS processor that dynamic content (that is, an incrementing page number) is to be inserted at the span tag.

Exporting to PDF

You can use the built-in [Confluence PDF export](#) to export a single page, a selection of pages or an entire space to a single PDF file.

Exporting a Single Page to PDF

You can export a Confluence page to PDF. This option exports a single page and is available to all users who have permission to view the page.

- Go to a page in the space and choose **Tools > Export to PDF**. Follow the prompts to export the page.

Exporting a Selection of Pages or a Space to PDF

1. Go to the space and choose **Space tools > Content Tools** on the sidebar.
2. Choose **Export**. This option will only be visible if you have the 'Export Space' permission.
3. Select **PDF** then choose **Next**
4. Decide whether you need to customise the export:
 - Select **Normal Export** to produce a PDF file containing all the pages that you have permission to view.
 - Select **Custom Export** if you want to export a subset of pages.
5. Select the pages you want to export.
 - You have the option to **Select All** or **Deselect All** pages.
 - When you select a page, all its child pages will also be selected. Similarly, when you deselect a page all its child pages will also be deselected.
6. Choose **Export**.
7. When the export process has finished, download and save the PDF file as prompted.

If your space uses the Documentation theme:

1. Choose **Browse > Space Operations**
2. Choose **PDF Export** from the left menu.
3. Follow the steps above to export the Space.

Export PDF Options

Export content within this space as PDF. You can customise the layout and styling of this exported PDF in the [PDF Stylesheet](#) page.

☐ Normal Export
Generates a PDF file of all pages and blog posts in this space, including comments and attachments.

☒ Custom Export
Generates a PDF file of selected pages based on options that you choose from below.

Choose pages to export:

[Select All](#) · [Deselect All](#)

☒ Crowd Documentation

☒ Crowd 101

☒ Crowd Administration Guide

☒ Getting Started

☒ Concepts
☒ Supported Applications and Directories
☒ About the Crowd Administration Console

☒ Managing Directories

☒ Using the Directory Browser
☒ Adding a Directory

☒ Configuring an Internal Directory
☒ Configuring an LDAP Directory Connector

☒ Apache Directory Server (ApacheDS)
☒ Apple Open Directory
☒ Fedora Directory Server
☒ Generic LDAP Directories
☒ Microsoft Active Directory

☒ Configuring an SSL Certificate for Microsoft Active Directory

☒ Novell eDirectory
☒ OpenDS

Using the Scroll PDF Exporter Plugin to Export to PDF *(Not applicable to Confluence OnDemand.)*

The Scroll PDF Exporter provides flexible themes for configuring PDF layout and styles. You can select one of Scroll PDF Exporter's built-in themes and [configure](#) your table of contents, header and title pages. For even more flexibility, see the section [HowTos](#) in the Scroll PDF Exporter documentation.

For this advanced PDF export functionality, you will need to install the [Scroll PDF Exporter](#) plugin to your Confluence site.

Notes

- **Permissions required to export a space:** To use the space export functionality, you need the 'Export Space' permission. See the guide to [space permissions](#).
- **Installing plugins:** If you decide to use additional plugins, your site administrator will need to install the plugins to your Confluence site. Refer to the documentation on [installing plugins](#). *(Not applicable to Confluence OnDemand.)*
- **Plugin support:** *Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#).*

Related Topics

[Developing Technical Documentation on Confluence Wiki](#)
[Customising Exports to PDF](#)

Exporting Confluence Pages and Spaces to PDF

Scroll PDF Exporter

Installing Add-ons (*Not applicable to Confluence OnDemand.*)

Next Steps

Now you know all about providing PDF versions of your documentation. What next? See other ways of [Exporting and Printing Technical Documentation](#).

Exporting and Printing Technical Documentation

This page is part of the guide to [developing technical documentation on Confluence Wiki](#). Confluence is a great tool for writing and maintaining technical documentation. There are times when we need to export the content out of Confluence into other forms, such as PDF, HTML, Microsoft Word and paper.

Confluence itself provides an export to both PDF and HTML. Plugins provide additional functionality. Below are guidelines on exporting your technical documentation to various formats, including printed output.



Quick guide to printing and exporting content

- Use the browser's print option to print a single page.
- To print more than one page and for more advanced printing options, export your documentation to PDF.
- Confluence can export your pages to PDF, HTML, Confluence-specific XML and Word.
- Consider installing plugins to export your pages to PDF (enhanced functionality). Word (enhanced functionality), DocBook XML, Eclipse Help and JavaHelp.
- Make your exports available to your customers for download by attaching the exported file to a Confluence page.

The rest of this page gives more details of the above procedures.

On this page:

- [Printing](#)
- [Exporting to PDF](#)
- [Exporting to HTML](#)
- [Exporting to Confluence-Specific XML](#)
- [Exporting to DocBook XML via a Plugin \(*Not applicable to Confluence OnDemand.*\)](#)
- [Exporting to Microsoft Word](#)
- [Exporting to Microsoft Word via a Plugin \(*Not applicable to Confluence OnDemand.*\)](#)
- [Exporting to Eclipse Help via a Plugin \(*Not applicable to Confluence OnDemand.*\)](#)
- [Exporting to EPUB via a Plugin \(*Not applicable to Confluence OnDemand.*\)](#)
- [Exporting to HTML via a Plugin \(*Not applicable to Confluence OnDemand.*\)](#)
- [Making the PDF and Other Exported Files Available to your Readers](#)
- [Notes](#)
- [Further Reading](#)

Printing

To print a single Confluence page, just use the browser's print option. This option is available to all users who have permission to view the page.

To print more than one page and for more advanced printing options, export your documentation to PDF. See [Providing PDF Versions of your Technical Documentation](#).

Exporting to PDF

Because this is such an important topic, we have a section of this guide dedicated to PDF. See [Providing PDF Versions of your Technical Documentation](#).

Exporting to HTML

Using the built-in [Confluence HTML export](#), you can export a single page, a selection of pages or an entire space to HTML. Confluence supplies the HTML and associated files in a zip file.

1. Go to the space and choose **Space tools > Content Tools** on the sidebar.
2. Choose **Export**. This option will only be visible if you have the 'Export Space' permission.
3. Select **HTML** then choose **Next**.
4. Decide whether you need to customise the export:
 - Select **Normal Export** to produce an HTML file containing all the pages that you have permission to view.
 - Select **Custom Export** if you want to export a subset of pages, or to exclude comments from the export.
5. Select the **Include Comments** check box if you want to include comments for the pages you are exporting.
6. Select the pages you want to export.
 - You have the option to **Select All** or **Deselect All** pages.
 - When you select a page, all its child pages will also be selected. Similarly, when you deselect a page all its child pages will also be deselected.
7. Choose **Export**. This will create a zipped archive of HTML files.
8. When the export process has finished, download the zipped archive as prompted, and extract the files into a folder.

If your space uses the Documentation theme:

1. Choose **Browse > Space Operations**.
2. Choose **HTML Export** from the left menu.
3. Follow the steps above to export the Space.

Export HTML Options

Export content within this space as HTML.

☐ Normal Export
Generates a HTML file of all pages and blog posts in this space, including comments and attachments.

☒ Custom Export
Generates a HTML file of selected pages based on options that you choose from below.

Includes:

☒ Include comments

Choose pages to export:

[Select All](#) · [Deselect All](#)

- ☒ Crowd Documentation
 - ☒ Crowd 101
 - ☒ Crowd Administration Guide
 - ☒ Getting Started
 - ☒ Concepts
 - ☒ Supported Applications and Directories
 - ☒ About the Crowd Administration Console
 - ☒ Managing Directories
 - ☒ Using the Directory Browser
 - ☒ Adding a Directory
 - ☒ Configuring an Internal Directory
 - ☒ Configuring an LDAP Directory Connector
 - ☒ Apache Directory Server (ApacheDS)
 - ☒ Apple Open Directory
 - ☒ Fedora Directory Server
 - ☒ Generic LDAP Directories
 - ☒ Microsoft Active Directory

Exporting to Confluence-Specific XML

Confluence provides an [XML export](#). The XML produced is a proprietary format and is intended for backups or for transferring a space from one Confluence instance to another. If you write your documentation on Confluence and your customers have Confluence too, then you can export your manuals to XML and customers can upload them onto their own Confluence site.

Exporting to DocBook XML via a Plugin (*Not applicable to Confluence OnDemand.*)

[Scroll DocBook Exporter](#) converts Confluence pages to [DocBook XML](#). Your Confluence system administrator will need install the plugin onto your Confluence site.

Exporting to Microsoft Word

Confluence can export a page to Word. (Select '**Export to Word**' from the '**Tools**' menu.) This option performs a basic conversion of wiki content to HTML and applies some Word CSS stylesheets. It processes just one page at a time.

Exporting to Microsoft Word via a Plugin (*Not applicable to Confluence OnDemand.*)

[Scroll Office](#) is a Confluence plugin. Once installed, Scroll Office replaces Confluence's built-in 'Export to Word' functionality. You can export a single page or a hierarchy of pages.

You can define your templates in Word in the usual way, and upload them to Confluence as global templates or space templates. When you export your Confluence pages to Word, Scroll Office will use those templates to

build native Word documents from the wiki pages.

Scroll Office provides additional features such as [enforcing page-breaks](#), [setting the page orientation](#) to landscape or portrait, and [ignoring content](#). The latest version offers a REST-style API for automated export.

Exporting to Eclipse Help via a Plugin (Not applicable to Confluence OnDemand.)

[Scroll EclipseHelp Exporter](#) provides an export to Eclipse Help format.

You can produce embeddable online help for Eclipse-based applications. Scroll EclipseHelp Exporter converts the Confluence content into EclipseHelp-compatible JAR files to create a standalone online help or a context-sensitive help.

A hint about the Eclipse Help platform: You can use a cut-down version of the Eclipse Help platform to provide online documentation for any system. It doesn't have to be an Eclipse tool that you are documenting. For some ideas, take a look at a couple of articles about [documenting your project using the Eclipse help system](#).

Exporting to EPUB via a Plugin (Not applicable to Confluence OnDemand.)

The [Scroll EPUB Exporter](#) outputs an ebook in the common EPUB format that can be read on iPads, iPhones and any other ebook reader.

Exporting to HTML via a Plugin (Not applicable to Confluence OnDemand.)

The [Scroll HTML Exporter](#) enables the delivery of Confluence content from a web server. It converts the pages into static HTML pages that can be uploaded to a web server. The output of the Scroll HTML exporter can also be used as an input to produce other HTML-based help formats such as WinHelp and HTML Help.

Making the PDF and Other Exported Files Available to your Readers

There are a number of ways to make your exported files available to your readers, such as putting the files on a disc and shipping them with your product.

One of the simplest ways is to attach the files to a Confluence page. (See [Attaching Files to a Page](#).)

For example, Atlassian uses the out-of-the-box Confluence export functionality to provide PDF, HTML and XML versions of our documentation. People can download the files from our [documentation wiki](#). For example, here are the [JIRA documentation downloads](#) and the [Confluence documentation downloads](#).

Notes

- **Permissions required to export a space.** To use the space export functionality, you need the 'Export Space' permission. See the guide to [space permissions](#).
- **Installing plugins.** If you decide to use additional plugins, your site administrator will need to install the plugins into your Confluence site. Refer to the documentation on [installing plugins](#). *Not applicable to Confluence OnDemand.*
- **Plugin support.** *Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#).*

Further Reading

- A blog post about exporting and importing content from/to Confluence: [Technical Writing in a Wiki - Single Source Publishing](#) (November 2010).
- A good overview of the Scroll Office features in this [blog post](#) (August 2010) and the [followup post](#) (November 2010).

Next Steps

Now you know about a number of ways to get your technical documentation out of Confluence into various formats, for printing or for input into another system or process flow. What next? Take a look at [Essential Confluence Features for Technical Documentation](#).

Essential Confluence Features for Technical Documentation

This page is part of the guide to [developing technical documentation on Confluence](#). In this section we highlight the built-in Confluence macros that are most useful in technical documentation. For more information about Confluence macros, see [Working with Macros](#).

On this page:


- [Auto-Generating a Table of Contents for Page Content](#)
- [Drawing Attention to Elements of a Page](#)
- [Putting Content inside Customisable Panels](#)
- [Inserting Anchor Links on Pages](#)
- [Structuring Content using Sections and Columns](#)
- [Making your Documentation more Engaging by Embedding Videos](#)

Auto-Generating a Table of Contents for Page Content

It is important to make it easy for viewers to jump to the section of a Confluence page that they are most interested in. The [Table of Contents macro](#) helps you navigate lengthy pages by summarising the content structure and providing links to headings used on the page.

▼ [Click here to see a common example >>](#)

1. You document the *Release Notes* for the latest version of your product in a Confluence page.
2. Each feature in the release is a heading on the page.
3. You can generate a list of hyperlinks to each of the features in the release notes by inserting the Table of Contents macro:



4. The image below shows the Table of Contents macro inserted at the top of the 'Release Notes' page. Note that we have excluded the 'Highlights of Confluence 4.0' heading from the table of contents by modifying the macro's parameters.

Confluence 4.0 Release Notes

30 Added by Sarah Maddox [Atlassian Technical Writer], last edited by Edwin Dawson [Atlassian Technical Writer] on Sep 20, 2011 (view change) show comments

19 September 2011

DOWNLOAD
latest version

With great pleasure, Atlassian presents Confluence 4.0. This is one of the most significant updates to Confluence since we're confident that Confluence 4.0 is the most productive and user-friendly version to date.

Highlights of Confluence 4.0:

- [Brand New Editor](#)
- [Simplified Editing Experience](#)
- [New Macros](#)
- [Faster Editing Experience](#)
- [Introducing @mentions](#)
- [Improved Page Comparison Functionality](#)
- [Email Notification Improvements](#)
- [New Confluence Installer and Guided Upgrades](#)
- [New Editor Plugin Points for Developers](#)
- [Other Improvements](#)
- [Helping You Transition to Confluence 4.0](#)
- [Release Notices](#)

More:

- Read the [Upgrade Notes](#) for important information about this release.
- See the full list of [issues resolved in this release](#).

Learn more
about Confluence 4.0

Table of Contents Macro

- Minimum Heading Level Set to '2'
- Maximum Heading Level set to '7'

Highlights of Confluence 4.0 ← **Heading Style 1**

1 Brand New Editor ← **Heading Style 2**

We've rebuilt the Confluence editor from the ground up, bringing you an editing experience that's simpler, faster and richer.

5. The image below shows the macro parameters specified in the macro browser. Note the 'Minimum Heading Level' and 'Maximum Heading Level' parameters.

Edit 'Table of Contents' Macro

Preview Refresh

- [Brand New Editor](#)
- [Simplified Editing Experience](#)
- [New Macros](#)
- [Faster Editing Experience](#)
- [Introducing @mentions](#)
- [Improved Page Comparison Functionality](#)
- [Email Notifications Improvements](#)
- [New Confluence Installer and Guided Upgrades](#)
- [New Editor Plugin Points for Developers](#)
- [Other Improvements](#)
- [Helping You Transition to Confluence 4.0](#)
- [Release Notices](#)

List Style
none
The style of bullet-point applied to each item in the list. Any CSS styles are valid. Examples: disc, circle, square.

Heading Indent

The amount by which to indent each heading level (in CSS units). Example: 10px

Separator
brackets
The type of separator used when 'Output Type' is set to 'flat'. Examples: brackets, braces, pipe.

Minimum Heading Level
2
The minimum heading level to report in the TOC. For example, '3' will list headings from 'h3.' onwards, but not 'h1.' or 'h2.'

Maximum Heading Level
4
The maximum heading level to report in the TOC. For example, '4' will list headings up to 'h4.' but not from 'h1.'

Back Save Cancel

[Return to top of page](#)

Drawing Attention to Elements of a Page

Often when creating documentation there are elements of a page that you want to highlight, or draw the the viewers attention to. Confluence ships with the following macros that help you focus a viewer's attention to a note, information, tip or warning.

▼ [Click here to see common examples >>](#)

Note Macro

What is it?	Example
The Note macro allows you to highlight a note on a Confluence page. It creates a yellow coloured box surrounding your text, as shown to the right.	 Draft in progress This document is a draft and is under development.

See [Note Macro](#) for more examples and instructions.

Info Macro

What is it?	Example
The Info macro allows you to highlight helpful information on a Confluence page. It creates a blue coloured box surrounding your text, as shown to the right.	 Did you know? Confluence is the best wiki ever.

See [Info Macro](#) for more examples and instructions.

Tip Macro

What is it?	Example
The Tip macro allows you to highlight a helpful tip on a Confluence page. It creates a green coloured box surrounding your text, as shown to the right.	 Learn more Check out this blog post: Technical Writing in a Wiki: Technical Communicators Explain How & Why?

See [Tip Macro](#) for more examples and instructions.

Warning Macro

What is it?	Example
The Warning macro allows you to highlight a warning note on a Confluence page. It creates a red coloured box surrounding your text, as shown to the right.	 Draft This page is a draft in progress and visible to Atlassian staff only.

See [Warning Macro](#) for more examples and instructions.

[Return to top of page](#)

Putting Content inside Customisable Panels


The **Panel macro** allows you to place content inside a customisable coloured panel. This is particularly useful when you want to clearly separate elements on a page.

▼ [Click here to see a common example >>](#)

1. You are documenting a procedure which involves a number of steps.
2. You want to call out the steps of the procedure from the rest of the page by placing it inside a coloured box, or panel.
3. You can create a coloured panel using the Panel macro.
4. The image below shows the parameters set for the panel using the macro browser.

Edit 'Panel' Macro

Preview



Refresh

Draw a panel with an optional title and border
[Documentation](#)

Panel Title

Border Style

Examples: solid, dashed

Border Colour

Border Pixel Width (Value Only)

Background Colour

Title Background Colour

Title Text Colour

Back

Save Cancel

[Return to top of page](#)

Inserting Anchor Links on Pages


Anchor links can be especially useful when navigating between sections of a long document or when you want to link to a segment of a page from another page. The **Anchor macro** allows you to link to specific parts of a page.

▼ [Click here to see a common example >>](#)

1. You are documenting part of a user guide.
2. The page is split into multiple sections.
3. After each section you want to provide a link for viewers to click, taking them back to the top of the page.

Created in 2013 by Atlassian. Licensed under a [Creative Commons Attribution 2.5 Australia License](#).

4. To achieve this you first must create an *anchor* at the top of the page using the Anchor macro. You can give the anchor any name you like. In the image below, the anchor at the top of the page will be named 'top'.



Insert 'Anchor' Macro

Preview Refresh


Create an anchor that allows people to link to a specific point in a page [Documentation](#)

Anchor Name *

top

Back Insert Cancel

5. The anchor placeholder will appear to indicate where your anchor link is located on the page:



[Anchor | top](#)

This guide is for people who want to author and publish technical documentation on Confluence on. This page is highlights out-of-the-box Confluence macros that you may want to use to create document in Confluence

6. Create a link to the anchor, anywhere on the page, using the [Link Browser](#). The image below shows a link to the anchor called 'top' by using the hash '#' followed by the name of the anchor you created earlier, with an alias of 'Return to Top'.

Insert Link

Search

Recently Viewed

Attachments

Web Link

Advanced

Here you can insert a link into the page using [Wiki Markup](#).

Link:

To insert a link to a new page, type in the desired page title.
To insert an anchor link, type #anchormame.

Link Text:

Hint: type "[" in the Editor to see a list of suggested pages and insert a link.

See [Working with Anchors](#) for more examples and instructions.

[Return to top of page](#)

Structuring Content using Sections and Columns

Sometimes it is necessary to structure content into sections and columns. The details are in [Working with Page Layouts and Columns and Sections](#).

- Page layouts offer a set of predefined columns and sections.
- The Section and Column macros allow more flexibility. You can set the width of the columns, and put the sections and columns in any part of the page.
- You can create any number of sections on a Confluence page using the Section macro.
- Each section can contain any number of columns, created using the Column macro.
- Columns can either have a fixed width, specified in pixels, or a dynamic width, specified as a percentage of the page width.
- Note: A *column* must be created inside a *section*.

▼ [Click here to see a common example >>](#)

The images below show part of a Confluence page with two sections (outlined in red), each with two columns (blue) of different widths.

1. Section 1:

1. Put a name to your face

2. Learn how content is organised

3. Get familiar with the Confluence screens

4. Start creating content

5. Add a panel to your page

 Tweet it! »

 Share It! »

1

Put a face to your name

Your profile picture is used to identify you across Confluence. Upload your own picture via your **Profile**.

[Learn More >>](#)

Dashboard > People > Fred Flintstone > Profile Picture

Help ▾ Browse ▾ Fred Flintstone ▾ Search

 **Fred Flintstone**

Profile

Network

Status Updates

Labels

Watches

Drafts

Settings

Profile

Details

Picture

Password

Your profile picture is used as the icon for your personal space, and to represent you in Confluence. You can upload your own profile picture, or you can choose from one of our standard icons.

Upload a Profile Picture: Upload your own profile picture. Profile pictures will be resized to 48 x 48 pixels.

2. Columns in section 1 – left column has a fixed width of 400 pixels:

1. Put a name to your face

2. Learn how content is organised

3. Get familiar with the Confluence screens

4. Start creating content

5. Add a panel to your page

 Tweet it! »

 Share It! »

1

Put a face to your name

Your profile picture is used to identify you across Confluence. Upload your own picture via your **Profile**.

[Learn More >>](#)

Dashboard > People > Fred Flintstone > Profile Picture

Help ▾ Browse ▾ Fred Flintstone ▾ Search

 **Fred Flintstone**

Profile

Network

Status Updates

Labels

Watches

Drafts

Settings

Profile

Details

Picture

Password

Your profile picture is used as the icon for your personal space, and to represent you in Confluence. You can upload your own profile picture, or you can choose from one of our standard icons.

Upload a Profile Picture: Upload your own profile picture. Profile pictures will be resized to 48 x 48 pixels.

3. Section 2:

- Put a name to your face
- Learn how content is organised
- Get familiar with the Confluence screens
- Start creating content
- Add a panel to your page

 Tweet it! »

 Share It! »

1 Put a face to your name

Your profile picture is used to identify you across Confluence. Upload your own picture via your **Profile**.

► Learn More >>

Dashboard › People › Fred Flintstone › Profile Picture
 Help ▾ Browse ▾ Fred Flintstone ▾ Search


Fred Flintstone

Profile Network Status Updates Labels Watches Drafts Settings

Profile

Details
Picture
Password

Your profile picture is used as the icon for your personal space, and to represent you in Confluence. You can upload your own profile picture, or you can choose from one of our standard icons.

Upload a Profile Picture: Upload your own profile picture. Profile pictures will be resized to 48 x 48 pixels.

4. Columns in section 2 – left column has a fixed width of 10 pixels:

- Put a name to your face
- Learn how content is organised
- Get familiar with the Confluence screens
- Start creating content
- Add a panel to your page

 Tweet it! »

 Share It! »

1 Put a face to your name

Your profile picture is used to identify you across Confluence. Upload your own picture via your **Profile**.

► Learn More >>

Dashboard › People › Fred Flintstone › Profile Picture
 Help ▾ Browse ▾ Fred Flintstone ▾ Search


Fred Flintstone

Profile Network Status Updates Labels Watches Drafts Settings

Profile

Details
Picture
Password

Your profile picture is used as the icon for your personal space, and to represent you in Confluence. You can upload your own profile picture, or you can choose from one of our standard icons.

Upload a Profile Picture: Upload your own profile picture. Profile pictures will be resized to 48 x 48 pixels.

[Return to top of page](#)


Making your Documentation more Engaging by Embedding Videos

Pictures can be worth a thousand words. The same can be said for videos. Often, it's easy to explain a concept or demonstrate a procedure using a video. The [Widget macro](#) allows you to embed web content, including YouTube, Episodic and Vimeo videos, in a Confluence page.


▼ [Click here to see a common example >>](#)

- You release a new version of your product.
- You document the Release Notes on a Confluence page.
- The marketing team creates a video demonstrating the new features of the release and uploads it to YouTube.

4. You can embed the video in your Release Notes using the Widget macro, for playback on your Confluence page.
 - a. Select '**Other Macros**' from the '**Insert**' menu in the Rich Text Editor toolbar.



- b. Search for the 'Widget Connector' in the macro browser.



- c. Insert the URL of your YouTube video into the 'Web Sites Widget URL' field.

The screenshot shows the 'Insert Widget Connector Macro' dialog box. It has a 'Preview' section on the left and a configuration section on the right. The configuration section includes a 'Web Sites Widget URL' field, which is highlighted with a red rectangle. Below it are 'Pixel Width (Value Only)' and 'Pixel Height (Value Only)' fields. An 'Insert' button is located at the bottom right of the dialog.

- d. Click 'Insert' and save your page.

The screenshot shows the 'Confluence 4.0 Release Notes' page. It features a 'DOWNLOAD latest version' button, a list of highlights for Confluence 4.0, and a 'Learn more' button. A video player titled 'New Atlassian Confluence Editor Demo Video' is highlighted with a red rectangle. The video player shows a play button and a progress bar.

See [Widget Connector Macro](#) for information on the supported services and for more usage examples.

[Return to top of page](#)

Next Steps

Take a look at [Confluence Add-ons for Technical Documentation](#).

Confluence Add-ons for Technical Documentation

This page is part of the guide to [developing technical documentation on Confluence](#). In this section we highlight some of the Confluence add-ons that are useful for technical writers in designing and developing documentation.

An add-on is an extension module that you can add to your Confluence site to extend the wiki's core functionality. It is similar to an add-on for your browser.

An add-on that specifically plugs into an Atlassian application such as Confluence is sometimes called a plugin.

The terms 'plugin' and 'add-on' are often used interchangeably. Confluence add-ons may be developed by Atlassian or by third parties. To find an add-on featured on this page, and other add-ons too, visit the [Atlassian Marketplace](#).

✔ Quick guide to the plugins featured below

- [Gliffy plugin](#) – Provides an embedded diagram editor. Commercial.
- [Scroll Versions](#) – Adds functionality for sophisticated version management, enhanced content reuse, support for context-sensitive help, permalinks, and duplicate page titles. This is a commercial plugin.
- [Composition plugin](#) – Provides macros which allow finer control over the layout (composition) of a page. For example, outline text; add tabs to your page; flow your text around diagrams. Commercial.
- [Scaffolding plugin](#) – Provides macros for creating 'permanent templates' and editable forms. Commercial.
- [Attachment Checkout plugin](#) – Adds check-out/check-in functionality for Confluence attachments. Free.

✔ Plugins featured in other parts of this guide

- [Copy Space plugin](#) – Provides an easy way of copying a space within a Confluence site. Free. See [Creating your Technical Documentation Space](#).
- [Multi Excerpt plugin](#) – Enables you to have more than one excerpt (re-usable chunk) on a page. Commercial. See [Re-using Content in Technical Documentation](#).
- [Ad Hoc Workflows plugin](#) – Provides advanced workflow features. Commercial. See [Managing the Life Cycle of your Technical Documentation](#).
- [Content Publishing plugin](#) – Publishes content from a master space to a published space. Commercial. See [Managing the Life Cycle of your Technical Documentation](#).
- [Scroll Office](#) – Provides advanced features for export to Microsoft Word. Commercial. See [Exporting and Printing Technical Documentation](#).
- [Scroll PDF Exporter](#) – Provides advanced PDF export features. Commercial. See [Providing PDF Versions of your Technical Documentation](#) and [Exporting and Printing Technical Documentation](#).
- [Scroll DocBook Exporter](#) – Provides DocBook exports. Commercial.
- [Scroll EPUB Exporter](#) – Outputs an ebook in the common EPUB format that can be read on iPads, iPhones and any other ebook reader. Commercial.
- [Scroll HTML Exporter](#) – Enables the delivery of Confluence content from a web server. It converts the pages into static HTML pages that can be uploaded to a web server. The output of the Scroll HTML exporter can also be used as an input to produce other HTML-based help formats such as WinHelp and HTML Help. Commercial.
- [Scroll EclipseHelp Exporter](#) – Enables you to collaborate and author all your content in your wiki, and generate embeddable online help for Eclipse-based applications. Commercial.

Drawing Tools

Gliffy Plugin

The [Gliffy plugin](#) provides an embedded diagram editor. Gliffy allows you to create and edit diagrams directly from a Confluence page. It supports various [diagram types](#) (UML, business process, and so on).

Alternatives: As an alternative you can use the standalone version of Gliffy available at <http://www.gliffy.com/>. Gliffy online has a free basic version.

For more information, see the [Gliffy plugin page](#).

Extended Wiki Markup Features (*Not applicable to Confluence OnDemand.*)

All wiki markup extensions are provided by **macros** in Confluence. Some macros are built in to Confluence. Other macros are supplied by plugins.

Quick Overview of Macros

Before looking at plugins, let's take a quick look at macros in general. There are two ways to add a macro to your page:

- Use the [macro browser](#). This is the simplest and recommended way.
- Or insert the macro's name in curly brackets into the text of your page and specify the parameters.

▼ [Click here to see an example of a macro >>](#)

The following code uses the `{include}` macro to insert the text from the page called 'My Page'. The text will appear on the page where the macro is used:

```
Page text...
{include:My Page}
page text...
```

The resulting page will look like this:

```
Page text...
<text from the 'My Page' page>
page text...
```

A number of macros are shipped with your Confluence installation by default. See [Working with Macros](#). Below we describe some plugins that provide additional useful macros for Confluence:

Composition Plugin

The [Composition plugin](#) adds some formatting features to compose a page in a more flexible way. Using the macros provided by the Composition plugin, you can:

- Outline your text blocks.
- Add tabs to a page.
- Flow your text around the images or diagrams on the page.

Using the Composition Plugin to Outline Text Blocks

Use the `{cloak}` macro to outline a text block.

Usage: The following code creates a text block named 'SeeAlso' for the outlined 'See Also' section within a page. The text block with `id='SeeAlso'` will be hidden after the 'See Also' title:

```
{composition-setup}
h2. {toggle-cloak:id=SeeAlso} See Also
{cloak:id=SeeAlso}
h3. Working With Macros:
[Link 1]
[Link 2]
h3. Working with Rich Text Editor:
[Link 3]
[Link 4]
{cloak}
```

Alternatives: You can also use the `{expand}` macro available in Confluence by default, but this macro can outline only text of the same level and cannot hide headings within the text. The `{expand}` macro does not

require parameters and just hides the text placed between the {expand} tags.

Note: If you need to outline a text block containing nested headings, consider the text structure. Maybe the block is too big. You could create a child page from this block to decompose the whole text. Then you can include and outline the text block using the {include} macro within {expand}.

Using the Composition Plugin to Add Tabs to a Page

Use the {deck} and {card} macros to separate content between tabs on the same page.

Usage: The following code creates two tabs with client information:

```
{composition-setup}
h1. Client Name
{deck:id=ClientName}
{card:label=Basic}
Client Company Name: Company
[Client Web Site|http://url.com]
Our projects: [Project1|Project1 Home]
{card}
{card:label=Contacts}
Company CEO: John Brown, e_mail: brown@company.com
{card}
{deck}
```

The tabs on a page will look like this:



Using the Composition Plugin to Flow your Text around Images

Use the {float} macro to make your text flow around images or diagrams.

Usage: The following code demonstrates how a picture can be surrounded by the description, as often shown in printed publications:

```
{composition-setup}
{float:left}
!shakespeare.jpg!
{float}
William Shakespeare (baptised 26 April 1564; died 23 April 1616) was an English
poet and playwright, widely regarded as the greatest writer in the English language
and the world's pre-eminent dramatist.
...
```

The page will look like this:

Floating Text demo

 Edit
  Add
  Tools

1 Added by [Ekaterina Stepalina](#), last edited by [Ekaterina Stepalina](#) on Nov 08, 2010 ([view change](#))



William Shakespeare (baptised 26 April 1564; died 23 April 1616) was an English poet and playwright, widely regarded as the greatest writer in the English language and the world's pre-eminent dramatist. He is often called England's national poet and the "Bard of Avon". His surviving works, including some collaborations, consist of about 38 plays, 154 sonnets, two long narrative poems, and several other poems. His plays have been translated into every major living language and are performed more often than those of any other playwright.

Shakespeare was born and raised in Stratford-upon-Avon. At the age of 18, he married Anne Hathaway, with whom he had three children: Susanna, and twins Hamnet and Judith. Between 1585 and 1592, he began a successful career in London as an actor, writer, and part owner of a playing company called the Lord Chamberlain's Men, later known as the King's Men. He appears to have retired to Stratford around 1613, where he died three years later. Few records of Shakespeare's private life survive, and there has been considerable speculation about such matters as his physical appearance, sexuality, religious beliefs, and whether the works attributed to him were written by others.

Shakespeare produced most of his known work between 1589 and 1613. [nb 4](#) His early plays were mainly comedies and histories, genres he raised to the peak of sophistication and artistry by the end of the 16th century. He then wrote mainly tragedies until about 1608, including Hamlet, King Lear, and Macbeth, considered some of the finest works in the English language. In his last phase, he wrote tragicomedies, also known as romances, and collaborated with other playwrights.

For more macros, see the [Composition plugin page](#).

Scaffolding Plugin (Not applicable to Confluence OnDemand.)

The [Scaffolding plugin](#) allows you to create sophisticated page templates in order to add content easily and fast. Scaffolding templates are suitable for dynamically-filled data and allow people to create pages by completing form fields and selecting values from drop-down lists.

The Scaffolding templates are useful for creating pages with a well-determined structure, such as:

- API methods or property descriptions.
- Constant list.
- Feature description.
- Software requirement specifications.

Example: The following Scaffolding template creates a description of an API method:

```

h3. Method Name
{text-data:methodName|required=true}{text-data}
h3. Method Description
{text-data:methodDescription|type=area|required=true|width=100%}description{text-da
ta}
h3. Parameters
{table-data:parameters}
|| Name || Type || Mandatory || Description ||
| {text-data:paramName}ParamName{text-data} |
{list-data:paramType}{list-option:Number}Number{list-option}{list-option:String}Str
ing{list-option}{list-option:DateTime}DateTime{list-option}{list-option:MACAddress}
MACAddress{list-option}{list-option:IPAddress}IPAddress{list-option}{list-data} |
{list-data:paramMandatory}{list-option:Required}Required{list-option}{list-option:O
ptional}Optional{list-option}{list-data} |
{text-data:paramDescription|type=area}param description{text-data} |
{table-data}
h3. Return Value
The returned value is an XML structure of the following format:
\{code:xml\}
\{code\}
Where elements mean:
{table-data:returnValues}
|| Name || Type || Description ||
| {text-data:paramName}ParamName{text-data} |
{list-data:paramType}{list-option:Number}Number{list-option}{list-option:String}Str
ing{list-option}{list-option:DateTime}DateTime{list-option}{list-option:MACAddress}
MACAddress{list-option}{list-option:IPAddress}IPAddress{list-option}{list-data} |
{text-data:paramDescription}param description{text-data} |
{table-data}
h3. Remarks
{text-data:remarks}remarks{text-data}
h3. See Also

```

This template will look like this:

Dashboard > Документирование > ... > Черновики > API Method demo > Edit Page Data

Browse Ekaterina Stepalina Search

API Method demo

Edit Data Preview **Notation Guide** Save Cancel Edit Layout

Method Name

API Method demo

Method Description

description

Parameters

Name	Type	Mandatory	Description
Param1	Number	Required	param description
Param2	Number	Required Required Optional	param description

+

Return Value

The returned value is an XML structure of the following format:

Where elements mean:

Name	Type	Description
Element1	String	param description

+

Remarks

remarks

For more information on how to create templates in Confluence, see [Adding a Template](#).

Alternatives: Confluence includes built-in templates which are useful for static data and simple text. For more information, see [Working with Templates](#).

Notes: The Scaffolding (and any) template changes will affect only new pages created from the modified template. In order to change the existing pages, you need to edit each individual page and add or modify the formatting manually.

For more information on Scaffolding, see the [Scaffolding plugin page](#).

Extended Version Control (Not applicable to Confluence OnDemand.)

Scroll Versions

[Scroll Versions](#) enables you to set up and manage concurrent versions of your documentation in a single space. Multiple versions of software, different product variants, and even multiple translations of documentation can be managed. Changes to pages are scheduled for a specified version and then published all at once. See the [Scroll Versions documentation](#) for an overview of the [key features](#).

Video: [Scroll Versions - Version Management for Confluence \(4:20\)](#)

Attachment Checkout Plugin

The [Attachment Checkout plugin](#) adds check-out/check-in functionality for Confluence attachments. It allows you to control the versions of the documents attached to a page with the same file name.

Attachment checkout allows Confluence to warn contributors that the document is being edited by someone else. Note that there are no merge features for attachments.

Example: To store and control the versions of Project Vision documentation received from a customer on the Confluence page:

Name	Size	Creator (Last Modifier)	Comment
 Client1_Project1_Vision.doc	30 kB	Ekaterina Stepalina	Checkout Edit Remove
 Version 2 (30 kB - Ekaterina Stepalina - Nov 8, 2010 11:19:49 AM MSK)			
 Version 1 (30 kB - Ekaterina Stepalina - Nov 8, 2010 11:19:03 AM MSK)			

For information on working with attachments, see [Working with Attachments](#).

For information on attachment versioning, see [Attachment Versions](#).

Notes

- **Installing plugins.** If you decide to use additional plugins, your site administrator will need to install the plugins into your Confluence site. Refer to the documentation on [installing plugins](#). *Not applicable to Confluence OnDemand.*
- **Plugin support.** Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#).

Further Reading

- A blog post about useful plugins and tools for exporting and importing content from/to Confluence: [Technical Writing in a Wiki - Single Source Publishing](#) (November 2010).
- Website for exploring and downloading the available plugins: [Atlassian Marketplace](#).
- Documentation on installing and configuring plugins: [Universal Plugin Manager Documentation](#).
- Documentation on using macros: [Working with Macros](#).
- [Further Reading about Developing Technical Documentation on Confluence](#)

Further Reading about Developing Technical Documentation on Confluence

This page is part of the guide to [developing technical documentation on Confluence](#). Once you have absorbed all the information in this guide, you may be ready for more reading. 😊

- The Confluence documentation: [Confluence Latest](#).
- Tips from other technical writers, in the Confluence documentation: [Tips of the Trade](#). *Not applicable to Confluence OnDemand.*
- Blog post about using Confluence for online help: [Using a wiki for online help](#).
- Blog posts about version management in Confluence with Scroll Versions plugin:
 - [Announcing Scroll Versions](#).
 - [Version management gets serious with Confluence Scroll Versions plugin](#).
- Now you have your documentation space up and running, it's fun and rewarding to use the full power of the wiki to engage your readers and embed content from other social sites. Here is a blog post and presentation slides on [engaging readers in the documentation](#).
- Sarah Maddox's book about technical communication in Confluence: [Confluence, Tech Comm, Chocolate - A Wiki as Platform Extraordinaire for Technical Communication](#).
- Webinar recording: [Confluence as a Platform for Technical Documentation](#).



Let us know about more links

We plan to add more links to this page or to the 'Tips of the Trade' page. Let us know of any we have missed.

Developing a Knowledge Base on Confluence Wiki

Welcome! This is a guide to using Confluence as a knowledge base. You will find this guide useful if you want to produce a knowledge base with a survey, content curation, intelligent search and standardized templates.

In these pages, we'll show you how to use Confluence to achieve a high-functioning knowledge base, including these features:

- **Using Templates**
- **Subscriptions** (RSS or Email)
- **Exporting** articles (PDF or Word)
- **Organizing content** (hierarchically or by label)
- **Involving Customers** (using comments)
- **Populating data**
- **Scripts** to update content programatically
- A **"Was This Helpful?"** survey
- **Intelligent searching** algorithms (higher ranked articles are promoted in search results)
- **Targeted searching** across specified Confluence spaces and content types
- How to show **related content**
- Extensive **metrics and reporting**
- Maintenance

PAGES IN THE GUIDE

- [Creating Your Knowledge Base Space](#)
- [Using Templates and Formatting Macros in a Knowledge Base](#)
- [Proactive Communications in a Knowledge Base](#)
- [Additional Add-ons for a Knowledge Base](#)

RELATED TOPICS

[Confluence User's Guide](#)

[Confluence Administrator's Guide](#)

Creating Your Knowledge Base Space

This guide is for people who want to develop and publish a knowledge base using Confluence. You'll find Confluence useful because it combines professional web publishing features with the ease-of-use and flexibility of a wiki - requiring a low barrier to entry, but high quality output for all your team members. Confluence provides all of the collaborative features for your reports (such as automatic versioning, granular enterprise security, email and RSS subscriptions, and JIRA integration). This page is a quick-start guide to creating a wiki space for a knowledge base.



Quick guide to creating a knowledge base space

- Add a Space and Select the Documentation Theme
- Set the Space Permissions
- Customise the Title and Content of the Homepage
- Customise the Documentation Theme
- Create an Inclusions Library to Manage Reusable Content
- Create the Table of Contents
- Make your Knowledge Base Proactive with a Subscribable RSS Feed
- Set up Atlassian's Content Survey and Reporting Plugin
- Insert Google Analytics Code into Confluence's Custom HTML - *Not applicable to Confluence OnDemand.*

The rest of this page gives more details of the above procedure.

On this page:

- [Step 1. Add a Space and Select the Documentation Theme](#)
- [Step 2. Set the Space Permissions](#)
- [Step 3. Customise the Title and Content of the Homepage](#)
- [Step 4. Customise the Documentation Theme](#)
- [Step 5. Create an Inclusions Library to Manage Reusable Content](#)
- [Step 6. Create the Table of Contents](#)
- [Step 7. Make your Knowledge Base Proactive with a Subscribable RSS Feed](#)
- [Step 8. Set up Atlassian's Content Survey and Reporting Plugin](#)
- [Step 9. Insert Google Analytics Code into Confluence's Custom HTML](#)
- [Note about Plugin Support](#)

Step 1. Add a Space and Select the Documentation Theme

Below is a quick guide to adding a space. See [Setting up a New Global Space](#) for a full description.

1. Go to the Confluence dashboard and choose **Add Space**.
Hint: If you cannot see **Add Space**, this means that you do not have permission to add spaces. Please contact your Confluence administrator.
2. In the 'Create Space' screen, enter a **space name** and a short, unique **space key**.
3. Leave the **permission** settings as default, or choose to allow only yourself to view or contribute content to this space. You can change these settings later and with more flexible options.
4. Choose **OK**.
5. Your new space appears. Choose **Space Tools** in the sidebar.
6. Choose **Look and Feel > Themes** and select the **Documentation** theme.
7. Choose **OK**.

The homepage of your new space will appear, with the Documentation theme. Because you created the space, you are the space administrator. Now you can do some basic configuration, as described in the sections below. From this point on, instructions will refer to navigating in the Documentation theme, which is slightly different to the default theme.

Step 2. Set the Space Permissions

Define the space permissions to determine who can do what in your new space.

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Permissions**.
3. Choose **Edit Permissions**.
4. Set the permissions to suit your needs then click **Save All**.
 - You can add **groups** and/or individual **users** to the list, then select the permissions for each group or user.
 - You can also set the permissions for **anonymous** users – these are people who have not logged in to the wiki. Anonymous access is available only if enabled for the entire Confluence site. We recommend this setting if you are using this space for Technical Documentation or for a Knowledge Base.
 - Note that you can change these permissions at any time. You may want to restrict the permissions to specific groups now, and later open the space to more people.

A Bit More about Permissions

Confluence has a robust and granular permissions scheme that you can use to determine who can view, comment on and even update the documentation. There are three levels of permissions in Confluence:

- Global permissions apply across the entire site.
- Space permissions apply to a space.
- Page restrictions allow you to restrict the editing and/or viewing of a specific page. Below we discuss a way of using these in the draft, review and publishing workflow.

Space permissions in Confluence are simple yet granular enough to be useful for technical documentation. You can:

- Use the permission levels to control who can create pages in the space, delete pages, create comments, delete comments, administer the space, and so on.
- Grant a permission level to one or more users, and/or to one or more groups, and/or to anonymous users.

Terminology:

- 'Anonymous' means people who have not logged in to the wiki. These are users that won't affect your the number permitted by your license.
- The 'confluence-users' group is the default group into which all new users are assigned. Everyone who can log in to Confluence is a member of this group.

For example, you might allow 'Anonymous' users specific view and content creation rights so that they can access and engage with your knowledge base while your team lead (Rach) maintains full Space Administration rights.

Screenshot: Allow anonymous users to add specific content

Individual Users													
These are the permissions currently assigned to individual users for this space.													
	All	Pages			Blog		Comments		Attachments		Mail	Space	
	View	Add	Restrict	Remove	Add	Remove	Add	Remove	Add	Remove	Remove	Export	Admin
Rach Admin (admin)	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
Edit Permissions													
Anonymous Access													
When a user is using Confluence while not logged in, they are using it anonymously. For example: Enabling anonymous 'commenting' permission, allows non-logged-in users to make comments in this space.													
	All	Pages			Blog		Comments		Attachments		Mail	Space	
	View	Add	Restrict	Remove	Add	Remove	Add	Remove	Add	Remove	Remove	Export	Admin
Anonymous	✓	✓	✗	✗	✓	✗	✓	✗	✓	✗	✗	✓	✗
Edit Permissions													

For detailed information, see the documentation on:

- [Global permissions](#)
- [Space permissions](#)
- [Page restrictions](#)
- [Users and groups](#)

Step 3. Customise the Title and Content of the Homepage

When you created your space, Confluence created a homepage with default content and a default title, 'Home'. You will want to change the title and content.

1. Go back to your space homepage, by clicking the space name in the breadcrumbs at the top of the screen.
2. The space homepage appears. By default, the page title is 'X Home', where 'X' is the name you gave your space.
3. Click **Edit**.
4. Change the title to suit your needs.
5. Update the content to suit your needs.
Hint: If you do not know what to add yet, just add a short description. You can refine the content of the page later. Take a look at an [example of a homepage](#).
6. Click **Save**.

Step 4. Customise the Documentation Theme

When you added this space you chose the Documentation theme, which provides a left-hand navigation bar and a good look and feel for a knowledge base. If necessary, you can configure the Documentation theme to add your own page header and footer or to customise the default left-hand navigation bar. These customisations affect the online look and feel of your knowledge base. See [Configuring the Documentation Theme](#) for the full description in our product documentation.

1. Choose **Browse > Space Admin** (if you have not yet selected the documentation theme choose Space Tools > Look and Feel)
2. Choose **Themes**.
3. If the space is not yet using the Documentation theme, apply the theme now.
4. Choose **Configure theme**.

Current Theme

The current theme controls the layout and colours of this space.



Documentation Theme

This theme is well suited for structured content, such as documentation. It features a table of contents (page tree) on the left, making it easier to see the structure of a space and move from page to page. You can customise the left-hand panel, page header and page footer.

[Configure theme](#) - further customise this theme's options

5. The 'Documentation Theme Configuration' screen appears. Customise the left-hand navigation bar, header and footer to suit your needs. Details are in the [documentation](#). Here are some hints:
 - The **Page Tree** check box determines whether your space will display the default search box and table of contents (page tree) in the left-hand panel.
 - The **Limit search results to the current space** check box determines whether Confluence will search only the current space or the whole Confluence site. This setting affects the default search. Viewers can override it each time they do a search.
 - Enter text, images, macros and other wiki markup into any or all of the three text boxes for the left-hand navigation bar, header and footer. You can use the [Include macro](#) and the [Excerpt Include macro](#) to include re-usable content.
 - Any content you add to the navigation panel will appear *above* the default page tree.
 - If you like, you can remove the default page tree (by unticking the box) and add your own, customised version of the [Pagetree](#) macro instead.
6. Choose **Save**.

Example of a Customised Footer

Take a look at the footer of a page in the [Crowd documentation space](#).

[Get Support](#)
 Log a request with our support team.

[Report a Bug](#)
 Raise an issue for our developers.

[Get Answers](#)
 See answers from the community.

[Add to our Docs](#)
 Tweet, blog and update our documentation.

Except where otherwise noted, content in this space is licensed under a [Creative Commons Attribution 2.5 Australia License](#).

To produce the above footer, we have the following content in the footer panel in the Documentation theme configuration screen:

Footer

```
{include:_Documentation Footer|nopanel=true}
{include:ALLDOC:_Copyright Notice|nopanel=true}
```

Here it is in text form:

```
{include:_Documentation Footer|npanel=true}  
{include:ALLDOC:_Copyright Notice|npanel=true}
```

The above content consists of two [Include macros](#).


- The first macro includes a page called [_Documentation Footer](#). This page contains the big blue buttons and hyperlinked text.
- The second macro includes a page from a different space, the ALLDOC space, called [_Copyright Notice](#). This page includes our standard copyright notice, used in all our documentation spaces.
- In each include macro, the content has been drawn from an inclusions library, a hidden content repository, from which you can store frequently and re-usable content throughout your knowledge base space.

Step 5. Create an Inclusions Library to Manage Reusable Content

Using Confluence, you can dynamically include content from one page into another page. You can include a whole page into another one, using the [Include macro](#). You can also define an 'excerpt' on a page, and then include that excerpted text into another page using the [Excerpt Include macro](#).

To organise your re-usable content, we recommend that you create a set of pages called an 'inclusions library'.

1. Choose **Create** and create a new page in your space
2. Enter a suitable title. We use `'_InclusionsLibrary'`. The unusual format of the title helps to let people know this page is special.
3. Enter some content and **save** the page. We enter text explaining the purpose of the inclusions library and how to re-use the content. You can copy our text by clicking through to one of the example pages listed below.
4. Choose **Browse > Pages** and drag your new page *above* the space homepage.
5. Go to your new inclusions page and choose **Create** to add child pages containing your re-usable content. See the examples of our own inclusions libraries listed in the [examples](#) below.



Some notes about inclusions libraries:

- The inclusions library is not a specific feature of Confluence. The pages in the inclusions library are just like any other Confluence page.
- The pages are located at the root of the wiki space, not under the homepage. This means that they will not appear in the table of contents on the left and they will not be picked up by the search in the left-hand navigation bar either.
- The pages will be picked up by other global searches, because they are just normal wiki pages.
- We have decided to start the page name with an underscore. For example, `'_InclusionLibrary'`. This indicates that the page is slightly unusual, and will help prevent people from changing the page name or updating the content without realising that the content is re-used in various pages.

Examples of Inclusions Libraries

Here are some examples in our documentation:

- [Crowd inclusions library](#)
- [Confluence inclusions library](#)

Step 6. Create the Table of Contents

Create the table of contents for your knowledge base, by adding the top-level pages for all the usual sections. For instance, our Technical Support Team designed the following pages in the [Confluence Knowledge Base](#) on our public wiki:

- Browse Articles by Label
- Browse Articles by Top Ranked Content
- Browse Articles by Page Tree Hierarchy
- Browse Articles by Version
- Subscribe to Proactive Announcements

1. Go back to your space homepage, by clicking the space name in the breadcrumbs at the top of the screen.
2. Choose **Create** to add the page as a child of the homepage.
3. Enter the page title, for instance: 'Browse Articles by Label'.
4. Enter the content of the page.
 - *Hint:* If you do not know what to add yet, just add a short description then refine the content of the page later. If you like, you can follow a similar outline as the Confluence Knowledge Base and add the [Label List macro](#). This displays a hyperlinked alphabetical index of all labels within the current space. As you create content in this space and apply appropriate labels, the macro will update this page automatically.

Browse Content by Label

Click on one of the labels below to find related content:

Below are the **181** labels used in **Confluence Knowledge Base** listed alphabetically. Click a label to see its associated content.

A-B [apache](#),
[applinks](#),
[appserver](#),
[attachments](#), [backup](#),
[bamboo](#), [build](#)

C [cache](#),
[calendar](#),
[camelcase](#),
[camel_case](#),
[captcha](#),
[case_sensitivity](#),

D [dashboard](#),
[database](#), [db2](#),
[deadlock](#), [directory](#),
[doc_import](#),
[documentation_theme](#),
[dynamictasklist](#)

5. Choose **Save**.

Now do the same for all the sections of your Knowledge Base that you wish to appear in the left-navigation bar of the Documentation theme. Below is what the Table of Contents looks like for our Confluence Knowledge Base:

Search the Knowledge Base and Documentation Spaces

Browse Content

- Browse Articles by Label
- Browse Articles by Top Ranked Content
- › Browse Articles by Page Tree Hierarchy
- › Browse Articles by Version
- › Subscribe to Proactive Announcements

Step 7. Make your Knowledge Base Proactive with a Subscribable RSS Feed

Let's populate the knowledge base homepage with content by creating an RSS feed that your coworkers and customers can subscribe to and receive important updates on your knowledge base and technical alerts on your products.

This is a strategy that Atlassian's Technical Support Team uses to create a proactive knowledge base that provides technical alerts to customers and coworkers and helps solve support issues before they're even created.

By following the quick guide below, you'll create a homepage similar to the one Atlassian's Technical Support Team has created for the [Confluence Knowledge Base](#) on our public wiki and turn your knowledge base from reactive to proactive:

Technical Announcements

Copy the RSS feed into your favourite RSS reader:

Important Technical Announcements for Confluence

Blog Posts

Confluence 5.0-rc1 released created by Sarah Maddox [Atlassian Technical Writer]	Confluence Knowledge Base Feb 13, 2013
Confluence 5.0 Beta 4 released created by Sarah Maddox [Atlassian Technical Writer]	Confluence Knowledge Base Feb 05, 2013
Confluence 4.3.7 released created by Sarah Maddox [Atlassian Technical Writer]	Confluence Knowledge Base Jan 28, 2013
Confluence 5.0 Beta 2 released created by Sarah Maddox [Atlassian Technical Writer]	Confluence Knowledge Base Jan 23, 2013
Confluence 4.3.6 released created by Sarah Maddox [Atlassian Technical Writer]	Confluence Knowledge Base Jan 23, 2013

[View more recent blog posts](#)

RSS 2.0

Creating your RSS Feed

Confluence can filter spaces by content type. To filter your knowledge base for 'blog post' content, do the following:


1. Go to a page in the space and choose **Blog** in the sidebar.
Or, if you are using the Documentation theme, choose **Browse > Blog** at the top of the screen.
2. Copy this URL to your clipboard.
3. Create an RSS feed for the URL of your knowledge base space.
 Now your RSS feed will consist of any blog posts created in the knowledge base space.

Highlighting Your Technical Announcement RSS Feed

1. Go to your space home page.
2. Choose **Edit**.
3. Insert an 'h2' heading, such as 'Important Technical Announcements'.
4. Insert bold text that reads something like, 'Copy the RSS feed into your favourite RSS reader:'.
5. Choose **Insert** > **Other Macros** to open the Macro Browser.
6. Select the 'Panel' macro in the Macro Browser and specify your desired macro preferences.
We recommend that you change the **Panel Title**, **Border Style**, and **Background Color** to further highlight the panel on the page.
7. Choose **Insert**.

Insert a Blog Posts Macro

1. Inside the Panel macro placeholder choose **Insert** > **Other Macros** to open the Macro Browser again.
2. Select the **Blog Posts** macro in the Macro Browser and specify the following preferences:



- **Content Type to Display:** Title
 - **Restrict to These Spaces:** Your knowledge base Spacekey
 - **Maximum Number of News Items:** 5
 - **Sort By:** Creation
 - **Reverse Sort:** Tick the box
3. Choose **Insert** to insert the Blog Posts macro onto the page inside your Panel macro.
 Now your panel will display the last 5 blog posts created in your knowledge base space.

Inserting your RSS Feed into your 'Technical Announcement' Panel

First, let's create a link so that your coworkers and customers can view all of the blog posts in your knowledge base space. See [Working with Links](#) for a full description in our product documentation.

1. Place your cursor after/below the Blog Posts macro in the Panel macro placeholder.
2. Type: 'View more recent blog posts'.
3. Highlight this text and click **Link** on the editor toolbar.

Insert Link

Search

Recently Viewed

Attachments

Web Link

URL:

Link Text:

4. Select 'Web Link' and paste the link you copied to create your RSS Feed.
5. Choose **Insert**.

Now, let's insert your RSS Feed into your panel by linking an image. See [Linking an Image](#) for a full description in our product documentation.

1. Attach an RSS Icon  to the page by dragging and dropping it into the editor (preferably below the link you just created). See [Drag-and-Drop](#) for a full description in our product documentation.
2. Choose the RSS Icon image and choose the 'Align right' button on the editor toolbar.
3. Choose **Border** in the image properties panel.
4. Link the RSS Icon by selecting the image and then choosing **Link** on the editor toolbar.
5. Choose the 'Web Link' tab and insert the RSS Feed URL you created.
6. Choose **Insert** to link your RSS Feed to the RSS Icon image.
7. Choose **Save** to save your page and test your RSS Icon.

Congratulations! You have successfully created a proactive knowledge base.

Step 8. Set up Atlassian's Content Survey and Reporting Plugin

Now that you can monitor the traffic and activity of your knowledge base, let's measure its effectiveness. When the [Content Survey and Reporting Plugin](#) is activated for a space, it will generate a report that includes:

- Direct feedback from customers about article quality
- Amalgamated "composite score" results
- Answers to secondary questions, such as "Was the info complete?" or "Was the article well-written?".
- Rollup at-a-glance view of the metrics for the whole space.

Lastly, the Content Survey and Reporting Plugin will institute 'intelligent searching' which means that based on the results of the surveys, higher ranked pages are promoted in search results, so your best and most popular pages are found easiest. This is a quick guide for how to set up the Content Survey and Reporting Plugin.

 This plugin only functions properly if the Documentation Theme is applied to the space.

Let's install the Content Survey and Reporting Plugin using Confluence's [Universal Plugin Manager](#).

Installing the Content Survey and Reporting Plugin


1. Log into Confluence as a System Administrator or Confluence Administrator.
2. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
3. Choose **Manage Add-ons**
4. Search for the 'Content Survey and Reporting Plugin'
5. Choose **Install**.

You can also go to the Atlassian Marketplace and download the plugin and install it directly.

Now that you've installed the Content Survey and Reporting Plugin, let's configure a survey:

Configuring a Survey

1. Go to your space.
2. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
3. Click **Configure Survey** under 'Knowledge Base Survey'. Here you can:
 - Add a question
 - Edit a question's text
 - Activate or deactivate a question
 - Edit the response text
4. Configure a 'Primary Question' for the survey



Primary Question: Was this helpful?

Add an Additional Question:

Edit Survey Completed Response (anonymous): Thanks !

Edit Survey Completed Response (user): Thanks !

Save Cancel

5. Choose **Save**.

Now that you've added a primary question, let's test out the plugin by adding it to the footer of the Documentation theme so that every page within your Knowledge Base space includes your survey.

Invoking the Content Survey and Reporting Macro

1. Choose **Browse > Space Admin** at the top of the screen.
Note: The 'Space Admin' option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).
2. Choose **Themes**.
3. Choose **Configure theme**.
4. Go to the 'Footer' section of the 'Documentation Theme Configuration' page and insert this recommended markup to achieve a nice layout of the Content Survey and Reporting Plugin:

```
{section}
{column:width=5%}
{column}
{column:width=90%}
{panel}
{kbsurvey}
{panel}
{column}
{column:width=5%}
{column}
{section}
```

5. Choose **Save** and go to your space homepage to view your Content Survey and Reporting Plugin in the footer of the page.

With the Content Survey and Reporting Plugin you can dramatically improve the quality of your knowledge base and the efficiency with which your team creates and maintains it. Here is an example of how our Technical Support Team uses the Content Survey and Reporting Plugin in the [Confluence Knowledge Base](#):

Help us improve!

Is this article helpful? ☐ Yes ☐ No

Is the content complete? ☐ Yes ☐ No

Is it well written? ☐ Yes ☐ No

Content Survey and Reporting Plugin Results:

Survey results are viewable by Space Administrators only. The plugin develops three results:

- **Pages with Results** - Determine page-by-page, which are you most effective knowledge base articles and which ones need improvement.

View: **Pages with Results** | Pages without Results | Rollup Report

Confluence Knowledge Base	Total Ballots	Composite Score	Is this article helpful?	Is the content complete?	Is it well written?
LDAP Error Code 49	284	585	73% (208/285)	57% (111/195)	75% (144/193)
Confluence Does Not Start with 'MySQL session isolation level 'REPEATABLE-READ' is no longer supported' Message	69	167	86% (59/69)	75% (39/52)	82% (42/51)
Unable to Connect to SSL Services due to PKIX Path Building Failed sun.security.provider.certpath.SunCertPathBuilderException	86	110	57% (49/86)	51% (33/65)	56% (34/61)
How to Edit the Footer in Confluence	3	102	67% (2/3)	50% (1/2)	100% (2/2)
Exceeds Max Allowed Packet for MySQL	44	100	82% (36/44)	69% (24/35)	94% (33/35)
MySQL Table is Marked as Crashed and Should be Repaired	63	77	56% (35/63)	47% (22/47)	47% (20/43)
Problems Installing Confluence as a Service on Windows 64bit	32	72	81% (26/32)	71% (17/24)	82% (18/22)

As you can see, the plugin develops a '**Composite Score**' which ranks articles in search, so your highest scoring (best) content can be found most easily. The score is based on the last 32 votes cast, using the global search configuration. See [Confluence Content Survey and Reporting Plugin](#) for a full description on how Global Search boosting works.

- **Pages without Results** - These are the pages in your knowledge base without survey results.
- **Rollup Report** - This is the summary of all survey results. The report can be used to determine how effective your overall knowledge base content is.


View: Pages with Results Pages without Results Rollup Report				
Number of Pages in Space	Total Ballots Cast	Is this article helpful?	Is the content complete?	Is it well written?
1292	3351	58% (1934/3351)	50% (1237/2454)	67% (1596/2381)

Searching Multiple Spaces from your Knowledge Base

As mentioned, the Content Survey and Reporting Plugin generates a composite score that ranks pages and articles within your knowledge base to make the highest (most well regarded) pages more retrievable by visitors. The plugin also improves Confluence search by allowing users to search multiple spaces without ever leaving your knowledge base space. This is really helpful for users that are unfamiliar with Confluence because they can keep the knowledge base as a point of reference within the greater instance of Confluence.

At Atlassian, our product knowledge bases and product documentation exist in the same Confluence instance so that we can make both available to 'Anonymous' users. Our Technical Support team uses the Content Survey and Reporting Plugin to allow visiting users to search for Confluence resources in the product documentation space from the Confluence Knowledge Base space. This provides the visitor twice the chances of finding an answer to their question.

In the image below, you can see the space specific search used in the left-navigation bar to find content related to Confluence in both the 'Documentation' and 'Knowledge Base' spaces. Pages in the 'Documentation' space are listed first and pages in the 'Knowledge Base' space are listed second.



Step 9. Insert Google Analytics Code into Confluence's Custom HTML

Now that you have a strong foundation for a knowledge base, it's critical to assess how effectively it services your customers. Google Analytics is a tool that gives you rich insights into your website traffic and marketing effectiveness. You are going to want to understand how your customers are accessing the resources in your knowledge base. This is a quick guide to inserting Google Analytics HTML code into Confluence so you can measure your knowledge base traffic.

 *The information in this step does not apply to Confluence OnDemand.*

1. If you don't have one already, create a Google Account and then create a Google Analytics Account using your Confluence instance's URL.
2. Copy the Google Analytics code to your clipboard.
3. Log into Confluence as a System Administrator or Confluence Administrator.
4. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
5. Choose **Custom HTML** under 'Look and Feel'.
6. Choose **Edit** to insert custom HTML into your Confluence instance.

Custom HTML

Insert Custom HTML

At end of the HEAD

At beginning of the BODY

At end of the BODY

Save

Cancel

7. Paste your Analytics code you have saved to your clipboard into the table labeled **At end of the BODY**.
8. Choose **Save**.

You can now monitor the activity and traffic for every page you create in your Confluence instance and Knowledge Base.

Hint: If your knowledge base only represents a space within your greater Confluence instance, you can search Google Analytics for activity in the specific space by exclusively filtering for the space key.

Filter Page:

containing

MYKB

Go

Advanced Filter

Filter 'Top Content' using a Space Key

 Read David Simpson's blog post about [Tracking Confluence Usage with Google Analytics](#) for more information.

Note about Plugin Support

Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#).

Next Steps

See [Using Templates and Formatting Macros in a Knowledge Base](#) for next steps.

Using Templates and Formatting Macros in a Knowledge Base

This page is part of the guide to [developing a knowledge base on Confluence Wiki](#). We have already shown you how to [create your knowledge base space](#). Now we offer an introduction to the templates that Confluence provides.



Quick guide to templates in Confluence

- A template is a page with predefined content that can be used as a prototype when creating other pages.
- Templates are available across the Confluence site (global templates) or per space (space templates).
- Both 'global templates' and 'space templates', as described on this page, define the content of a page. They do not define the content of an entire space.
- You can import predefined templates, including those shipped with Confluence and additional templates from the [Atlassian Plugin Exchange](#).
- To create a template for an entire space, see our guide to [creating your documentation space](#).

Space Information Design

One question that comes up is whether a knowledge base should be implemented as a decision matrix, with a multi-select or other list. We knew that most of our users visit our documentation directly from search engines. Early on, we learned that at least for us, Google Analytics was showing that most traffic was coming from search engines, not from within our site. So, we knew to focus on optimising page titles and tags rather than focus on a decision matrix.

Confluence's Built-in Feature Set

Page Templates

Confluence's [page templates](#) are an easy place to start. Begin by choosing how you want your templates to look. Here's the [wiki markup](#) for our page template:

```
h3. Symptoms
FILL IN SYMPTOMS HERE

h3. Cause
FILL IN CAUSE HERE

h3. Resolution
FILL IN RESOLUTION HERE

{htmlcomment}
ENTER SUPPORT TICKET LINKS
{htmlcomment}
```



The `{htmlcomment}` macro is part of Adaptavist's [Content Formatting Macros](#), a handy plugin.

You might consider the [scaffolding plugin](#) or [Form Field Markup](#) for filling out forms. Our support engineers are quite used to using wiki markup (we live and breathe Confluence!), so we left this template as is.

Construct a Home Page: Section, Panels, RSS, and Notifications

Check out the Confluence Knowledge Base Home. The colored content in the middle of the page is an amalgamation of panel, rss and attachment macros. Go to Tools >> Wiki Markup to see.

✓ Wondering how we just made Tools >> Wiki Markup in a different font in the sentence above? Use the `{{ }}` notation to get the courier font, which you can use for breaking out text. And this would be, of course, a `{tip}`. Remember, you can visit Tools >> Wiki Markup on this page as well!

The wiki markup there is a little confusing, but it breaks down like this:

1. A [Section](#) macro, defining the top and bottom of the page
2. [Column](#) macros, dividing the panels into three
3. [Panel macros](#), with hot, hot, hot html colours
4. [Content By Label](#) Macros
5. An RSS Icon, embedded as an attachment, with a link to the RSS feed. Notice the magic on this one:

```
[!rss20.gif|align=right!|http://confluence.atlassian.com/createrssfeed.action?
types=page&sort=created&showContent=true&spaces=CONFKB&labelString=conf32&rssT
ype=rss1&maxResults=50&timeSpan=120&publicFeed=true&title=Confluence+3.2+Knowl
edge+Base+Articles&showDiff=false]
```

i That's a link, with the attachment as the alias, an alignment parameter, and the URL to the RSS feed. Cool, right?

Exporting Pages

These are built-in Confluence features. Check [Page Exports](#). You can learn how to customise the PDF export as well.

Content Macros

Besides the ones listed above, some favourite macros for formatting content around the site are the [Tip](#), [Info](#), [Warning](#), and [Note](#) Macros, and the [Code](#) macro. They make things look great. We also use Adaptavist's [Content Formatting Macros](#) when we really want to bring our A-game.

✓ Every once in a while we get mileage out of the `{nomarkup}` [user macro](#), when we want to discuss using a macro itself. I suppose that's because Confluence is one of the products we support! It might be useful for other reasons...

JIRA Issues Macro

Using JIRA for bug tracking? You can't expect your users to necessarily have exactly the right JQL filters to show the appropriate topics. We have some nice JIRA Issues Macros on display. One of my favourites is in the JIRA KB's [Causes for OutOfMemory Errors](#):

```
{jiraissues:url=http://jira.atlassian.com/sr/jira.issueviews:searchrequest-xml/temp
/SearchRequest.xml?jqlQuery=project+%3DJRA+AND+issuetype+in+%28Bug%2C+Improvement%
2C+subTaskIssueTypes%28%29%29+AND+component+%3D+%22Performance+-+Memory+leaks%22+OR
DER+BY+key+DESC&tempMax=200|columns=fixversion;summary;status;key|anonymous=true}
```

Notice the JQL there including components and sorting, plus the specific columns.

Labels

Sometimes, an article needs to be cross listed. For that we label our articles. Some great macros to use for this

are {contentbylabel}, {listlabels} and the {dynamiccontentbylabels} macro in the [Content Survey Plugin](#).

Next Steps

You now have a good idea of how Confluence templates work. What next? Take a look at [Proactive Communications in a Knowledge Base](#).

Proactive Communications in a Knowledge Base

This page is part of the guide to [developing a knowledge base on Confluence Wiki](#). We have already shown you how to [create your knowledge base space](#) and how to [use templates and formatting macros](#). We touched a bit on creating proactive communications in [Creating Your Knowledge Base Space](#), and discuss a bit further here.



Quick guide to proactive communications

- A template is a page with predefined content that can be used as a prototype when creating other pages.
- Confluence can either produce or consume rss feeds
- Both the rss and blog-posts macro are a good way to show summaries

Proactive Alerts

Sending technical alerts to customers is a great way to keep customers and staff informed, and good way to reduce support load. At Atlassian we use the Knowledge Base both to consume and produce proactive content for which customers can opt in. This page describes how to achieve that.

Using Confluence as a producer

- The [Working with Blog Posts](#) describes how to produce blog posts from Confluence.
- [Emailing a Page](#) is a great way to send mass emails to users or an email distribution list.

Using Confluence as a consumer

Even if your Confluence instance isn't producing your proactive content, it can consume and display it in a prominent way:

- The [RSS Feed Macro](#) can consume content from any RSS feed on the Internet.
- We use the [Blog Posts Macro](#) for It looks especially handsome in a panel, accentuated by an RSS image in a link. Here's the wiki markup:

```
h4. Technical Alerts
{panel:title=Important Technical Alerts for Confluence| borderStyle=solid|
borderColor=#ccc| titleBGColor=#f93 | bgColor=#fc9}
{blog-posts:content=title|max=5|sort=modified|spaces=CONFKB|time=30d}
*[View more recent blog
posts|http://confluence.atlassian.com/pages/viewrecentblogposts.action?key=CON
FKB]*
[!CONFKB:Confluence Knowledge
Base^rss20.gif|align=right!|http://confluence.atlassian.com/createrssfeed.acti
on?types=blogpost&blogpostSubTypes=comment&blogpostSubTypes=attachment&spaces=
CONFKB&title=Confluence+KB+-+Technical+Alerts&labelString=techalert&excludedSp
aceKeys%3D&sort=modified&maxResults=10&timeSpan=30&showContent=true&showDiff=t
rue&confirm=Create+RSS+Feed|showTitleOnly=true]
{panel}
```

Next Steps

You now have a good idea of how to do proactive communications. Next up, consider [Additional Add-ons for a Knowledge Base](#) in more detail.

Additional Add-ons for a Knowledge Base

This page is part of the guide to [developing a knowledge base on Confluence Wiki](#). This page lists additional add-ons that might expand your usage.

Useful Add-ons for a Knowledge Base

These are some great add-ons for Confluence as a Knowledge Base:

- The [Content Survey and Reporting Plugin](#) gives a good report on popular and unpopular content.
- The [Confluence Archiving Plugin](#) flags old content.
- The [Ad hoc Workflows Plugin](#) or [Content Publishing Plugin](#) manage workflows and review process.

Note about Add-on Support

Before installing an add-on (also called a plugin) into your Confluence site, please check the add-on's information page to see whether it is supported by Atlassian, by another vendor, or not at all. See our guidelines on [add-on support](#).

Bye

Hope you enjoyed the tutorial! Have a chocolate, and please share with us your experiences. You can comment directly on this page.

Developing an Intranet on Confluence Wiki

This guide is for people who are using Confluence as a platform for an intranet. You will find this guide useful if you want to create a space where your team can collaborate and share information.



Quick guide to creating an intranet space

- Create a space.
- Set the space permissions.
- Customise the title and content of the home page.
- Subscribe to email notifications for any updates made to the space.
- Manage your existing Office documents.
- Import page templates.
- Set up your personal space.
- Publish a blog post.

Step 1. Create a Space

Below is a quick guide to adding a space for your team.

1. Go to the Confluence dashboard and choose **Create Space**.
2. The **Create Space** screen appears. Enter a **space name** and a short, unique **space key**.
3. Choose **Create**.

Create Space [Help](#)

Create a space for your team or project:

Space name

Space key

Used in the space's URL:
<http://localhost:8090/display/IT>

☐ [Make this space private](#)

[Create](#) [Cancel](#)

The home page of your new space will appear. Because you created the space, you are the space administrator. Now you can do some basic configuration, as described in the sections below.

Step 2. Set the Space Permissions

Define the space permissions to determine who can do what in your new space.

1.
 - If this space has the Default theme applied, go to the space and choose **Space tools** on the sidebar.
 - If this space has the Documentation theme applied, go to **Browse** in the top bar and select **Space Admin**.

Note: This option appears only if you are a space administrator for the space or you are a super user (a member of the confluence-administrators group).

2. The **Permissions** page appears.
3. Choose **Edit Permissions**.
4. Set the permissions to suit your needs then choose **Save All**.
 - You can add **groups** and/or individual **users** to the list, then select the permissions for each group or user.
 - You can also set the permissions for **anonymous** users – these are people who have not logged in to Confluence and will not count towards the number allocated by your license. Anonymous access is only available if enabled for your entire Confluence site. It is unlikely you will need anonymous users for your intranet.
 - You can change these permissions at any time. You may want to restrict the permissions to specific groups now, and later open the space to more people.

[More about Permissions](#)

Confluence has a robust and granular permissions scheme that you can use to determine who can view, create content and comment within your intranet. There are three levels of permissions in Confluence:

- Global permissions apply across the entire site.
- Space permissions apply to a space.
- Page restrictions allow you to restrict the editing and/or viewing of a specific page.

Space permissions in Confluence are simple yet granular enough to be useful for an intranet. You can:

- Use the permission levels to control who can create pages, delete pages, create comments, delete comments, administer the space, and so on.
- Grant a permission level to one or more users, and/or to one or more groups, and/or to anonymous users. A space administrator has complete control.

Terminology:

- '**Anonymous**' means people who have not logged in to Confluence
- The '**confluence-users**' group is the default group into which all new users are assigned. Everyone who can log in to Confluence is a member of this group.

For example, you might allow the '**confluence-users**' group permission to create and edit comments, but reserve full editing rights for your team members. Let's assume your team members are all members of the '**developers**' group. The example below shows that members of the '**developers**' group have all permissions except space administration, but, members of the '**confluence-users**' group and the individual '**Josh User**' only have a few editing rights.

Groups													
These are the permissions currently assigned to groups for this space.													
	All	Pages			Blog		Comments		Attachments		Mail	Space	
	View	Add	Restrict	Remove	Add	Remove	Add	Remove	Add	Remove	Remove	Export	Admin
confluence-users	✓	✓	✗	✗	✓	✗	✓	✗	✓	✗	✓	✓	✗
developers	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✗
Edit Permissions													
Individual Users													
These are the permissions currently assigned to individual users for this space.													
	All	Pages			Blog		Comments		Attachments		Mail	Space	
	View	Add	Restrict	Remove	Add	Remove	Add	Remove	Add	Remove	Remove	Export	Admin
Rach Admin (admin)	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
Josh User (josh)	✓	✓	✗	✗	✓	✗	✓	✗	✓	✗	✓	✓	✗
Edit Permissions													

For detailed information, see the documentation on:

- [Global permissions](#)
- [Space permissions](#)
- [Page restrictions](#)
- [Users and groups](#)

Step 3. Customise the Title and Content of the Home Page

When you created your space, Confluence created a home page with default content and a default title, 'Home'. You will want to change the title and content to suit your team.

1. Go to your space home page
2. By default, the page title is 'X Home' (where 'X' is the name you gave your space).
3. Choose **Edit**.
4. The page opens in the editor.
5. Change the title and update the content to suit your needs.
Hint: If you do not know what to add yet, add a short description. You can refine the content of the page at any time.
6. Choose **Save** to save your home page.

Step 4. Subscribe to Email Notifications for Updates Made to the Space


You can configure your email notifications to suit your needs: You can choose to be notified about all pages in a space, blog posts in a space, or both. Below is a quick guide to monitoring a space's content. See [Watching a Space](#) for a full description.

1. Go to your space homepage.
2. Choose **Pages** in the sidebar.
3. Choose **Watch this space**.
4. Choose **Blog** in the sidebar.
5. Choose **Watch this blog**.

If at any time you wish to stop watching activity in the space, just click '**Stop watching this space**' or '**Stop watching this blog**'.

Example of an Email Notification

Here is an example of the email notification you will receive when someone adds a comment to a page or blog post:



More about Notifications

You can specify the notifications you want to receive on a global, space and page level. The quick guide above demonstrated how to set up notifications for a space. Now we will show you how to configure your notifications on the global and page levels.

Global Notifications

Global notification settings determine the overall behaviour of the notifications you receive from Confluence.


1. Choose **your profile picture** at top right of the screen, then choose **Settings**.
2. Choose **Email**.
3. Choose **Edit**.
4. Change the default settings to suit your needs. You can alter these email settings at any time.
5. Choose **Submit** to save your changes.

Page and Blog Post Notifications

Follow the quick guide below to receive notifications from Confluence about changes to and comments on a specific page or blog post. See [Watching a Page or Blog Post](#) for a full description.

You can watch any given page or blog post that you have permission to view. We will use your space's home page as an example.

1. Go to the home page of your space.
2. Choose **Tools > Watch**.



You are now watching the current page and Confluence will notify you about any updates made or comments added.

Note that Confluence will **not** notify you about content changes that are due to the output of a macro. For example: The output of the [Children macro](#) will change if someone adds a child page. The page containing the Children macro will show the new child page. But the page content itself has not been edited, so no notifications will be sent.

You can stop watching a page or blog post at any time. Simply choose **Tools > Stop Watching**.


Step 5. Attach or Import Office Documents if Applicable

Below are some guidelines on managing your existing Microsoft Office documents in Confluence. You can choose to attach them to a Confluence page, so that team members can view and access them in Confluence, and edit them in Office. Or you can import the documents into Confluence, converting the content to Confluence pages.

Attaching Office Documents to a Page

You can use Confluence as a central repository for your team's Office documents. This means that you can share your Office documents without having to email them to your teammates. People can view the Office documents even if they do not have Office installed on their computers.


1. Go to a page in your space.
2. Choose **Tools** > **Attachments**.
3. Use one of the following methods for attaching files to the page:
 - Choose **Browse** and to locate the file on your computer, enter a **comment** then choose **Attach**



The 'Attach File' dialog box contains the following elements:

- Upload file**: A text input field followed by a **Browse...** button.
- Comment**: A text input field.
- Attach more files**: A blue link.
- Attach**: A button.

- Alternatively, **drag and drop** one or more file(s) directly onto the 'Drop files here' region of the attachments screen. The 'Attach File(s)' message box appears, indicating the upload status of the file(s) being attached to your page.



The 'Attach File(s)' dialog box displays the upload progress for three files:

File Name	Progress	Status
MyPresentation.ppt	180.00 kB of 180.00 kB	✓
Confluence a history.doc	10.50 kB of 10.50 kB	✓
Spreadsheet.xls	7.00 kB of 7.00 kB	✓

A **Done** button is located at the bottom right of the dialog.

Importing Existing Word Documents into Confluence

You can also import content from Microsoft Word into Confluence, so that it becomes a Confluence page. See [Importing a Word Document into Confluence](#) for a full description.

1. Go to your space homepage.
2. Choose **Tools** > **Import Word Document** The Office Connector import screen will appear.
3. Choose **Browse** and locate the Office document on your local drive or network.
4. Choose **Next**. The import document options screen will display.

Pages ← View ⚙ Tools ▾

Intranet Home

Import Word Document: Configuration

Root page title:

Where to import: ☒ Import as a new page in the current space
☐ Replace Intranet Home
☐ Delete existing children of Intranet Home

Title conflicts: ☒ Rename imported pages if page name already exists
☐ Replace existing pages with imported pages of the same title
☐ Remove existing pages with the same title as imported pages

Split by heading: *Can't split this document. It contains no Heading styles.*

5. Choose how you would like the Office Connector to import the file:
 - **Root page title** – This will be the title of the page.
 - **Import as a new page in the current space** – This option specifies that a new page will be created with the title specified.
 - **Rename imported pages if page name already exists** – This is what Confluence will do if there is a conflict.
 - **Split by heading** – If your document contains headings, Confluence can use the heading information to split the document into multiple wiki pages. If you do not want to split your document leave the default 'Don't split' option selected.
6. Choose **Import**.

When the upload has finished, the content of the Office document will have been transformed into Confluence page content. You can now view and edit this page in the normal way, using the Confluence editor. There is now no connection between the original Office document and this page.

Step 6. Import Page Templates

In order for an intranet to be effective, people need to use it. One way to spur new user adoption is to provide your team mates with templates so that they can focus more on content creation and less on page format. You can create your own templates or download some from the [Atlassian Marketplace](#). See [Importing Templates](#) and [Adding a Template](#) for a more information. In this example we have downloaded some HR related templates from [Atlassian Marketplace](#).

1. Log in to Confluence as an administrator.
2. Choose the **cog icon**  at top right of the screen, then choose **Confluence Admin**.
3. Choose **Import Templates**. The 'Import Templates' screen will appear, listing the template packages deployed to your Confluence instance (for example, 'Human Resources Templates') and the templates included in each package.

Import Templates

The following template package plugins were found. To import templates, tick the checkboxes for the desired templates, select where to import the templates to, and click the Import button.

Human Resources Templates (8)

[Check All](#) [Uncheck All](#)

- ☐ HOW-TO Guide
- ☐ Induction Tasks
- ☐ Job Description
- ☐ Meeting Minutes
- ☐ Recruitment Dashboard
- ☐ Space Home Page
- ☐ Time Sheet
- ☐ Wiki Induction


Import To:

4. Select the templates you want to import.
Note: You can view a preview of the template by clicking the template name.
5. Choose the destination to **Import To**. If you want the templates to be available to your Intranet space only, select the name of the space, otherwise select 'Global Templates' to make the templates available to all spaces.
6. Choose **Import** to import the selected templates.

Creating a page from a template

Now that you have made some templates available to your site or space, other Confluence users will be able to choose a template when they want to create a page. Templates appear in the **Create** dialog for users to select when creating a new page.

1. Go to your Intranet space.
2. Choose **Create** on the header. Available templates will be listed in the Create dialog.
3. Select a template and choose **Next**.



4. If the template contains variables, a form will appear. Type the relevant information into the form fields, and choose **Next**.
5. Enter a title for the page, update the content and choose **Save**.

Step 7. Set Up your Personal Space

Now that you have created a space for your team, let's create your **personal space**. This is a place where you can publish your own pages and blog posts. Once you have created it, Confluence users can reach your personal space by clicking your name in the [People Directory](#) or by searching for your name via the [quick navigation search box](#).

1. Choose **your profile picture** at top right of the screen, then choose **Add Personal Space**.
2. Enter a few details about your space:
 - Choose who can **view** content.
 - Choose who can **contribute** (create and edit) content.
 - Choose the '**Global Look and Feel**' for your personal space.
3. Choose **Create**.
4. The 'Home' page for your new space is displayed.

Step 8. Publish a Blog Post

Blog posts are a good way of letting your team mates and the company know your news. People can blog about product and strategic ideas, team updates, and things they want to get ideas about. New employees can write blog posts introducing themselves. People write about getting married or the birth of a child. Blog posts are a great way for people to share their visions, get to know their c-oworkers and start lively discussions.

Remember to set your email notifications to alert you about the blog posts published within Confluence, as described in an earlier step.

See [Working with Blog Posts](#) for a full description of adding, editing, viewing and linking to blog posts.

1. Go to a page in your space.
2. Choose **Create** in the header.
3. Select **Blog** then choose **Next**.
4. Add a title and some content.
5. Choose **Save** to publish your blog post.

Related Topics

[Creating a Space](#)

[Global Permissions Overview](#)

[Assigning Space Permissions](#)

[Setting a Page's Restrictions](#)

[Users and Groups](#)